# Additional Exercises for *Convex Optimization*

Stephen Boyd          Lieven Vandenberghe

August 4, 2023

This is a collection of additional exercises, meant to supplement those found in the book *Convex Optimization*, by Stephen Boyd and Lieven Vandenberghe. These exercises were used in several courses on convex optimization, EE364a (Stanford), EE236b (UCLA), or 6.975 (MIT), usually for homework, but sometimes as exam questions. Some of the exercises were originally written for the book, but were removed at some point.

Many of them include a computational component using one of the software packages for convex optimization: CVXPY (Python), Convex.jl (Julia), CVX (Matlab), or CVXR (R). We refer to these collectively as CVX*. (Some problems have not yet been updated for all languages.) The files required for these exercises can be found at the book web site `www.stanford.edu/~boyd/cvxbook/`.

You are free to use these exercises any way you like (for example in a course you teach), provided you acknowledge the source. In turn, we gratefully acknowledge the teaching assistants (and in some cases, students) who have helped us develop and debug these exercises. Pablo Parrilo helped develop some of the exercises that were originally used in MIT 6.975, Sanjay Lall and John Duchi developed some other problems when they taught EE364a, and the instructors of EE364a during summer quarters developed others.

We'll update this document as new exercises become available, so the exercise numbers and sections will occasionally change. We have categorized the exercises into sections that follow the book chapters, as well as various additional application areas. Some exercises fit into more than one section, or don't fit well into any section, so we have just arbitrarily assigned these.

Course instructors can obtain solutions to these exercises by email to us. Please specify the course you are teaching and give its URL.

*Stephen Boyd and Lieven Vandenberghe*

# Contents

# 1  Introduction

**1.1** *Convex optimization.* Are the following statements true or false?

    (a) Least squares is a special case of convex optimization.

    (b) By and large, convex optimization problems can be solved efficiently.

    (c) Almost any problem you'd like to solve in practice is convex.

    (d) Convex optimization problems are attractive because they always have a unique solution.

**1.2** *Device sizing.* In a device sizing problem the goal is to minimize power consumption subject to the total area not exceeding 50, as well as some timing and manufacturing constraints. Four candidate designs meet the timing and manufacturing constraints, and have power and area listed in the table below.

| Design | Power | Area |
|--------|-------|------|
| A | 10 | 50 |
| B | 8 | 55 |
| C | 10 | 45 |
| D | 11 | 50 |

Are the statements below true or false?

    (a) Design B is better than design A.

    (b) Design C is better than design A.

    (c) Design D cannot be optimal.

**1.3** *Computation time.* Very roughly, how long would it take to solve a linear program with 100 variables and 1000 constraints on a computer capable of carrying out a 10 Gflops/sec (*i.e.*, $10^{10}$ floating-point operations per second)?

    (a) Microseconds.

    (b) Milliseconds.

    (c) Seconds.

    (d) Minutes.

**1.4** *Local optimization.* Are the statements below true or false?

    (a) Local optimization can be quite useful in some contexts, and therefore is widely used.

    (b) Local optimization is currently illegal in 17 states.

    (c) Local optimization can't guarantee finding a (global) solution, and so is not widely used.

# 2 Convex sets

**2.1** Is the set $\{a \in \mathbf{R}^k \mid p(0) = 1, \ |p(t)| \le 1 \text{ for } \alpha \le t \le \beta\}$, where

$$p(t) = a_1 + a_2 t + \cdots + a_k t^{k-1},$$

convex?

**2.2** *Set distributive characterization of convexity* [Rockafellar]. Show that $C \subseteq \mathbf{R}^n$ is convex if and only if $(\alpha + \beta)C = \alpha C + \beta C$ for all nonnegative $\alpha$, $\beta$. Here we use standard notation for scalar-set multiplication and set addition, *i.e.*, $\alpha C = \{ac \mid c \in C\}$ and $A + B = \{a + b \mid a \in A, \ b \in B\}$.

**2.3** *Composition of linear-fractional functions.* Suppose $\phi : \mathbf{R}^n \to \mathbf{R}^m$ and $\psi : \mathbf{R}^m \to \mathbf{R}^p$ are the linear-fractional functions

$$\phi(x) = \frac{Ax + b}{c^T x + d}, \qquad \psi(y) = \frac{Ey + f}{g^T y + h},$$

with domains $\mathbf{dom}\,\phi = \{x \mid c^T x + d > 0\}$, $\mathbf{dom}\,\psi = \{y \mid g^T x + h > 0\}$. We associate with $\phi$ and $\psi$ the matrices

$$\begin{bmatrix} A & b \\ c^T & d \end{bmatrix}, \qquad \begin{bmatrix} E & f \\ g^T & h \end{bmatrix},$$

respectively.

Now consider the composition $\Gamma$ of $\psi$ and $\phi$, *i.e.*, $\Gamma(x) = \psi(\phi(x))$, with domain

$$\mathbf{dom}\,\Gamma = \{x \in \mathbf{dom}\,\phi \mid \phi(x) \in \mathbf{dom}\,\psi\}.$$

Show that $\Gamma$ is linear-fractional, and that the matrix associated with it is the product

$$\begin{bmatrix} E & f \\ g^T & h \end{bmatrix} \begin{bmatrix} A & b \\ c^T & d \end{bmatrix}.$$

**2.4** *Dual of exponential cone.* The exponential cone $K_{\exp} \subseteq \mathbf{R}^3$ is defined as

$$K_{\exp} = \{(x, y, z) \mid y > 0, \ ye^{x/y} \le z\}.$$

Find the dual cone $K_{\exp}^*$.

We are not worried here about the fine details of what happens on the boundaries of these cones, so you really needn't worry about it. But we make some comments here for those who do care about such things.

The cone $K_{\exp}$ as defined above is not closed. To obtain its closure, we need to add the points

$$\{(x, y, z) \mid x \le 0, \ y = 0, \ z \ge 0\}.$$

(This makes no difference, since the dual of a cone is equal to the dual of its closure.)

**2.5** *Dual of intersection of cones.* Let $C$ and $D$ be closed convex cones in $\mathbf{R}^n$. In this problem we will show that

$$(C \cap D)^* = C^* + D^*$$

when $C^* + D^*$ is closed. Here, $+$ denotes set addition: $C^* + D^*$ is the set $\{u + v \mid u \in C^*, \ v \in D^*\}$. In other words, the dual of the intersection of two closed convex cones is the sum of the dual cones. (A sufficient condition for of $C^* + D^*$ to be closed is that $C \cap \mathbf{int}\, D \neq \emptyset$. The general statement is that $(C \cap D)^* = \mathbf{cl}(C^* + D^*)$, and that the closure is unnecessary if $C \cap \mathbf{int}\, D \neq \emptyset$, but we won't ask you to show this.)

(a) Show that $C \cap D$ and $C^* + D^*$ are convex cones.

(b) Show that $(C \cap D)^* \supseteq C^* + D^*$.

(c) Now let's show $(C \cap D)^* \subseteq C^* + D^*$ when $C^* + D^*$ is closed. You can do this by first showing

$$(C \cap D)^* \subseteq C^* + D^* \iff C \cap D \supseteq (C^* + D^*)^*.$$

You can use the following result:

If $K$ is a closed convex cone, then $K^{**} = K$.

Next, show that $C \cap D \supseteq (C^* + D^*)^*$ and conclude $(C \cap D)^* = C^* + D^*$.

(d) Show that the dual of the polyhedral cone $V = \{x \mid Ax \succeq 0\}$ can be expressed as

$$V^* = \{A^T v \mid v \succeq 0\}.$$

**2.6** *Polar of a set.* The *polar* of $C \subseteq \mathbf{R}^n$ is defined as the set

$$C^\circ = \{y \in \mathbf{R}^n \mid y^T x \leq 1 \text{ for all } x \in C\}.$$

(a) Show that $C^\circ$ is convex (even if $C$ is not).

(b) What is the polar of a cone?

(c) What is the polar of the unit ball for a norm $\|\cdot\|$?

(d) What is the polar of the set $C = \{x \mid \mathbf{1}^T x = 1, \ x \succeq 0\}$?

(e) Show that if $C$ is closed and convex, with $0 \in C$, then $(C^\circ)^\circ = C$.

**2.7** *Dual cones in $\mathbf{R}^2$.* Describe the dual cone for each of the following cones.

(a) $K = \{0\}$.

(b) $K = \mathbf{R}^2$.

(c) $K = \{(x_1, x_2) \mid |x_1| \leq x_2\}$.

(d) $K = \{(x_1, x_2) \mid x_1 + x_2 = 0\}$.

**2.8** *Convexity of some sets.* Determine if each set below is convex.

(a) $\{(x, y) \in \mathbf{R}^2_{++} \mid x/y \leq 1\}$

(b) $\{(x, y) \in \mathbf{R}^2_{++} \mid x/y \geq 1\}$

(c) $\{(x, y) \in \mathbf{R}_+^2 \mid xy \leq 1\}$

(d) $\{(x, y) \in \mathbf{R}_+^2 \mid xy \geq 1\}$

**2.9** *Correlation matrices.* Determine if the following subsets of $\mathbf{S}^n$ are convex.

(a) the set of correlation matrices, $\mathcal{C}^n = \{C \in \mathbf{S}_+^n \mid C_{ii} = 1, \; i = 1, \ldots, n\}$

(b) the set of nonnegative correlation matrices, $\{C \in \mathcal{C}^n \mid C_{ij} \geq 0, \; i, j = 1, \ldots, n\}$

(c) the set of highly correlated correlation matrices, $\{C \in \mathcal{C}^n \mid C_{ij} \geq 0.8, \; i, j = 1, \ldots, n\}$

**2.10** *Helly's theorem.*

(a) (Radon's theorem) Let $X = \{x_1, \ldots, x_m\}$ be a set of $m$ points in $\mathbf{R}^n$, where $m \geq n + 2$. Show that $X$ can be partitioned in two sets $S$ and $T = X \setminus S$ such that

$$\mathbf{conv} \, S \cap \mathbf{conv} \, T \neq \emptyset.$$

Here $\mathbf{conv} \, S$ and $\mathbf{conv} \, T$ denote the convex hulls of $S$ and $T$.

*Hint.* Since $m \geq n + 2$, the vectors $(x_i, 1)$, $i = 1, \ldots, m$, are linearly dependent. Therefore there exists a nonzero $y$ such that

$$\begin{bmatrix} x_1 & x_2 & \cdots & x_m \\ 1 & 1 & \cdots & 1 \end{bmatrix} \begin{bmatrix} y_1 \\ y_2 \\ \vdots \\ y_m \end{bmatrix} = 0.$$

Use $y$ to define $S$ and $T$, and to construct a point $x \in \mathbf{conv} \, S \cap \mathbf{conv} \, T$.

(b) Use the result in (a) to prove the following. Let $S_1, \ldots, S_m$ be a collection of convex sets in $\mathbf{R}^n$, where $m \geq n + 2$. Suppose the intersection of every $m - 1$ sets from the collection is nonempty, *i.e.*, the set

$$\bigcap_{i \in \{1, \ldots, m\} \setminus \{k\}} S_i = S_1 \cap \cdots \cap S_{k-1} \cap S_{k+1} \cap \cdots \cap S_m$$

is nonempty for each $k = 1, \ldots, m$. Then the intersection of all sets $S_1, \ldots, S_m$ is nonempty:

$$\bigcap_{i=1, \ldots, m} S_i = S_1 \cap \cdots \cap S_m \neq \emptyset.$$

*Hint.* Apply the result in part (a) to $m$ points $x_1, \ldots, x_m$ chosen to satisfy

$$x_k \in \bigcap_{i \in \{1, \ldots, m\} \setminus \{k\}} S_i.$$

The result in (b) is easily rephrased in a more general form, known as Helly's theorem. Let $S_1, \ldots, S_m$ be a collection of $m$ convex sets in $\mathbf{R}^n$. Suppose the intersection of every $k \leq n + 1$ sets from the collection is nonempty. Then the intersection of all sets $S_1, \ldots, S_m$ is nonempty.

**2.11** Define the square $S = \{x \in \mathbf{R}^2 \mid 0 \leq x_i \leq 1, \; i = 1, 2\}$, and the disk $D = \{x \in \mathbf{R}^2 \mid \|x\|_2 \leq 1\}$. Are the following statements true or false?

(a) $S \cap D$ is convex.

(b) $S \cup D$ is convex.

(c) $S \setminus D$ is convex.

**2.12** *Convex and conic hull.* Let $C = \{(1,0), (1,1), (-1,-1), (0,0)\}$. Are the following statements true or false?

(a) $(0,-1/3) \in \mathbf{conv}\, C$.

(b) $(0,1/3) \in \mathbf{conv}\, C$.

(c) $(0,1/3)$ is in the conic hull of $C$.

**2.13** *Minimal and minimum elements.* Consider the set $S = \{(0,2),\ (1,1),\ (2,3),\ (1,2),\ (4,0)\}$. Are the following statements true or false?

(a) $(0,2)$ is the minimum element of $S$.

(b) $(0,2)$ is a minimal element of $S$.

(c) $(2,3)$ is a minimal element of $S$.

(d) $(1,1)$ is a minimal element of $S$.

Here, minimum and minimal are with respect to the nonnegative orthant $K = \mathbf{R}_+^2$.

**2.14** *Affine set.* Show that the set $\{Ax + b \mid Fx = g\}$ is affine. Here $A \in \mathbf{R}^{m \times n}$, $b \in \mathbf{R}^m$, $F \in \mathbf{R}^{p \times n}$, and $g \in \mathbf{R}^p$.

**2.15** Let $S = \{\alpha \in \mathbf{R}^3 \mid \alpha_1 + \alpha_2 e^{-t} + \alpha_3 e^{-2t} \leq 1.1 \text{ for } t \geq 1\}$. Is $S$ affine, a halfspace, a convex cone, a convex set, or none of these? (For each one, you can respond true or false.)

**2.16** *Generalized inequality.* Let $K = \{(x_1, x_2) \mid 0 \leq x_1 \leq x_2\}$. Are the following statements true or false?

(a) $(1,3) \preceq_K (3,4)$.

(b) $(-1,2) \in K^*$.

(c) The unit circle (*i.e.*, $\{x \mid \|x\|_2 = 1\}$) does not contain a minimum element with respect to $K$.

(d) The unit circle does not contain a minimal element with respect to $K$.

# 3  Convex functions

**3.1** *Maximum of a convex function over a polyhedron.* Show that the maximum of a convex function $f$ over the polyhedron $\mathcal{P} = \mathbf{conv}\{v_1, \dots, v_k\}$ is achieved at one of its vertices, *i.e.*,

$$\sup_{x \in \mathcal{P}} f(x) = \max_{i=1,\dots,k} f(v_i).$$

(A stronger statement is: the maximum of a convex function over a closed bounded convex set is achieved at an extreme point, *i.e.*, a point in the set that is not a convex combination of any other points in the set.) *Hint.* Assume the statement is false, and use Jensen's inequality.

**3.2** *A general vector composition rule.* Suppose

$$f(x) = h(g_1(x), g_2(x), \dots, g_k(x))$$

where $h : \mathbf{R}^k \to \mathbf{R}$ is convex, and $g_i : \mathbf{R}^n \to \mathbf{R}$. Suppose that for each $i$, one of the following holds:

- $h$ is nondecreasing in the $i$th argument, and $g_i$ is convex
- $h$ is nonincreasing in the $i$th argument, and $g_i$ is concave
- $g_i$ is affine.

Show that $f$ is convex. This composition rule subsumes all the ones given in the book, and is the one used in software systems that are based on disciplined convex programming (DCP) such as CVX*. You can assume that $\mathbf{dom}\, h = \mathbf{R}^k$; the result also holds in the general case when the monotonicity conditions listed above are imposed on $\tilde{h}$, the extended-valued extension of $h$.

**3.3** *Logarithmic barrier for the second-order cone.* The function $f(x, t) = -\log(t^2 - x^T x)$, with $\mathbf{dom}\, f = \{(x, t) \in \mathbf{R}^n \times \mathbf{R} \mid t > \|x\|_2\}$ (*i.e.*, the interior of the second-order cone), is called the logarithmic barrier function for the second-order cone. There are several ways to show that $f$ is convex, for example by evaluating the Hessian and demonstrating that it is positive semidefinite. In this exercise you establish convexity of $f$ using a relatively painless method, leveraging some composition rules and known convexity of a few other functions.

   (a) Explain why $t - (1/t)u^T u$ is a concave function on $\mathbf{dom}\, f$. *Hint.* Use convexity of the quadratic over linear function.

   (b) From this, show that $-\log(t - (1/t)u^T u)$ is a convex function on $\mathbf{dom}\, f$.

   (c) From this, show that $f$ is convex.

**3.4** *A quadratic-over-linear composition theorem.* Suppose that $f : \mathbf{R}^n \to \mathbf{R}$ is nonnegative and convex, and $g : \mathbf{R}^n \to \mathbf{R}$ is positive and concave. Show that the function $f^2/g$, with domain $\mathbf{dom}\, f \cap \mathbf{dom}\, g$, is convex.

**3.5** *A perspective composition rule* [Maréchal]. Let $f : \mathbf{R}^n \to \mathbf{R}$ be a convex function with $f(0) \leq 0$.

   (a) Show that the perspective $tf(x/t)$, with domain $\{(x, t) \mid t > 0, \ x/t \in \mathbf{dom}\, f\}$, is nonincreasing as a function of $t$.

(b) Let $g$ be concave and positive on its domain. Show that the function

$$h(x) = g(x)f(x/g(x)), \qquad \mathbf{dom}\, h = \{x \in \mathbf{dom}\, g \mid x/g(x) \in \mathbf{dom}\, f\}$$

is convex.

(c) As an example, show that

$$h(x) = \frac{x^T x}{(\prod_{k=1}^n x_k)^{1/n}}, \qquad \mathbf{dom}\, h = \mathbf{R}_{++}^n$$

is convex.

**3.6** *Perspective of log determinant.* Show that $f(X, t) = nt \log t - t \log \det X$, with $\mathbf{dom}\, f = \mathbf{S}_{++}^n \times \mathbf{R}_{++}$, is convex in $(X, t)$. Use this to show that

$$
\begin{aligned}
g(X) &= n(\mathbf{tr}\, X) \log(\mathbf{tr}\, X) - (\mathbf{tr}\, X)(\log \det X) \\
&= n\left(\sum_{i=1}^n \lambda_i\right)\left(\log \sum_{i=1}^n \lambda_i - \sum_{i=1}^n \log \lambda_i\right),
\end{aligned}
$$

where $\lambda_i$ are the eigenvalues of $X$, is convex on $\mathbf{S}_{++}^n$.

**3.7** *Pre-composition with a linear fractional mapping.* Suppose $f : \mathbf{R}^m \to \mathbf{R}$ is convex, and $A \in \mathbf{R}^{m \times n}$, $b \in \mathbf{R}^m$, $c \in \mathbf{R}^n$, and $d \in \mathbf{R}$. Show that $g : \mathbf{R}^n \to \mathbf{R}$, defined by

$$g(x) = (c^T x + d)f((Ax + b)/(c^T x + d)), \qquad \mathbf{dom}\, g = \{x \mid c^T x + d > 0\},$$

is convex.

**3.8** *Scalar valued linear fractional functions.* A function $f : \mathbf{R}^n \to \mathbf{R}$ is called *linear fractional* if it has the form $f(x) = (a^T x + b)/(c^T x + d)$, with $\mathbf{dom}\, f = \{x \mid c^T x + d > 0\}$. When is a linear fractional function convex? When is a linear fractional function quasiconvex?

**3.9** Show that the function

$$f(x) = \frac{\|Ax - b\|_2^2}{1 - x^T x}$$

is convex on $\{x \mid \|x\|_2 < 1\}$.

**3.10** *Weighted geometric mean.* The geometric mean $f(x) = (\prod_k x_k)^{1/n}$ with $\mathbf{dom}\, f = \mathbf{R}_{++}^n$ is concave, as shown on page 74 of the book. Extend the proof to show that

$$f(x) = \prod_{k=1}^n x_k^{\alpha_k}, \qquad \mathbf{dom}\, f = \mathbf{R}_{++}^n$$

is concave, where $\alpha_k$ are nonnegative numbers with $\sum_{k=1}^n \alpha_k \leq 1$.

**3.11** Suppose that $f : \mathbf{R}^n \to \mathbf{R}$ is convex, and define

$$g(x, t) = f(x/t), \qquad \mathbf{dom}\, g = \{(x, t) \mid x/t \in \mathbf{dom}\, f, \ t > 0\}.$$

Show that $g$ is quasiconvex.

**3.12** *Continued fraction function.* Show that the function

$$f(x) = \cfrac{1}{x_1 - \cfrac{1}{x_2 - \cfrac{1}{x_3 - \cfrac{1}{x_4}}}}$$

defined where every denominator is positive, is convex and decreasing. (There is nothing special about $n = 4$ here; the same holds for any number of variables.)

**3.13** *Circularly symmetric Huber function.* The scalar Huber function is defined as

$$f_{\text{hub}}(x) = \begin{cases} (1/2)x^2 & |x| \leq 1 \\ |x| - 1/2 & |x| > 1. \end{cases}$$

This convex function comes up in several applications, including robust estimation. This problem concerns generalizations of the Huber function to $\mathbf{R}^n$. One generalization to $\mathbf{R}^n$ is given by $f_{\text{hub}}(x_1) + \cdots + f_{\text{hub}}(x_n)$, but this function is not circularly symmetric, *i.e.*, invariant under transformation of $x$ by an orthogonal matrix. A generalization to $\mathbf{R}^n$ that *is* circularly symmetric is

$$f_{\text{cshub}}(x) = f_{\text{hub}}(\|x\|) = \begin{cases} (1/2)\|x\|_2^2 & \|x\|_2 \leq 1 \\ \|x\|_2 - 1/2 & \|x\|_2 > 1. \end{cases}$$

(The subscript stands for 'circularly symmetric Huber function'.) Show that $f_{\text{cshub}}$ is convex. Find the conjugate function $f_{\text{cshub}}^*$.

**3.14** *Reverse Jensen inequality.* Suppose $f$ is convex, $\lambda_1 > 0$, $\lambda_i \leq 0$, $i = 2, \ldots, k$, and $\lambda_1 + \cdots + \lambda_n = 1$, and let $x_1, \ldots, x_n \in \mathbf{dom}\, f$. Show that the inequality

$$f(\lambda_1 x_1 + \cdots + \lambda_n x_n) \geq \lambda_1 f(x_1) + \cdots + \lambda_n f(x_n)$$

always holds. *Hints.* Draw a picture for the $n = 2$ case first. For the general case, express $x_1$ as a convex combination of $\lambda_1 x_1 + \cdots + \lambda_n x_n$ and $x_2, \ldots, x_n$, and use Jensen's inequality.

**3.15** *Monotone extension of a convex function.* Suppose $f : \mathbf{R}^n \to \mathbf{R}$ is convex. Recall that a function $h : \mathbf{R}^n \to \mathbf{R}$ is monotone nondecreasing if $h(x) \geq h(y)$ whenever $x \succeq y$. The *monotone extension* of $f$ is defined as

$$g(x) = \inf_{z \succeq 0} f(x + z).$$

(We will assume that $g(x) > -\infty$.) Show that $g$ is convex and monotone nondecreasing, and satisfies $g(x) \leq f(x)$ for all $x$. Show that if $h$ is any other convex function that satisfies these properties, then $h(x) \leq g(x)$ for all $x$. Thus, $g$ is the maximum convex monotone underestimator of $f$.

*Remark.* For simple functions (say, on $\mathbf{R}$) it is easy to work out what $g$ is, given $f$. On $\mathbf{R}^n$, it can be very difficult to work out an explicit expression for $g$. However, systems such as CVX* can immediately handle functions such as $g$, defined by partial minimization.

**3.16** *Circularly symmetric convex functions.* Suppose $f : \mathbf{R}^n \to \mathbf{R}$ is convex and symmetric with respect to orthogonal transformations, *i.e.*, $f(x)$ depends only on $\|x\|_2$. Show that $f$ must have the form $f(x) = \phi(\|x\|_2)$, where $\phi : \mathbf{R} \to \mathbf{R}$ is nondecreasing and convex, with $\mathbf{dom}\, f = \mathbf{R}$. (Conversely, any function of this form is symmetric and convex, so this form characterizes such functions.)

**3.17** *Infimal convolution.* Let $f_1, \ldots, f_m$ be convex functions on $\mathbf{R}^n$. Their *infimal convolution*, denoted $g = f_1 \diamond \cdots \diamond f_m$ (several other notations are also used), is defined as

$$g(x) = \inf\{f_1(x_1) + \cdots + f_m(x_m) \mid x_1 + \cdots + x_m = x\},$$

with the natural domain (*i.e.*, defined by $g(x) < \infty$). In one simple interpretation, $f_i(x_i)$ is the cost for the $i$th firm to produce a mix of products given by $x_i$; $g(x)$ is then the optimal cost obtained if the firms can freely exchange products to produce, all together, the mix given by $x$. (The name 'convolution' presumably comes from the observation that if we replace the sum above with the product, and the infimum above with integration, then we obtain the normal convolution.)

   (a) Show that $g$ is convex.

   (b) Show that $g^* = f_1^* + \cdots + f_m^*$. In other words, the conjugate of the infimal convolution is the sum of the conjugates.

**3.18** *Conjugate of composition of convex and linear function.* Suppose $A \in \mathbf{R}^{m \times n}$ with $\mathbf{rank}\, A = m$, and $g$ is defined as $g(x) = f(Ax)$, where $f : \mathbf{R}^m \to \mathbf{R}$ is convex. Show that

$$g^*(y) = f^*((A^\dagger)^T y), \qquad \mathbf{dom}(g^*) = A^T \mathbf{dom}(f^*),$$

where $A^\dagger = (AA^T)^{-1} A$ is the pseudo-inverse of $A$. (This generalizes the formula given on page 95 for the case when $A$ is square and invertible.)

**3.19** [Roberts and Varberg] Suppose $\lambda_1, \ldots, \lambda_n$ are positive. Show that the function $f : \mathbf{R}^n \to \mathbf{R}$, given by

$$f(x) = \prod_{i=1}^n (1 - e^{-x_i})^{\lambda_i},$$

is concave on

$$\mathbf{dom}\, f = \left\{ x \in \mathbf{R}_{++}^n \;\middle|\; \sum_{i=1}^n \lambda_i e^{-x_i} \leq 1 \right\}.$$

*Hint.* The Hessian is given by

$$\nabla^2 f(x) = f(x)(yy^T - \mathbf{diag}(z))$$

where $y_i = \lambda_i e^{-x_i}/(1 - e^{-x_i})$ and $z_i = y_i/(1 - e^{-x_i})$.

**3.20** Show that the following functions $f : \mathbf{R}^n \to \mathbf{R}$ are convex.

   (a) The difference between the maximum and minimum value of a polynomial on a given interval $[a, b]$, as a function of its coefficients:

$$f(x) = \sup_{t \in [a,b]} p(t) - \inf_{t \in [a,b]} p(t) \quad \text{where} \quad p(t) = x_1 + x_2 t + x_3 t^2 + \cdots + x_n t^{n-1}.$$

(b) The 'exponential barrier' of a set of inequalities:

$$f(x) = \sum_{i=1}^{m} e^{-1/f_i(x)}, \qquad \mathbf{dom}\, f = \{x \mid |f_i(x) < 0,\ i = 1, \ldots, m\}.$$

The functions $f_i$ are convex.

(c) The function

$$f(x) = \inf_{\alpha > 0} \frac{g(y + \alpha x) - g(y)}{\alpha}$$

if $g$ is convex and $y \in \mathbf{dom}\, g$. (It can be shown that this is the directional derivative of $g$ at $y$ in the direction $x$.)

**3.21** *Symmetric convex functions of eigenvalues.* A function $f : \mathbf{R}^n \to \mathbf{R}$ is said to be *symmetric* if it is invariant with respect to a permutation of its arguments, *i.e.*, $f(x) = f(Px)$ for any permutation matrix $P$. An example of a symmetric function is $f(x) = \log(\sum_{k=1}^{n} \exp x_k)$.

In this problem we show that if $f : \mathbf{R}^n \to \mathbf{R}$ is *convex* and *symmetric*, then the function $g : \mathbf{S}^n \to \mathbf{R}$ defined as $g(X) = f(\lambda(X))$ is convex, where $\lambda(X) = (\lambda_1(X),\ \lambda_2(x),\ \ldots,\ \lambda_n(X))$ is the vector of eigenvalues of $X$. This implies, for example, that the function

$$g(X) = \log \mathbf{tr}\, e^X = \log \sum_{k=1}^{n} e^{\lambda_k(X)}$$

is convex on $\mathbf{S}^n$.

(a) A square matrix $S$ is *doubly stochastic* if its elements are nonnegative and all row sums and column sums are equal to one. It can be shown that every doubly stochastic matrix is a convex combination of permutation matrices.

Show that if $f$ is convex and symmetric and $S$ is doubly stochastic, then

$$f(Sx) \le f(x).$$

(b) Let $Y = Q \, \mathbf{diag}(\lambda) Q^T$ be an eigenvalue decomposition of $Y \in \mathbf{S}^n$ with $Q$ orthogonal. Show that the $n \times n$ matrix $S$ with elements $S_{ij} = Q_{ij}^2$ is doubly stochastic and that $\mathbf{diag}(Y) = S\lambda$.

(c) Use the results in parts (a) and (b) to show that if $f$ is convex and symmetric and $X \in \mathbf{S}^n$, then

$$f(\lambda(X)) = \sup_{V \in \mathcal{V}} f(\mathbf{diag}(V^T X V))$$

where $\mathcal{V}$ is the set of $n \times n$ orthogonal matrices. Show that this implies that $f(\lambda(X))$ is convex in $X$.

**3.22** *Convexity of nonsymmetric matrix fractional function.* Consider the function $f : \mathbf{R}^{n \times n} \times \mathbf{R}^n \to \mathbf{R}$, defined by

$$f(X, y) = y^T X^{-1} y, \qquad \mathbf{dom}\, f = \{(X, y) \mid X + X^T \succ 0\}.$$

When this function is restricted to $X \in \mathbf{S}^n$, it is convex.

Is $f$ convex? If so, prove it. If not, give a (simple) counterexample.

**3.23** Show that the following functions $f : \mathbf{R}^n \to \mathbf{R}$ are convex.

(a) $f(x) = -\exp(-g(x))$ where $g : \mathbf{R}^n \to \mathbf{R}$ has a convex domain and satisfies

$$\begin{bmatrix} \nabla^2 g(x) & \nabla g(x) \\ \nabla g(x)^T & 1 \end{bmatrix} \succeq 0$$

for $x \in \mathbf{dom}\, g$.

(b) The function

$$f(x) = \max\{\|APx - b\| \mid P \text{ is a permutation matrix}\}$$

with $A \in \mathbf{R}^{m \times n}$, $b \in \mathbf{R}^m$.

**3.24** *Convex hull of functions.* Suppose $g$ and $h$ are convex functions, bounded below, with $\mathbf{dom}\, g = \mathbf{dom}\, h = \mathbf{R}^n$. The convex hull function of $g$ and $h$ is defined as

$$f(x) = \inf\{\theta g(y) + (1-\theta)h(z) \mid \theta y + (1-\theta)z = x, \ 0 \le \theta \le 1\},$$

where the infimum is over $\theta$, $y$, $z$. Show that the convex hull of $h$ and $g$ is convex. Describe **epi** $f$ in terms of **epi** $g$ and **epi** $h$.

**3.25** Show that a function $f : \mathbf{R} \to \mathbf{R}$ is convex if and only if $\mathbf{dom}\, f$ is convex and

$$\det \begin{bmatrix} 1 & 1 & 1 \\ x & y & z \\ f(x) & f(y) & f(z) \end{bmatrix} \ge 0$$

for all $x$, $y$, $z \in \mathbf{dom}\, f$ with $x < y < z$.

**3.26** *Generalization of the convexity of* $\log \det X^{-1}$. Let $P \in \mathbf{R}^{n \times m}$ have rank $m$. In this problem we show that the function $f : \mathbf{S}^n \to \mathbf{R}$, with $\mathbf{dom}\, f = \mathbf{S}^n_{++}$, and

$$f(X) = \log \det(P^T X^{-1} P)$$

is convex. To prove this, we assume (without loss of generality) that $P$ has the form

$$P = \begin{bmatrix} I \\ 0 \end{bmatrix},$$

where $I$. The matrix $P^T X^{-1} P$ is then the leading $m \times m$ principal submatrix of $X^{-1}$.

(a) Let $Y$ and $Z$ be symmetric matrices with $0 \prec Y \preceq Z$. Show that $\det Y \le \det Z$.

(b) Let $X \in \mathbf{S}^n_{++}$, partitioned as

$$X = \begin{bmatrix} X_{11} & X_{12} \\ X_{12}^T & X_{22} \end{bmatrix},$$

with $X_{11} \in \mathbf{S}^m$. Show that the optimization problem

$$\begin{array}{ll} \text{minimize} & \log \det Y^{-1} \\ \text{subject to} & \begin{bmatrix} Y & 0 \\ 0 & 0 \end{bmatrix} \preceq \begin{bmatrix} X_{11} & X_{12} \\ X_{12}^T & X_{22} \end{bmatrix}, \end{array}$$

13

with variable $Y \in \mathbf{S}^m$, has the solution

$$Y = X_{11} - X_{12}X_{22}^{-1}X_{12}^T.$$

(As usual, we take $\mathbf{S}^m_{++}$ as the domain of $\log \det Y^{-1}$.)

*Hint.* Use the Schur complement characterization of positive definite block matrices (page 651 of the book): if $C \succ 0$ then

$$\begin{bmatrix} A & B \\ B^T & C \end{bmatrix} \succeq 0$$

if and only if $A - BC^{-1}B^T \succeq 0$.

(c) Combine the result in part (b) and the minimization property (page 3-19, lecture notes) to show that the function

$$f(X) = \log \det(X_{11} - X_{12}X_{22}^{-1}X_{12}^T)^{-1},$$

with $\mathbf{dom}\, f = \mathbf{S}^n_{++}$, is convex.

(d) Show that $(X_{11} - X_{12}X_{22}^{-1}X_{12}^T)^{-1}$ is the leading $m \times m$ principal submatrix of $X^{-1}$, *i.e.*,

$$(X_{11} - X_{12}X_{22}^{-1}X_{12}^T)^{-1} = P^T X^{-1} P.$$

Hence, the convex function $f$ defined in part (c) can also be expressed as $f(X) = \log \det(P^T X^{-1} P)$.

*Hint.* Use the formula for the inverse of a symmetric block matrix:

$$\begin{bmatrix} A & B \\ B^T & C \end{bmatrix}^{-1} = \begin{bmatrix} 0 & 0 \\ 0 & C^{-1} \end{bmatrix} + \begin{bmatrix} -I \\ C^{-1}B^T \end{bmatrix} (A - BC^{-1}B^T)^{-1} \begin{bmatrix} -I \\ C^{-1}B^T \end{bmatrix}^T$$

if $C$ and $A - BC^{-1}B^T$ are invertible.

**3.27** *Functions of a random variable with log-concave density.* Suppose the random variable $X$ on $\mathbf{R}^n$ has log-concave density, and let $Y = g(X)$, where $g : \mathbf{R}^n \to \mathbf{R}$. For each of the following statements, either give a counterexample, or show that the statement is true.

(a) If $g$ is affine and not constant, then $Y$ has log-concave density.

(b) If $g$ is convex, then $\mathbf{prob}(Y \le a)$ is a log-concave function of $a$.

(c) If $g$ is concave, then $\mathbf{E}\left((Y - a)_+\right)$ is a convex and log-concave function of $a$. (This quantity is called the tail expectation of $Y$; you can assume it exists. We define $(s)_+$ as $(s)_+ = \max\{s, 0\}$.)

**3.28** *Majorization.* Define $C$ as the set of all permutations of a given $n$-vector $a$, *i.e.*, the set of vectors $(a_{\pi_1}, a_{\pi_2}, \ldots, a_{\pi_n})$ where $(\pi_1, \pi_2, \ldots, \pi_n)$ is one of the $n!$ permutations of $(1, 2, \ldots, n)$.

(a) The support function of $C$ is defined as $S_C(y) = \max_{x \in C} y^T x$. Show that

$$S_C(y) = a_{[1]}y_{[1]} + a_{[2]}y_{[2]} + \cdots + a_{[n]}y_{[n]}.$$

($u_{[1]}$, $u_{[2]}$, ..., $u_{[n]}$ denote the components of an $n$-vector $u$ in nonincreasing order.)

*Hint.* To find the maximum of $y^T x$ over $x \in C$, write the inner product as

$$
\begin{aligned}
y^T x \;=\; & (y_1 - y_2)x_1 + (y_2 - y_3)(x_1 + x_2) + (y_3 - y_4)(x_1 + x_2 + x_3) + \cdots \\
& + (y_{n-1} - y_n)(x_1 + x_2 + \cdots + x_{n-1}) + y_n(x_1 + x_2 + \cdots + x_n)
\end{aligned}
$$

and assume that the components of $y$ are sorted in nonincreasing order.

(b) Show that $x$ satisfies $x^T y \le S_C(y)$ for all $y$ if and only if

$$s_k(x) \le s_k(a), \quad k = 1, \ldots, n-1, \qquad s_n(x) = s_n(a),$$

where $s_k$ denotes the function $s_k(x) = x_{[1]} + x_{[2]} + \cdots + x_{[k]}$. When these inequalities hold, we say the vector $a$ *majorizes* the vector $x$.

(c) Conclude from this that the conjugate of $S_C$ is given by

$$S_C^*(x) = \begin{cases} 0 & \text{if } x \text{ is majorized by } a \\ +\infty & \text{otherwise.} \end{cases}$$

Since $S_C^*$ is the indicator function of the convex hull of $C$, this establishes the following result: $x$ is a convex combination of the permutations of $a$ if and only if $a$ majorizes $x$.

**3.29** *Convexity of products of powers.* This problem concerns the product of powers function $f : \mathbf{R}_{++}^n \to \mathbf{R}$ given by $f(x) = x_1^{\theta_1} \cdots x_n^{\theta_n}$, where $\theta \in \mathbf{R}^n$ is a vector of powers. We are interested in finding values of $\theta$ for which $f$ is convex or concave. You already know a few, for example when $n = 2$ and $\theta = (2, -1)$, $f$ is convex (the quadratic-over-linear function), and when $\theta = (1/n)\mathbf{1}$, $f$ is concave (geometric mean). Of course, if $n = 1$, $f$ is convex when $\theta \ge 1$ or $\theta \le 0$, and concave when $0 \le \theta \le 1$.

Show each of the statements below. We will not read long or complicated proofs, or ones that involve Hessians. We are looking for short, snappy ones, that (where possible) use composition rules, perspective, partial minimization, or other operations, together with known convex or concave functions, such as the ones listed in the previous paragraph. Feel free to use the results of earlier statements in later ones.

(a) When $n = 2$, $\theta \succeq 0$, and $\mathbf{1}^T \theta = 1$, $f$ is concave. (This function is called the weighted geometric mean.)

(b) When $\theta \succeq 0$ and $\mathbf{1}^T \theta = 1$, $f$ is concave. (This is the same as part (a), but here it is for general $n$.)

(c) When $\theta \succeq 0$ and $\mathbf{1}^T \theta \le 1$, $f$ is concave.

(d) When $\theta \preceq 0$, $f$ is convex.

(e) When $\mathbf{1}^T \theta = 1$ and exactly *one* of the elements of $\theta$ is positive, $f$ is convex.

(f) When $\mathbf{1}^T \theta \ge 1$ and exactly *one* of the elements of $\theta$ is positive, $f$ is convex.

*Remark.* Parts (c), (d), and (f) exactly characterize the cases when $f$ is either convex or concave. That is, if none of these conditions on $\theta$ hold, $f$ is neither convex nor concave. Your teaching staff has, however, kindly refrained from asking you to show this.

**3.30** *Huber penalty.* The infimal convolution of two functions $f$ and $g$ on $\mathbf{R}^n$ is defined as

$$h(x) = \inf_y \left( f(y) + g(x - y) \right)$$

(see exercise 3.17). Show that the infimal convolution of $f(x) = \|x\|_1$ and $g(x) = (1/2)\|x\|_2^2$, *i.e.,* the function

$$h(x) = \inf_y \left( f(y) + g(x - y) \right) = \inf_y \left( \|y\|_1 + \frac{1}{2}\|x - y\|_2^2 \right),$$

is the *Huber penalty*

$$h(x) = \sum_{i=1}^{n} \phi(x_i), \qquad \phi(u) = \begin{cases} u^2/2 & |u| \le 1 \\ |u| - 1/2 & |u| > 1. \end{cases}$$

**3.31** Suppose the function $h : \mathbf{R} \to \mathbf{R}$ is convex, nondecreasing, with $\mathbf{dom}\, h = \mathbf{R}$, and $h(t) = h(0)$ for $t \le 0$.

(a) Show that the function $f(x) = h(\|x\|_2)$ is convex on $\mathbf{R}^n$.

(b) Show that the conjugate of $f$ is $f^*(y) = h^*(\|y\|_2)$.

(c) As an example, derive the conjugate of $f(x) = (1/p)\|x\|_2^p$ for $p > 1$, by applying the result of part (b) with the function

$$h(t) = \frac{1}{p} \max\{0, t\}^p = \begin{cases} \frac{1}{p}t^p & t \ge 0 \\ 0 & t < 0. \end{cases}$$

**3.32** *DCP rules.* The function $f(x, y) = -1/(xy)$ with $\mathbf{dom}\, f = \mathbf{R}_{++}^2$ is concave. Briefly explain how to represent it, using disciplined convex programming (DCP), limited to the atoms $1/u$, $\sqrt{uv}$, $\sqrt{v}$, $u^2$, $u^2/v$, addition, subtraction, and scalar multiplication. Justify any statement about the curvature, monotonicity, or other properties of the functions you use. Assume these atoms take their usual domains (*e.g.*, $\sqrt{u}$ has domain $u \ge 0$), and that DCP is sign-sensitive (*e.g.*, $u^2/v$ is increasing in $u$ when $u \ge 0$).

**3.33** *DCP rules.* The function $f(x, y) = \sqrt{1 + x^4/y}$, with $\mathbf{dom}\, f = \mathbf{R} \times \mathbf{R}_{++}$, is convex. Use disciplined convex programming (DCP) to express $f$ so that it is DCP convex. You can use any of the following atoms

    `inv_pos(u)`, which is $1/u$, with domain $\mathbf{R}_{++}$

    `square(u)`, which is $u^2$, with domain $\mathbf{R}$

    `sqrt(u)`, which is $\sqrt{u}$, with domain $\mathbf{R}_+$

    `geo_mean(u,v)`, which is $\sqrt{uv}$, with domain $\mathbf{R}_+^2$

    `quad_over_lin(u,v)`, which is $u^2/v$, with domain $\mathbf{R} \times \mathbf{R}_{++}$

    `norm2(u,v)`, which is $\sqrt{u^2 + v^2}$, with domain $\mathbf{R}^2$.

You may also use addition, subtraction, scalar multiplication, and any constant functions. Assume that DCP is sign-sensitive, *e.g.*, `square(u)` is known to be increasing in $u$ for $u \ge 0$.

**3.34** *Convexity of some sets.* Determine if each set is convex.

(a) $\{P \in \mathbf{R}^{n \times n} \mid x^T P x \ge 0 \text{ for all } x \succeq 0\}$.

(b) $\{(c_0, c_1, c_2) \in \mathbf{R}^3 \mid c_0 = 1, \ |c_0 + c_1 t + c_2 t^2| \le 1 \text{ for all } -1 \le t \le 1\}$.

(c) $\{(u, v) \in \mathbf{R}^2 \mid \cos(u + v) \ge \sqrt{2}/2, \ u^2 + v^2 \le \pi^2/4\}$. *Hint:* $\cos(\pi/4) = \sqrt{2}/2$.

(d) $\{x \in \mathbf{R}^n \mid x^T A^{-1} x \ge 0\}$, where $A \prec 0$.

**3.35** Let $f, g : \mathbf{R}^n \to \mathbf{R}$ and $\phi : \mathbf{R} \to \mathbf{R}$ be given functions. Determine if each statement is true or false.

(a) If $f, g$ are convex, then $h(x, y) = (f(x) + g(y))^2$ is convex.

(b) If $f, \phi$ are convex, differentiable, and $\phi' > 0$, then $\phi(f(x))$ is convex.

(c) If $f, g$ are concave and positive, then $\sqrt{f(x)g(x)}$ is concave.

**3.36** *DCP compliance.* Determine if each expression below is (sign-sensitive) DCP compliant, and if it is, state whether it is affine, convex, or concave.

(a) `sqrt(1 + 4 * square(x) + 16 * square(y))`

(b) `min(x, log(y)) - max(y, z)`

(c) `log(exp(2 * x + 3) + exp(4 * y + 5))`

**3.37** *Curvature of some functions.* Determine the curvature of the functions below. Your responses can be: affine, convex, concave, and none (meaning, neither convex nor concave).

(a) $f(u, v) = uv$, with $\mathbf{dom} f = \mathbf{R}^2$.

(b) $f(x, u, v) = \log(v - x^T x/u)$, with $\mathbf{dom} f = \{(x, u, v) \mid uv > x^T x, \ u > 0\}$.

(c) the 'exponential barrier' for a polyhedron,

$$f(x) = \sum_{i=1}^{m} \exp\left(\frac{1}{b_i - a_i^T x}\right),$$

with $\mathbf{dom} f = \{x \mid a_i^T x < b_i, \ i = 1, \ldots, m\}$, and $a_i \in \mathbf{R}^n$, $b \in \mathbf{R}^m$.

**3.38** *Curvature of some functions.* Determine the curvature of the functions below. Your responses can be: affine, convex, concave, and none (meaning, neither convex nor concave).

(a) $f(x) = \min\{2, x, \sqrt{x}\}$, with $\mathbf{dom} f = \mathbf{R}_+$

(b) $f(x) = x^3$, with $\mathbf{dom} f = \mathbf{R}$

(c) $f(x) = x^3$, with $\mathbf{dom} f = \mathbf{R}_{++}$

(d) $f(x, y) = \sqrt{x \min\{y, 2\}}$, with $\mathbf{dom} f = \mathbf{R}_+^2$

(e) $f(x, y) = (\sqrt{x} + \sqrt{y})^2$, with $\mathbf{dom} f = \mathbf{R}_+^2$

(f) $f(\theta) = \log \det \theta - \mathbf{tr}(S\theta)$, with $\mathbf{dom} f = \mathbf{S}_{++}^n$, and where $S \succ 0$

**3.39** *Convexity of some sets.* Determine if each set below is convex.

(a) $\{(x, y) \in \mathbf{R}_{++}^2 \mid x/y \le 1\}$

(b) $\{(x, y) \in \mathbf{R}_{++}^2 \mid x/y \ge 1\}$

(c) $\{(x, y) \in \mathbf{R}_+^2 \mid xy \le 1\}$

(d) $\{(x, y) \in \mathbf{R}_+^2 \mid xy \ge 1\}$

**3.40** *Correlation matrices.* Determine if the following subsets of $\mathbf{S}^n$ are convex.

(a) the set of correlation matrices, $\mathcal{C}^n = \{C \in \mathbf{S}_+^n \mid C_{ii} = 1, \ i = 1, \ldots, n\}$

(b) the set of nonnegative correlation matrices, $\{C \in \mathcal{C}^n \mid C_{ij} \ge 0, \ i, j = 1, \ldots, n\}$

(c) the set of volume-constrained correlation matrices, $\{C \in \mathcal{C}^n \mid \det C \geq (1/2)^n\}$

(d) the set of highly correlated correlation matrices, $\{C \in \mathcal{C}^n \mid C_{ij} \geq 0.8, \ i,j = 1, \ldots, n\}$

**3.41** *CDF of the maximum of a vector random variable with log-concave density.* Let $X$ be an $\mathbf{R}^n$-valued random variable, with log-concave probability density function $p$. Define the scalar random variable $Y = \max_i X_i$, which has cumulative distribution function $\phi(a) = \mathbf{prob}(Y \leq a)$. Determine whether $\phi$ must be a log-concave function, given only the assumptions above. If it must be log-concave, give a brief justification. Otherwise, provide a (very) simple counterexample. (We will deduct points for overly complicated solutions.) *Please note.* The coordinates $X_i$ need not be independent random variables.

**3.42** *Fuel use as function of distance and speed.* A vehicle uses fuel at a rate $f(s)$, which is a function of the vehicle speed $s$. We assume that $f : \mathbf{R} \to \mathbf{R}$ is a positive increasing convex function, with $\mathbf{dom}\, f = \mathbf{R}_+$. The physical units of $s$ are m/s (meters per second), and the physical units of $f(s)$ are kg/s (kilograms per second).

(a) Let $g(d,t)$ be the total fuel used (in kg) when the vehicle moves a distance $d \geq 0$ (in meters) in time $t > 0$ (in seconds) at a constant speed. Show that $g$ is convex.

(b) Let $h(d)$ be the minimum fuel used (in kg) to move a distance $d$ (in m) at a constant speed $s$ (in m/s). Show that $h$ is convex.

**3.43** *Inverse of product.* The function $f(x,y) = 1/(xy)$ with $x, y \in \mathbf{R}$, $\mathbf{dom}\, f = \mathbf{R}_{++}^2$, is convex. How do we represent it using disciplined convex programming (DCP), and the functions $1/u$, $\sqrt{uv}$, $\sqrt{u}$, $u^2$, $u^2/v$, addition, subtraction, and scalar multiplication? (These functions have the obvious domains, and you can assume a sign-sensitive version of DCP, *e.g.*, $u^2/v$ increasing in $u$ for $u \geq 0$.) *Hint.* There are several ways to represent $f$ using the atoms given above.

**3.44** Let $h : \mathbf{R}^n \to \mathbf{R}$ be a convex function, nondecreasing in each of its $n$ arguments, and with domain $\mathbf{R}^n$.

(a) Show that the function $f(x) = h(|x_1|, \ldots, |x_n|)$ is convex.

(b) Suppose $h$ has the property that $h(u) = h((u_1)_+, \ldots, (u_n)_+)$ for all $u$, where $(u_k)_+ = \max\{u_k, 0\}$. Show that the conjugate of $f(x) = h(|x_1|, \ldots, |x_n|)$ is

$$f^*(y) = h^*(|y_1|, \ldots, |y_n|).$$

(c) As an example, take $n = 1$, $h(u) = \exp(u)_+$, and $f(x) = \exp|x|$. Find the conjugates of $h$ and $f$, and verify that $f^*(y) = h^*(|y|)$.

**3.45** *Curvature of some functions.* Determine the curvature of the functions below, among the choices convex, concave, affine, or none (meaning, neither convex nor concave).

(a) $f(x) = \min\{2, x, \sqrt{x}\}$, with $\mathbf{dom}\, f = \mathbf{R}_+$

(b) $f(x) = x^3$, with $\mathbf{dom}\, f = \mathbf{R}$

(c) $f(x) = x^3$, with $\mathbf{dom}\, f = \mathbf{R}_{++}$

(d) $f(x,y) = \sqrt{x \min\{y, 2\}}$, with $\mathbf{dom}\, f = \mathbf{R}_+^2$

(e) $f(x,y) = (\sqrt{x} + \sqrt{y})^2$, with $\mathbf{dom}\, f = \mathbf{R}_+^2$

(f) $f(x) = \int_0^x g(t)\,dt$, with $\mathbf{dom}\,g = \mathbf{R}_+$, and $g : \mathbf{R} \to \mathbf{R}$ is decreasing

**3.46** *Curvature of some order statistics.* For $x \in \mathbf{R}^n$, with $n > 1$, $x_{[k]}$ denotes the $k$th largest entry of $x$, for $k = 1, \ldots, n$, so, for example, $x_{[1]} = \max_{i=1,\ldots,n} x_i$ and $x_{[n]} = \min_{i=1,\ldots,n} x_i$. Functions that depend on these sorted values are called order statistics or order functions. Determine the curvature of the order statistics below, from the choices convex, concave, or neither. For each function, explain why the function has the curvature you claim. If you say it is neither convex nor concave, give a counterexample showing it is not convex, and a counterexample showing it is not concave. All functions below have domain $\mathbf{R}^n$.

(a) $\mathrm{median}(x) = x_{[(n+1)/2]}$. (You can assume that $n$ is odd.)

(b) The range of values, $x_{[1]} - x_{[n]}$.

(c) The midpoint of the range, $(x_{[1]} + x_{[n]})/2$.

(d) Interquartile range, defined as $x_{[n/4]} - x_{[3n/4]}$. (You can assume that $n/4$ is an integer.)

(e) Symmetric trimmed mean, defined as

$$\frac{x_{[n/10]} + x_{[n/10+1]} + \cdots + x_{[9n/10]}}{0.8n + 1},$$

the mean of the values between the 10th and 90th percentiles. (You can assume that $n/10$ is an integer.)

(f) Lower trimmed mean, defined as

$$\frac{x_{[1]} + x_{[2]} + \cdots + x_{[9n/10]}}{0.9n + 1},$$

the mean of the entries, excluding the bottom decile. (You can assume that $n/10$ is an integer.)

*Remark.* For the functions defined in (d)–(f), you might find slightly different definitions in the literature. Please use the formulas above to answer each question.

**3.47** *A composition rule for log-log convex functions.* A function $f : \mathbf{R}_{++}^n \to \mathbf{R}_{++}$ is called *log-log convex* if $F(u) = \log f(e^u)$ is convex, where the exponentiation is applied elementwise. Similarly, $f$ is log-log concave if $F$ is concave, and it is log-log affine if $F$ is affine. For example, posynomials are log-log convex and monomials are log-log affine.

It turns that log-log convex functions obey a composition rule, analogous to the one for convex functions. Suppose

$$f(x) = h(g_1(x), g_2(x), \ldots, g_k(x)),$$

where $h : \mathbf{R}_{++}^k \to \mathbf{R}_{++}$ is log-log convex, and $g_i : \mathbf{R}_{++}^n \to \mathbf{R}_{++}$. Suppose that for each $i$, one of the following holds:

- $h$ is nondecreasing in the $i$th argument, and $g_i$ is log-log convex,
- $h$ is nonincreasing in the $i$th argument, and $g_i$ is log-log concave,
- $g_i$ is log-log affine.

Show that $f$ is log-log convex. (This composition rule is the basis of *disciplined geometric programming*, which is implemented in CVXPY.)

**3.48** Explain why the following functions are convex. In each problem, $x$ is an $n$-vector.

    (a) $f(x) = \cosh(\|x\|)$ where $\cosh(u) = (\exp(u) + \exp(-u))/2$ and $\|\cdot\|$ is a norm on $\mathbf{R}^n$.

    (b) $f(x) = (x^T A x)/g(x)$, where $A$ is positive definite, and $g$ is concave and positive on $\mathbf{dom}\, g$.

    (c) $f(x) = \inf\{\|y\|_1 \mid Ay = x\}$, where $A$ is an $n \times m$ matrix.

**3.49** *Symmetric convex matrix functions.* We call a function $f : \mathbf{R}^n \to \mathbf{R}$ *symmetric* if $f(x) = f(Px)$ for all permutation matrices $P$, *i.e.*, matrices $P$ that satisfy $P \in \{0,1\}^{n \times n}$, $P\mathbf{1} = \mathbf{1}$, and $P^T\mathbf{1} = \mathbf{1}$. We call a function $f : \mathbf{S}^n \to \mathbf{R}$ *unitarily invariant* if for all orthogonal $Q \in \mathbf{R}^{n \times n}$, *i.e.*, $Q^T Q = I$, we have $f(X) = f(QXQ^T)$. For a matrix $X \in \mathbf{S}^n$, let $\lambda(X) \in \mathbf{R}^n$ be the vector of its eigenvalues. In this exercise you will prove the following result: if $F : \mathbf{S}^n \to \mathbf{R}$ is convex and unitarily invariant, there is a symmetric $f : \mathbf{R}^n \to \mathbf{R}$ such that $F(X) = f(\lambda(X))$. Conversely, if $f : \mathbf{R}^n \to \mathbf{R}$ is symmetric and convex, then the function $F(X) = f(\lambda(X))$ is convex and unitarily invariant. (See also Exercise 3.21 for a different proof.)

    (a) Show that $F : \mathbf{S}^n \to \mathbf{R}$ is unitarily invariant if and only if there exists a symmetric $f : \mathbf{R}^n \to \mathbf{R}$ such that $F(X) = f(\lambda(X))$.

    (b) For any symmetric function $g : \mathbf{R}^n \to \mathbf{R}$, define the matricization $g_{\mathrm{sy}}(X) = g(\lambda(X))$. Let $f : \mathbf{R}^n \to \mathbf{R}$ be convex and symmetric. Use the result of Exercise 12.3 (Von Neumann's trace inequality) to show that the convex conjugate of $f_{\mathrm{sy}}$ is the matricization of $f^*$, that is,

$$f_{\mathrm{sy}}^*(Y) = \sup_X \{\mathbf{tr}(XY) - f_{\mathrm{sy}}(X) \mid X \in \mathbf{S}^n\} = (f^*)_{\mathrm{sy}}(Y).$$

    (c) Use the result of exercise 3.39(d) in the book to show that if $f : \mathbf{R}^n \to \mathbf{R}$ is closed convex and symmetric, then $f_{\mathrm{sy}}(X) = f(\lambda(X))$ is also closed convex and unitarily invariant.

    (d) Show that if $F : \mathbf{S}^n \to \mathbf{R}$ is closed convex and unitarily invariant, then $F(X) = f(\lambda(X))$ for some symmetric convex $f$. *Hint.* This is the easy part. Consider diagonal matrices.

    (e) A *subgradient* of a convex function $f : \mathbf{R}^n \to \mathbf{R}$ at the point $x \in \mathbf{dom}\, f$ is a vector $g \in \mathbf{R}^n$ such that $f(y) \geq f(x) + g^T(y - x)$ for all $y \in \mathbf{R}^n$. Show that if $f$ is symmetric and convex, then

$$f_{\mathrm{sy}}(Y) \geq f_{\mathrm{sy}}(X) + \mathbf{tr}(G(Y - X))$$

for all matrices $G \in \mathbf{S}^n$ of the form $G = U\,\mathbf{diag}(g)U^T$, where $g \in \partial f(x)$ and $X = U\,\mathbf{diag}(x)U^T$. That is, the subgradients of $f$ determine the subgradients of $f_{\mathrm{sy}}$.

**3.50** *Functions of the eigenvalues of symmetric matrices.* Use the results of exercise 3.21 or 3.49 to give one-line proofs of the following.

    (a) The maximum eigenvalue $\lambda_1(X)$ is convex in $X \in \mathbf{S}^n$.

    (b) The minimum eigenvalue $\lambda_n(X)$ is concave in $X \in \mathbf{S}^n$.

    (c) The trace inverse $\mathbf{tr}(X^{-1})$ is convex on $\mathbf{S}_{++}^n$.

    (d) The geometric mean $(\det X)^{1/n}$ is concave on $\mathbf{S}_{++}^n$. (See page 74 of the book.)

    (e) The log determinant $\log \det X$ is concave on $\mathbf{S}_{++}^n$.

    (f) The sum of the $k$-largest eigenvalues $\sum_{i=1}^k \lambda_i(X)$ is convex in $X \in \mathbf{S}^n$.

(g) All Ky-Fan $p$-norms, defined by the usual $p \geq 1$-norm on the eigenvalues $\|X\| = \|\lambda(X)\|_p$, are convex in $X$.

**3.51** Prove that the following functions are convex.

(a) The function $f : \mathbf{R}^n \to \mathbf{R}$ defined by

$$f(x) = -(\sqrt{x_1} + \cdots + \sqrt{x_n})^2, \qquad \mathbf{dom}\, f = \mathbf{R}^n_{++}.$$

(b) The function $f : \mathbf{S}^n \to \mathbf{R}$ defined by

$$f(X) = \log(a^T X^{-1} a), \qquad \mathbf{dom}\, f = \mathbf{S}^n_{++},$$

where $a$ is a nonzero $n$-vector.

*Hint.* Show that $f(X)$ is the optimal value of the following optimization problem with scalar variable $y$:

$$
\begin{array}{ll}
\text{minimize} & -\log y \\
\text{subject to} & yaa^T \preceq X.
\end{array}
$$

(c) The function $f : \mathbf{S}^n \to \mathbf{R}$ defined by

$$f(X) = \frac{\lambda_1(X)^{\alpha+1}}{\lambda_n(X)^\alpha}, \qquad \mathbf{dom}\, f = \mathbf{S}^n_{++},$$

for $\alpha \geq 0$, where $\lambda_1(X)$ is the largest eigenvalue of $X$ and $\lambda_n(X)$ the smallest eigenvalue.

*Hint.* Show that the epigraph of $f$ is a convex set. Note that $f(X) \leq t$ if and only if $X \succ 0$, $t > 0$, and $\lambda_1(X)^{\alpha+1}/t \leq \lambda_n(X)^\alpha$.

**3.52** *Functions of a log-concave scalar random variable.* Suppose the random variable $X$ defined on $\mathbf{R}_+$ has a log-concave and decreasing density $p_X$.

(a) *Square root.* Let $Y = \sqrt{X}$. Does $Y$ have a log-concave density? Either show that it does, or give a counterexample, *i.e.*, a specific log-concave decreasing density for $X$ for which the density of $Y$ is not log-concave.

(b) *Square.* Let $Z = X^2$. Does $Z$ have a log-concave density? Either show that it does, or give a counterexample, *i.e.*, a specific log-concave decreasing density for $X$ for which the density of $Z$ is not log-concave.

**3.53** *Curvature of functions.* Are the following functions affine, convex, concave, quasi-convex, quasi-linear, or none of these?

(a) $f(x) = \max(1/2, x, x^2)$.

(b) $f(x) = \min(1/2, x, x^2)$.

**3.54** *Square and reciprocal of convex and concave functions.* For each of the following, determine if the function $f$ is convex, concave, or neither.

(a) $f(x) = g(x)^2$, where $g$ is convex and nonnegative.

(b) $f(x) = 1/g(x)$, where $g$ is concave and positive.

**3.55** State whether each of the following statements is true or false.

    (a) $f(x) = (x^2 + 2)/(x + 2)$, with $\mathbf{dom}\, f = (-\infty, -2)$ is convex.

    (b) $f(x) = 1/(1 - x^2)$, with $\mathbf{dom} f = (-1, 1)$ is convex.

    (c) $f(x) = 1/(1 - x^2)$, with $\mathbf{dom} f = (-1, 1)$ is log-convex.

    (d) $f(x) = \cosh x = (e^x + e^{-x})/2$ is convex.

    (e) $f(x) = \cosh x$ is log-concave.

    (f) $f(x) = \cosh x$ is log-convex.

**3.56** For $x \in \mathbf{R}^n$, we define $f(x) = \min\{k \mid \sum_{i=1}^k |x_i| > 1\}$, with $f(x) = \infty$ if $\sum_{i=1}^n |x_i| \leq 1$. Is $f$ quasiconvex, quasiconcave, both, or neither?

**3.57** *Conjugate of the positive part function.* Let $f(x) = (x)_+ = \max\{0, x\}$ for $x \in \mathbf{R}$. (This function has various names, such as the positive part of $x$, or ReLU for Rectified Linear Unit in the context of neural networks.) What is $f^*$?

**3.58** *Leverage limit.* Let $w \in \mathbf{R}^n$, with $\mathbf{1}^T w = 1$, denote the set of weights for a portfolio of $n$ investments, with $w_i$ the fraction of the total portfolio value (assumed to be positive) invested in asset $i$. When $w_i < 0$, it means we hold a short position in asset $i$; when $w_i > 0$, we hold a long position in asset $i$. (You do not need to know what these mean.)

The total long weight and total short weight are defined as

$$L = \mathbf{1}^T(w)_+ = \sum_{i=1}^n \max\{0, w_i\}, \qquad S = \mathbf{1}^T(w)_- = \sum_{i=1}^n \max\{0, -w_i\},$$

respectively. As a common example, a portfolio with weights $w$ with $L(w) = 1.3$ and $S(w) = 0.3$ is called a 130–30 portfolio.

A *leverage limit* is a constraint of the form $S \leq \eta L$, where $\eta \in [0, 1)$ is a parameter. Is a leverage limit constraint convex (*i.e.*, is the set of weights that satisfy it convex)? If so, explain. If not, give a specific counterexample. *Hint.* $L - S = 1$.

**3.59** *Distances between probability distributions on a finite set.* We describe a probability distribution on $n$ outcomes as a vector $p \in \mathbf{R}_+^n$ with $\mathbf{1}^T p = 1$, with $p_i$ the probability of event $i$, for $i = 1, \ldots, n$. Suppose $p$ and $q$ are two such probability distributions. There are several ways to define a distance or deviation $d(p, q)$ between $p$ and $q$. Show that each of the metrics below is a convex function of $(p, q)$.

    (a) *Max difference in probability.* We take

$$d^{\mathrm{mp}}(p, q) = \max\{|\,\mathbf{prob}(S; p) - \mathbf{prob}(S; q)| \mid S \subseteq \{1, \ldots, n\}\},$$

    where $\mathbf{prob}(S; p)$ is the probability of the event $S$ under the distribution $p$, *i.e.*, $\mathbf{prob}(S; p) = \sum_{i \in S} p_i$. Since there are $2^n$ subsets of $\{1, \ldots, n\}$, the maximum sbove is over $2^n$ numbers. In words, $d^{\mathrm{mp}}(p, q)$ is the maximum difference in probability assigned to any set of outcomes by the distributions $p$ and $q$.

    In addition to showing that $d^{\mathrm{mp}}$ is convex, express it in a simple explicit form involving $\|p - q\|_1$.

(b) *Hellinger distance.* The Hellinger distance is defined as

$$d^{\text{he}}(p, q) = \sum_{i=1}^{n} (\sqrt{p_i} - \sqrt{q_i})^2.$$

*Remark.* There are many others, for example the usual $\ell_2$-norm $\|p - q\|_2$ or the Kullback-Leibler divergence

$$d^{\text{kl}}(p, q) = \sum_{i=1}^{n} p_i \log(p_i/q_i),$$

which are also convex in $(p, q)$. (See *Convex Optimization*, Example 3.19.)

**3.60** *Cube of convex and concave functions.* For each of the following, determine if the function $f$ is convex, concave, or neither. 'Convex' means that $f$ must be convex, with no further assumptions.

(a) $f(x) = g(x)^3$, where $g$ is convex and nonnegative on its domain.

(b) $f(x) = g(x)^3$, where $g$ is concave and nonnegative on its domain.

(c) $f(x) = g(x)^3$, where $g$ is convex and nonpositive on its domain.

(d) $f(x) = g(x)^3$, where $g$ is concave and nonpositive on its domain.

**3.61** *Fractional or relative error.* The fractional or relative error between two positive numbers $u, v$ is defined as

$$E(u, v) = \frac{|u - v|}{\min\{u, v\}}.$$

Are the statements below true or false?

(a) $E$ is a convex function of $(u, v)$.

(b) $E$ is a quasiconvex function of $(u, v)$.

(c) $E$ is a convex function of $u$, for fixed $v$.

**3.62** *Some functions of graph weights.* Consider a connected weighted graph $\mathcal{G} = (\mathcal{V}, \mathcal{E})$, with weights $w_e \in \mathbf{R}_+$ for $e \in \mathcal{E}$.

(a) *Distance between two sets of vertices.* Let $S \subset \mathcal{E}$, $T \subset \mathcal{E}$ be disjoint sets of vertices. The distance between $S$ and $T$, denoted $\mathbf{dist}(S, T)$ is defined as the minimum of the sum of edge weights over any path that starts in $S$ and ends in $T$.

Considered as a function of edge weights $w \in \mathbf{R}_+^{|\mathcal{E}|}$, is $\mathbf{dist}(S, T)$ convex, concave, or neither of these?

(b) *Optimal value of traveling salesman problem.* A tour is a path that includes each vertex in the graph exactly once. The traveling salesman problem is to find a tour that minimizes total edge weight along the tour. Its optimal value, denoted $\mathcal{T}^\star$, is the minimum of the total edge weight among all tours.

Considered as a function of edge weights $w \in \mathbf{R}_+^{|\mathcal{E}|}$, is $\mathcal{T}^\star$ convex, concave, or neither of these?

Justify your response.

**3.63** *Perspective of the perspective.* In this exercise we explore what happens when you take the perspective of a convex function twice. Suppose $f : \mathbf{R}^n \to \mathbf{R}$ is convex. Let $g : \mathbf{R}^n \times \mathbf{R}_{++} \to \mathbf{R}$ be its perspective function, which is also convex. Let $h : \mathbf{R}^n \times \mathbf{R}_{++} \times \mathbf{R}_{++} \to \mathbf{R}$ be the perspective function of $g$, which is also convex. What can you say about $h$? Be as specific as you can be. For example, is $h$ related to $f$ or $g$ in some simple way?

**3.64** *Tail bounds for log-concave densities.* When $X \sim \mathcal{N}(0, 1)$ and $a > 0$, a well-known upper bound on $\mathbf{prob}(X \geq a)$ is $\mathbf{prob}(X \geq a) \leq \varphi(a)/a$, where $\varphi$ is the Gaussian density. In this exercise we explore a generalization of this bound to vector random variables and non-Gaussian, but log-concave, distributions.

Let $X \in \mathbf{R}^n$ be a random variable with log-concave differentiable probability density function $p : \mathbf{R}^n \to \mathbf{R}_+$. We can express $p$ as $p(x) = \exp(-\psi(x))$, where $\psi : \mathbf{R}^n \to \mathbf{R}$ is convex and differentiable.

(a) *Tail bound.* Suppose that $\nabla p(a) \prec 0$ (which is the same as $\nabla \psi(a) \succ 0$). Show that

$$\mathbf{prob}(X \succeq a) \leq p(a) \left( \prod_{i=1}^{n} (\nabla \psi(a))_i \right)^{-1}.$$

We expect a solution based on ideas from this course, without reference to other tail bounds you might know about. *Remark.* When $X \sim \mathcal{N}(0, 1)$, this recovers the well-known tail bound mentioned above.

*Hints.*

- Start with a basic inequality involving $\psi(x)$, $\psi(a)$, and $\nabla \psi(a)$, and from this obtain an upper bound on $p(x)$.
- Recall that $\int_{x \succeq a} f_1(x_1) \cdots f_n(x_n) \, dx = \prod_{i=1}^{n} \int_{x_i \geq a_i} f_i(x_i) \, dx_i$.

(b) Evaluate the upper bound for the specific case $n = 2$, $X \sim \mathcal{N}(0, \Sigma)$, with

$$\Sigma = \begin{bmatrix} 1 & \rho \\ \rho & 1 \end{bmatrix}, \qquad \rho = 0.5, \qquad a = (3, 3).$$

We estimated $\mathbf{prob}(X \succeq a)$ (using a Monte Carlo method) as $8.2 \times 10^{-5}$; compare this to the upper bound.

**3.65** *Convex function of a random vector with log-concave density.* Let $X$ be a random variable on $\mathbf{R}^n$ with log-concave density $p$. Let $Y = f(X)$, where $f : \mathbf{R}^n \to \mathbf{R}$ is convex. The CDF of $Y$ is $F(a) = \mathbf{prob}(Y \leq a)$.

Is $F$ log-concave (with no further assumptions)? If yes, give a justification. If no, give a *simple and specific* counterexample.

**3.66** *Gumbel distribution.* The (standard) Gumbel distribution on $\mathbf{R}$ has density

$$p(x) = \exp(-x - \exp(-x)).$$

Is $p$ log-concave? That is, does the Gumbel distribution have log-concave density?

**3.67** *Square of sum of squareroots.* You know that the squareroot of the sum of squares of the entries of a vector is a convex function, its Euclidean norm. Here we consider a similar function, with the roles reversed: The square of the sum of the squareroots,

$$f(x) = (\sqrt{x_1} + \cdots + \sqrt{x_n})^2, \quad \mathbf{dom}\, f = \mathbf{R}_+^n.$$

Is $f$ convex, concave, or neither?

Briefly justify your response.

**3.68** *Some functions of the values of a probability distribution.* Let $x$ be a real-valued random variable with $\mathbf{prob}(x = a_i) = p_i$, $i = 1,\ldots,n$, where $p \succeq 0$, $\mathbf{1}^T p = 1$ is the given vector of probabilities. Below we give several functions of $a \in \mathbf{R}^n$, the values that the random variable takes. Is each of these functions convex, concave, affine, or neither? For each function, choose one of these. (If you select affine, this means you think the function is both convex and concave.)

*Note.* In this problem we consider $p$ as given, and the quantities below as functions of $a$. In some homework problems, you considered the opposite, where $a$ was given and we considered $p$ as the variable.

(a) *Mean.* $\mathbf{E}\, x$.
(b) *Second moment.* $\mathbf{E}\, x^2$.
(c) *Third moment.* $\mathbf{E}\, x^3$.
(d) *Variance.* $\mathbf{var}(x) = \mathbf{E}(x - \mathbf{E}\, x)^2$.

**3.69** *Conjugate of pinball loss function.* The *pinball loss function* $f : \mathbf{R} \to \mathbf{R}$ has the form

$$f(x) = \begin{cases} -ax & x \le 0 \\ (1-a)x & x > 0, \end{cases}$$

where $a \in [0,1]$ is a parameter. (The pinball loss is used for quantile regression, but that's not relevant for this problem.)

What is the conjugate of the pinball loss? That is, what is $f^*(y)$? Be sure to specify its domain if it is not all of $\mathbf{R}$.

**3.70** *Minimum fuel regulation cost.* Consider the linear dynamical system

$$x_{t+1} = Ax_t + Bu_t, \quad t = 1,\ldots,T-1,$$

where $x_t \in \mathbf{R}^n$ is the state and $u_t \in \mathbf{R}^m$ is the input at time $t$, and the matrices $A$ and $B$ are given. Consider the function $\phi : \mathbf{R}^n \to \mathbf{R}$, where $\phi(z)$ is the optimal value of the problem

$$\begin{array}{ll} \text{minimize} & \|u_1\|_1 + \cdots + \|u_{T-1}\|_1 \\ \text{subject to} & x_{t+1} = Ax_t + Bu_t, \quad t = 1,\ldots,T-1 \\ & x_1 = z, \quad x_T = 0, \end{array}$$

with variables $x_1,\ldots,x_T$ and $u_1,\ldots,u_{T-1}$. This problem is called the minimum fuel regulation problem, since the objective is a basic model of fuel use, and regulation refers to finding a sequence of inputs that results in the state being zero at $t = T$. We will assume that the problem above is feasible for any $z \in \mathbf{R}^n$. Roughly speaking, $\phi(z)$ gives the minimum fuel required to move the state from $x_1 = z$ to $x_T = 0$.

Is $\phi$ convex, concave, affine, or neither?

**3.71** *DCP representation of inverse product.* The function $f(x) = 1/(xy)$, with $\mathbf{dom}\, f = \mathbf{R}^2_{++}$, is convex. CVXPY includes an atom for it, called `inv_prod()`. Here we ask you to implement or express this function using other atoms and of course the DCP rules. The atoms you can use are

```
square, inv_pos, sqrt, quad_over_lin, geo_mean, norm,
pos, max, min, log, exp, log_sum_exp, power,
```

as well as affine operations like sum, difference, matrix multiply, slicing, and stacking. You can assume sign-dependent monotonicity, *e.g.*, `square` is known to be decreasing if its argument is nonpositive.

**3.72** *Coordinate convexity.* Consider a function $f : \mathbf{R}^2 \to \mathbf{R}$. Suppose that for each $x \in \mathbf{R}$, $f(x, y)$ is a convex function of $y$, and for each $y \in \mathbf{R}$, $f(x, y)$ is a convex function of $x$. (You might call such a function coordinate convex.)

Is $f$ convex? If so, give a very brief justification. If not, give a simple counter-example, *i.e.*, a specific function $f$ that satisfies the conditions above, but isn't convex.

**3.73** *Relations among convexity, quasi-convexity, and log-convexity.* Are the following statements true or false? As usual, 'true' means that it holds with no additional assumptions.

(a) If a function is convex, it is also quasi-convex.

(b) If a positive function is convex, it is also log-convex.

(c) If a function is log-convex, then it is also convex.

(d) If a function is log-concave, then it is quasi-concave.

(e) If a function is both quasi-convex and quasi-concave, then it is affine.

(f) The pointwise maximum of quasi-convex functions is quasi-convex.

(g) The pointwise minimum of log-concave functions is log-concave.

# 4 Convex optimization problems

**4.1** *Minimizing a function over the probability simplex.* Find simple necessary and sufficient conditions for $x \in \mathbf{R}^n$ to minimize a differentiable convex function $f$ over the probability simplex $\{x \mid \mathbf{1}^T x = 1, \ x \succeq 0\}$.

**4.2** *'Hello World' in CVX\*.* Use CVX\* to verify the optimal values you obtained (analytically) for exercise 4.1 in *Convex Optimization*.

**4.3** *Formulating constraints in CVX\*.* Below we give several convex constraints on scalar variables $x$, $y$, and $z$. Express each one as a set of valid constraints in CVX\*. (Directly expressing them in CVX\* will lead to invalid constraints.) You can also introduce additional variables, if needed.

Check your reformulations by creating a small problem that includes these constraints, and solving it using CVX\*. Your test problem doesn't have to be feasible; it's enough to verify that CVX\* processes your constraints without error.

    (a) $1/x + 1/y \le 1$, $x \ge 0$, $y \ge 0$.

    (b) $xy \ge 1$, $x \ge 0$, $y \ge 0$.

    (c) $(x+y)^2/\sqrt{y} \le x - y + 5$ (with implicit constraint $y \ge 0$).

    (d) $x + z \le 1 + \sqrt{xy - z^2}$, $x \ge 0$, $y \ge 0$ (with implicit constraint $y > 0$).

**4.4** *Optimal activity levels.* Solve the optimal activity level problem described in exercise 4.17 in *Convex Optimization*, for the instance with problem data

$$
A = \begin{bmatrix} 1 & 2 & 0 & 1 \\ 0 & 0 & 3 & 1 \\ 0 & 3 & 1 & 1 \\ 2 & 1 & 2 & 5 \\ 1 & 0 & 3 & 2 \end{bmatrix}, \quad
c^{\mathrm{max}} = \begin{bmatrix} 100 \\ 100 \\ 100 \\ 100 \\ 100 \end{bmatrix}, \quad
p = \begin{bmatrix} 3 \\ 2 \\ 7 \\ 6 \end{bmatrix}, \quad
p^{\mathrm{disc}} = \begin{bmatrix} 2 \\ 1 \\ 4 \\ 2 \end{bmatrix}, \quad
q = \begin{bmatrix} 4 \\ 10 \\ 5 \\ 10 \end{bmatrix}.
$$

You can do this by forming the LP you found in your solution of exercise 4.17, or more directly, using CVX\*. Give the optimal activity levels, the revenue generated by each one, and the total revenue generated by the optimal solution. Also, give the average price per unit for each activity level, *i.e.*, the ratio of the revenue associated with an activity, to the activity level. (These numbers should be between the basic and discounted prices for each activity.) Give a *very brief* story explaining, or at least commenting on, the solution you find.

**4.5** *Minimizing the ratio of convex and concave piecewise-linear functions.* We consider the problem

$$
\begin{array}{ll}
\text{minimize} & \dfrac{\max_{i=1,\dots,m}(a_i^T x + b_i)}{\min_{i=1,\dots,p}(c_i^T x + d_i)} \\
\text{subject to} & Fx \preceq g,
\end{array}
$$

with variable $x \in \mathbf{R}^n$. We assume that $c_i^T x + d_i > 0$ and $\max_{i=1,\dots,m}(a_i^T x + b_i) \ge 0$ for all $x$ satisfying $Fx \preceq g$, and that the feasible set is nonempty and bounded. This problem is quasiconvex, and can be solved using bisection, with each iteration involving a feasibility LP. Show how the problem can be solved by solving *one* LP, using a trick similar to one described in §4.3.2.

**4.6** *Two problems involving two norms.* We consider the problem

$$\text{minimize} \quad \frac{\|Ax - b\|_1}{1 - \|x\|_\infty}, \tag{1}$$

and the very closely related problem

$$\text{minimize} \quad \frac{\|Ax - b\|_1^2}{1 - \|x\|_\infty}. \tag{2}$$

In both problems, the variable is $x \in \mathbf{R}^n$, and the data are $A \in \mathbf{R}^{m \times n}$ and $b \in \mathbf{R}^m$. Note that the only difference between problem (1) and (2) is the square in the numerator. In both problems, the constraint $\|x\|_\infty < 1$ is implicit. You can assume that $b \notin \mathcal{R}(A)$, in which case the constraint $\|x\|_\infty < 1$ can be replaced with $\|x\|_\infty \leq 1$.

Answer the following two questions, for each of the two problems. (So you will answer four questions all together.)

(a) Is the problem, exactly as stated (and for all problem data), convex? If not, is it quasiconvex? Justify your answer.

(b) Explain how to solve the problem. Your method can involve an SDP solver, an SOCP solver, an LP solver, or any combination. You can include a one-parameter bisection, if necessary. (For example, you can solve the problem by bisection on a parameter, where each iteration consists of solving an SOCP feasibility problem.)

Give the best method you can. In judging best, we use the following rules:

  • *Bisection methods are worse than 'one-shot' methods.* Any method that solves the problem above by solving *one* LP, SOCP, or SDP problem is better than any method that uses a one-parameter bisection. In other words, use a bisection method only if you cannot find a 'one-shot' method.

  • *Use the simplest solver needed to solve the problem.* We consider an LP solver to be simpler than an SOCP solver, which is considered simpler than an SDP solver. Thus, a method that uses an LP solver is better than a method that uses an SOCP solver, which in turn is better than a method that uses an SDP solver.

**4.7** *The illumination problem.* In lecture 1 we encountered the function

$$f(p) = \max_{i=1,\dots,n} |\log a_i^T p - \log I_{\text{des}}|$$

where $a_i \in \mathbf{R}^m$, and $I_{\text{des}} > 0$ are given, and $p \in \mathbf{R}_+^m$.

(a) Show that $\exp f$ is convex on $\{p \mid a_i^T p > 0, \ i = 1, \dots, n \}$.

(b) Show that the constraint 'no more than half of the total power is in any 10 lamps' is convex (*i.e.*, the set of vectors $p$ that satisfy the constraint is convex).

(c) Show that the constraint 'no more than half of the lamps are on' is (in general) *not* convex.

**4.8** *Schur complements and LMI representation.* Recognizing Schur complements (see §A5.5) often helps to represent nonlinear convex constraints as linear matrix inequalities (LMIs). Consider the function

$$f(x) = (Ax + b)^T (P_0 + x_1 P_1 + \cdots + x_n P_n)^{-1}(Ax + b)$$

where $A \in \mathbf{R}^{m \times n}$, $b \in \mathbf{R}^m$, and $P_i = P_i^T \in \mathbf{R}^{m \times m}$, with domain

$$\mathbf{dom}\, f = \{x \in \mathbf{R}^n \mid P_0 + x_1 P_1 + \cdots + x_n P_n \succ 0\}.$$

This is the composition of the matrix fractional function and an affine mapping, and so is convex. Give an LMI representation of **epi** $f$. That is, find a symmetric matrix $F(x,t)$, affine in $(x,t)$, for which

$$x \in \mathbf{dom}\, f, \quad f(x) \leq t \qquad \Longleftrightarrow \qquad F(x,t) \succeq 0.$$

*Remark.* LMI representations, such as the one you found in this exercise, can be directly used in CVX*.

**4.9** *Complex least-norm problem.* We consider the complex least $\ell_p$-norm problem

$$
\begin{array}{ll}
\text{minimize} & \|x\|_p \\
\text{subject to} & Ax = b,
\end{array}
$$

where $A \in \mathbf{C}^{m \times n}$, $b \in \mathbf{C}^m$, and the variable is $x \in \mathbf{C}^n$. Here $\|\cdot\|_p$ denotes the $\ell_p$-norm on $\mathbf{C}^n$, defined as

$$\|x\|_p = \left( \sum_{i=1}^n |x_i|^p \right)^{1/p}$$

for $p \geq 1$, and $\|x\|_\infty = \max_{i=1,\ldots,n} |x_i|$. We assume $A$ is full rank, and $m < n$.

(a) Formulate the complex least $\ell_2$-norm problem as a least $\ell_2$-norm problem with real problem data and variable. *Hint.* Use $z = (\Re x, \Im x) \in \mathbf{R}^{2n}$ as the variable.

(b) Formulate the complex least $\ell_\infty$-norm problem as an SOCP.

(c) Solve a random instance of both problems with $m = 30$ and $n = 100$. To generate the matrix $A$, you can use the Matlab command `A = randn(m,n) + i*randn(m,n)`. Similarly, use `b = randn(m,1) + i*randn(m,1)` to generate the vector $b$. Use the Matlab command `scatter` to plot the optimal solutions of the two problems on the complex plane, and comment (briefly) on what you observe. You can solve the problems using the CVX functions `norm(x,2)` and `norm(x,inf)`, which are overloaded to handle complex arguments. To utilize this feature, you will need to declare variables to be `complex` in the `variable` statement. (In particular, you do not have to manually form or solve the SOCP from part (b).)

**4.10** *Linear programming with random cost vector.* We consider the linear program

$$
\begin{array}{ll}
\text{minimize} & c^T x \\
\text{subject to} & Ax \preceq b.
\end{array}
$$

Here, however, the cost vector $c$ is random, normally distributed with mean $\mathbf{E}\, c = c_0$ and covariance $\mathbf{E}(c - c_0)(c - c_0)^T = \Sigma$. ($A$, $b$, and $x$ are deterministic.) Thus, for a given $x \in \mathbf{R}^n$, the cost $c^T x$ is a (scalar) Gaussian variable.

We can attach several different meanings to the goal 'minimize $c^T x$'; we explore some of these below.

(a) How would you minimize the expected cost $\mathbf{E}\, c^T x$ subject to $Ax \preceq b$?

(b) In general there is a tradeoff between small expected cost and small cost variance. One way to take variance into account is to minimize a linear combination

$$\mathbf{E}\, c^T x + \gamma\, \mathbf{var}(c^T x) \tag{3}$$

of the expected value $\mathbf{E}\, c^T x$ and the variance $\mathbf{var}(c^T x) = \mathbf{E}(c^T x)^2 - (\mathbf{E}\, c^T x)^2$. This is called the 'risk-sensitive cost', and the parameter $\gamma \geq 0$ is called the *risk-aversion parameter*, since it sets the relative values of cost variance and expected value. (For $\gamma > 0$, we are willing to tradeoff an increase in expected cost for a decrease in cost variance.) How would you minimize the risk-sensitive cost? Is this problem a convex optimization problem? Be as specific as you can.

(c) We can also minimize the risk-sensitive cost, but with $\gamma < 0$. This is called 'risk-seeking'. Is this problem a convex optimization problem?

(d) Another way to deal with the randomness in the cost $c^T x$ is to formulate the problem as

$$
\begin{array}{ll}
\text{minimize} & \beta \\
\text{subject to} & \mathbf{prob}(c^T x \geq \beta) \leq \alpha \\
& Ax \preceq b.
\end{array}
$$

Here, $\alpha$ is a fixed parameter, which corresponds roughly to the reliability we require, and might typically have a value of 0.01. Is this problem a convex optimization problem? Be as specific as you can. Can you obtain risk-seeking by choice of $\alpha$? Explain.

**4.11** Formulate the following optimization problems as semidefinite programs. The variable is $x \in \mathbf{R}^n$; $F(x)$ is defined as

$$F(x) = F_0 + x_1 F_1 + x_2 F_2 + \cdots + x_n F_n$$

with $F_i \in \mathbf{S}^m$. The domain of $f$ in each subproblem is $\mathbf{dom}\, f = \{x \in \mathbf{R}^n \mid F(x) \succ 0\}$.

(a) Minimize $f(x) = c^T F(x)^{-1} c$ where $c \in \mathbf{R}^m$.

(b) Minimize $f(x) = \max_{i=1,\dots,K} c_i^T F(x)^{-1} c_i$ where $c_i \in \mathbf{R}^m$, $i = 1, \dots, K$.

(c) Minimize $f(x) = \sup_{\|c\|_2 \leq 1} c^T F(x)^{-1} c$.

(d) Minimize $f(x) = \mathbf{E}(c^T F(x)^{-1} c)$ where $c$ is a random vector with mean $\mathbf{E}\, c = \bar{c}$ and covariance $\mathbf{E}(c - \bar{c})(c - \bar{c})^T = S$.

**4.12** *A matrix fractional function* [Ando]. Show that $X = B^T A^{-1} B$ solves the SDP

$$
\begin{array}{ll}
\text{minimize} & \mathbf{tr}\, X \\
\text{subject to} & \begin{bmatrix} A & B \\ B^T & X \end{bmatrix} \succeq 0,
\end{array}
$$

with variable $X \in \mathbf{S}^n$, where $A \in \mathbf{S}^m_{++}$ and $B \in \mathbf{R}^{m \times n}$ are given.

Conclude that $\mathbf{tr}(B^T A^{-1} B)$ is a convex function of $(A, B)$, for $A$ positive definite.

**4.13** *Trace of harmonic mean of matrices* [Ando]. The matrix $H(A, B) = 2(A^{-1} + B^{-1})^{-1}$ is known as the *harmonic mean* of positive definite matrices $A$ and $B$. Show that $X = (1/2)H(A, B)$ solves the SDP

$$\begin{array}{ll} \text{maximize} & \mathbf{tr}\, X \\ \text{subject to} & \begin{bmatrix} X & X \\ X & X \end{bmatrix} \preceq \begin{bmatrix} A & 0 \\ 0 & B \end{bmatrix}, \end{array}$$

with variable $X \in \mathbf{S}^n$. The matrices $A \in \mathbf{S}^n_{++}$ and $B \in \mathbf{S}^n_{++}$ are given. Conclude that the function $\mathbf{tr}\left((A^{-1} + B^{-1})^{-1}\right)$, with domain $\mathbf{S}^n_{++} \times \mathbf{S}^n_{++}$, is concave.

*Hint.* Verify that the matrix

$$R = \begin{bmatrix} A^{-1} & I \\ B^{-1} & -I \end{bmatrix}$$

is nonsingular. Then apply the congruence transformation defined by $R$ to the two sides of matrix inequality in the SDP, to obtain an equivalent inequality

$$R^T \begin{bmatrix} X & X \\ X & X \end{bmatrix} R \preceq R^T \begin{bmatrix} A & 0 \\ 0 & B \end{bmatrix} R.$$

**4.14** *Trace of geometric mean of matrices* [Ando].

$$G(A, B) = A^{1/2} \left( A^{-1/2} B A^{-1/2} \right)^{1/2} A^{1/2}$$

is known as the *geometric mean* of positive definite matrices $A$ and $B$. Show that $X = G(A, B)$ solves the SDP

$$\begin{array}{ll} \text{maximize} & \mathbf{tr}\, X \\ \text{subject to} & \begin{bmatrix} A & X \\ X & B \end{bmatrix} \succeq 0. \end{array}$$

The variable is $X \in \mathbf{S}^n$. The matrices $A \in \mathbf{S}^n_{++}$ and $B \in \mathbf{S}^n_{++}$ are given.

Conclude that the function $\mathbf{tr}\, G(A, B)$ is concave, for $A$, $B$ positive definite.

*Hint.* The symmetric matrix square root is monotone: if $U$ and $V$ are positive semidefinite with $U \preceq V$ then $U^{1/2} \preceq V^{1/2}$.

**4.15** *Transforming a standard form convex problem to conic form.* In this problem we show that any convex problem can be cast in conic form, provided some technical conditions hold. We start with a standard form convex problem with linear objective (without loss of generality):

$$\begin{array}{ll} \text{minimize} & c^T x \\ \text{subject to} & f_i(x) \leq 0, \quad i = 1, \ldots, m, \\ & Ax = b, \end{array}$$

where $f_i : \mathbf{R}^n \to \mathbf{R}$ are convex, and $x \in \mathbf{R}^n$ is the variable. For simplicity, we will assume that $\mathbf{dom}\, f_i = \mathbf{R}^n$ for each $i$.

Now introduce a new scalar variable $t \in \mathbf{R}$ and form the convex problem

$$\begin{array}{ll} \text{minimize} & c^T x \\ \text{subject to} & tf_i(x/t) \leq 0, \quad i = 1, \ldots, m, \\ & Ax = b, \quad t = 1. \end{array}$$

Define
$$K = \mathbf{cl}\{(x,t) \in \mathbf{R}^{n+1} \mid t f_i(x/t) \le 0, \ i = 1, \dots, m, \ t > 0\}.$$

Then our original problem can be expressed as

$$
\begin{array}{ll}
\text{minimize} & c^T x \\
\text{subject to} & (x,t) \in K, \\
& Ax = b, \quad t = 1.
\end{array}
$$

This is a conic problem when $K$ is proper.

You will relate some properties of the original problem to $K$.

(a) Show that $K$ is a convex cone. (It is closed by definition, since we take the closure.)

(b) Suppose the original problem is strictly feasible, *i.e.*, there exists a point $\bar{x}$ with $f_i(x) < 0$, $i = 1, \dots, m$. (This is called Slater's condition.) Show that $K$ has nonempty interior.

(c) Suppose that the inequalities define a bounded set, *i.e.*, $\{x \mid f_i(x) \le 0, \ i = 1, \dots, m\}$ is bounded. Show that $K$ is pointed.

**4.16** *Exploring nearly optimal points.* An optimization algorithm will find *an* optimal point for a problem, provided the problem is feasible. It is often useful to explore the set of nearly optimal points. When a problem has a 'strong minimum', the set of nearly optimal points is small; all such points are close to the original optimal point found. At the other extreme, a problem can have a 'soft minimum', which means that there are many points, some quite far from the original optimal point found, that are feasible and have nearly optimal objective value. In this problem you will use a typical method to explore the set of nearly optimal points.

We start by finding the optimal value $p^\star$ of the given problem

$$
\begin{array}{ll}
\text{minimize} & f_0(x) \\
\text{subject to} & f_i(x) \le 0, \quad i = 1, \dots, m \\
& h_i(x) = 0, \quad i = 1, \dots, p,
\end{array}
$$

as well as an optimal point $x^\star \in \mathbf{R}^n$. We then pick a small positive number $\epsilon$, and a vector $c \in \mathbf{R}^n$, and solve the problem

$$
\begin{array}{ll}
\text{minimize} & c^T x \\
\text{subject to} & f_i(x) \le 0, \quad i = 1, \dots, m \\
& h_i(x) = 0, \quad i = 1, \dots, p \\
& f_0(x) \le p^\star + \epsilon.
\end{array}
$$

Note that any feasible point for this problem is $\epsilon$-suboptimal for the original problem. Solving this problem multiple times, with different $c$'s, will generate (perhaps different) $\epsilon$-suboptimal points. If the problem has a strong minimum, these points will all be close to each other; if the problem has a weak minimum, they can be quite different.

There are different strategies for choosing $c$ in these experiments. The simplest is to choose the $c$'s randomly; another method is to choose $c$ to have the form $\pm e_i$, for $i = 1, \dots, n$. (This method gives the 'range' of each component of $x$, over the $\epsilon$-suboptimal set.)

You will carry out this method for the following problem, to determine whether it has a strong minimum or a weak minimum. You can generate the vectors $c$ randomly, with enough samples for you to come to your conclusion. You can pick $\epsilon = 0.01p^\star$, which means that we are considering the set of 1% suboptimal points.

The problem is a minimum fuel optimal control problem for a vehicle moving in $\mathbf{R}^2$. The position at time $kh$ is given by $p(k) \in \mathbf{R}^2$, and the velocity by $v(k) \in \mathbf{R}^2$, for $k = 1, \ldots, K$. Here $h > 0$ is the sampling period. These are related by the equations

$$p(k+1) = p(k) + hv(k), \quad v(k+1) = (1-\alpha)v(k) + (h/m)f(k), \quad k = 1, \ldots, K-1,$$

where $f(k) \in \mathbf{R}^2$ is the force applied to the vehicle at time $kh$, $m > 0$ is the vehicle mass, and $\alpha \in (0,1)$ models drag on the vehicle; in the absense of any other force, the vehicle velocity decreases by the factor $1 - \alpha$ in each discretized time interval. (These formulas are approximations of more accurate formulas that involve matrix exponentials.)

The force comes from two thrusters, and from gravity:

$$f(k) = \left[ \begin{array}{c} \cos\theta_1 \\ \sin\theta_1 \end{array} \right] u_1(k) + \left[ \begin{array}{c} \cos\theta_2 \\ \sin\theta_2 \end{array} \right] u_2(k) + \left[ \begin{array}{c} 0 \\ -mg \end{array} \right], \quad k = 1, \ldots, K-1.$$

Here $u_1(k) \in \mathbf{R}$ and $u_2(k) \in \mathbf{R}$ are the (nonnegative) thruster force magnitudes, $\theta_1$ and $\theta_2$ are the directions of the thrust forces, and $g = 10$ is the constant acceleration due to gravity.

The total fuel use is

$$F = \sum_{k=1}^{K-1} (u_1(k) + u_2(k)).$$

(Recall that $u_1(k) \geq 0$, $u_2(k) \geq 0$.)

The problem is to minimize fuel use subject to the initial condition $p(1) = 0$, $v(1) = 0$, and the way-point constraints

$$p(k_i) = w_i, \quad i = 1, \ldots, M.$$

(These state that at the time $hk_i$, the vehicle must pass through the location $w_i \in \mathbf{R}^2$.) In addition, we require that the vehicle should remain in a square operating region,

$$\|p(k)\|_\infty \leq P^{\mathrm{max}}, \quad k = 1, \ldots, K.$$

Both parts of this problem concern the specific problem instance with data given in `thrusters_data.*`.

(a) Find an optimal trajectory, and the associated minimum fuel use $p^\star$. Plot the trajectory $p(k)$ in $\mathbf{R}^2$ (*i.e.*, in the $p_1$, $p_2$ plane). Verify that it passes through the way-points.

(b) Generate several 1% suboptimal trajectories using the general method described above, and plot the associated trajectories in $\mathbf{R}^2$. Would you say this problem has a strong minimum, or a weak minimum?

**4.17** *Minimum fuel optimal control.* Solve the minimum fuel optimal control problem described in exercise 4.16 of *Convex Optimization*, for the instance with problem data

$$A = \left[ \begin{array}{ccc} -1 & 0.4 & 0.8 \\ 1 & 0 & 0 \\ 0 & 1 & 0 \end{array} \right], \quad b = \left[ \begin{array}{c} 1 \\ 0 \\ 0.3 \end{array} \right], \quad x_{\mathrm{des}} = \left[ \begin{array}{c} 7 \\ 2 \\ -6 \end{array} \right], \quad N = 30.$$

You can do this by forming the LP you found in your solution of exercise 4.16, or more directly using CVX*. Plot the actuator signal $u(t)$ as a function of time $t$.

**4.18** *Heuristic suboptimal solution for Boolean LP.* This exercise builds on exercises 4.15 and 5.13 in *Convex Optimization*, which involve the Boolean LP

$$\begin{array}{ll} \text{minimize} & c^T x \\ \text{subject to} & Ax \preceq b \\ & x_i \in \{0, 1\}, \quad i = 1, \dots, n, \end{array}$$

with optimal value $p^\star$. Let $x^{\text{rlx}}$ be a solution of the LP relaxation

$$\begin{array}{ll} \text{minimize} & c^T x \\ \text{subject to} & Ax \preceq b \\ & 0 \preceq x \preceq \mathbf{1}, \end{array}$$

so $L = c^T x^{\text{rlx}}$ is a lower bound on $p^\star$. The relaxed solution $x^{\text{rlx}}$ can also be used to guess a Boolean point $\hat{x}$, by rounding its entries, based on a threshold $t \in [0, 1]$:

$$\hat{x}_i = \left\{ \begin{array}{ll} 1 & x_i^{\text{rlx}} \geq t \\ 0 & \text{otherwise,} \end{array} \right.$$

for $i = 1, \dots, n$. Evidently $\hat{x}$ is Boolean (*i.e.*, has entries in $\{0, 1\}$). If it is feasible for the Boolean LP, *i.e.*, if $A\hat{x} \preceq b$, then it can be considered a guess at a good, if not optimal, point for the Boolean LP. Its objective value, $U = c^T \hat{x}$, is an upper bound on $p^\star$. If $U$ and $L$ are close, then $\hat{x}$ is nearly optimal; specifically, $\hat{x}$ cannot be more than $(U - L)$-suboptimal for the Boolean LP.

This rounding need not work; indeed, it can happen that for all threshold values, $\hat{x}$ is infeasible. But for some problem instances, it can work well.

Of course, there are many variations on this simple scheme for (possibly) constructing a feasible, good point from $x^{\text{rlx}}$.

Finally, we get to the problem. Generate problem data using one of the following.

Matlab code:

```
rand('state',0);
n=100;
m=300;
A=rand(m,n);
b=A*ones(n,1)/2;
c=-rand(n,1);
```

Python code:

```
import numpy as np
np.random.seed(0)
(m, n) = (300, 100)
A = np.random.rand(m, n); A = np.asmatrix(A)
b = A.dot(np.ones((n, 1)))/2; b = np.asmatrix(b)
c = -np.random.rand(n, 1); c = np.asmatrix(c)
```

Julia code:

```
srand(0);
n=100;
m=300;
A=rand(m,n);
b=A*ones(n,1)/2;
c=-rand(n,1);
```

You can think of $x_i$ as a job we either accept or decline, and $-c_i$ as the (positive) revenue we generate if we accept job $i$. We can think of $Ax \preceq b$ as a set of limits on $m$ resources. $A_{ij}$, which is positive, is the amount of resource $i$ consumed if we accept job $j$; $b_i$, which is positive, is the amount of resource $i$ available.

Find a solution of the relaxed LP and examine its entries. Note the associated lower bound $L$. Carry out threshold rounding for (say) 100 values of $t$, uniformly spaced over $[0, 1]$. For each value of $t$, note the objective value $c^T \hat{x}$ and the maximum constraint violation $\max_i (A\hat{x} - b)_i$. Plot the objective value and the maximum violation versus $t$. Be sure to indicate on the plot the values of $t$ for which $\hat{x}$ is feasible, and those for which it is not.

Find a value of $t$ for which $\hat{x}$ is feasible, and gives minimum objective value, and note the associated upper bound $U$. Give the gap $U - L$ between the upper bound on $p^\star$ and the lower bound on $p^\star$.

In Matlab, if you define vectors `obj` and `maxviol`, you can find the upper bound as

`|U=min(obj(find(maxviol<=0)))|`

**4.19** *Optimal operation of a hybrid vehicle.* Solve the instance of the hybrid vehicle operation problem described in exercise 4.65 in *Convex Optimization*, with problem data given in the file `hybrid_veh_data.*`, and fuel use function $F(p) = p + \gamma p^2$ (for $p \geq 0$).

*Hint.* You will actually formulate and solve a *relaxation* of the original problem. You may find that some of the equality constraints you relaxed to inequality constraints do not hold for the solution found. This is not an error: it just means that there is no incentive (in terms of the objective) for the inequality to be tight. You can fix this in (at least) two ways. One is to go back and adjust certain variables, without affecting the objective and maintaining feasibility, so that the relaxed constraints hold with equality. Another simple method is to add to the objective a term of the form

$$\epsilon \sum_{t=1}^{T} \max\{0, -P_{\mathrm{mg}}(t)\},$$

where $\epsilon$ is small and positive. This makes it more attractive to use the brakes to extract power from the wheels, even when the battery is (or will be) full (which removes any fuel incentive).

Find the optimal fuel consumption, and compare to the fuel consumption with a non-hybrid version of the same vehicle (*i.e.*, one without a battery). Plot the braking power, engine power, motor/generator power, and battery energy versus time.

How would you use optimal dual variables for this problem to find $\partial F_{\mathrm{total}}/\partial E_{\mathrm{batt}}^{\mathrm{max}}$, *i.e.*, the partial derivative of optimal fuel consumption with respect to battery capacity? (You can just assume

that this partial derivative exists.) You do not have to give a long derivation or proof; you can just state how you would find this derivative from optimal dual variables for the problem. Verify your method numerically, by changing the battery capacity a small amount and re-running the optimization, and comparing this to the prediction made using dual variables.

**4.20** *Optimal vehicle speed scheduling.* A vehicle (say, an airplane) travels along a fixed path of $n$ segments, between $n + 1$ waypoints labeled $0, \ldots, n$. Segment $i$ starts at waypoint $i - 1$ and terminates at waypoint $i$. The vehicle starts at time $t = 0$ at waypoint 0. It travels over each segment at a constant (nonnegative) speed; $s_i$ is the speed on segment $i$. We have lower and upper limits on the speeds: $s^{\min} \preceq s \preceq s^{\max}$. The vehicle does not stop at the waypoints; it simply proceeds to the next segment. The travel distance of segment $i$ is $d_i$ (which is positive), so the travel time over segment $i$ is $d_i/s_i$. We let $\tau_i$, $i = 1, \ldots, n$, denote the time at which the vehicle arrives at waypoint $i$. The vehicle is required to arrive at waypoint $i$, for $i = 1, \ldots, n$, between times $\tau_i^{\min}$ and $\tau_i^{\max}$, which are given. The vehicle consumes fuel over segment $i$ at a rate that depends on its speed, $\Phi(s_i)$, where $\Phi$ is positive, increasing, and convex, and has units of kg/s.

You are given the data $d$ (segment travel distances), $s^{\min}$ and $s^{\max}$ (speed bounds), $\tau^{\min}$ and $\tau^{\max}$ (waypoint arrival time bounds), and the fuel use function $\Phi : \mathbf{R} \to \mathbf{R}$. You are to choose the speeds $s_1, \ldots, s_n$ so as to minimize the total fuel consumed in kg.

(a) Show how to pose this as a convex optimization problem. If you introduce new variables, or change variables, you must explain how to recover the optimal speeds from the solution of your problem. If convexity of the objective or any constraint function in your formulation is not obvious, explain why it is convex.

(b) Carry out the method of part (a) on the problem instance with data in
    `veh_speed_sched_data.*`. Use the fuel use function $\Phi(s_i) = as_i^2 + bs_i + c$ (the parameters $a$, $b$, and $c$ are defined in the data file). What is the optimal fuel consumption? Plot the optimal speed versus segment, using the matlab command `stairs` or the function `step` from matplotlib in Python and Julia to better show constant speed over the segments.

**4.21** *Norm approximation via SOCP, for $\ell_p$-norms with rational $p$.*

(a) Use the observation at the beginning of exercise 4.26 in *Convex Optimization* to express the constraint
$$y \leq \sqrt{z_1 z_2}, \qquad y, z_1, z_2 \geq 0,$$
with variables $y$, $z_1$, $z_2$, as a second-order cone constraint. Then extend your result to the constraint
$$y \leq (z_1 z_2 \cdots z_n)^{1/n}, \qquad y \geq 0, \qquad z \succeq 0,$$
where $n$ is a positive integer, and the variables are $y \in \mathbf{R}$ and $z \in \mathbf{R}^n$. First assume that $n$ is a power of two, and then generalize your formulation to arbitrary positive integers.

(b) Express the constraint
$$f(x) \leq t$$
as a second-order cone constraint, for the following two convex functions $f$:
$$f(x) = \begin{cases} x^\alpha & x \geq 0 \\ 0 & x < 0, \end{cases}$$

where $\alpha$ is rational and greater than or equal to one, and

$$f(x) = x^\alpha, \qquad \mathbf{dom}\, f = \mathbf{R}_{++},$$

where $\alpha$ is rational and negative.

(c) Formulate the norm approximation problem

$$\text{minimize} \quad \|Ax - b\|_p$$

as a second-order cone program, where $p$ is a rational number greater than or equal to one. The variable in the optimization problem is $x \in \mathbf{R}^n$. The matrix $A \in \mathbf{R}^{m \times n}$ and the vector $b \in \mathbf{R}^m$ are given. For an $m$-vector $y$, the norm $\|y\|_p$ is defined as

$$\|y\|_p = \left( \sum_{k=1}^{m} |y_k|^p \right)^{1/p}$$

when $p \geq 1$.

**4.22** *Linear optimization over the complement of a convex set.* Suppose $\mathcal{C} \subseteq \mathbf{R}_+^n$ is a closed bounded convex set with $0 \in \mathcal{C}$, and $c \in \mathbf{R}_+^n$. We define

$$\tilde{\mathcal{C}} = \mathbf{cl}(\mathbf{R}_+^n \setminus \mathcal{C}) = \mathbf{cl}\{x \in \mathbf{R}_+^n \mid x \notin \mathcal{C}\},$$

which is the closure of the complement of $\mathcal{C}$ in $\mathbf{R}_+^n$.

Show that $c^T x$ has a minimizer over $\tilde{\mathcal{C}}$ of the form $\alpha e_k$, where $\alpha \geq 0$ and $e_k$ is the $k$th standard unit vector. (If you have not had a course on analysis, you can give an intuitive argument.)

If follows that we can minimize $c^T x$ over $\tilde{\mathcal{C}}$ by solving $n$ one-dimensional optimization problems (which, indeed, can each be solved by bisection, provided we can check whether a point is in $\mathcal{C}$ or not).

**4.23** *Jensen's inequality for posynomials.* Suppose $f : \mathbf{R}^n \to \mathbf{R}$ is a posynomial function, $x, y \in \mathbf{R}_{++}^n$, and $\theta \in [0, 1]$. Define $z \in \mathbf{R}_{++}^n$ by $z_i = x_i^\theta y_i^{1-\theta}$, $i = 1, \ldots, n$. Show that $f(z) \leq f(x)^\theta f(y)^{1-\theta}$.

*Interpretation.* We can think of $z$ as a $\theta$-weighted geometric mean between $x$ and $y$. So the statement above is that a posynomial, evaluated at a weighted geometric mean of two points, is no more than the weighted geometric mean of the posynomial evaluated at the two points.

**4.24** *CVX implementation of a concave function.* Consider the concave function $f : \mathbf{R} \to \mathbf{R}$ defined by

$$f(x) = \begin{cases} (x+1)/2 & x > 1 \\ \sqrt{x} & 0 \leq x \leq 1, \end{cases}$$

with $\mathbf{dom}\, f = \mathbf{R}_+$. Give a CVX implementation of $f$, via a partially specified optimization problem. Check your implementation by maximizing $f(x) + f(a - x)$ for several interesting values of $a$ (say, $a = -1$, $a = 1$, and $a = 3$).

**4.25** The following optimization problem arises in portfolio optimization:

$$\begin{array}{ll}
\text{maximize} & \dfrac{r^T x + d}{\|Rx + q\|_2} \\
\text{subject to} & \sum\limits_{i=1}^{n} f_i(x_i) \le b \\
& x \succeq c.
\end{array}$$

The variable is $x \in \mathbf{R}^n$. The functions $f_i$ are defined as

$$f_i(x) = \alpha_i x_i + \beta_i |x_i| + \gamma_i |x_i|^{3/2},$$

with $\beta_i > |\alpha_i|$, $\gamma_i > 0$. We assume there exists a feasible $x$ with $r^T x + d > 0$.

Show that this problem can be solved by solving an SOCP (if possible) or a sequence of SOCP feasibility problems (otherwise).

**4.26** *Positive nonconvex QCQP.* We consider a (possibly nonconvex) QCQP, with nonnegative variable $x \in \mathbf{R}^n$,

$$\begin{array}{ll}
\text{minimize} & f_0(x) \\
\text{subject to} & f_i(x) \le 0, \quad i = 1, \ldots, m \\
& x \succeq 0,
\end{array}$$

where $f_i(x) = (1/2)x^T P_i x + q_i^T x + r_i$, with $P_i \in \mathbf{S}^n$, $q_i \in \mathbf{R}^n$, and $r_i \in \mathbf{R}$, for $i = 0, \ldots, m$. We do *not* assume that $P_i \succeq 0$, so this need not be a convex problem.

Suppose that $q_i \preceq 0$, and $P_i$ have nonpositive off-diagonal entries, *i.e.*, they satisfy

$$(P_i)_{jk} \le 0, \quad j \ne k, \quad j, k = 1, \ldots, n,$$

for $i = 0, \ldots, m$. (A matrix with nonpositive off-diagonal entries is called a *Z-matrix*.) Explain how to reformulate this problem as a convex problem.

*Hint.* Change variables using $y_j = \phi(x_j)$, for some suitable function $\phi$.

**4.27** *Affine policy.* We consider a family of LPs, parametrized by the random variable $u$, which is uniformly distributed on $\mathcal{U} = [-1, 1]^p$,

$$\begin{array}{ll}
\text{minimize} & c^T x \\
\text{subject to} & Ax \preceq b(u),
\end{array}$$

where $x \in \mathbf{R}^n$, $A \in \mathbf{R}^{m \times n}$, and $b(u) = b_0 + Bu \in \mathbf{R}^m$ is an affine function of $u$. You can think of $u_i$ as representing a deviation of the $i$th parameter from its nominal value. The parameters might represent (deviations in) levels of resources available, or other varying limits.

The problem is to be solved many times; in each time, the value of $u$ (*i.e.*, a sample) is given, and then the decision variable $x$ is chosen. The mapping from $u$ into the decision variable $x(u)$ is called the *policy*, since it gives the decision variable value for each value of $u$. When enough time and computing hardware is available, we can simply solve the LP for each new value of $u$; this is an optimal policy, which we denote $x^\star(u)$.

In some applications, however, the decision $x(u)$ must be made very quickly, so solving the LP is not an option. Instead we seek a suboptimal policy, which is affine: $x^{\text{aff}}(u) = x_0 + Ku$, where $x_0$ is

called the *nominal decision* and $K \in \mathbf{R}^{n \times p}$ is called the *feedback gain matrix*. (Roughly speaking, $x_0$ is our guess of $x$ before the value of $u$ has been revealed; $Ku$ is our modification of this guess, once we know $u$.) We determine the policy (*i.e.*, suitable values for $x_0$ and $K$) ahead of time; we can then evaluate the policy (that is, find $x^{\mathrm{aff}}(u)$ given $u$) very quickly, by matrix multiplication and addition.

We will choose $x_0$ and $K$ in order to minimize the expected value of the objective, while insisting that for any value of $u$, feasibility is maintained:

$$\begin{array}{ll} \text{minimize} & \mathbf{E}\, c^T x^{\mathrm{aff}}(u) \\ \text{subject to} & Ax^{\mathrm{aff}}(u) \preceq b(u) \quad \forall u \in \mathcal{U}. \end{array}$$

The variables here are $x_0$ and $K$. The expectation in the objective is over $u$, and the constraint requires that $Ax^{\mathrm{aff}}(u) \preceq b(u)$ hold almost surely.

(a) Explain how to find optimal values of $x_0$ and $K$ by solving a standard explicit convex optimization problem (*i.e.*, one that does not involve an expectation or an infinite number of constraints, as the one above does.) The numbers of variables or constraints in your formulation should not grow exponentially with the problem dimensions $n$, $p$, or $m$.

(b) Carry out your method on the data given in `affine_pol_data.m`. To evaluate your affine policy, generate 100 independent samples of $u$, and for each value, compute the objective value of the affine policy, $c^T x^{\mathrm{aff}}(u)$, and of the optimal policy, $c^T x^{\star}(u)$. Scatter plot the objective value of the affine policy (*y*-axis) versus the objective value of the optimal policy (*x*-axis), and include the line $y = x$ on the plot. Report the average values of $c^T x^{\mathrm{aff}}(u)$ and $c^T x^{\star}(u)$ over your samples. (These are estimates of $\mathbf{E}\, c^T x^{\mathrm{aff}}(u)$ and $\mathbf{E}\, c^T x^{\star}(u)$. The first number, by the way, can be found exactly.)

**4.28** *Probability bounds.* Consider random variables $X_1, X_2, X_3, X_4$ that take values in $\{0, 1\}$. We are given the following marginal and conditional probabilities:

$$\begin{aligned} \mathbf{prob}(X_1 = 1) &= 0.9, \\ \mathbf{prob}(X_2 = 1) &= 0.9, \\ \mathbf{prob}(X_3 = 1) &= 0.1, \\ \mathbf{prob}(X_1 = 1, X_4 = 0 \mid X_3 = 1) &= 0.7, \\ \mathbf{prob}(X_4 = 1 \mid X_2 = 1, X_3 = 0) &= 0.6. \end{aligned}$$

Explain how to find the minimum and maximum possible values of $\mathbf{prob}(X_4 = 1)$, over all (joint) probability distributions consistent with the given data. Find these values and report them.

*Hints.* (You should feel free to ignore these hints.)

- Matlab:
  - CVX supports multidimensional arrays; for example, `variable p(2,2,2,2)` declares a 4-dimensional array of variables, with each of the four indices taking the values 1 or 2.
  - The function `sum(p,i)` sums a multidimensional array `p` along the $i$th index.
  - The expression `sum(a(:))` gives the sum of all entries of a multidimensional array `a`. You might want to use the function definition `sum_all = @(A) sum( A(:));`, so `sum_all(a)` gives the sum of all entries in the multidimensional array `a`.

- Python:
  - Create a 1-dimensional Variable and manually index the entries. You should come up with a reasonable scheme to avoid confusion.
- Julia:
  - You can create a multidimensional array of variables in Convex.jl. For example, the following creates a 4-dimensional array of variables, with each of the four indices taking the values 1 or 2.
    ```
    p = [Variable() for i in 1:16];
    p = reshape(p, 2, 2, 2, 2)
    ```
  - You can use the function sum to sum over various indices in the multidimesional array.
    ```
    sum(p[:,:,:,:]) # sum all entries
    sum(p[1,:,2,:]) # fix first and third indices
    ```
  - To create constraints with the variables in the array, you need to access each variable independently. Something like p >= 0 will not work.

**4.29** *Robust quadratic programming.* In this problem, we consider a robust variation of the (convex) *quadratic* program

$$\text{minimize} \quad (1/2)x^T P x + q^T x + r$$
$$\text{subject to} \quad Ax \preceq b.$$

For simplicity we assume that only the matrix $P$ is subject to errors, and the other parameters ($q$, $r$, $A$, $b$) are exactly known. The robust quadratic program is defined as

$$\text{minimize} \quad \sup_{P \in \mathcal{E}}((1/2)x^T P x + q^T x + r)$$
$$\text{subject to} \quad Ax \preceq b$$

where $\mathcal{E}$ is the set of possible matrices $P$.

For each of the following sets $\mathcal{E}$, express the robust QP as a *tractable* convex problem. Be as specific as you can. (Here, tractable means that the problem can be reduced to an LP, QP, QCQP, SOCP, or SDP. But you do not have to work out the reduction, if it is complicated; it is enough to argue that it can be reduced to one of these.)

(a) A finite set of matrices: $\mathcal{E} = \{P_1, \ldots, P_K\}$, where $P_i \in \mathbf{S}^n_+$, $i = 1, \ldots, K$.

(b) A set specified by a nominal value $P_0 \in \mathbf{S}^n_+$ plus a bound on the eigenvalues of the deviation $P - P_0$:

$$\mathcal{E} = \{P \in \mathbf{S}^n \mid -\gamma I \preceq P - P_0 \preceq \gamma I\}$$

where $\gamma \in \mathbf{R}$ and $P_0 \in \mathbf{S}^n_+$.

(c) An ellipsoid of matrices:

$$\mathcal{E} = \left\{ P_0 + \sum_{i=1}^{K} P_i u_i \,\middle|\, \|u\|_2 \leq 1 \right\}.$$

You can assume $P_i \in \mathbf{S}^n_+$, $i = 0, \ldots, K$.

**4.30** *Smallest confidence ellipsoid.* Suppose the random variable $X$ on $\mathbf{R}^n$ has log-concave density $p$. Formulate the following problem as a convex optimization problem: Find an ellipsoid $\mathcal{E}$ that satisfies $\mathbf{prob}(X \in \mathcal{E}) \geq 0.95$ and is smallest, in the sense of minimizing the sum of the squares of its semi-axis lengths. You do not need to worry about how to solve the resulting convex optimization problem; it is enough to formulate the smallest confidence ellipsoid problem as the problem of minimizing a convex function over a convex set involving the parameters that define $\mathcal{E}$.

**4.31** *Stochastic optimization via Monte Carlo sampling.* In (convex) stochastic optimization, the goal is to minimize a cost function of the form $F(x) = \mathbf{E} \, f(x, \omega)$, where $\omega$ is a random variable on $\Omega$, and $f : \mathbf{R}^n \times \Omega \to \mathbf{R}$ is convex in its first argument for each $\omega \in \Omega$. (For simplicity we consider the unconstrained problem; it is not hard to include constraints.) Evidently $F$ is convex. Let $p^\star$ denote the optimal value, *i.e.*, $p^\star = \inf_x F(x)$ (which we assume is finite).

In a few very simple cases we can work out what $F$ is analytically, but in general this is not possible. Moreover in many applications, we do not know the distribution of $\omega$; we only have access to an oracle that can generate independent samples from the distribution.

A standard method for approximately solving the stochastic optimization problem is based on Monte Carlo sampling. We first generate $N$ independent samples, $\omega_1, \ldots, \omega_N$, and form the empirical expectation

$$\hat{F}(x) = \frac{1}{N} \sum_{i=1}^{N} f(x, \omega_i).$$

This is a random function, since it depends on the particular samples drawn. For each $x$, we have $\mathbf{E} \, \hat{F}(x) = F(x)$, and also $\mathbf{E}(\hat{F}(x) - F(x))^2 \propto 1/N$. Roughly speaking, for $N$ large enough, $\hat{F}(x) \approx F(x)$.

To (approximately) minimize $F$, we instead minimize $\hat{F}(x)$. The minimizer, $\hat{x}^\star$, and the optimal value $\hat{p}^\star = \hat{F}(\hat{x}^\star)$, are also random variables. The hope is that for $N$ large enough, we have $\hat{p}^\star \approx p^\star$. (In practice, stochastic optimization via Monte Carlo sampling works very well, even when $N$ is not that big.)

One way to check the result of Monte Carlo sampling is to carry it out multiple times. We repeatedly generate different batches of samples, and for each batch, we find $\hat{x}^\star$ and $\hat{p}^\star$. If the values of $\hat{p}^\star$ are near each other, it's reasonable to believe that we have (approximately) minimized $F$. If they are not, it means our value of $N$ is too small.

Show that $\mathbf{E} \, \hat{p}^\star \leq p^\star$.

This inequality implies that if we repeatedly use Monte Carlo sampling and the values of $\hat{p}^\star$ that we get are all very close, then they are (likely) close to $p^\star$.

*Hint.* Show that for any function $G : \mathbf{R}^n \times \Omega \to \mathbf{R}$ (convex or not in its first argument), and any random variable $\omega$ on $\Omega$, we have

$$\inf_x \mathbf{E} \, G(x, \omega) \geq \mathbf{E} \inf_x G(x, \omega).$$

**4.32** *Satisfying a minimum number of constraints.* Consider the problem

$$
\begin{array}{ll}
\text{minimize} & f_0(x) \\
\text{subject to} & f_i(x) \leq 0 \text{ holds for at least } k \text{ values of } i,
\end{array}
$$

with variable $x \in \mathbf{R}^n$, where the objective $f_0$ and the constraint functions $f_i$, $i = 1, \ldots, m$ (with $m \geq k$), are convex. Here we require that only $k$ of the constraints hold, instead of all $m$ of them. In general this is a hard combinatorial problem; the brute force solution is to solve all $\binom{m}{k}$ convex problems obtained by choosing subsets of $k$ constraints to impose, and selecting one with smallest objective value.

In this problem we explore a convex restriction that can be an effective heuristic for the problem.

(a) Suppose $\lambda > 0$. Show that the constraint

$$\sum_{i=1}^{m} (1 + \lambda f_i(x))_+ \leq m - k$$

guarantees that $f_i(x) \leq 0$ holds for at least $k$ values of $i$. ($(u)_+$ means $\max\{u, 0\}$.)

*Hint.* For each $u \in \mathbf{R}$, $(1 + \lambda u)_+ \geq 1(u > 0)$, where $1(u > 0) = 1$ for $u > 0$, and $1(u > 0) = 0$ for $u \leq 0$.

(b) Consider the problem

$$
\begin{array}{ll}
\text{minimize} & f_0(x) \\
\text{subject to} & \sum_{i=1}^{m} (1 + \lambda f_i(x))_+ \leq m - k \\
& \lambda > 0,
\end{array}
$$

with variables $x$ and $\lambda$. This is a restriction of the original problem: If $(x, \lambda)$ are feasible for it, then $x$ is feasible for the original problem. Show how to solve this problem using convex optimization. (This may involve a change of variables.)

(c) Apply the method of part (b) to the problem instance

$$
\begin{array}{ll}
\text{minimize} & c^T x \\
\text{subject to} & a_i^T x \leq b_i \text{ holds for at least } k \text{ values of } i,
\end{array}
$$

with $m = 70$, $k = 58$, and $n = 12$. The vectors $b$, $c$ and the matrix $A$ with rows $a_i^T$ are given in the file `satisfy_some_constraints_data.*`.

Report the optimal value of $\lambda$, the objective value, and the actual number of constraints that are satisfied (which should be larger than or equal to $k$). To determine if a constraint is satisfied, you can use the tolerance $a_i^T x - b_i \leq \epsilon^{\text{feas}}$, with $\epsilon^{\text{feas}} = 10^{-5}$.

A standard trick is to take this tentative solution, choose the $k$ constraints with the smallest values of $f_i(x)$, and then minimize $f_0(x)$ subject to these $k$ constraints (*i.e.*, ignoring the other $m - k$ constraints). This improves the objective value over the one found using the restriction. Carry this out for the problem instance, and report the objective value obtained.

**4.33** [Barvinok, Pataki] A standard form semidefinite program is defined as

$$
\begin{array}{lll}
\text{minimize} & \mathbf{tr}(CX) \\
\text{subject to} & \mathbf{tr}(A_i X) = b_i, & i = 1, \ldots, m \\
& X \succeq 0.
\end{array}
\tag{4}
$$

The variable $X$ and the coefficients $A_1, \ldots, A_m$ are symmetric $n \times n$ matrices.

A matrix $\hat{X}$ is called an *extreme point* of the feasible set of (4) if $\hat{X}$ is feasible and if the only matrix $V \in \mathbf{S}^n$ that satisfies the conditions

$$\mathbf{tr}\,(A_i V) = 0, \quad i = 1, \dots, m, \qquad \hat{X} + V \succeq 0, \qquad \hat{X} - V \succeq 0 \tag{5}$$

is $V = 0$. In this problem we work out a bound on the rank of extreme points.

(a) Suppose $\hat{X}$ is feasible for (4) and has rank $r$. Define an eigenvalue decomposition

$$\hat{X} = \begin{bmatrix} Q_1 & Q_2 \end{bmatrix} \begin{bmatrix} \Lambda_1 & 0 \\ 0 & 0 \end{bmatrix} \begin{bmatrix} Q_1 & Q_2 \end{bmatrix}^T,$$

where $\begin{bmatrix} Q_1 & Q_2 \end{bmatrix}$ is orthogonal, $Q_1$ has $r$ columns, and $\Lambda_1$ is a diagonal $r \times r$ matrix with positive diagonal elements. Show that $V$ satisfies (5) if and only if it can be expressed as $V = Q_1 Y Q_1^T$ where $Y \in \mathbf{S}^r$ satisfies

$$\mathbf{tr}\,(Q_1^T A_i Q_1 Y) = 0, \quad i = 1, \dots, m, \qquad \Lambda_1 + Y \succeq 0, \qquad \Lambda_1 - Y \succeq 0.$$

(b) Show that if $r(r+1)/2 > m$, then $\hat{X}$ is not an extreme point.

(c) Interpret the SDP (4) as a relaxation of the non-convex QCQP

$$\begin{array}{ll}
\text{minimize} & x^T C x \\
\text{subject to} & x^T A_i x = b_i, \quad i = 1, \dots, m.
\end{array}$$

What are the implications of part b for the exactness of the relaxation? (You can assume that the feasible set of (4) is non-empty and bounded. Under this assumption, the SDP is guaranteed to have optimal solutions that are extreme points of the feasible set.)

**4.34** *Exact relaxation of a rank constrained problem.* Consider the following optimization problem, which we shall call problem $A$.

$$\begin{array}{ll}
\text{minimize} & \mathbf{tr}(AP) \\
\text{subject to} & \mathbf{rank}(P) = k, \\
& \lambda_i(P) \in \{0, 1\} \quad \text{for all } i = 1, \dots, n
\end{array}$$

Here the variable $P \in \mathbf{S}^n$, and $\lambda_i(P)$ is its $i$th largest eigenvalue. We are give $A \in \mathbf{R}^{n \times n}$ and $k \in \mathbf{Z}$ with $k > 0$. Both of the constraints are not convex.

Problem $B$ is the following semidefinite program, with the same problem data.

$$\begin{array}{ll}
\text{minimize} & \mathbf{tr}(AP) \\
\text{subject to} & \mathbf{tr}(P) = k, \\
& 0 \preceq P \preceq I,
\end{array}$$

(a) Show that problem $B$ is a relaxation of problem $A$. That is, show that if $P$ is feasible for problem $A$ then it is also feasible for problem $B$.

(b) Consider the problem

$$\begin{array}{ll}
\text{minimize} & c^T x \\
\text{subject to} & \sum_i x_i = k \\
& 0 \leq x_i \leq 1
\end{array}$$

where the variable is $x \in \mathbf{R}^n$, and $c \in \mathbf{R}^n$ is given. Explain why there always exists an optimal $x$ for which all components are integers.

(c) Using the previous result, show that problem $B$ is a *tight* relaxation of problem $A$. Specifically, show that there is an optimal solution $P$ to problem $B$ for which $\lambda_i(P) \in \{0, 1\}$ for all $i$.

**4.35** *A robust SDP.* We consider the robust optimization problem

$$
\begin{array}{ll}
\text{minimize} & c^T x \\
\text{subject to} & \sum_{i=1}^{n} x_i(A_i + U_i) \preceq B \quad \text{for all } U_i \in \mathbf{S}^p \text{ with } \|U_i\|_2 \leq 1, \ i = 1, \ldots, n.
\end{array}
$$

The optimization variable is an $n$-vector $x$. The $n$-vector $c$ and the matrices $A_i, B \in \mathbf{S}^p$ are given. The norm $\|U_i\|_2$ is the matrix norm. (For symmetric matrices $\|U\|_2 = \max_k |\lambda_k(U)|$.)

(a) Show that $x$ satisfies the constraint in the problem if and only if

$$
\|x\|_1 \leq \lambda_{\min}(B - \sum_{i=1}^{n} x_i A_i).
$$

The right-hand side is the smallest eigenvalue of $B - \sum_i x_i A_i$.

(b) Use the observation of part (a) to formulate the robust optimization problem as an SDP.

**4.36** For a symmetric $n \times n$ matrix $A$ we define $f(A)$ as the optimal value of the semidefinite program

$$
\begin{array}{ll}
\text{minimize} & \mathbf{tr}\, X + \mathbf{tr}\, Y \\
\text{subject to} & \begin{bmatrix} X & A \\ A & Y + I \end{bmatrix} \succeq 0 \\
& Y \succeq 0,
\end{array}
$$

with variables $X \in \mathbf{S}^n$ and $Y \in \mathbf{S}^n$.

(a) Is $f(A)$ a convex function of $A$?

(b) Express $f(A)$ as a function of the eigenvalues of $A$, *i.e.*, in the form

$$
f(A) = \sum_{i=1}^{n} \phi(\lambda_i(A)),
$$

where $\lambda_1(A), \ldots, \lambda_n(A)$ are the eigenvalues of $A$. Give an explicit formula for $\phi$.

**4.37** In this problem we generalize the optimality condition in §4.2.3 of *Convex Optimization* (page 4-9 of the slides). We consider an optimization problem

$$
\text{minimize} \quad f(x) + g(x)
$$

where $f : \mathbf{R}^n \to \mathbf{R}$ is differentiable and $g : \mathbf{R}^n \to \mathbf{R}$ is convex. We do not assume that $f$ is convex or that its domain is a convex set. (However, recall our convention that the domain of a differentiable function is an open set.) The problem in §4.2.3 is a special case with $g$ the indicator function of a convex set. (The indicator function of a set $C$ is the function with domain $C$, and function value zero on $C$.)

The generalization of the optimality criterion in §4.2.3 is

$$
\hat{x} \in \mathbf{dom}\, f \cap \mathbf{dom}\, g, \quad \nabla f(\hat{x})^T (y - \hat{x}) + g(y) - g(\hat{x}) \geq 0 \text{ for all } y \in \mathbf{dom}\, g. \tag{6}
$$

(a) Show that (6) is a necessary condition for $\hat{x}$ to be locally optimal.

(b) Assume $f$ is convex. Show that (6) is also sufficient for $\hat{x}$ to be optimal.

(c) Take $g(x) = \|x\|_1$. Show that (6) reduces to the following: $\hat{x} \in \mathbf{dom}\, f$ and for each $i = 1, \ldots, n$,

$$\frac{\partial f(\hat{x})}{\partial x_i} = -1 \quad \text{if } \hat{x}_i > 0, \qquad \left|\frac{\partial f(\hat{x})}{\partial x_i}\right| \leq 1 \quad \text{if } \hat{x}_i = 0, \qquad \frac{\partial f(\hat{x})}{\partial x_i} = 1 \quad \text{if } \hat{x}_i < 0.$$

**4.38** *Robust piecewise-linear optimization.* Consider the robust piecewise-linear minimization problem

$$\text{minimize} \quad \sup_{a_i \in \mathcal{A}_i,\ i=1,\ldots,m} \ \max_{i=1,\ldots,m} \ (a_i^T x + b_i)$$

with variable $x \in \mathbf{R}^n$. For each of the following definitions of $\mathcal{A}_i$, formulate the problem as an SOCP.

(a) Each set $\mathcal{A}_i$ is a Euclidean ball

$$\mathcal{A}_i = \{a_i \mid \|a_i - c_i\|_2 \leq r_i\}.$$

The vectors $c_i$ and positive scalars $r_i$ are given.

(b) Each set $\mathcal{A}_i$ is the union of $p_i$ Euclidean balls

$$\mathcal{A}_i = \bigcup_{j=1,\ldots,p_i} \{a_i \mid \|a_i - c_{ij}\|_2 \leq r_{ij}\}.$$

The vectors $c_{ij}$ and positive scalars $r_{ij}$ are given.

(c) Each set $\mathcal{A}_i$ is the intersection of $p_i$ Euclidean balls

$$\mathcal{A}_i = \bigcap_{j=1,\ldots,p_i} \{a_i \mid \|a_i - c_{ij}\|_2 \leq r_{ij}\}.$$

The vectors $c_{ij}$ and positive scalars $r_{ij}$ are given. We assume the sets $\mathcal{A}_i$ have nonempty interior.

**4.39** *Risk-sensitive linear programming.* We revisit the linear programming problem with random cost (page 154 of *Convex Optimization*). The goal is to give an interpretation to the LP

$$\begin{aligned} \text{minimize} \quad & c^T x \\ \text{subject to} \quad & Gx \preceq h \end{aligned}$$

when the cost vector $c$ is random. For simplicity, we assume a discrete distribution with $m$ possible values: $c$ takes the value $c_i$ with probability $p_i$, for $i = 1, \ldots, m$. The vectors $c_i$ represent different scenarios or cases, each occurring with probability $p_i$. The mean and covariance matrix are denoted by

$$\bar{c} = \sum_{i=1}^{m} p_i c_i, \qquad \Sigma = \sum_{i=1}^{m} p_i (c_i - \bar{c})(c_i - \bar{c})^T.$$

In this exercise, we formulate the problem as

$$\begin{aligned} \text{minimize} \quad & \frac{1}{\gamma} \log \mathbf{E}\, e^{\gamma c^T x} = \frac{1}{\gamma} \log \sum_{i=1}^{m} p_i e^{\gamma c_i^T x} \\ \text{subject to} \quad & Gx \preceq h. \end{aligned} \tag{7}$$

We will see that the parameter $\gamma$ controls the *risk sensitivity* of the optimization model. To simplify some notation, we define the function $f_\gamma : \mathbf{R}^m \to \mathbf{R}$ with

$$f_\gamma(y) = \frac{1}{\gamma} \log \sum_{i=1}^m p_i e^{\gamma y_i}$$

(where $p_i > 0$ and $\sum_i p_i = 1$). With this notation, problem (7) can be written as

$$\begin{array}{ll} \text{minimize} & f_\gamma(Cx) \\ \text{subject to} & Gx \preceq h, \end{array} \tag{8}$$

where $C$ is the matrix with rows $c_i^T$, $i = 1, \ldots, m$.

(a) We first interpret the limits for $\gamma \to \pm\infty$ and $\gamma \to 0$. Show that

$$\lim_{\gamma \to \infty} f_\gamma(Cx) = \max_{i=1,\ldots,m} c_i^T x, \qquad \lim_{\gamma \to -\infty} f_\gamma(Cx) = \min_{i=1,\ldots,m} c_i^T x, \qquad \lim_{\gamma \to 0} f_\gamma(Cx) = \bar{c}^T x.$$

In (7) these three values of $\gamma$ correspond to extreme pessimism (minimizing the worst case $\max_i c_i^T x$), extreme optimism (minimizing the best case $\min_i c_i^T x$), and a risk-neutral attitude (minimizing the average case $\bar{c}^T x$).

(b) Next we examine the effect of choosing $\gamma$ positive or negative. Show that

$$f_\gamma(Cx) \geq \bar{c}^T x \quad \text{if } \gamma > 0, \qquad f_\gamma(Cx) \leq \bar{c}^T x \quad \text{if } \gamma < 0.$$

Hence, if $\gamma > 0$, the variability of $c^T x$ around its mean increases the cost function; if $\gamma < 0$, it decreases it. In problem (7), choosing $\gamma > 0$ makes the optimization strategy *risk-averse*; choosing $\gamma < 0$ makes it *risk-seeking*. We also note that the objective function is convex if $\gamma > 0$ and concave if $\gamma < 0$.

(c) Finally, we relate (7) to the QP formulation on page 155 of *Convex Optimization*. We make a quadratic approximation of the function $f_\gamma(y)$ around the vector $\hat{y} = (\bar{c}^T x)\mathbf{1}$. Verify that

$$\nabla f_\gamma(\hat{y}) = p, \qquad \nabla^2 f_\gamma(\hat{y}) = \gamma(\mathbf{diag}(p) - pp^T),$$

where $p = (p_1, \ldots, p_m)$. Then show that if we make the approximation

$$f_\gamma(Cx) \approx f_\gamma(\hat{y}) + \nabla f_\gamma(\hat{y})^T (Cx - \hat{y}) + \frac{1}{2}(Cx - \hat{y})^T \nabla^2 f_\gamma(\hat{y})(Cx - \hat{y})$$

in (8), the problem reduces to

$$\begin{array}{ll} \text{minimize} & \bar{c}^T x + (\gamma/2)x^T \Sigma x \\ \text{subject to} & Gx \preceq h. \end{array}$$

**4.40** Consider the optimization problem

$$\begin{array}{ll} \text{minimize} & x_1^2 \\ \text{subject to} & x_1 \leq -1, \quad x_1^2 + x_2^2 \leq 2, \end{array}$$

with variable $x = (x_1, x_2)$. Determine whether each of the following statements is true or false.

(a) The point $(-1, 1)$ is a solution.

(b) The optimal value is 1.

(c) The problem is convex.

(d) The problem has multiple solutions.

**4.41** *Feasibility and optimal value.* Consider an optimization problem in which we seek to minimize the objective. We let $p^\star$ denote the optimal value of the problem. Which of the following statements are true?

(a) The problem is feasible if and only if $p^\star < \infty$.

(b) The problem has an optimal point if and only if $p^\star$ is finite.

(c) If $p^\star = -\infty$, the problem is feasible.

**4.42** *Scalarizing a bi-criterion problem using the max function.* Consider the bi-criterion optimization problem
$$\text{minimize} \quad (f(x), g(x)),$$
with variable $x$. Suppose $\tilde{x}$ is the unique minimizer of $\max\{f(x), g(x)\}$. Is $\tilde{x}$ Pareto optimal? Either explain why it is, or give a counterexample.

**4.43** *Optimal value of a linear program as a function of data.* Consider the LP
$$\begin{array}{ll} \text{minimize} & c^T x \\ \text{subject to} & Ax = b, \quad x \succeq 0, \end{array}$$
with variable $x \in \mathbf{R}^n$, with data $A \in \mathbf{R}^{m \times n}$, $b \in \mathbf{R}^m$, and $c \in \mathbf{R}^n$. We denote the optimal value as $f(A, b, c)$. This can be $+\infty$ (if the LP is infeasible) or $-\infty$ (if it is unbounded below).

(a) Suppose we fix $A$ and $b$ at values for which the LP is feasible. What can you say about the curvature of the mapping from $c$ to $f(A, b, c)$? Is it convex? Concave? Neither?

(b) Suppose we fix $A$ and $c$, with $c \succeq 0$ (which implies the LP is not unbounded below). What can you say about the curvature of the mapping from $b$ to $f(A, b, c)$? Is it convex? Concave? Neither?

**4.44** *Convex-concave procedure.* This exercise is about a very simple but powerful heuristic for approximately solving problems of the form
$$\begin{array}{ll} \text{minimize} & f_0(x) + g(x) \\ \text{subject to} & f_i(x) \leq 0, \quad i = 1, \ldots, m \\ & Ax = b, \end{array}$$
with variable $x \in \mathbf{R}^n$, where $f_i$ are convex, $i = 0, \ldots, m$, but $g$ is *concave*. The objective term $g$ makes this problem not convex.

We will assume that $g$ is differentiable. We denote the linearization or first order Taylor expansion of $g$ at the point $z$ as
$$\hat{g}(x; z) = g(z) + \nabla g(z)^T (x - z)$$

(considered a function of $x$).

The *convex-concave procedure* is an iterative algorithm where $x^{k+1}$ is a solution of the problem

$$
\begin{array}{ll}
\text{minimize} & f_0(x) + \hat{g}(x; x^k) \\
\text{subject to} & f_i(x) \le 0, \quad i = 1, \dots, m \\
& Ax = b.
\end{array}
$$

In words: Each new iterate is the solution of the original problem, with the concave term replaced by its linearization at the previous iterate. (We assume that these problems have solutions.) This algorithm need not solve the origonal nonconvex problem globally, but it often finds a very good approximate solution.

(a) Explain why the problem solved in each iteration of the convex-concave procedure is convex.

(b) Show that $f_0(x^{k+1}) + g(x^{k+1}) \le f_0(x^k) + g(x^k)$. This means that the convex-concave procedure is a descent method, *i.e.*, the objective decreases in each iteration.

(c) Consider the problem

$$
\begin{array}{ll}
\text{minimize} & -x^T P x \\
\text{subject to} & \|x\|_2 \le 1,
\end{array}
$$

where $P \in \mathbf{S}_{++}^n$. (This problem has a simple analytical solution in terms of the eigenvectors of $P$.) Explain how to obtain the update in the convex-concave procedure. (For this simple problem, the update has an analytical solution.)

Generate a random instance of the problem (*i.e.*, choose $P \in \mathbf{S}_{++}^n$) and run the convex-concave procedure from several different starting points. Plot the objective value versus iteration for each run, along with a horizontal line that shows the (globally) optimal value. How well does the convex-concave procedure work for this problem?

**4.45** *A simple GP.* Use CVXPY to solve an instance of the GP described in the book in exercise 4.30, with data

$$\alpha_1 = 0.2, \quad \alpha_2 = 0.1, \alpha_3 = 0.3, \quad \alpha_4 = 1, \quad C_{\max} = 60,$$

and

$$T_{\min} = 10, \quad T_{\max} = 40, \quad r_{\min} = 35, \quad r_{\max} = 80, \quad w_{\min} = 3, \quad w_{\max} = 4.$$

Give the optimal cost, and optimal values of the variables $T$, $r$, and $w$.

You do not need to express the problem as a canonical GP (*i.e.*, with righthand sides all one), or convert the GP to a convex problem. In CVXPY, you'll use disciplined geometric programming (DGP), as described in cvxpy.org/tutorial/dgp/.

# 5 Duality

**5.1** *Numerical perturbation analysis example.* Consider the quadratic program

$$\begin{array}{ll} \text{minimize} & x_1^2 + 2x_2^2 - x_1 x_2 - x_1 \\ \text{subject to} & x_1 + 2x_2 \leq u_1 \\ & x_1 - 4x_2 \leq u_2, \\ & 5x_1 + 76x_2 \leq 1, \end{array}$$

with variables $x_1$, $x_2$, and parameters $u_1$, $u_2$.

(a) Solve this QP, for parameter values $u_1 = -2$, $u_2 = -3$, to find optimal primal variable values $x_1^\star$ and $x_2^\star$, and optimal dual variable values $\lambda_1^\star$, $\lambda_2^\star$ and $\lambda_3^\star$. Let $p^\star$ denote the optimal objective value. Verify that the KKT conditions hold for the optimal primal and dual variables you found (within reasonable numerical accuracy).

*Hint:* Check the documentation or users' guides for CVX* to find out how to retrieve optimal dual variables.

(b) We will now solve some perturbed versions of the QP, with

$$u_1 = -2 + \delta_1, \qquad u_2 = -3 + \delta_2,$$

where $\delta_1$ and $\delta_2$ each take values from $\{-0.1, 0, 0.1\}$. (There are a total of nine such combinations, including the original problem with $\delta_1 = \delta_2 = 0$.) For each combination of $\delta_1$ and $\delta_2$, make a prediction $p_{\text{pred}}^\star$ of the optimal value of the perturbed QP, and compare it to $p_{\text{exact}}^\star$, the exact optimal value of the perturbed QP (obtained by solving the perturbed QP). Put your results in the two righthand columns in a table with the form shown below. Check that the inequality $p_{\text{pred}}^\star \leq p_{\text{exact}}^\star$ holds.

| $\delta_1$ | $\delta_2$ | $p_{\text{pred}}^\star$ | $p_{\text{exact}}^\star$ |
|------------|------------|-------------------------|--------------------------|
| 0 | 0 | | |
| 0 | $-0.1$ | | |
| 0 | 0.1 | | |
| $-0.1$ | 0 | | |
| $-0.1$ | $-0.1$ | | |
| $-0.1$ | 0.1 | | |
| 0.1 | 0 | | |
| 0.1 | $-0.1$ | | |
| 0.1 | 0.1 | | |

**5.2** *A determinant maximization problem.* We consider the problem

$$\begin{array}{ll} \text{minimize} & \log \det X^{-1} \\ \text{subject to} & A_i^T X A_i \preceq B_i, \quad i = 1, \ldots, m, \end{array}$$

with variable $X \in \mathbf{S}^n$, and problem data $A_i \in \mathbf{R}^{n \times k_i}$, $B_i \in \mathbf{S}_{++}^{k_i}$, $i = 1, \ldots, m$. The constraint $X \succ 0$ is implicit.

We can give several interpretations of this problem. Here is one, from statistics. Let $z$ be a random variable in $\mathbf{R}^n$, with covariance matrix $X$, which is unknown. However, we do have (matrix) upper

bounds on the covariance of the random variables $y_i = A_i^T z \in \mathbf{R}^{k_i}$, which is $A_i^T X A_i$. The problem is to find the covariance matrix for $z$, that is consistent with the known upper bounds on the covariance of $y_i$, that has the largest volume confidence ellipsoid.

Derive the Lagrange dual of this problem. Be sure to state what the dual variables are (*e.g.*, vectors, scalars, matrices), any constraints they must satisfy, and what the dual function is. If the dual function has any implicit equality constraints, make them explicit. You can assume that $\sum_{i=1}^m A_i A_i^T \succ 0$, which implies the feasible set of the original problem is bounded.

What can you say about the optimal duality gap for this problem?

**5.3** The relative entropy between two vectors $x$, $y \in \mathbf{R}_{++}^n$ is defined as

$$\sum_{k=1}^n x_k \log(x_k/y_k).$$

This is a convex function, jointly in $x$ and $y$. In the following problem we calculate the vector $x$ that minimizes the relative entropy with a given vector $y$, subject to equality constraints on $x$:

$$\begin{array}{ll} \text{minimize} & \sum_{k=1}^n x_k \log(x_k/y_k) \\ \text{subject to} & Ax = b \\ & \mathbf{1}^T x = 1 \end{array}$$

The optimization variable is $x \in \mathbf{R}^n$. The domain of the objective function is $\mathbf{R}_{++}^n$. The parameters $y \in \mathbf{R}_{++}^n$, $A \in \mathbf{R}^{m \times n}$, and $b \in \mathbf{R}^m$ are given.

Derive the Lagrange dual of this problem and simplify it to get

$$\text{maximize} \quad b^T z - \log \sum_{k=1}^n y_k e^{a_k^T z}$$

($a_k$ is the $k$th column of $A$).

**5.4** *Source localization from range measurements* [Beck, Stoica, and Li]. A signal emitted by a source at an unknown position $x \in \mathbf{R}^n$ ($n = 2$ or $n = 3$) is received by $m$ sensors at known positions $y_1$, $\ldots$, $y_m \in \mathbf{R}^n$. From the strength of the received signals, we can obtain noisy estimates $d_k$ of the distances $\|x - y_k\|_2$. We are interested in estimating the source position $x$ based on the measured distances $d_k$.

In the following problem the error between the squares of the actual and observed distances is minimized:

$$\text{minimize} \quad f_0(x) = \sum_{k=1}^m \left( \|x - y_k\|_2^2 - d_k^2 \right)^2.$$

Introducing a new variable $t = x^T x$, we can express this as

$$\begin{array}{ll} \text{minimize} & \sum_{k=1}^m \left( t - 2y_k^T x + \|y_k\|_2^2 - d_k^2 \right)^2 \\ \text{subject to} & x^T x - t = 0. \end{array} \tag{9}$$

The variables are $x \in \mathbf{R}^n$, $t \in \mathbf{R}$. Although this problem is not convex, it can be shown that strong duality holds. (It is a variation on the problem discussed on page 229 and in exercise 5.29 of *Convex Optimization*.)

Solve (9) for an example with $m = 5$,

$$y_1 = \begin{bmatrix} 1.8 \\ 2.5 \end{bmatrix}, \qquad y_2 = \begin{bmatrix} 2.0 \\ 1.7 \end{bmatrix}, \qquad y_3 = \begin{bmatrix} 1.5 \\ 1.5 \end{bmatrix}, \qquad y_4 = \begin{bmatrix} 1.5 \\ 2.0 \end{bmatrix}, \qquad y_5 = \begin{bmatrix} 2.5 \\ 1.5 \end{bmatrix},$$

and

$$d = (2.00,\ 1.24,\ 0.59,\ 1.31,\ 1.44).$$

The figure shows some contour lines of the cost function $f_0$, with the positions $y_k$ indicated by circles.



To solve the problem, you can note that $x^\star$ is easily obtained from the KKT conditions for (9) if the optimal multiplier $\nu^\star$ for the equality constraint is known. You can use one of the following two methods to find $\nu^\star$.

- Derive the dual problem, express it as an SDP, and solve it using CVX.
- Reduce the KKT conditions to a nonlinear equation in $\nu$, and pick the correct solution (similarly as in exercise 5.29 of *Convex Optimization*).

**5.5** *Projection on the $\ell_1$ ball.* Consider the problem of projecting a point $a \in \mathbf{R}^n$ on the unit ball in $\ell_1$-norm:

$$\begin{array}{ll} \text{minimize} & (1/2)\|x - a\|_2^2 \\ \text{subject to} & \|x\|_1 \leq 1. \end{array}$$

Derive the dual problem and describe an efficient method for solving it. Explain how you can obtain the optimal $x$ from the solution of the dual problem.

**5.6** *A nonconvex problem with strong duality.* On page 229 of *Convex Optimization*, we consider the problem

$$
\begin{array}{ll}
\text{minimize} & f(x) = x^T A x + 2b^T x \\
\text{subject to} & x^T x \le 1
\end{array}
\tag{10}
$$

with variable $x \in \mathbf{R}^n$, and data $A \in \mathbf{S}^n$, $b \in \mathbf{R}^n$. We do not assume that $A$ is positive semidefinite, and therefore the problem is not necessarily convex. In this exercise we show that $x$ is (globally) optimal if and only if there exists a $\lambda$ such that

$$
\|x\|_2 \le 1, \qquad \lambda \ge 0, \qquad A + \lambda I \succeq 0, \qquad (A + \lambda I)x = -b, \qquad \lambda(1 - \|x\|_2^2) = 0.
\tag{11}
$$

From this we will develop an efficient method for finding the global solution. The conditions (11) are the KKT conditions for (10) with the inequality $A + \lambda I \succeq 0$ added.

(a) Show that if $x$ and $\lambda$ satisfy (11), then $f(x) = \inf_{\tilde{x}} L(\tilde{x}, \lambda) = g(\lambda)$, where $L$ is the Lagrangian of the problem and $g$ is the dual function. Therefore strong duality holds, and $x$ is globally optimal.

(b) Next we show that the conditions (11) are also necessary. Assume that $x$ is globally optimal for (10). We distinguish two cases.

  (i) $\|x\|_2 < 1$. Show that (11) holds with $\lambda = 0$.

  (ii) $\|x\|_2 = 1$. First prove that $(A + \lambda I)x = -b$ for some $\lambda \ge 0$. (In other words, the negative gradient $-(Ax + b)$ of the objective function is normal to the unit sphere at $x$, and point away from the origin.) You can show this by contradiction: if the condition does not hold, then there exists a direction $v$ with $v^T x < 0$ and $v^T(Ax + b) < 0$. Show that $f(x + tv) < f(x)$ for small positive $t$.

It remains to show that $A + \lambda I \succeq 0$. If not, there exists a $w$ with $w^T(A + \lambda I)w < 0$, and without loss of generality we can assume that $w^T x \ne 0$. Show that the point $y = x + tw$ with $t = -2w^T x / w^T w$ satisfies $\|y\|_2 = 1$ and $f(y) < f(x)$.

(c) The optimality conditions (11) can be used to derive a simple algorithm for (10). Using the eigenvalue decomposition $A = \sum_{i=1}^n \alpha_i q_i q_i^T$, of $A$, we make a change of variables $y_i = q_i^T x$, and write (10) as

$$
\begin{array}{ll}
\text{minimize} & \sum_{i=1}^n \alpha_i y_i^2 + 2 \sum_{i=1}^n \beta_i y_i \\
\text{subject to} & y^T y \le 1
\end{array}
$$

where $\beta_i = q_i^T b$. The transformed optimality conditions (11) are

$$
\|y\|_2 \le 1, \qquad \lambda \ge -\alpha_n, \qquad (\alpha_i + \lambda)y_i = -\beta_i, \quad i = 1, \ldots, n, \qquad \lambda(1 - \|y\|_2) = 0,
$$

if we assume that $\alpha_1 \ge \alpha_2 \ge \cdots \ge \alpha_n$. Give an algorithm for computing the solution $y$ and $\lambda$.

**5.7** *Connection between perturbed optimal cost and Lagrange dual functions.* In this exercise we explore the connection between the optimal cost, as a function of perturbations to the righthand sides of the constraints,

$$
p^\star(u) = \inf\{f_0(x) \mid \exists x \in \mathcal{D}, \ f_i(x) \le u_i, \ i = 1, \ldots, m\},
$$

(as in §5.6), and the Lagrange dual function

$$
g(\lambda) = \inf_x \left( f_0(x) + \lambda_1 f_1(x) + \cdots + \lambda_m f_m(x) \right),
$$

with domain restricted to $\lambda \succeq 0$. We assume the problem is convex. We consider a problem with inequality constraints only, for simplicity.

We have seen several connections between $p^\star$ and $g$:

- *Slater's condition and strong duality.* Slater's condition is: there exists $u \prec 0$ for which $p^\star(u) < \infty$. Strong duality (which follows) is: $p^\star(0) = \sup_\lambda g(\lambda)$. (Note that we include the condition $\lambda \succeq 0$ in the domain of $g$.)
- *A global inequality.* We have $p^\star(u) \geq p^\star(0) - \lambda^{\star T} u$, for any $u$, where $\lambda^\star$ maximizes $g$.
- *Local sensitivity analysis.* If $p^\star$ is differentiable at 0, then we have $\nabla p^\star(0) = -\lambda^\star$, where $\lambda^\star$ maximizes $g$.

In fact the two functions are closely related by conjugation. Show that

$$p^\star(u) = (-g)^*(-u).$$

Here $(-g)^*$ is the conjugate of the function $-g$. You can show this for $u \in \mathbf{int\,dom}\,p^\star$.

*Hint.* Consider the problem

$$
\begin{aligned}
\text{minimize} \quad & f_0(x) \\
\text{subject to} \quad & \tilde{f}_i(x) = f_i(x) - u_i \leq 0, \quad i = 1, \ldots, m.
\end{aligned}
$$

Verify that Slater's condition holds for this problem, for $u \in \mathbf{int\,dom}\,p^\star$.

**5.8** *Exact penalty method for SDP.* Consider the pair of primal and dual SDPs

$$
\begin{array}{llll}
\text{(P)} & \text{minimize} \quad c^T x & \text{(D)} \quad & \text{maximize} \quad \mathbf{tr}(F_0 Z) \\
& \text{subject to} \quad F(x) \preceq 0 & & \text{subject to} \quad \mathbf{tr}(F_i Z) + c_i = 0, \quad i = 1, \ldots, m \\
& & & \qquad\qquad\quad\, Z \succeq 0,
\end{array}
$$

where $F(x) = F_0 + x_1 F_1 + \cdots + x_n F_n$ and $F_i \in \mathbf{S}^p$ for $i = 0, \ldots, n$. Let $Z^\star$ be a solution of (D). Show that every solution $x^\star$ of the unconstrained problem

$$\text{minimize} \quad c^T x + M \max\{0, \lambda_{\max}(F(x))\},$$

where $M > \mathbf{tr}\, Z^\star$, is a solution of (P).

**5.9** *Quadratic penalty.* Consider the problem

$$
\begin{aligned}
\text{minimize} \quad & f_0(x) \\
\text{subject to} \quad & f_i(x) \leq 0, \quad i = 1, \ldots, m,
\end{aligned}
\tag{12}
$$

where the functions $f_i : \mathbf{R}^n \to \mathbf{R}$ are differentiable and convex.

Show that

$$\phi(x) = f_0(x) + \alpha \sum_{i=1}^{m} \max\{0, f_i(x)\}^2,$$

where $\alpha > 0$, is convex. Suppose $\tilde{x}$ minimizes $\phi$. Show how to find from $\tilde{x}$ a feasible point for the dual of (12). Find the corresponding lower bound on the optimal value of (12).

**5.10** *Boolean least-squares.* We consider the non-convex least-squares approximation problem with Boolean constraints

$$\begin{array}{ll} \text{minimize} & \|Ax - b\|_2^2 \\ \text{subject to} & x_k^2 = 1, \quad k = 1, \dots, n, \end{array} \tag{13}$$

where $A \in \mathbf{R}^{m \times n}$ and $b \in \mathbf{R}^m$. We assume that $\mathbf{rank}(A) = n$, *i.e.*, $A^T A$ is nonsingular.

One possible application of this problem is as follows. A signal $\hat{x} \in \{-1, 1\}^n$ is sent over a noisy channel, and received as $b = A\hat{x} + v$ where $v \sim \mathcal{N}(0, \sigma^2 I)$ is Gaussian noise. The solution of (13) is the maximum likelihood estimate of the input signal $\hat{x}$, based on the received signal $b$.

(a) Derive the Lagrange dual of (13) and express it as an SDP.

(b) Derive the dual of the SDP in part (a) and show that it is equivalent to

$$\begin{array}{ll} \text{minimize} & \mathbf{tr}(A^T A Z) - 2b^T A z + b^T b \\ \text{subject to} & \mathbf{diag}(Z) = \mathbf{1} \\ & \begin{bmatrix} Z & z \\ z^T & 1 \end{bmatrix} \succeq 0. \end{array} \tag{14}$$

Interpret this problem as a relaxation of (13). Show that if

$$\mathbf{rank}\left( \begin{bmatrix} Z & z \\ z^T & 1 \end{bmatrix} \right) = 1 \tag{15}$$

at the optimum of (14), then the relaxation is exact, *i.e.*, the optimal values of problems (13) and (14) are equal, and the optimal solution $z$ of (14) is optimal for (13). This suggests a heuristic for rounding the solution of the SDP (14) to a feasible solution of (13), if (15) does not hold. We compute the eigenvalue decomposition

$$\begin{bmatrix} Z & z \\ z^T & 1 \end{bmatrix} = \sum_{i=1}^{n+1} \lambda_i \begin{bmatrix} v_i \\ t_i \end{bmatrix} \begin{bmatrix} v_i \\ t_i \end{bmatrix}^T,$$

where $v_i \in \mathbf{R}^n$ and $t_i \in \mathbf{R}$, and approximate the matrix by a rank-one matrix

$$\begin{bmatrix} Z & z \\ z^T & 1 \end{bmatrix} \approx \lambda_1 \begin{bmatrix} v_1 \\ t_1 \end{bmatrix} \begin{bmatrix} v_1 \\ t_1 \end{bmatrix}^T.$$

(Here we assume the eigenvalues are sorted in decreasing order). Then we take $x = \mathbf{sign}(v_1)$ as our guess of good solution of (13).

(c) We can also give a probabilistic interpretation of the relaxation (14). Suppose we interpret $z$ and $Z$ as the first and second moments of a random vector $v \in \mathbf{R}^n$ (*i.e.*, $z = \mathbf{E} \, v$, $Z = \mathbf{E} \, vv^T$). Show that (14) is equivalent to the problem

$$\begin{array}{ll} \text{minimize} & \mathbf{E} \, \|Av - b\|_2^2 \\ \text{subject to} & \mathbf{E} \, v_k^2 = 1, \quad k = 1, \dots, n, \end{array}$$

where we minimize over all possible probability distributions of $v$.

This interpretation suggests another heuristic method for computing suboptimal solutions of (13) based on the result of (14). We choose a distribution with first and second moments

$\mathbf{E} \, v = z$, $\mathbf{E} \, vv^T = Z$ (for example, the Gaussian distribution $\mathcal{N}(z, Z - zz^T)$). We generate a number of samples $\tilde{v}$ from the distribution and round them to feasible solutions $x = \mathbf{sign}(\tilde{v})$. We keep the solution with the lowest objective value as our guess of the optimal solution of (13).

(d) Solve the dual problem (14) using CVX. Generate problem instances using the Matlab code

```
randn('state',0)
m = 50;
n = 40;
A = randn(m,n);
xhat = sign(randn(n,1));
b = A*xhat + s*randn(m,1);
```

for four values of the noise level $s$: $s = 0.5$, $s = 1$, $s = 2$, $s = 3$. For each problem instance, compute suboptimal feasible solutions $x$ using the the following heuristics and compare the results.

(i) $x^{(a)} = \mathbf{sign}(x_{\mathrm{ls}})$ where $x_{\mathrm{ls}}$ is the solution of the least-squares problem

$$\text{minimize} \quad \|Ax - b\|_2^2.$$

(ii) $x^{(b)} = \mathbf{sign}(z)$ where $z$ is the optimal value of the variable $z$ in the SDP (14).

(iii) $x^{(c)}$ is computed from a rank-one approximation of the optimal solution of (14), as explained in part (b) above.

(iv) $x^{(d)}$ is computed by rounding 100 samples of $\mathcal{N}(z, Z - zz^T)$, as explained in part (c) above.

**5.11** *Monotone transformation of the objective.* Consider the optimization problem

$$\begin{array}{ll} \text{minimize} & f_0(x) \\ \text{subject to} & f_i(x) \le 0, \quad i = 1, \dots, m. \end{array} \tag{16}$$

where $f_i : \mathbf{R}^n \to \mathbf{R}$ for $i = 0, 1, \dots, m$ are convex. Suppose $\phi : \mathbf{R} \to \mathbf{R}$ is increasing and convex. Then the problem

$$\begin{array}{ll} \text{minimize} & \tilde{f}_0(x) = \phi(f_0(x)) \\ \text{subject to} & f_i(x) \le 0, \quad i = 1, \dots, m \end{array} \tag{17}$$

is convex and equivalent to it; in fact, it has the same optimal set as (16).

In this problem we explore the connections between the duals of the two problems (16) and (17). We assume $f_i$ are differentiable, and to make things specific, we take $\phi(a) = \exp a$.

(a) Suppose $\lambda$ is feasible for the dual of (16), and $\bar{x}$ minimizes

$$f_0(x) + \sum_{i=1}^{m} \lambda_i f_i(x).$$

Show that $\bar{x}$ also minimizes

$$\exp f_0(x) + \sum_{i=1}^{m} \tilde{\lambda}_i f_i(x)$$

for appropriate choice of $\tilde{\lambda}$. Thus, $\tilde{\lambda}$ is dual feasible for (17).

(b) Let $p^\star$ denote the optimal value of (16) (so the optimal value of (17) is $\exp p^\star$). From $\lambda$ we obtain the bound

$$p^\star \geq g(\lambda),$$

where $g$ is the dual function for (16). From $\tilde{\lambda}$ we obtain the bound $\exp p^\star \geq \tilde{g}(\tilde{\lambda})$, where $\tilde{g}$ is the dual function for (17). This can be expressed as

$$p^\star \geq \log \tilde{g}(\tilde{\lambda}).$$

How do these bounds compare? Are they the same, or is one better than the other?

**5.12** *Variable bounds and dual feasibility.* In many problems the constraints include *variable bounds*, as in

$$\begin{array}{ll}
\text{minimize} & f_0(x) \\
\text{subject to} & f_i(x) \leq 0, \quad i = 1, \ldots, m \\
& l_i \leq x_i \leq u_i, \quad i = 1, \ldots, n.
\end{array} \qquad (18)$$

Let $\mu \in \mathbf{R}_+^n$ be the Lagrange multipliers associated with the constraints $x_i \leq u_i$, and let $\nu \in \mathbf{R}_+^n$ be the Lagrange multipliers associated with the constraints $l_i \geq x_i$. Thus the Lagrangian is

$$L(x, \lambda, \mu, \nu) = f_0(x) + \sum_{i=1}^m \lambda_i f_i(x) + \mu^T(x - u) + \nu^T(l - x).$$

(a) Show that for any $x \in \mathbf{R}^n$ and any $\lambda$, we can choose $\mu \succeq 0$ and $\nu \succeq 0$ so that $x$ minimizes $L(x, \lambda, \mu, \nu)$. In particular, it is very easy to find dual feasible points.

(b) Construct a dual feasible point $(\lambda, \mu, \nu)$ by applying the method you found in part (a) with $x = (l + u)/2$ and $\lambda = 0$. From this dual feasible point you get a lower bound on $f^\star$. Show that this lower bound can be expressed as

$$f^\star \geq f_0((l+u)/2) - ((u-l)/2)^T |\nabla f_0((l+u)/2)|$$

where $|\cdot|$ means componentwise. Can you prove this bound directly?

**5.13** *Deducing costs from samples of optimal decision.* A system (such as a firm or an organism) chooses a vector of values $x$ as a solution of the LP

$$\begin{array}{ll}
\text{minimize} & c^T x \\
\text{subject to} & Ax \succeq b,
\end{array}$$

with variable $x \in \mathbf{R}^n$. You can think of $x \in \mathbf{R}^n$ as a vector of activity levels, $b \in \mathbf{R}^m$ as a vector of requirements, and $c \in \mathbf{R}^n$ as a vector of costs or prices for the activities. With this interpretation, the LP above finds the cheapest set of activity levels that meet all requirements. (This interpretation is not needed to solve the problem.)

We suppose that $A$ is known, along with a set of data

$$(b^{(1)}, x^{(1)}), \quad \ldots, \quad (b^{(r)}, x^{(r)}),$$

where $x^{(j)}$ is an optimal point for the LP, with $b = b^{(j)}$. (The solution of an LP need not be unique; all we say here is that $x^{(j)}$ is *an* optimal solution.) Roughly speaking, we have samples of optimal decisions, for different values of requirements.

You *do not* know the cost vector $c$. Your job is to compute the tightest possible bounds on the costs $c_i$ from the given data. More specifically, you are to find $c_i^{\max}$ and $c_i^{\min}$, the maximum and minimum possible values for $c_i$, consistent with the given data.

Note that if $x$ is optimal for the LP for a given $c$, then it is also optimal if $c$ is scaled by any positive factor. To normalize $c$, then, we will assume that $c_1 = 1$. Thus, we can interpret $c_i$ as the relative cost of activity $i$, compared to activity 1.

(a) Explain how to find $c_i^{\max}$ and $c_i^{\min}$. Your method can involve the solution of a reasonable number (not exponential in $n$, $m$ or $r$) of convex or quasiconvex optimization problems.

(b) Carry out your method using the data found in `deducing_costs_data.m`. You may need to determine whether individual inequality constraints are tight; to do so, use a tolerance threshold of $\epsilon = 10^{-3}$. (In other words: if $a_k^T x - b_k \leq 10^{-3}$, you can consider this inequality as tight.)

Give the values of $c_i^{\max}$ and $c_i^{\min}$, and make a very brief comment on the results.

**5.14** *Kantorovich inequality.*

(a) Suppose $a \in \mathbf{R}^n$ with $a_1 \geq a_2 \geq \cdots \geq a_n > 0$, and $b \in \mathbf{R}^n$ with $b_k = 1/a_k$.

Derive the KKT conditions for the convex optimization problem

$$\begin{array}{ll} \text{minimize} & -\log(a^T x) - \log(b^T x) \\ \text{subject to} & x \succeq 0, \quad \mathbf{1}^T x = 1. \end{array}$$

Show that $x = (1/2, 0, \ldots, 0, 1/2)$ is optimal.

(b) Suppose $A \in \mathbf{S}_{++}^n$ with eigenvalues $\lambda_k$ sorted in decreasing order. Apply the result of part (a), with $a_k = \lambda_k$, to prove the *Kantorovich inequality:*

$$2 \left(u^T A u\right)^{1/2} \left(u^T A^{-1} u\right)^{1/2} \leq \sqrt{\frac{\lambda_1}{\lambda_n}} + \sqrt{\frac{\lambda_n}{\lambda_1}}$$

for all $u$ with $\|u\|_2 = 1$.

**5.15** State and solve the optimality conditions for the problem

$$\begin{array}{ll} \text{minimize} & \log \det \left( \begin{bmatrix} X_1 & X_2 \\ X_2^T & X_3 \end{bmatrix}^{-1} \right) \\ \text{subject to} & \mathbf{tr}\, X_1 = \alpha \\ & \mathbf{tr}\, X_2 = \beta \\ & \mathbf{tr}\, X_3 = \gamma. \end{array}$$

The optimization variable is

$$X = \begin{bmatrix} X_1 & X_2 \\ X_2^T & X_3 \end{bmatrix},$$

with $X_1 \in \mathbf{S}^n$, $X_2 \in \mathbf{R}^{n \times n}$, $X_3 \in \mathbf{S}^n$. The domain of the objective function is $\mathbf{S}_{++}^{2n}$. We assume $\alpha > 0$, and $\alpha\gamma > \beta^2$.

**5.16** Consider the optimization problem

$$
\begin{array}{ll}
\text{minimize} & -\log \det X + \mathbf{tr}(SX) \\
\text{subject to} & X \text{ is tridiagonal}
\end{array}
$$

with domain $\mathbf{S}^n_{++}$ and variable $X \in \mathbf{S}^n$. The matrix $S \in \mathbf{S}^n$ is given. Show that the optimal $X_{\text{opt}}$ satisfies

$$
(X_{\text{opt}}^{-1})_{ij} = S_{ij}, \quad |i - j| \le 1.
$$

**5.17** We denote by $f(A)$ the sum of the largest $r$ eigenvalues of a symmetric matrix $A \in \mathbf{S}^n$ (with $1 \le r \le n$), *i.e.*,

$$
f(A) = \sum_{k=1}^{r} \lambda_k(A),
$$

where $\lambda_1(A)$, ..., $\lambda_n(A)$ are the eigenvalues of $A$ sorted in decreasing order.

(a) Show that the optimal value of the SDP

$$
\begin{array}{ll}
\text{maximize} & \mathbf{tr}(AX) \\
\text{subject to} & \mathbf{tr}\, X = r \\
& 0 \preceq X \preceq I,
\end{array}
$$

with variable $X \in \mathbf{S}^n$, is equal to $f(A)$.

(b) Show that $f$ is a convex function.

(c) Assume $A(x) = A_0 + x_1 A_1 + \cdots + x_m A_m$, with $A_k \in \mathbf{S}^n$. Use the observation in part (a) to formulate the optimization problem

$$
\text{minimize} \quad f(A(x)),
$$

with variable $x \in \mathbf{R}^m$, as an SDP.

**5.18** *An exact penalty function.* Suppose we are given a convex problem

$$
\begin{array}{ll}
\text{minimize} & f_0(x) \\
\text{subject to} & f_i(x) \le 0, \ i = 1, \ldots, m
\end{array}
\tag{19}
$$

with dual

$$
\begin{array}{ll}
\text{maximize} & g(\lambda) \\
\text{subject to} & \lambda \succeq 0.
\end{array}
\tag{20}
$$

We assume that Slater's condition holds, so we have strong duality and the dual optimum is attained. For simplicity we will assume that there is a unique dual optimal solution $\lambda^\star$.

For fixed $t > 0$, consider the unconstrained minimization problem

$$
\text{minimize } f_0(x) + t \max_{i=1,\ldots,m} f_i(x)^+,
\tag{21}
$$

where $f_i(x)^+ = \max\{f_i(x), 0\}$.

(a) Show that the objective function in (21) is convex.

(b) We can express (21) as

$$
\begin{aligned}
\text{minimize} \quad & f_0(x) + ty \\
\text{subject to} \quad & f_i(x) \le y, \quad i = 1. \dots, m \\
& 0 \le y
\end{aligned}
\tag{22}
$$

where the variables are $x$ and $y \in \mathbf{R}$.

Find the Lagrange dual problem of (22) and express it in terms of the Lagrange dual function $g$ for problem (19).

(c) Use the result in (b) to prove the following property. If $t > \mathbf{1}^T \lambda^\star$, then any minimizer of (21) is also an optimal solution of (19).

(The second term in (21) is called a *penalty function* for the constraints in (19). It is zero if $x$ is feasible, and adds a penalty to the cost function when $x$ is infeasible. The penalty function is called *exact* because for $t$ large enough, the solution of the unconstrained problem (21) is also a solution of (19).)

**5.19** *Infimal convolution.* Let $f_1, \dots, f_m$ be convex functions on $\mathbf{R}^n$. Their *infimal convolution*, denoted $g = f_1 \diamond \cdots \diamond f_m$ (several other notations are also used), is defined as

$$
g(x) = \inf\{f_1(x_1) + \cdots + f_m(x_m) \mid x_1 + \cdots + x_m = x\},
$$

with the natural domain (*i.e.*, defined by $g(x) < \infty$). In one simple interpretation, $f_i(x_i)$ is the cost for the $i$th firm to produce a mix of products given by $x_i$; $g(x)$ is then the optimal cost obtained if the firms can freely exchange products to produce, all together, the mix given by $x$. (The name 'convolution' presumably comes from the observation that if we replace the sum above with the product, and the infimum above with integration, then we obtain the normal convolution.)

(a) Show that $g$ is convex.

(b) Show that $g^* = f_1^* + \cdots + f_m^*$. In other words, the conjugate of the infimal convolution is the sum of the conjugates.

(c) Verify the identity in part (b) for the specific case of two strictly convex quadratic functions, $f_i(x) = (1/2)x^T P_i x$, with $P_i \in \mathbf{S}_{++}^n$, $i = 1, 2$.

*Hint:* Depending on how you work out the conjugates, you might find the matrix identity $(X + Y)^{-1}Y = X^{-1}(X^{-1} + Y^{-1})^{-1}$ useful.

**5.20** Derive the Lagrange dual of the optimization problem

$$
\begin{aligned}
\text{minimize} \quad & \sum_{i=1}^{n} \phi(x_i) \\
\text{subject to} \quad & Ax = b
\end{aligned}
$$

with variable $x \in \mathbf{R}^n$, where

$$
\phi(u) = \frac{|u|}{c - |u|} = -1 + \frac{c}{c - |u|}, \qquad \mathbf{dom}\,\phi = (-c, c).
$$

$c$ is a positive parameter. The figure shows $\phi$ for $c = 1$.

**5.21** *Robust LP with polyhedral cost uncertainty.* We consider a robust linear programming problem, with polyhedral uncertainty in the cost:

$$\begin{array}{ll} \text{minimize} & \sup_{c \in \mathcal{C}} c^T x \\ \text{subject to} & Ax \succeq b, \end{array}$$

with variable $x \in \mathbf{R}^n$, where $\mathcal{C} = \{c \mid Fc \preceq g\}$. You can think of $x$ as the quantities of $n$ products to buy (or sell, when $x_i < 0$), $Ax \succeq b$ as constraints, requirements, or limits on the available quantities, and $\mathcal{C}$ as giving our knowledge or assumptions about the product prices at the time we place the order. The objective is then the worst possible (*i.e.*, largest) cost, given the quantities $x$, consistent with our knowledge of the prices.

In this exercise, you will work out a tractable method for solving this problem. You can assume that $\mathcal{C} \neq \emptyset$, and the inequalities $Ax \succeq b$ are feasible.

(a) Let $f(x) = \sup_{c \in \mathcal{C}} c^T x$ be the objective in the problem above. Explain why $f$ is convex.

(b) Find the dual of the problem

$$\begin{array}{ll} \text{maximize} & c^T x \\ \text{subject to} & Fc \preceq g, \end{array}$$

with variable $c$. (The problem data are $x$, $F$, and $g$.) Explain why the optimal value of the dual is $f(x)$.

This shows that you can express the worst-case cost $\sup_{c \in \mathcal{C}} c^T x$ as the optimal value of a convex *minimization* problem, in which $x$, $F$, and $g$ appear as data.

(c) Use the expression for $f(x)$ found in part (b) in the original problem, to obtain a single LP equivalent to the original robust LP.

*Hint.* Use the rule expressed roughly as: min-min is the same as min. More precisely the problem

$$\begin{array}{ll} \text{minimize} & \inf_{v \in \mathcal{V}} f(u, v) \\ \text{subject to} & u \in \mathcal{U}, \end{array}$$

with variable $u$ (and $v$ being a dummy variable), is equivalent to the problem

$$\begin{array}{ll} \text{minimize} & f(u, v) \\ \text{subject to} & u \in \mathcal{U}, \quad v \in \mathcal{V}, \end{array}$$

with variables $u$ and $v$.

(d) Carry out the method found in part (c) to solve a robust LP with the data below. In Matlab:

```
rand('seed',0);
A = rand(30,10);
b = rand(30,1);
c_nom = 1+rand(10,1);  % nominal c values
```

In Python:

```
import numpy as np
np.random.seed(10)
(m, n) = (30, 10)
A = np.random.rand(m, n); A = np.asmatrix(A)
b = np.random.rand(m, 1); b = np.asmatrix(b)
c_nom = np.ones((n, 1)) + np.random.rand(n, 1); c_nom = np.asmatrix(c_nom)
```

In Julia:

```
Random.seed!(10)
n = 10;
m = 30;
A = rand(m, n);
b = rand(m, 1);
c_nom = 1 .+ rand(n, 1);
```

Then, use $\mathcal{C}$ described as follows. Each $c_i$ deviates no more than 25% from its nominal value, *i.e.*, $0.75c_{\mathrm{nom}} \preceq c \preceq 1.25c_{\mathrm{nom}}$, and the average of $c$ does not deviate more than 10% from the average of the nominal values, *i.e.*, $0.9(\mathbf{1}^T c_{\mathrm{nom}})/n \leq \mathbf{1}^T c/n \leq 1.1(\mathbf{1}^T c_{\mathrm{nom}})/n$.

Compare the worst-case cost $f(x)$ and the nominal cost $c_{\mathrm{nom}}^T x$ for $x$ optimal for the robust problem, and for $x$ optimal for the nominal problem, *i.e.*, with objective $c_{\mathrm{nom}}^T x$. Compare the values and make a brief comment.

**5.22** *Diagonal scaling with prescribed column and row sums* [Marshall and Olkin]. Let $A$ be an $n \times n$ matrix with positive entries, and let $c$ and $d$ be positive $n$-vectors that satisfy $\mathbf{1}^T c = \mathbf{1}^T d = 1$. Consider the geometric program

$$
\begin{aligned}
\text{minimize} \quad & x^T A y \\
\text{subject to} \quad & \prod_{i=1}^n x_i^{c_i} = 1 \\
& \prod_{j=1}^n y_j^{d_j} = 1,
\end{aligned}
$$

with variables $x, y \in \mathbf{R}^n$ (and implicit constraints $x \succ 0$, $y \succ 0$). Write this geometric program in convex form and derive the optimality conditions. Show that if $x$ and $y$ are optimal, then the matrix

$$
B = \frac{1}{x^T A y} \operatorname{\mathbf{diag}}(x) A \operatorname{\mathbf{diag}}(y)
$$

satisfies $B\mathbf{1} = c$ and $B^T\mathbf{1} = d$.

**5.23** [Schoenberg] Suppose $m$ balls in $\mathbf{R}^n$, with centers $a_i$ and radii $r_i$, have a nonempty intersection. We define $y$ to be a point in the intersection, so

$$\|y - a_i\|_2 \leq r_i, \quad i = 1, \ldots, m. \tag{23}$$

Suppose we move the centers to new positions $b_i$ in such a way that the distances between the centers do not increase:

$$\|b_i - b_j\|_2 \leq \|a_i - a_j\|_2, \quad i, j = 1, \ldots, m. \tag{24}$$

We will prove that the intersection of the translated balls is nonempty, *i.e.*, there exists a point $x$ with $\|x - b_i\|_2 \leq r_i$, $i = 1, \ldots, m$. To show this we prove that the optimal value of

$$\begin{array}{ll} \text{minimize} & t \\ \text{subject to} & \|x - b_i\|_2^2 \leq r_i^2 + t, \quad i = 1, \ldots, m, \end{array} \tag{25}$$

with variables $x \in \mathbf{R}^n$ and $t \in \mathbf{R}$, is less than or equal to zero.

(a) Show that (24) implies that

$$t - (x - b_i)^T (x - b_j) \leq -(y - a_i)^T (y - a_j) \quad \text{for } i, j \in I,$$

if $(x, t)$ is feasible in (25), and $I \subseteq \{1, \ldots, m\}$ is the set of active constraints at $x, t$.

(b) Suppose $x, t$ are optimal in (25) and that $\lambda_1$, ..., $\lambda_m$ are optimal dual variables. Use the optimality conditions for (25) and the inequality in part a to show that

$$t = t - \|\sum_{i=1}^m \lambda_i (x - b_i)\|_2^2 \leq -\|\sum_{i=1}^m \lambda_i (y - a_i)\|_2^2.$$

**5.24** *Controlling a switched linear system via duality.* We consider a discrete-time dynamical system with state $x_t \in \mathbf{R}^n$. The state propagates according to the recursion

$$x_{t+1} = A_t x_t, \quad t = 0, 1, \ldots, T - 1,$$

where the matrices $A_t$ are to be chosen from a finite set $\mathcal{A} = \{A^{(1)}, \ldots, A^{(K)}\}$ in order to control the state $x_t$ over a finite time horizon of length $T$. More formally, the switched-linear control problem is

$$\begin{array}{ll} \text{minimize} & \sum_{t=1}^T f(x_t) \\ \text{subject to} & x_{t+1} = A^{(u_t)} x_t, \quad \text{for } t = 0, \ldots, T - 1 \end{array}$$

The problem variables are $x_t \in \mathbf{R}^n$, for $t = 1, \ldots, T$, and $u_t \in \{1, \ldots, K\}$, for $t = 0, \ldots, T - 1$. We assume the initial state, $x_0 \in \mathbf{R}^n$ is a problem parameter (*i.e.*, is known and fixed). You may assume the function $f$ is convex, though it isn't necessary for this problem.

Note that, to find a feasible point, we take any sequence $u_0, \ldots, u_{T-1} \in \{1, \ldots, K\}$; we then generate a feasible point according to the recursion

$$x_{t+1} = A^{(u_t)} x_t, \quad t = 0, 1, \ldots, T - 1.$$

The switched-linear control problem is *not* convex, and is hard to solve globally. Instead, we consider a heuristic based on Lagrange duality.

(a) Find the dual of the switched-linear control problem explicitly in terms of $x_0$, $A^{(1)}, \ldots, A^{(K)}$, the function $f$, and its conjugate $f^*$. Your formulation cannot involve a number of constraints or objective terms that is exponential in $K$ or $T$. (This includes minimization or maximization with an exponential number of terms.)

(b) Given optimal dual variables $\nu_1^\star, \ldots, \nu_T^\star$ corresponding to the $T$ constraints of the switched-linear control problem, a heuristic to choose $u_t$ is to minimize the Langrangian using these optimal dual variables:

$$(\tilde{u}_0, \ldots, \tilde{u}_{T-1}) \in \operatorname*{argmin}_{u_0, \ldots, u_{T-1} \in \{1, \ldots, K\}} \inf_{x_1, \ldots, x_T} L(x_1, \ldots, x_T, u_0, \ldots, u_{T-1}, \nu_1^\star, \ldots, \nu_T^\star),$$

Given the optimal dual variables, show (explicitly) how to find $\tilde{u}_0, \ldots, \tilde{u}_{T-1}$.

(c) Consider the case $f(x) = (1/2)x^T Q x$. with $Q \in \mathbf{S}_{++}^n$. For the data given in sw_lin_ctrl_data.*, solve the dual problem and report its optimal value $d^\star$, which is a lower bound on $p^\star$. (As a courtesy, we also included $p^\star$ in the data file, so you can check your bound.)

(d) Using the same data as is part (c), carry out the heuristic method of part (b) to compute $\tilde{u}_0, \ldots, \tilde{u}_{T-1}$. Use these values to generate a feasible point. Report the value of the objective at this feasible point, which is an upper bound on $p^\star$.

**5.25** [Friedland and Karlin] Let $A$ be an $n \times n$ matrix with positive entries, and let $u$ and $v$ be two positive $n$-vectors. Show that one can compute positive diagonal matrices $D_1$ and $D_2$ that satisfy

$$(D_1 A D_2) u = u, \qquad (D_1 A D_2)^T v = v \tag{26}$$

by the following method. Define $\alpha_i = u_i v_i$ for $i = 1, \ldots, n$, and solve the optimization problem

$$
\begin{aligned}
\text{minimize} \quad & \prod_{i=1}^{n} \left( \sum_{j=1}^{n} A_{ij} x_j \right)^{\alpha_i} \\
\text{subject to} \quad & \prod_{i=1}^{n} x_i^{\alpha_i} = 1
\end{aligned}
\tag{27}
$$

with domain $\{x \in \mathbf{R}^n \mid x \succ 0\}$. Then use the solution $x$ to define

$$D_1 = \mathbf{diag}(u)\,\mathbf{diag}(Ax)^{-1}, \qquad D_2 = \mathbf{diag}(u)^{-1}\,\mathbf{diag}(x).$$

The first equality in (26) follows immediately from the expressions of $D_1$ and $D_2$. To show the second equality in (26), express (27) as a convex optimization problem and derive the optimality conditions.

**5.26** Consider the optimization problem

$$\text{minimize } \|Ax - b\|_2 + \gamma \|x\|_1$$

with $A \in \mathbf{R}^{m \times n}$, $b \in \mathbf{R}^m$, and $\gamma > 0$. The variable is an $n$-vector $x$.

(a) Derive the Lagrange dual of the equivalent problem

$$
\begin{aligned}
\text{minimize} \quad & \|y\|_2 + \gamma \|x\|_1 \\
\text{subject to} \quad & Ax - b = y
\end{aligned}
$$

with variables $x \in \mathbf{R}^n$ and $y \in \mathbf{R}^m$.

(b) Suppose $Ax^\star - b \neq 0$ where $x^\star$ is an optimal point. Define $r = (Ax^\star - b)/\|Ax^\star - b\|_2$. Show that

$$\|A^T r\|_\infty \leq \gamma, \qquad r^T Ax^\star + \gamma \|x^\star\|_1 = 0.$$

(c) Show that if the Euclidean norm of the $i$th column of $A$ is less than $\gamma$, then $x_i^\star = 0$.

**5.27** Consider the optimization problem

$$\text{minimize} \quad \sum_{i=1}^{m} h(\|A_i x + b_i\|_2) - c^T x$$

with variable $x \in \mathbf{R}^n$, where $c \in \mathbf{R}^n$, $A_i \in \mathbf{R}^{3 \times n}$, $b_i \in \mathbf{R}^3$, and

$$h(u) = \begin{cases} (u-1)^2/2 & u \geq 1 \\ 0 & \text{otherwise.} \end{cases}$$

Derive the Lagrange dual of the equivalent problem

$$\begin{aligned} \text{minimize} \quad & \sum_{i=1}^{m} h(\|y_i\|_2) - c^T x \\ \text{subject to} \quad & A_i x + b_i - y_i = 0, \quad i = 1, \ldots, m, \end{aligned}$$

with variables $x \in \mathbf{R}^n$ and $y_i \in \mathbf{R}^3$ for $i = 1, \ldots, m$.

This optimization problem describes the equilibrium of a structure consisting of $m$ elastic cables suspended between different points or nodes. Some of the nodes are anchored, other nodes are free. The variable $x$ contains the displacements of the free nodes. The vector $c$ specifies the external forces applied to the nodes. The norm $\|A_i x + b_i\|_2$ is the distance between the endpoints of the $i$th cable as a function of the node displacements. The $i$th term in the sum in the cost function is the potential energy stored in the $i$th cable, assuming its undeformed length is one.

**5.28** *Robust least squares with polyhedral uncertainty.* We consider a robust least-squares problem

$$\text{minimize} \quad \sum_{i=1}^{m} \sup_{a_i \in P_i} (a_i^T x - b_i)^2$$

with variable $x \in \mathbf{R}^n$. Each set $P_i$ is a nonempty and bounded polyhedron, defined as

$$P_i = \{a_i \in \mathbf{R}^n \mid C_i a_i \preceq d_i\}$$

with $C_i \in \mathbf{R}^{p_i \times n}$, $d_i \in \mathbf{R}^{p_i}$. If we introduce variables $t_i \geq \sup_{a_i \in P_i} |a_i^T x - b_i|$ we can write the problem as

$$\begin{aligned} \text{minimize} \quad & \sum_{i=1}^{m} t_i^2 \\ \text{subject to} \quad & \sup_{a_i \in P_i} \max\{a_i^T x - b_i, -a_i^T x + b_i\} \leq t_i, \quad i = 1, \ldots, m. \end{aligned}$$

Formulate this problem as a QP.

**5.29** For an $m \times n$-matrix $A$ (with $m \geq n$) and an integer $k$ between 1 and $n$, we define $f(A)$ as the sum of the largest $k$ singular values of $A$:

$$f(A) = \sigma_1(A) + \cdots + \sigma_k(A),$$

where $\sigma_1(A)$, $\sigma_2(A)$, ..., $\sigma_n(A)$ denote the singular values of $A$ in nonincreasing order.

(a) Show that $f(A)$ is the optimal value of the SDP

$$
\begin{array}{ll}
\text{maximize} & \mathbf{tr}(A^T X) \\
\text{subject to} & \begin{bmatrix} U & X \\ X^T & V \end{bmatrix} \succeq 0 \\
& U \preceq I \\
& V \preceq I \\
& \mathbf{tr}\, U + \mathbf{tr}\, V = 2k,
\end{array}
$$

with variables $X \in \mathbf{R}^{m \times n}$, $U \in \mathbf{S}^m$, $V \in \mathbf{S}^n$.

*Hint.* The singular value decomposition of $A$ can be written as $A = P\Sigma Q^T$, where $P \in \mathbf{R}^{m \times m}$ and $Q \in \mathbf{R}^{n \times n}$ are orthogonal matrices ($P^T P = I$, $Q^T Q = I$), and $\Sigma$ is a diagonal $m \times n$ matrix with elements $\Sigma_{ii} = \sigma_i(A)$ for $i = 1, \dots, n$, and $\Sigma_{ij} = 0$ for $i \neq j$. Use the decomposition to reformulate the SDP as an equivalent SDP in which $A$ in the objective is replaced by $\Sigma$.

(b) What does the result of part (a) imply about the convexity properties of $f(A)$?

(c) Derive the Lagrange dual of the SDP in part (a). Use the dual problem to give an SDP formulation of the problem

$$\text{minimize} \quad f(A_0 + x_1 A_1 + \cdots + x_p A_p)$$

with variable $x \in \mathbf{R}^p$, where $A_0$, ..., $A_p$ are given $m \times n$ matrices.

**5.30** Consider the convex optimization problem

$$\text{minimize} \quad c^T x + \frac{1}{\mu} \sum_{i=1}^m \log(1 + e^{\mu(a_i^T x - b_i)}) \tag{28}$$

with variable $x \in \mathbf{R}^n$, where $\mu$ is a positive constant.

(a) Derive the Lagrange dual of the equivalent problem

$$
\begin{array}{ll}
\text{minimize} & c^T x + \dfrac{1}{\mu} \sum_{i=1}^m \log(1 + \exp(\mu y_i)) \\
\text{subject to} & Ax - b \preceq y
\end{array}
$$

with variables $x \in \mathbf{R}^n$, $y \in \mathbf{R}^m$, where $A$ is the $m \times n$-matrix with $i$th row $a_i^T$.

(b) Suppose the pair of primal and dual linear programs

$$
\begin{array}{ll}
\text{minimize} & c^T x \\
\text{subject to} & Ax \preceq b
\end{array}
\qquad
\begin{array}{ll}
\text{maximize} & -b^T z \\
\text{subject to} & A^T z + c = 0 \\
& z \succeq 0
\end{array}
$$

has a finite optimal value $p^\star$ and a dual optimal solution $z^\star$ that satisfies $z^\star \preceq \mathbf{1}$. Let $q^\star$ be the optimal value of (28). Show that

$$p^\star \le q^\star \le p^\star + \frac{m \log 2}{\mu}.$$

**5.31** In this problem, $r$ is an integer between 1 and $n$, and $\|x\|$ denotes the norm

$$\|x\| = \max_{1 \le i_1 < \cdots < i_r \le n} |x_{i_1}| + \cdots + |x_{i_r}|$$

on $\mathbf{R}^n$ ($\|x\|$ is the sum of the largest $r$ absolute values of entries of $x$). For $r = 1$, this is the Chebyshev norm $\|x\|_\infty = \max_i |x_i|$; for $r = n$, it is the 1-norm $\|x\|_1 = \sum_k |x_k|$.

(a) Explain why $\|x\|$ is the optimal value of the optimization problem

$$
\begin{array}{ll}
\text{maximize} & x^T y \\
\text{subject to} & \|y\|_\infty \le 1 \\
& \|y\|_1 \le r.
\end{array}
$$

The variable in this problem is an $n$-vector $y$.

(b) From part (a), $-\|x\|$ is the optimal value of the convex optimization problem

$$
\begin{array}{ll}
\text{minimize} & f(y) \\
\text{subject to} & \|y\|_1 \le r
\end{array}
$$

where $\mathbf{dom}\, f = \{y \mid \|y\|_\infty \le 1\}$ and $f(y) = -x^T y$ for $y \in \mathbf{dom}\, f$.

Derive the dual of this problem (exactly as it is stated, *i.e.*, treating the constraint $\|y\|_\infty \le 1$ as an implicit constraint).

(c) Suppose $A \in \mathbf{R}^{m \times n}$ and $b \in \mathbf{R}^m$. Use your result in part (b) to formulate the problem

$$\text{minimize} \quad \|Ax - b\|_2^2 + \|x\|$$

as a quadratic program.

**5.32** Consider the following optimization problem with two variables $x_1$ and $x_2$:

$$
\begin{array}{ll}
\text{minimize} & x_1 \\
\text{subject to} & \sqrt{x_1^2 + x_2^2} \le x_2 \\
& -x_1 \le 1.
\end{array}
$$

(a) What is the optimal value?

(b) Derive the Lagrange dual of the problem (exactly as stated, without first reformulating or simplifying the problem).

(c) Find the dual optimal value. Does strong duality hold? If the result is surprising, explain briefly why it does not contradict duality theory.

**5.33** In this problem $\phi$ denotes the function

$$\phi(u) = \begin{cases} 0 & u \le 0 \\ u^2/2 & 0 < u \le 1 \\ u - 1/2 & u > 1. \end{cases}$$



$\phi(u)$

$0.5$

$1$

$u$

(This is one side of the Huber penalty function.)

Derive the Lagrange duals of the following two problems. In each problem, $A$ is an $m \times n$ matrix and $b$ is an $m$-vector. The variables are $x \in \mathbf{R}^n$ and $y \in \mathbf{R}^m$.

(a)

$$\begin{array}{ll} \text{minimize} & \sum_{i=1}^{m} \phi(y_i) \\ \text{subject to} & Ax + b = y \end{array}$$

(b)

$$\begin{array}{ll} \text{minimize} & \phi(\|y\|_2) \\ \text{subject to} & Ax + b = y. \end{array}$$

**5.34** *Some standard duals.* Give (Lagrange) dual problems for the following convex optimization problems.

(a)

$$\begin{array}{ll} \text{minimize} & \frac{1}{2}x^T P x \\ \text{subject to} & Ax = b \end{array}$$

where $P \succeq 0$ but may be indefinite.

(b)

$$\text{minimize} \quad \frac{1}{2}\|Ax - b\|_2^2 + \lambda\|x\|_1.$$

(c) For convex functions $f_i : \mathbf{R}^n \to \mathbf{R}$,

$$\text{minimize} \quad \sum_{i=1}^{m} f_i(x).$$

**5.35** *Showing concavity via duality.* The geometric mean function

$$g(x) = \left(\prod_{i=1}^{n} x_i\right)^{1/n}$$

and the geometric mean of the $k$ smallest values of a vector $x$,

$$g_k(x) = \left( \prod_{i=n-k+1}^{n} x_{[i]} \right)^{1/k}$$

(where we recall the notation that $x_{[i]}$ is the $i$th largest component of $x \in \mathbf{R}^n$, so that $x_{[1]} \geq x_{[2]} \geq \cdots \geq x_{[n]}$) are both concave on $\mathbf{R}^n_{++}$.

(a) Use Lagrange duality to show that

$$g(x) = \frac{1}{n} \inf_{v} \left\{ v^T x \mid \prod_{i=1}^{n} v_i = 1, v \in \mathbf{R}^n_{++} \right\}.$$

(b) Use Lagrange duality to show that

$$g_k(x) = \frac{1}{k} \inf_{v,S} \left\{ \sum_{i \in S} v_i x_i \mid \prod_{i \in S} v_i = 1, \ S \subset \{1, \ldots, n\}, \ \mathbf{card}\, S = k, \ v \in \mathbf{R}^n_{++} \right\}.$$

(c) Explain (in one sentence) why parts (a) and (b) imply that $g$ and $g_k$ are concave over their domains $\mathbf{R}^n_{++}$.

**5.36** *Sensitivity analysis.* Consider the convex optimization problem

$$\begin{array}{ll} \text{minimize} & f_0(x) \\ \text{subject to} & f_1(x) \leq s, \quad Ax = b, \end{array}$$

with variables $x \in \mathbf{R}^n$, parametrized by the real number $s$. We assume that a strong duality holds for some nominal value $s = s_{\text{nom}}$. Let $\lambda^\star$ be an optimal dual variable (Lagrange multiplier) associated with the constraint $f_1(x) \leq s_{\text{nom}}$. Below we consider scenarios in which we change the value of $s$ below or above the nominal value $s_{\text{nom}}$, and then solve the modified problem. We are interested in the optimal objective value of this modified problem, compared to the original one above.

For each of the following, choose the best response. (Please note that the words were carefully chosen.)

(a) If $\lambda^\star$ is large, then decreasing $s$ below $s_{\text{nom}}$

- might decrease the optimal value
- will increase the optimal value a lot
- can leave the optimal value unchanged

(b) If $\lambda^\star$ is large, then increasing $s$ above $s_{\text{nom}}$

- will decrease the optimal value a lot
- will increase the optimal value a lot
- can leave the optimal value unchanged

(c) If $\lambda^\star = 0$, then increasing $s$ above $s_{\text{nom}}$

- can decrease the objective value

- can increase the objective value
- will leave the optimal value unchanged

**5.37** Consider a convex optimization problem

$$
\begin{array}{ll}
\text{minimize} & f_0(x) \\
\text{subject to} & f_i(x) \leq 0, \quad i = 1, \ldots, m \\
& Ax = b,
\end{array}
$$

that satisfies Slater's constraint qualification. Determine whether each of the statements below is true or false.

(a) The primal and dual problems have the same objective value.

(b) The primal problem has a unique solution.

(c) The dual problem is not unbounded.

(d) Suppose $x^\star$ is optimal, with $f_1(x^\star) = -0.2$. Then for every dual optimal point $(\lambda^\star, \nu^\star)$, we have $\lambda_1^\star = 0$.

# 6 Approximation and fitting

**6.1** *Three measures of the spread of a group of numbers.* For $x \in \mathbf{R}^n$, we define three functions that measure the spread or width of the set of its elements (or coefficients). The first function is the *spread*, defined as

$$\phi_{\mathrm{sprd}}(x) = \max_{i=1,\ldots,n} x_i - \min_{i=1,\ldots,n} x_i.$$

This is the width of the smallest interval that contains all the elements of $x$.

The second function is the *standard deviation*, defined as

$$\phi_{\mathrm{stdev}}(x) = \left( \frac{1}{n} \sum_{i=1}^{n} x_i^2 - \left( \frac{1}{n} \sum_{i=1}^{n} x_i \right)^2 \right)^{1/2}.$$

This is the statistical standard deviation of a random variable that takes the values $x_1, \ldots, x_n$, each with probability $1/n$.

The third function is the average absolute deviation from the median of the values:

$$\phi_{\mathrm{aamd}}(x) = (1/n) \sum_{i=1}^{n} |x_i - \mathrm{med}(x)|,$$

where $\mathrm{med}(x)$ denotes the median of the components of $x$, defined as follows. If $n = 2k - 1$ is odd, then the median is defined as the value of middle entry when the components are sorted, *i.e.*, $\mathrm{med}(x) = x_{[k]}$, the $k$th largest element among the values $x_1, \ldots, x_n$. If $n = 2k$ is even, we define the median as the average of the two middle values, *i.e.*, $\mathrm{med}(x) = (x_{[k]} + x_{[k+1]})/2$.

Each of these functions measures the spread of the values of the entries of $x$; for example, each function is zero if and only if all components of $x$ are equal, and each function is unaffected if a constant is added to each component of $x$.

Which of these three functions is convex? For each one, either show that it is convex, or give a counterexample showing it is not convex. By a counterexample, we mean a specific $x$ and $y$ such that Jensen's inequality fails, *i.e.*, $\phi((x + y)/2) > (\phi(x) + \phi(y))/2$.

**6.2** *Minimax rational fit to the exponential.* (See exercise 6.9 of *Convex Optimization.*) We consider the specific problem instance with data

$$t_i = -3 + 6(i - 1)/(k - 1), \quad y_i = e^{t_i}, \quad i = 1, \ldots, k,$$

where $k = 201$. (In other words, the data are obtained by uniformly sampling the exponential function over the interval $[-3, 3]$.) Find a function of the form

$$f(t) = \frac{a_0 + a_1 t + a_2 t^2}{1 + b_1 t + b_2 t^2}$$

that minimizes $\max_{i=1,\ldots,k} |f(t_i) - y_i|$. (We require that $1 + b_1 t_i + b_2 t_i^2 > 0$ for $i = 1, \ldots, k$.)

Find optimal values of $a_0$, $a_1$, $a_2$, $b_1$, $b_2$, and give the optimal objective value, computed to an accuracy of 0.001. Plot the data and the optimal rational function fit on the same plot. On a different plot, give the fitting error, *i.e.*, $f(t_i) - y_i$.

*Hint.* To check if a feasibility problem is feasible, in Matlab, you can use `strcmp(cvx_status,'Solved')` after `cvx_end`. In Python, use `problem.status == 'optimal'`. In Julia, use `problem.status == :Optimal`.

**6.3** *Approximation with trigonometric polynomials.* Suppose $y : \mathbf{R} \to \mathbf{R}$ is a $2\pi$-periodic function. We will approximate $y$ with the trigonometric polynomial

$$f(t) = \sum_{k=0}^{K} a_k \cos(kt) + \sum_{k=1}^{K} b_k \sin(kt).$$

We consider two approximations: one that minimizes the $L_2$-norm of the error, defined as

$$\|f - y\|_2 = \left( \int_{-\pi}^{\pi} (f(t) - y(t))^2 \, dt \right)^{1/2},$$

and one that minimizes the $L_1$-norm of the error, defined as

$$\|f - y\|_1 = \int_{-\pi}^{\pi} |f(t) - y(t)| \, dt.$$

The $L_2$ approximation is of course given by the (truncated) Fourier expansion of $y$.

To find an $L_1$ approximation, we discretize $t$ at $2N$ points,

$$t_i = -\pi + i\pi/N, \quad i = 1, \ldots, 2N,$$

and approximate the $L_1$ norm as

$$\|f - y\|_1 \approx (\pi/N) \sum_{i=1}^{2N} |f(t_i) - y(t_i)|.$$

(A standard rule of thumb is to take $N$ at least 10 times larger than $K$.) The $L_1$ approximation (or really, an approximation of the $L_1$ approximation) can now be found by solving the (finite-dimensional) convex problem, which can be converted to an LP.

We consider a specific case, where $y$ is a $2\pi$-periodic square-wave, defined for $-\pi \le t \le \pi$ as

$$y(t) = \begin{cases} 1 & |t| \le \pi/2 \\ 0 & \text{otherwise.} \end{cases}$$

(The graph of $y$ over a few cycles explains the name 'square-wave'.)

Find the optimal $L_2$ approximation and (discretized) $L_1$ optimal approximation for $K = 10$. You can find the $L_2$ optimal approximation analytically, or by solving a least-squares problem associated with the discretized version of the problem. Since $y$ is even, you can take the sine coefficients in your approximations to be zero. Show $y$ and the two approximations on a single plot.

In addition, plot a histogram of the residuals (*i.e.*, the numbers $f(t_i) - y(t_i)$) for the two approximations. Use the same horizontal axis range, so the two residual distributions can easily be compared. Make some brief comments about what you see.

**6.4** *Penalty function approximation.* We consider the approximation problem

$$\text{minimize} \quad \phi(Ax - b)$$

where $A \in \mathbf{R}^{m \times n}$ and $b \in \mathbf{R}^m$, the variable is $x \in \mathbf{R}^n$, and $\phi : \mathbf{R}^m \to \mathbf{R}$ is a convex penalty function that measures the quality of the approximation $Ax \approx b$. We will consider the following choices of penalty function:

(a) *Euclidean norm.*

$$\phi(y) = \|y\|_2 = (\sum_{k=1}^{m} y_k^2)^{1/2}.$$

(b) *$\ell_1$-norm.*

$$\phi(y) = \|y\|_1 = \sum_{k=1}^{m} |y_k|.$$

(c) *Sum of the largest $m/2$ absolute values.*

$$\phi(y) = \sum_{k=1}^{\lfloor m/2 \rfloor} |y|_{[k]}$$

where $|y|_{[1]}$, $|y|_{[2]}$, $|y|_{[3]}$, $\ldots$, denote the absolute values of the components of $y$ sorted in decreasing order.

(d) *A piecewise-linear penalty.*

$$\phi(y) = \sum_{k=1}^{m} h(y_k), \qquad h(u) = \begin{cases} 0 & |u| \le 0.2 \\ |u| - 0.2 & 0.2 \le |u| \le 0.3 \\ 2|u| - 0.5 & |u| \ge 0.3. \end{cases}$$

(e) *Huber penalty.*

$$\phi(y) = \sum_{k=1}^{m} h(y_k), \qquad h(u) = \begin{cases} u^2 & |u| \le M \\ M(2|u| - M) & |u| \ge M \end{cases}$$

with $M = 0.2$.

(f) *Log-barrier penalty.*

$$\phi(y) = \sum_{k=1}^{m} h(y_k), \qquad h(u) = -\log(1 - u^2), \quad \mathbf{dom}\, h = \{u \mid |u| < 1\}.$$

Here is the problem. Generate data $A$ and $b$ as follows:

```
m = 200;
n = 100;
A = randn(m,n);
b = randn(m,1);
b = b/(1.01*max(abs(b)));
```

(The normalization of $b$ ensures that the domain of $\phi(Ax - b)$ is nonempty if we use the log-barrier penalty.) To compare the results, plot a histogram of the vector of residuals $y = Ax - b$, for each of the solutions $x$, using the Matlab command

```
hist(A*x-b,m/2);
```

Some additional hints and remarks for the individual problems:

(a) This problem can be solved using least-squares (`x=A\b`).

(b) Use the CVX function `norm(y,1)`.

(c) Use the CVX function `norm_largest()`.

(d) Use CVX, with the overloaded `max()`, `abs()`, and `sum()` functions.

(e) Use the CVX function `huber()`.

(f) The current version of CVX handles the logarithm using an iterative procedure, which is slow and not entirely reliable. However, you can reformulate this problem as

$$\text{maximize} \quad \left(\prod_{k=1}^{m} \left((1 - (Ax - b)_k)(1 + (Ax - b)_k)\right)\right)^{1/2m},$$

and use the CVX function `geo_mean()`.

**6.5** $\ell_{1.5}$ *optimization.* Optimization and approximation methods that use both an $\ell_2$-norm (or its square) and an $\ell_1$-norm are currently very popular in statistics, machine learning, and signal and image processing. Examples include Huber estimation, LASSO, basis pursuit, SVM, various $\ell_1$-regularized classification methods, total variation de-noising, etc. Very roughly, an $\ell_2$-norm corresponds to Euclidean distance (squared), or the negative log-likelihood function for a Gaussian; in contrast the $\ell_1$-norm gives 'robust' approximation, *i.e.*, reduced sensitivity to outliers, and also tends to yield sparse solutions (of whatever the argument of the norm is). (All of this is just background; you don't need to know any of this to solve the problem.)

In this problem we study a natural method for blending the two norms, by using the $\ell_{1.5}$-norm, defined as

$$\|z\|_{1.5} = \left(\sum_{i=1}^{k} |z_i|^{3/2}\right)^{2/3}$$

for $z \in \mathbf{R}^k$. We will consider the simplest approximation or regression problem:

$$\text{minimize} \quad \|Ax - b\|_{1.5},$$

with variable $x \in \mathbf{R}^n$, and problem data $A \in \mathbf{R}^{m \times n}$ and $b \in \mathbf{R}^m$. We will assume that $m > n$ and the $A$ is full rank (*i.e.*, rank $n$). The hope is that this $\ell_{1.5}$-optimal approximation problem should share some of the good features of $\ell_2$ and $\ell_1$ approximation.

(a) Give optimality conditions for this problem. Try to make these as simple as possible.

(b) Explain how to formulate the $\ell_{1.5}$-norm approximation problem as an SDP. (Your SDP can include linear equality and inequality constraints.)

(c) Solve the specific numerical instance generated by the following code:

```
randn('state',0);
A=randn(100,30);
b=randn(100,1);
```

Numerically verify the optimality conditions. Give a histogram of the residuals, and repeat for the $\ell_2$-norm and $\ell_1$-norm approximations. You can use any method you like to solve the problem (but of course you must explain how you did it); in particular, you do not need to use the SDP formulation found in part (b).

**6.6** *Total variation image interpolation.* A grayscale image is represented as an $m \times n$ matrix of intensities $U^{\text{orig}}$. You are given the values $U_{ij}^{\text{orig}}$, for $(i,j) \in \mathcal{K}$, where $\mathcal{K} \subset \{1,\ldots,m\} \times \{1,\ldots,n\}$. Your job is to *interpolate* the image, by guessing the missing values. The reconstructed image will be represented by $U \in \mathbf{R}^{m \times n}$, where $U$ satisfies the interpolation conditions $U_{ij} = U_{ij}^{\text{orig}}$ for $(i,j) \in \mathcal{K}$.

The reconstruction is found by minimizing a roughness measure subject to the interpolation conditions. One common roughness measure is the $\ell_2$ variation (squared),

$$\sum_{i=2}^{m} \sum_{j=1}^{n} (U_{ij} - U_{i-1,j})^2 + \sum_{i=1}^{m} \sum_{j=2}^{n} (U_{ij} - U_{i,j-1})^2.$$

Another method minimizes instead the *total variation*,

$$\sum_{i=2}^{m} \sum_{j=1}^{n} |U_{ij} - U_{i-1,j}| + \sum_{i=1}^{m} \sum_{j=2}^{n} |U_{ij} - U_{i,j-1}|.$$

Evidently both methods lead to convex optimization problems.

Carry out $\ell_2$ and total variation interpolation on the problem instance with data given in `tv_img_interp.m`. This will define `m`, `n`, and matrices `Uorig` and `Known`. The matrix `Known` is $m \times n$, with $(i,j)$ entry one if $(i,j) \in \mathcal{K}$, and zero otherwise. The mfile also has skeleton plotting code. (We give you the entire original image so you can compare your reconstruction to the original; obviously your solution cannot access $U_{ij}^{\text{orig}}$ for $(i,j) \notin \mathcal{K}$.)

**6.7** *Piecewise-linear fitting.* In many applications some function in the model is not given by a formula, but instead as tabulated data. The tabulated data could come from empirical measurements, historical data, numerically evaluating some complex expression or solving some problem, for a set of values of the argument. For use in a convex optimization model, we then have to fit these data with a convex function that is compatible with the solver or other system that we use. In this problem we explore a very simple problem of this general type.

Suppose we are given the data $(x_i, y_i)$, $i = 1,\ldots,m$, with $x_i$, $y_i \in \mathbf{R}$. We will assume that $x_i$ are sorted, *i.e.*, $x_1 < x_2 < \cdots < x_m$. Let $a_0 < a_1 < a_2 < \cdots < a_K$ be a set of fixed knot points, with $a_0 \le x_1$ and $a_K \ge x_m$. Explain how to find the convex piecewise linear function $f$, defined over $[a_0, a_K]$, with knot points $a_i$, that minimizes the least-squares fitting criterion

$$\sum_{i=1}^{m} (f(x_i) - y_i)^2.$$

You must explain what the variables are and how they parametrize $f$, and how you ensure convexity of $f$.

*Hints.* One method to solve this problem is based on the Lagrange basis, $f_0, \ldots, f_K$, which are the piecewise linear functions that satisfy

$$f_j(a_i) = \delta_{ij}, \quad i,j = 0,\ldots,K.$$

Another method is based on defining $f(x) = \alpha_i x + \beta_i$, for $x \in (a_{i-1}, a_i]$. You then have to add conditions on the parameters $\alpha_i$ and $\beta_i$ to ensure that $f$ is continuous and convex.

Apply your method to the data in the file `pwl_fit_data.m`, which contains data with $x_j \in [0, 1]$. Find the best affine fit (which corresponds to $a = (0, 1)$), and the best piecewise-linear convex function fit for 1, 2, and 3 internal knot points, evenly spaced in $[0, 1]$. (For example, for 3 internal knot points we have $a_0 = 0$, $a_1 = 0.25$, $a_2 = 0.50$, $a_3 = 0.75$, $a_4 = 1$.) Give the least-squares fitting cost for each one. Plot the data and the piecewise-linear fits found. Express each function in the form

$$f(x) = \max_{i=1\dots,K} (\alpha_i x + \beta_i).$$

(In this form the function is easily incorporated into an optimization problem.)

**6.8** *Least-squares fitting with convex splines.* A *cubic spline* (or *fourth-order spline*) with breakpoints $\alpha_0, \alpha_1, \dots, \alpha_M$ (that satisfy $\alpha_0 < \alpha_1 < \cdots < \alpha_M$) is a piecewise-polynomial function with the following properties:

- the function is a cubic polynomial on each interval $[\alpha_i, \alpha_{i+1}]$
- the function values, and the first and second derivatives are continuous on the interval $(\alpha_0, \alpha_M)$.

The figure shows an example of a cubic spline $f(t)$ with $M = 10$ segments and breakpoints $\alpha_0 = 0$, $\alpha_1 = 1$, $\dots$, $\alpha_{10} = 10$.



In approximation problems with splines it is convenient to parametrize a spline as a linear combination of basis functions, called *B-splines*. The precise definition of B-splines is not important for our purposes; it is sufficient to know that every cubic spline can be written as a linear combination of $M + 3$ cubic B-splines $g_k(t)$, *i.e.*, in the form

$$f(t) = x_1 g_1(t) + \cdots + x_{M+3} g_{M+3}(t) = x^T g(t),$$

and that there exist efficient algorithms for computing $g(t) = (g_1(t), \dots, g_{M+3}(t))$. The next figure shows the 13 B-splines for the breakpoints 0, 1, $\dots$, 10.

In this exercise we study the problem of fitting a cubic spline to a set of data points, subject to the constraint that the spline is a convex function. Specifically, the breakpoints $\alpha_0, \ldots, \alpha_M$ are fixed, and we are given $N$ data points $(t_k, y_k)$ with $t_k \in [\alpha_0, \alpha_M]$. We are asked to find the convex cubic spline $f(t)$ that minimizes the least-squares criterion

$$\sum_{k=1}^{N} (f(t_k) - y_k)^2.$$

We will use B-splines to parametrize $f$, so the variables in the problem are the coefficients $x$ in $f(t) = x^T g(t)$. The problem can then be written as

$$
\begin{aligned}
\text{minimize} \quad & \sum_{k=1}^{N} \left(x^T g(t_k) - y_k\right)^2 \\
\text{subject to} \quad & x^T g(t) \text{ is convex in } t \text{ on } [\alpha_0, \alpha_M].
\end{aligned}
\tag{29}
$$

(a) Express problem (29) as a convex optimization problem of the form

$$
\begin{aligned}
\text{minimize} \quad & \|Ax - b\|_2^2 \\
\text{subject to} \quad & Gx \preceq h.
\end{aligned}
$$

(b) Use CVX to solve a specific instance of the optimization problem in part (a). As in the figures above, we take $M = 10$ and $\alpha_0 = 0$, $\alpha_1 = 1$, ..., $\alpha_{10} = 10$.

Download the Matlab files `spline_data.m` and `bsplines.m`. The first m-file is used to generate the problem data. The command `[t, y] = spline_data` will generate two vectors $t$, $y$ of length $N = 51$, with the data points $t_k$, $y_k$.

The second function can be used to compute the B-splines, and their first and second derivatives, at any given point $u \in [0, 10]$. The command `[g, gp, gpp] = bsplines(u)` returns three vectors of length 13 with elements $g_k(u)$, $g_k'(u)$, and $g_k''(u)$. (The right derivatives are returned for $u = 0$, and the left derivatives for $u = 10$.)

Solve the convex spline fitting problem (29) for this example, and plot the optimal spline.

**6.9** *Robust least-squares with interval coefficient matrix.* An *interval matrix* in $\mathbf{R}^{m \times n}$ is a matrix whose entries are intervals:

$$\mathcal{A} = \{A \in \mathbf{R}^{m \times n} \mid |A_{ij} - \bar{A}_{ij}| \leq R_{ij}, \ i = 1, \ldots, m, \ j = 1, \ldots, n\}.$$

The matrix $\bar{A} \in \mathbf{R}^{m \times n}$ is called the *nominal value* or *center value*, and $R \in \mathbf{R}^{m \times n}$, which is elementwise nonnegative, is called the *radius*.

The robust least-squares problem, with interval matrix, is

$$\text{minimize} \quad \sup_{A \in \mathcal{A}} \|Ax - b\|_2,$$

with optimization variable $x \in \mathbf{R}^n$. The problem data are $\mathcal{A}$ (*i.e.*, $\bar{A}$ and $R$) and $b \in \mathbf{R}^m$. The objective, as a function of $x$, is called the *worst-case residual norm*. The robust least-squares problem is evidently a convex optimization problem.

(a) Formulate the interval matrix robust least-squares problem as a standard optimization problem, *e.g.*, a QP, SOCP, or SDP. You can introduce new variables if needed. Your reformulation should have a number of variables and constraints that grows linearly with $m$ and $n$, and not exponentially.

(b) Consider the specific problem instance with $m = 4$, $n = 3$,

$$\mathcal{A} = \begin{bmatrix} 60 \pm 0.05 & 45 \pm 0.05 & -8 \pm 0.05 \\ 90 \pm 0.05 & 30 \pm 0.05 & -30 \pm 0.05 \\ 0 \pm 0.05 & -8 \pm 0.05 & -4 \pm 0.05 \\ 30 \pm 0.05 & 10 \pm 0.05 & -10 \pm 0.05 \end{bmatrix}, \qquad b = \begin{bmatrix} -6 \\ -3 \\ 18 \\ -9 \end{bmatrix}.$$

(The first part of each entry in $\mathcal{A}$ gives $\bar{A}_{ij}$; the second gives $R_{ij}$, which are all 0.05 here.) Find the solution $x_{\text{ls}}$ of the nominal problem (*i.e.*, minimize $\|\bar{A}x - b\|_2$), and robust least-squares solution $x_{\text{rls}}$. For each of these, find the nominal residual norm, and also the worst-case residual norm. Make sure the results make sense.

**6.10** *Identifying a sparse linear dynamical system.* A linear dynamical system has the form

$$x(t+1) = Ax(t) + Bu(t) + w(t), \quad t = 1, \ldots, T-1,$$

where $x(t) \in \mathbf{R}^n$ is the state, $u(t) \in \mathbf{R}^m$ is the input signal, and $w(t) \in \mathbf{R}^n$ is the process noise, at time $t$. We assume the process noises are IID $\mathcal{N}(0, W)$, where $W \succ 0$ is the covariance matrix. The matrix $A \in \mathbf{R}^{n \times n}$ is called the dynamics matrix or the state transition matrix, and the matrix $B \in \mathbf{R}^{n \times m}$ is called the input matrix.

You are given accurate measurements of the state and input signal, *i.e.*, $x(1), \ldots, x(T)$, $u(1), \ldots, u(T-1)$, and $W$ is known. Your job is to find a state transition matrix $\hat{A}$ and input matrix $\hat{B}$ from these data, that are plausible, and in addition are sparse, *i.e.*, have many zero entries. (The sparser the better.)

By doing this, you are effectively estimating the structure of the dynamical system, *i.e.*, you are determining which components of $x(t)$ and $u(t)$ affect which components of $x(t+1)$. In some applications, this structure might be more interesting than the actual values of the (nonzero) coefficients in $\hat{A}$ and $\hat{B}$.

By plausible, we mean that

$$\sum_{t=1}^{T-1} \left\| W^{-1/2} \left( x(t+1) - \hat{A}x(t) - \hat{B}u(t) \right) \right\|_2^2 \leq n(T-1) + 2\sqrt{2n(T-1)}.$$

(You can just take this as our definition of plausible. But to explain this choice, we note that when $\hat{A} = A$ and $\hat{B} = B$, the left-hand side is $\chi^2$, with $n(T-1)$ degrees of freedom, and so has mean $n(T-1)$ and standard deviation $\sqrt{2n(T-1)}$. Thus, the constraint above states that the LHS does not exceed the mean by more than 2 standard deviations.)

(a) Describe a method for finding $\hat{A}$ and $\hat{B}$, based on convex optimization.

   We are looking for a *very simple* method, that involves solving *one* convex optimization problem. (There are many extensions of this basic method, that would improve the simple method, *i.e.*, yield sparser $\hat{A}$ and $\hat{B}$ that are still plausible. We're not asking you to describe or implement any of these.)

(b) Carry out your method on the data found in `sparse_lds_data.m`. Give the values of $\hat{A}$ and $\hat{B}$ that you find, and verify that they are plausible.

   In the data file, we give you the true values of $A$ and $B$, so you can evaluate the performance of your method. (Needless to say, you are not allowed to use these values when forming $\hat{A}$ and $\hat{B}$.) Using these true values, give the number of false positives and false negatives in both $\hat{A}$ and $\hat{B}$. A false positive in $\hat{A}$, for example, is an entry that is nonzero, while the corresponding entry in $A$ is zero. A false negative is an entry of $\hat{A}$ that is zero, while the corresponding entry of $A$ is nonzero. To judge whether an entry of $\hat{A}$ (or $\hat{B}$) is nonzero, you can use the test $|\hat{A}_{ij}| \geq 0.01$ (or $|\hat{B}_{ij}| \geq 0.01$).

**6.11** *Measurement with bounded errors.* A series of $K$ measurements $y_1, \ldots, y_K \in \mathbf{R}^p$, are taken in order to estimate an unknown vector $x \in \mathbf{R}^q$. The measurements are related to the unknown vector $x$ by $y_i = Ax + v_i$, where $v_i$ is a measurement noise that satisfies $\|v_i\|_\infty \leq \alpha$ but is otherwise unknown. (In other words, the entries of $v_1, \ldots, v_K$ are no larger than $\alpha$.) The matrix $A$ and the measurement noise norm bound $\alpha$ are known. Let $X$ denote the set of vectors $x$ that are consistent with the observations $y_1, \ldots, y_K$, *i.e.*, the set of $x$ that could have resulted in the measurements made. Is $X$ convex?

Now we will examine what happens when the measurements are occasionally in error, *i.e.*, for a few $i$ we have no relation between $x$ and $y_i$. More precisely suppose that $I_{\text{fault}}$ is a subset of $\{1, \ldots, K\}$, and that $y_i = Ax + v_i$ with $\|v_i\|_\infty \leq \alpha$ (as above) for $i \notin I_{\text{fault}}$, but for $i \in I_{\text{fault}}$, there is no relation between $x$ and $y_i$. The set $I_{\text{fault}}$ is the set of times of the faulty measurements.

Suppose you know that $I_{\text{fault}}$ has at most $J$ elements, *i.e.*, out of $K$ measurements, at most $J$ are faulty. You do not know $I_{\text{fault}}$; you know only a bound on its cardinality (size). For what values of $J$ is $X$, the set of $x$ consistent with the measurements, convex?

**6.12** *Least-squares with some permuted measurements.* We want to estimate a vector $x \in \mathbf{R}^n$, given some linear measurements of $x$ corrupted with Gaussian noise. Here's the catch: some of the measurements have been *permuted*.

More precisely, our measurement vector $y \in \mathbf{R}^m$ has the form

$$y = P(Ax + v),$$

where $v_i$ are IID $\mathcal{N}(0,1)$ measurement noises, $x \in \mathbf{R}^n$ is the vector of parameters we wish to estimate, and $P \in \mathbf{R}^{m \times m}$ is a permutation matrix. (This means that each row and column of $P$ has exactly one entry equal to one, and the remaining $m - 1$ entries zero.) We assume that $m > n$ and that at most $k$ of the measurements are permuted; *i.e.*, $Pe_i \neq e_i$ for no more than $k$ indices $i$. We are interested in the case when $k < m$ (*e.g.* $k = 0.4m$); that is, only *some* of the measurements have been permuted. We want to estimate $x$ and $P$.

Once we make a guess $\hat{P}$ for $P$, we can get the maximum likelihood estimate of $x$ by minimizing $\|Ax - \hat{P}^T y\|_2$. The residual $A\hat{x} - \hat{P}^T y$ is then our guess of what $v$ is, and should be consistent with being a sample of a $\mathcal{N}(0, I)$ vector.

In principle, we can find the maximum likelihood estimate of $x$ and $P$ by solving a set of $\binom{m}{k}(k!-1)$ least-squares problems, and choosing one that has minimum residual. But this is not practical unless $m$ and $k$ are both very small.

Describe a *heuristic* method for approximately solving this problem, using convex optimization. (There are many different approaches which work quite well.)

You might find the following fact useful. The solution to

$$\text{minimize} \quad \|Ax - P^T y\|_2$$

over $P \in \mathbf{R}^{m \times m}$ a permutation matrix, is the permutation that matches the smallest entry in $y$ with the smallest entry in $Ax$, does the same for the second smallest entries and so forth.

Carry out your method on the data in `ls_perm_meas_data.*`. Give your estimate of the permuted indices. The data file includes the true permutation matrix and value of $x$ (which of course you cannot use in forming your estimate). Compare the estimate of $x$ you get after your guessed permutation with the estimate obtained assuming $P = I$.

*Remark.* This problem comes up in several applications. In target tracking, we get multiple noisy measurements of a set of targets, and then guess which targets are the same in the different sets of measurements. If some of our guesses are wrong (*i.e.*, our target association is wrong) we have the present problem. In vision systems the problem arises when we have multiple camera views of a scene, which give us noisy measurements of a set of features. A feature correspondence algorithm guesses which features in one view correspond to features in other views. If we make some feature correspondence errors, we have the present problem.

**6.13** *Fitting with censored data.* In some experiments there are two kinds of measurements or data available: The usual ones, in which you get a number (say), and *censored data*, in which you don't get the specific number, but are told something about it, such as a lower bound. A classic example is a study of lifetimes of a set of subjects (say, laboratory mice). For those who have died by the end of data collection, we get the lifetime. For those who have not died by the end of data collection, we do not have the lifetime, but we do have a lower bound, *i.e.*, the length of the study. These are the censored data values.

We wish to fit a set of data points,

$$(x^{(1)}, y^{(1)}), \dots, (x^{(K)}, y^{(K)}),$$

with $x^{(k)} \in \mathbf{R}^n$ and $y^{(k)} \in \mathbf{R}$, with a linear model of the form $y \approx c^T x$. The vector $c \in \mathbf{R}^n$ is the model parameter, which we want to choose. We will use a least-squares criterion, *i.e.*, choose $c$ to

minimize

$$J = \sum_{k=1}^{K} \left( y^{(k)} - c^T x^{(k)} \right)^2 .$$

Here is the tricky part: some of the values of $y^{(k)}$ are censored; for these entries, we have only a (given) lower bound. We will re-order the data so that $y^{(1)}, \ldots, y^{(M)}$ are given (*i.e.*, uncensored), while $y^{(M+1)}, \ldots, y^{(K)}$ are all censored, *i.e.*, unknown, but larger than $D$, a given number. All the values of $x^{(k)}$ are known.

(a) Explain how to find $c$ (the model parameter) and $y^{(M+1)}, \ldots, y^{(K)}$ (the censored data values) that minimize $J$.

(b) Carry out the method of part (a) on the data values in `cens_fit_data.*`. Report $\hat{c}$, the value of $c$ found using this method.

Also find $\hat{c}_{\mathrm{ls}}$, the least-squares estimate of $c$ obtained by simply ignoring the censored data samples, *i.e.*, the least-squares estimate based on the data

$$(x^{(1)}, y^{(1)}), \ldots, (x^{(M)}, y^{(M)}).$$

The data file contains $c_{\mathrm{true}}$, the true value of $c$, in the vector `c_true`. Use this to give the two relative errors

$$\frac{\|c_{\mathrm{true}} - \hat{c}\|_2}{\|c_{\mathrm{true}}\|_2}, \qquad \frac{\|c_{\mathrm{true}} - \hat{c}_{\mathrm{ls}}\|_2}{\|c_{\mathrm{true}}\|_2}.$$

**6.14** *Spectrum analysis with quantized measurements.* A sample is made up of $n$ compounds, in quantities $q_i \geq 0$, for $i = 1, \ldots, n$. Each compound has a (nonnegative) spectrum, which we represent as a vector $s^{(i)} \in \mathbf{R}_+^m$, for $i = 1, \ldots, n$. (Precisely what $s^{(i)}$ means won't matter to us.) The spectrum of the sample is given by $s = \sum_{i=1}^{n} q_i s^{(i)}$. We can write this more compactly as $s = Sq$, where $S \in \mathbf{R}^{m \times n}$ is a matrix whose columns are $s^{(1)}, \ldots, s^{(n)}$.

Measurement of the spectrum of the sample gives us an interval for each spectrum value, *i.e.*, $l, u \in \mathbf{R}_+^m$ for which

$$l_i \leq s_i \leq u_i, \quad i = 1, \ldots, m.$$

(We don't directly get $s$.) This occurs, for example, if our measurements are quantized.

Given $l$ and $u$ (and $S$), we cannot in general deduce $q$ exactly. Instead, we ask you to do the following. For each compound $i$, find the range of possible values for $q_i$ consistent with the spectrum measurements. We will denote these ranges as $q_i \in [q_i^{\min}, q_i^{\max}]$. Your job is to find $q_i^{\min}$ and $q_i^{\max}$.

Note that if $q_i^{\min}$ is large, we can confidently conclude that there is a significant amount of compound $i$ in the sample. If $q_i^{\max}$ is small, we can confidently conclude that there is not much of compound $i$ in the sample.

(a) Explain how to find $q_i^{\min}$ and $q_i^{\max}$, given $S$, $l$, and $u$.

(b) Carry out the method of part (a) for the problem instance given in `spectrum_data.m`. (Executing this file defines the problem data, and plots the compound spectra and measurement bounds.) Plot the minimum and maximum values versus $i$, using the commented out code in the data file. Report your values for $q_4^{\min}$ and $q_4^{\max}$.

**6.15** *Learning a quadratic pseudo-metric from distance measurements.* We are given a set of $N$ pairs of points in $\mathbf{R}^n$, $x_1, \ldots, x_N$, and $y_1, \ldots, y_N$, together with a set of distances $d_1, \ldots, d_N > 0$.

The goal is to find (or estimate or learn) a quadratic pseudo-metric $d$,

$$d(x, y) = \left( (x - y)^T P (x - y) \right)^{1/2},$$

with $P \in \mathbf{S}_+^n$, which approximates the given distances, *i.e.*, $d(x_i, y_i) \approx d_i$. (The pseudo-metric $d$ is a metric only when $P \succ 0$; when $P \succeq 0$ is singular, it is a pseudo-metric.)

To do this, we will choose $P \in \mathbf{S}_+^n$ that minimizes the mean squared error objective

$$\frac{1}{N} \sum_{i=1}^{N} (d_i - d(x_i, y_i))^2.$$

(a) Explain how to find $P$ using convex or quasiconvex optimization. If you cannot find an exact formulation (*i.e.*, one that is guaranteed to minimize the total squared error objective), give a formulation that approximately minimizes the given objective, subject to the constraints.

(b) Carry out the method of part (a) with the data given in `quad_metric_data.m`. The columns of the matrices `X` and `Y` are the points $x_i$ and $y_i$; the row vector `d` gives the distances $d_i$. Give the optimal mean squared distance error.

We also provide a test set, with data `X_test`, `Y_test`, and `d_test`. Report the mean squared distance error on the test set (using the metric found using the data set above).

**6.16** *Polynomial approximation of inverse using eigenvalue information.* We seek a polynomial of degree $k$, $p(a) = c_0 + c_1 a + c_2 a^2 + \cdots + c_k a^k$, for which

$$p(A) = c_0 I + c_1 A + c_2 A^2 \cdots + c_k A^k$$

is an approximate inverse of the nonsingular matrix $A$, for all $A \in \mathcal{A} \subset \mathbf{R}^{n \times n}$. When $\hat{x} = p(A)b$ is used as an approximate solution of the linear equation $Ax = b$, the associated residual norm is $\|A(p(A)b) - b\|_2$. We will judge our polynomial (*i.e.*, the coefficients $c_0, \ldots, c_k$) by the worst case residual over $A \in \mathcal{A}$ and $b$ in the unit ball:

$$R^{\mathrm{wc}} = \sup_{A \in \mathcal{A}, \ \|b\|_2 \leq 1} \|A(p(A)b) - b\|_2.$$

The set of matrices we take is $\mathcal{A} = \{A \in \mathbf{S}^n \mid \sigma(A) \subseteq \Omega\}$, where $\sigma(A)$ is the set of eigenvalues of $A$ (*i.e.*, its spectrum), and $\Omega \subset \mathbf{R}$ is a union of a set of intervals (that do not contain 0).

(a) Explain how to find coefficients $c_0^\star, \ldots, c_k^\star$ that minimize $R^{\mathrm{wc}}$. Your solution can involve expressions that involve the supremum of a polynomial (with scalar argument) over an interval.

(b) Carry out your method for $k = 4$ and $\Omega = [-0.6, -0.3] \cup [0.7, 1.8]$. You can replace the supremum of a polynomial over $\Omega$ by a maximum over uniformly spaced (within each interval) points in $\Omega$, with spacing 0.01. Give the optimal value $R^{\mathrm{wc}\star}$ and the optimal coefficients $c^\star = (c_0^\star, \ldots, c_k^\star)$.

*Remarks.* (Not needed to solve the problem.)

- The approximate inverse $p(A)b$ would be computed by recursively, requiring the multiplication of $A$ with a vector $k$ times.

- This approximate inverse could be used as a preconditioner for an iterative method.

- The Cayley-Hamilton theorem tells us that the inverse of any (invertible) matrix is a polynomial of degree $n-1$ of the matrix. Our hope here, however, is to get a single polynomial, of relatively low degree, that serves as an approximate inverse for many different matrices.

**6.17** *Fitting a generalized additive regression model.* A *generalized additive model* has the form

$$f(x) = \alpha + \sum_{j=1}^{n} f_j(x_j),$$

for $x \in \mathbf{R}^n$, where $\alpha \in \mathbf{R}$ is the offset, and $f_j : \mathbf{R} \to \mathbf{R}$, with $f_j(0) = 0$. The functions $f_j$ are called the *regressor functions*. When each $f_j$ is linear, *i.e.*, has the form $w_j x_j$, the generalized additive model is the same as the standard (linear) regression model. Roughly speaking, a generalized additive model takes into account nonlinearities in each regressor $x_j$, but not nonlinear interactions among the regressors. To visualize a generalized additive model, it is common to plot each regressor function (when $n$ is not too large).

We will restrict the functions $f_j$ to be piecewise-affine, with given knot points $p_1 < \cdots < p_K$. This means that $f_j$ is affine on the intervals $(-\infty, p_1], [p_1, p_2], \ldots, [p_{K-1}, p_K], [p_K, \infty)$, and continuous at $p_1, \ldots, p_K$. Let $C$ denote the total (absolute value of) change in slope across all regressor functions and all knot points. The value $C$ is a measure of nonlinearity of the regressor functions; when $C = 0$, the generalized additive model reduces to a linear regression model.

Now suppose we observe samples or data $(x^{(1)}, y^{(1)}), \ldots, (x^{(N)}, y^{(N)}) \in \mathbf{R}^n \times \mathbf{R}$, and wish to fit a generalized additive model to the data. We choose the offset and the regressor functions to minimize

$$\frac{1}{N} \sum_{i=1}^{N} (y^{(i)} - f(x^{(i)})^2 + \lambda C,$$

where $\lambda > 0$ is a regularization parameter. (The first term is the mean-square error.)

(a) Explain how to solve this problem using convex optimization.

(b) Carry out the method of part (a) using the data in the file `gen_add_reg_data.m`. This file contains the data, given as an $N \times n$ matrix `X` (whose rows are $(x^{(i)})^T$), a column vector `y` (which give $y^{(i)}$), a vector `p` that gives the knot points, and the scalar `lambda`.

Give the mean-square error achieved by your generalized additive regression model. Compare the estimated and true regressor functions in a $3 \times 3$ array of plots (using the plotting code in the data file as a template), over the range $-10 \le x_i \le 10$. The true regressor functions (to be used only for plotting, of course) are given in the cell array `f`.

*Hints.*

- You can represent each regressor function $f_j$ as a linear combination of the basis functions $b_0(u) = u$ and $b_i(u) = (u - p_k)_+ - (-p_k)_+$ for $k = 1, 2, \ldots, K$, where $(a)_+ = \max\{a, 0\}$.

- You might find the matrix $\texttt{XX} = [b_0(\texttt{X})\ b_1(\texttt{X})\ \cdots\ b_K(\texttt{X})]$ useful.

**6.18** *Multi-label support vector machine.* The basic SVM described in the book is used for classification of data with two labels. In this problem we explore an extension of SVM that can be used to carry out classification of data with more than two labels. Our data consists of pairs $(x_i, y_i) \in \mathbf{R}^n \times \{1, \ldots, K\}$, $i = 1, \ldots, m$, where $x_i$ is the feature vector and $y_i$ is the label of the $i$th data point. (So the labels can take the values $1, \ldots, K$.) Our classifier will use $K$ affine functions, $f_k(x) = a_k^T x + b_k$, $k = 1, \ldots, K$, which we also collect into affine function from $\mathbf{R}^n$ into $\mathbf{R}^K$ as $f(x) = Ax + b$. (The rows of $A$ are $a_k^T$.) Given feature vector $x$, we guess the label $\hat{y} = \text{argmax}_k f_k(x)$. We assume that exact ties never occur, or if they do, an arbitrary choice can be made. Note that if a multiple of $\mathbf{1}$ is added to $b$, the classifier does not change. Thus, without loss of generality, we can assume that $\mathbf{1}^T b = 0$.

To correctly classify the data examples, we need $f_{y_i}(x_i) > \max_{k \neq y_i} f_k(x_i)$ for all $i$. This is a set of homogeneous strict inequalities in $a_k$ and $b_k$, which are feasible if and only if the set of nonstrict inequalities $f_{y_i}(x_i) \geq 1 + \max_{k \neq y_i} f_k(x_i)$ are feasible. This motivates the loss function

$$L(A, b) = \sum_{i=1}^{m} \left( 1 + \max_{k \neq y_i} f_k(x_i) - f_{y_i}(x_i) \right)_+ ,$$

where $(u)_+ = \max\{u, 0\}$. The multi-label SVM chooses $A$ and $b$ to minimize

$$L(A, b) + \mu \|A\|_F^2,$$

subject to $\mathbf{1}^T b = 0$, where $\mu > 0$ is a regularization parameter. (Several variations on this are possible, such as regularizing $b$ as well, or replacing the Frobenius norm squared with the sum of norms of the columns of $A$.)

(a) Show how to find $A$ and $b$ using convex optimization. Be sure to justify any changes of variables or reformulation (if needed), and convexity of the objective and constraints in your formulation.

(b) Carry out multi-label SVM on the data given in `multi_label_svm_data.m`. Use the data given in `X` and `y` to fit the SVM model, for a range of values of $\mu$. This data set includes an additional set of data, `Xtest` and `ytest`, that you can use to test the SVM models. Plot the test set classification error rate (*i.e.*, the fraction of data examples in the test set for which $\hat{y} \neq y$) versus $\mu$.

You don't need to try more than 10 or 20 values of $\mu$, and we suggest choosing them uniformly on a log scale, from (say) $10^{-2}$ to $10^2$.

**6.19** *Colorization with total variation regularization.* A $m \times n$ color image is represented as three matrices of intensities $R, G, B \in \mathbf{R}^{m \times n}$, with entries in $[0, 1]$, representing the red, green, and blue pixel intensities, respectively. A color image is converted to a monochrome image, represented as one matrix $M \in \mathbf{R}^{m \times n}$, using

$$M = 0.299R + 0.587G + 0.114B.$$

(These weights come from different perceived brightness of the three primary colors.)

In *colorization*, we are given $M$, the monochrome version of an image, and the color values of *some* of the pixels; we are to guess its color version, *i.e.*, the matrices $R, G, B$. Of course that's a very

underdetermined problem. A very simple technique is to minimize the total variation of $(R, G, B)$, defined as

$$\mathbf{tv}(R, G, B) = \sum_{i=1}^{m-1} \sum_{j=1}^{n-1} \left\| \begin{bmatrix} R_{ij} - R_{i,j+1} \\ G_{ij} - G_{i,j+1} \\ B_{ij} - B_{i,j+1} \\ R_{ij} - R_{i+1,j} \\ G_{ij} - G_{i+1,j} \\ B_{ij} - B_{i+1,j} \end{bmatrix} \right\|_2,$$

subject to consistency with the given monochrome image, the known ranges of the entries of $(R, G, B)$ (*i.e.*, in $[0, 1]$), and the given color entries. Note that the sum above is of the norm of 6-vectors, and not the norm-squared. (The 6-vector is an approximation of the spatial gradient of $(R, G, B)$.)

Carry out this method on the data given in `image_colorization_data.*`. The file loads `flower.png` and provides the monochrome version of the image, M, along with vectors of known color intensities, `R_known`, `G_known`, and `B_known`, and `known_ind`, the indices of the pixels with known values. If `R` denotes the red channel of an image, then `R(known_ind)` returns the known red color intensities in Matlab, and `R[known_ind]` returns the same in Python and Julia. The file also creates an image, `flower_given.png`, that is monochrome, with the known pixels colored.

The `tv` function, invoked as `tv(R,G,B)`, gives the total variation. CVXPY has the `tv` function built-in, but CVX and CVX.jl do not, so we have provided the files `tv.m` and `tv.jl` which contain implementations for you to use.

In Python and Julia we have also provided the function `save_img(filename,R,G,B)` which writes the image defined by the matrices R, G, B, to the file `filename`. To view an image in Matlab use the `imshow` function.

The problem instance is a small image, $75 \times 75$, so the solve time is reasonable, say, under ten seconds or so in CVX or CVXPY, and around 60 seconds in Julia.

Report your optimal objective value and, if you have access to a color printer, attach your reconstructed image. If you don't have access to a color printer, it's OK to just give the optimal objective value.

**6.20** *Recovering latent periodic signals.* First, a definition: a signal $x \in \mathbf{R}^n$ is *p-periodic* with $p < n$ if $x_{i+p} = x_i$ for $i = 1, \ldots, n - p$.

In this problem, we consider a noisy, measured signal $y \in \mathbf{R}^n$ which is (approximately) the sum of a several periodic signals, with unknown periods. Given only the noisy signal $y$, our task is to recover these latent periodic signals. In particular, $y$ is given as

$$y = v + \sum_{p \in \mathcal{P}} x^{(p)},$$

where $v \in \mathbf{R}^n$ is a (small) random noise term, and $x^{(p)}$ is a $p$-periodic signal. The set $\mathcal{P} \subset \{1, \ldots, p_{\max}\}$ contains the periods of the latent periodic signals that compose $y$.

If $\mathcal{P}$ were known, we could approximately recover the latent periodic signals $x^{(p)}$ using, say, least squares. Because $\mathcal{P}$ is *not* known, we instead propose to recover the latent periodic signals $x^{(p)}$ by

solving the following optimization problem:

$$
\begin{array}{ll}
\text{minimize} & \sum_{i=1}^{n}(y_i - \hat{y}_i)^2 + \sum_{p=1}^{p_{\max}} w_p \|\hat{x}^{(p)}\|_2 \\
\text{subject to} & \hat{y} = \sum_{p=1}^{p_{\max}} \hat{x}^{(p)} \\
& \hat{x}^{(p)} \text{ is } p\text{-periodic, for } p = 1, \ldots, p_{\max}.
\end{array}
$$

The variables are $\hat{y}$ and $\hat{x}^{(p)}$, for $p = 1, \ldots, p_{\max}$. The first sum in the objective penalizes the squared deviation of the measured signal $y$ from our estimate $\hat{y}$, and the second sum is a heuristic for producing vectors $\hat{x}^{(p)}$ that contain only zeros. The weight vector $w \succeq 0$ is increasing in its indices, which encodes our desire that the latent periodic signals have small period.

(a) Explain how to solve the given optimization problem using convex optimization, and how to use it to (approximately) recover the set $\mathcal{P}$ and the latent periodic signals $x^{(p)}$, for $p \in \mathcal{P}$.

(b) The file `periodic_signals_data.*` contains a signal $y$, as well as a weight vector $w$. Return your best guess of the set $\mathcal{P}$. plot the measured signal $y$, as well as the different periodic components that (approximately) compose it. (Use separate graphs for each signal, so you should have $|\mathcal{P}| + 1$ graphs.)

**6.21** *Rank one nonnegative matrix approximation.* We are given *some* entries of an $m \times n$ matrix $A$ with positive entries, and wish to approximate it as the outer product of vectors $x$ and $y$ with positive entries, *i.e.*, $xy^T$. We will use the average relative deviation between the entries of $A$ and $xy^T$ as our approximation criterion,

$$
\frac{1}{mn} \sum_{i=1}^{m} \sum_{j=1}^{n} R(A_{ij}, x_i y_j),
$$

where $R$ is the relative deviation of two positive numbers, defined as

$$
R(u, v) = \max\{u/v, v/u\} - 1.
$$

If we scale $x$ by the positive number $\alpha$, and $y$ by $1/\alpha$, the outer product $(\alpha x)(y/\alpha)^T$ is the same as $xy^T$, so we will normalize $x$ as $\mathbf{1}^T x = 1$.

The data in the problem consists of *some* of the values of $A$. Specifically, we are given $A_{ij}$ for $(i, j) \in \Omega \subseteq \{1, \ldots, m\} \times \{1, \ldots, n\}$. Thus, your goal is to find $x \in \mathbf{R}_{++}^m$ (which satisfies $\mathbf{1}^T x = 1$), $y \in \mathbf{R}_{++}^n$, and $A_{ij} > 0$ for $(i, j) \notin \Omega$, to minimize the average relative deviation between the entries of $A$ and $xy^T$.

(a) Explain how to solve this problem using convex or quasiconvex optimization.

(b) Solve the problem for the data given in `rank_one_nmf_data.*`. This includes a matrix `A`, and a set of indexes `Omega` for the given entries. (The other entries of `A` are filled in with zeros.) Report the optimal average relative deviation between $A$ and $xy^T$. Give your values for $x_1$, $y_1$, and $A_{11} = x_1 y_1$.

**6.22** *Total variation de-mosaicing.* A color image is represented by 3 $m \times n$ matrices $R$, $G$, and $B$ that give the red, green, and blue pixel intensities. A camera sensor, however, measures only *one* of the color intensities at each pixel. The pattern of pixel sensor colors varies, but most of the patterns

have twice as many green sensor pixels as red or blue. A common arrangement repeats the $2 \times 2$ block

$$\begin{array}{cc} R & G \\ G & B \end{array}$$

(assuming $m$ and $n$ are even).

*De-mosaicing* is the process of guessing, or interpolating, the missing color values at each pixel. The sensors give us $mn$ entries in the matrices $R$, $G$, and $B$; in de-mosaicing, we guess the remaining $2mn$ entries in the matrices.

First we describe a very basic method of de-mosaicing. For each $2 \times 2$ block of pixels we have the 4 intensity values

$$\begin{array}{cc} R_{i,j} & G_{i,j+1} \\ G_{i+1,j} & B_{i+1,j+1} \end{array}.$$

We use the value $R_{i,j}$ as the red value for the other three pixels, and we do the same for the blue value $B_{i+1,j+1}$. For guessing the green values at $i, j$ and $i+1, j+1$, we simply use the average of the two measured green values, $(G_{i,j+1} + G_{i+1,j})/2$.

A more sophisticated method relies on convex optimization. You choose the unknown pixel values in $R$, $G$, and $B$ to minimize the total variation of the color image, defined as

$$\sum_{i=1}^{m-1} \sum_{j=1}^{n-1} \left\| \begin{bmatrix} R_{i,j} - R_{i,j+1} \\ G_{i,j} - G_{i,j+1} \\ B_{i,j} - B_{i,j+1} \\ R_{i+1,j} - R_{i,j} \\ G_{i+1,j} - G_{i,j} \\ B_{i+1,j} - B_{i,j} \end{bmatrix} \right\|_2 .$$

Note that the norms in the sum here are *not* squared. The argument of the norms is a vector in $\mathbf{R}^6$, an estimate of the spatial gradient of the RGB values.

We have provided you with several files in the data directory. Three images are given (in png format): `demosaic_raw.png`, which contains the raw or mosaic image to de-mosaic, `demosaic_original.png`, which contains the original image from which the raw image was constructed, and `demosaic_simple.png`, which is the image de-mosaiced by the simple method described above. Remember that the raw image, and any reconstructed de-mosaiced image, have only one third the information of the original, so we cannot expect them to look as good as the original. You don't need the original or basic de-mosaiced image files to solve the problem; they are given only so you can look at them to see what they are. You should zoom in while viewing the raw image and the basic de-mosaic version, so you can see the pattern of $2 \times 2$ blocks in the first, and the simple de-mosaic method in the second.

The `tv` function, invoked as `tv(R,G,B)`, gives the total variation. CVXPY has the `tv` function built-in, but CVX and CVX.jl do not, so we have provided the files `tv.m` and `tv.jl` which contain implementations for you to use.

The file `demosaic_data.*` constructs arrays `R_mask`, `G_mask`, and `B_mask`, which contain the indices of pixels whose values we know in the original image, the number of rows and columns in the image, $m, n$ respectively, and arrays `R_raw`, `B_raw`, `G_raw`, which contain the known values of each color at each pixel, filled in with zeroes for the unknown values. So if `R` is an $m \times n$

matrix variable, the constraint `R[R_mask]==R_raw[R_mask]` in Julia and Python will impose the constraint that it agrees with the given red pixel values; in Matlab, the constraint can be expressed as `R(R_mask)==R_raw(R_mask)`. This file also contains a `save_image` method, which takes three arguments, `R`, `G`, `B` arrays (that you've reconstructed) and saves the file under the name `output_image.png`. To see the image in Matlab, use the `imshow` function.

Report the optimal value of total variation, and attach the de-mosaiced image. (If you don't have access to a color printer, you can submit a monochrome version. Print it large enough that we can see it, say, at least half the page width wide.)

*Hint.* Your solution code should take less than 10 seconds or so to run in Python and Matlab, but up to a minute or so in Julia. You might get a warning about an inaccurate solution, but you can ignore it.

**6.23** *Fitting with a nonnegative combination of vectors from ellipsoids.* You are given ellipsoids $\mathcal{E}_1, \dots, \mathcal{E}_n \subset \mathbf{R}^k$, and the vector $b \in \mathbf{R}^k$. Explain how to use convex optimization to choose $a_i \in \mathcal{E}_i$, $i = 1, \dots, n$, and nonnegative $x_1, \dots, x_n \in \mathbf{R}$, that minimize

$$\left\| \sum_{i=1}^n x_i a_i - b \right\|_2 .$$

You can use any parametrization of the ellipsoids you like, for example,

$$\mathcal{E}_i = \{ a \mid \|P_i a + q_i\|_2 \le 1 \} ,$$

or

$$\mathcal{E}_i = \{ P_i u + q_i \mid \|u\|_2 \le 1 \} ,$$

or

$$\mathcal{E}_i = \left\{ a \mid (a - c_i)^T P_i^{-1} (a - c_i) \le 1 \right\} ,$$

with $P_i \in \mathbf{S}_{++}^k$ and $c_i \in \mathbf{R}^k$.

*Remark.* This is the opposite situation from robust approximation. In robust approximation, the $a_i$'s would be chosen to maximize the objective, once you choose $x$. Here, however, the $a_i$'s are chosen to minimize the objective, along with $x$.

**6.24** *Phase retrieval.* In the phase retrieval problem, which has applications in X-ray crystallography, electron microscopy, and coherent diffractive imaging, one observes only the magnitude of complex measurements of a signal $x^{\text{true}} \in \mathbf{C}^n$, $b_i = |a_i^* x^{\text{true}}|$, where $a^*$ denotes the conjugate transpose of $a \in \mathbf{C}^n$; given $m$ such measurements, one seeks $x$ satisfying the nonlinear equalities $b_i = |a_i^* x|$ for $i = 1, \dots, m$. We consider a simplified variant of this in $\mathbf{R}$.

For vectors $a_i \in \mathbf{R}^n$, assume we have $m$ noisy observations

$$b_i = (a_i^T x^{\text{true}})^2 + w_i, \quad i = 1, \dots, m,$$

where $w_i$ is an unknown noise term, but which follows a known distribution. Let $\phi : \mathbf{R} \to \mathbf{R}$ be a closed convex function with conjugate $\phi^*$. We would like to solve the problem

$$\begin{array}{ll} \text{minimize} & \sum_{i=1}^m \phi(w_i) \\ \text{subject to} & b_i = (a_i^T x)^2 + w_i, \quad i = 1, \dots, m \\ & \|x\|_2^2 \le r^2 \end{array} \tag{30}$$

in variables $x \in \mathbf{R}^n$ and $w \in \mathbf{R}^m$, where we assume we know the signal $x$ has $\ell_2$-norm bounded by $r$, which seeks the $x$ satisfying the contraints while simultaneously minimizing some measure $\sum_{i=1}^{m} \phi(w_i)$ of the amount of noise. This is obviously a non-convex problem—the equality constraints are quadratic—but we can often effectively approximate its solutions by *lifting* it into a higher-dimensional space. We do so by taking the dual of the dual of the problem.

(a) By introducing variables $\nu_i \in \mathbf{R}$ for the equality constraints and $\lambda \geq 0$ for the constraint $\|x\|_2^2 \leq r^2$, show that a dual to problem (30) is the semidefinite program

$$
\begin{aligned}
\text{maximize} \quad & -\sum_{i=1}^{m} \phi^*(\nu_i) + \nu^T b - \lambda r^2 \\
\text{subject to} \quad & \lambda I - \sum_{i=1}^{m} \nu_i a_i a_i^T \succeq 0, \\
& \lambda \geq 0
\end{aligned}
\tag{31}
$$

in variables $\nu \in \mathbf{R}^m$ and $\lambda$.

(b) Introducing the dual variable $X \in \mathbf{S}_+^n$ for the semidefinite constraint, show that a dual to the problem (31) is

$$
\begin{aligned}
\text{minimize} \quad & \sum_{i=1}^{m} \phi(b_i - a_i^T X a_i) \\
\text{subject to} \quad & X \succeq 0, \quad \mathbf{tr}\, X \leq r^2,
\end{aligned}
$$

where $X \in \mathbf{S}^n$ is the variable.

(c) Suppose that $X^\star$ is optimal for the problem in part (b) and $X^\star$ has rank 1, i.e., $X^\star = x^\star (x^\star)^T$ for some vector $x^\star \in \mathbf{R}^n$. What does that tell you about problem (30)?

(d) Let $\phi(t) = |t|$ be the absolute value. Generate data according to the following process, which we write in Julia notation:

```
m = 40;
n = 6;
A = randn(m, n);
xtrue = randn(n);
b = (A * xtrue) .* (A * xtrue);
b[1:10] .= 1000;
```

(This means that we generate a matrix $A \in \mathbf{R}^{m \times n}$ with i.i.d. $\mathcal{N}(0,1)$ entries, set $x^{\mathrm{true}} \in \mathbf{R}^n$ to be a random vector with i.i.d. $\mathcal{N}(0,1)$ entries, set $b = (Ax^{\mathrm{true}})^2$ elementwise, and then corrupt the first 10 entries of $b$ to satisfy $b_i = 1000$.) Using CVX*, solve the SDP in part (b) for 25 different random realizations of the problem data.

The *numerical rank* of a symmetric matrix $X \in \mathbf{S}^n$ at tolerance $\epsilon > 0$ is the number of eigenvalues $\lambda_i$ of $X$ with $|\lambda_i| > \epsilon$. Plot a histogram of the numerical ranks at tolerance $\epsilon = 10^{-2}$ of your solutions.

(e) Given a positive semidefinite matrix $X$ with spectral decomposition $X = \sum_{i=1}^{n} \lambda_i v_i v_i^T$, the best rank-1 approximation to $X$ is $\lambda_1 v_1 v_1^T$. Thus, given a solution $X^\star = \sum_{i=1}^{n} \lambda_i v_i v_i^T$ to part (b), we approximate $x^{\mathrm{true}}$ by $\hat{x} = \sqrt{\lambda_1} v_1$. For your code in part (d), how frequently do you (effectively) recover $x^{\mathrm{true}}$? Note that we may not correctly recover the sign of $x$, so we measure the error by $\min\{\|\hat{x} - x^{\mathrm{true}}\|_2, \|\hat{x} + x^{\mathrm{true}}\|_2\}$.

**6.25** *Implementing the asymmetric Huber function in CVX\**. We define the *asymmetric Huber function* $\phi : \mathbf{R} \to \mathbf{R}$ as

$$\phi(u) = \begin{cases} M_-(-2u - M_-) & u < -M_- \\ u^2 & -M_- \leq u \leq M_+ \\ M_+(2u - M_+) & u > M_+, \end{cases}$$

where $M_- > 0$ and $M_+ > 0$ are parameters, the negative and positive thresholds, respectively. This function is the same as the standard Huber function with threshold $M > 0$,

$$h(u) = \begin{cases} u^2 & |u| \leq M \\ M(2|u| - M) & |u| > M, \end{cases}$$

when $M_- = M_+ = M$.

The standard Huber function is implemented in CVX\* as an atom. The asymmetric Huber function is not.

Explain how to implement the asymmetric Huber function in CVX\* using standard operations and functions, including the standard Huber function, satisfying the DCP (disciplined convex programming) rules. You may use any atom in CVX\* **except** the atoms `huber_circ`, `huber_pos`, and `berhu`. Your solution should be very short and should include an explanation of how the two thresholds $M_-$ and $M_+$ come in to your implementation. Verify your implementation by plotting it over the range $[-3, 3]$ with $M_- = 1$ and $M_+ = 2$.

*Hints.* Some of the following might be helpful: Pre-composing the standard Huber function with an affine function of $u$; adding an affine function of $u$; scaling.

*Remark.* The standard Huber function is used as a penalty function in regression when the data includes outliers, with $M$ interpreted roughly as the threshold in residuals between a valid sample and an outlier sample. The asymmetric Huber function can be used when the outliers might have different negative and positive thresholds.

**6.26** *Deconvolution of a known filter.* In a (simplified) imaging system, instead of observing a true image, one observes an image with slight blurring (or other aberrations due to sensor error), and wishes to recover the true image. We let $Z \in \mathbf{R}^{d \times d}$ by the true image, which is unobsered, and $Y \in \mathbf{R}^{d \times d}$ be the observed image. Here, $Y = F * Z$ is the convolution of $Z$ with a known filter $F$ (this is the *point spread function*), with entries

$$Y_{kl} = (F * Z)(k, l) = \sum_{i,j=1}^{d} F_{i,j} Z_{k-i,l-j}.$$

For those indices $(k - i, l - j)$ out of the range $\{1, \ldots, d\}^2$, we define $Z_{k-i,l-j} = 0$. Let $m = d^2$ be the number of measurements we take. If we let $z = \mathbf{vec}(Z)$, that is, the vectorized version of $Z$, and $y = \mathbf{vec}(Y)$, then there is a matrix $A \in \mathbf{R}^{m \times m}$ such that

$$y = Az.$$

(You do not need to know what the matrix $A$ is or precisely what **vec** does.) Sensor failures at some pixels $(k, l)$ mean that instead of observing $Y_{kl} = (F * Z)(k, l)$ we observe a $Y_{kl} = 0$.

A vectorized image $z \in \mathbf{R}^m$ is represented in an overcomplete basis $B \in \mathbf{R}^{m \times n}$, $n > m$, so there exist vectors $x \in \mathbf{R}^n$ such that $z = Bx$. Given $Y$ with $y = \mathbf{vec}(Y)$, the image deconvolution problem is to find $x$ minimizing an objective $f(x)$ while reconstructing the observed image, *i.e.* satisfying $y = ABx$.

Formulate the following as convex optimization problems:

(a) The deconvolution problem with objective $f(x) = \|x\|_1$.

(b) The deconvolution problem with objective $f(x) = \|x\|_2$.

(c) The deconvolution problem with objective $f(x) = \|x\|_\infty$.

Solve your optimization problems from parts (a), (b), and (c) on the data in `deconvolution_data.*`. In the file we have defined a vector $y \in \mathbf{R}^m$ and filter matrix $A \in \mathbf{R}^{m \times m}$, with zeroed-out entries indicating sensor failures, as well as a basis matrix $B \in \{-1, 0, 1\}^{m \times n}$.

(d) For each of (a)–(c), display the estimated true image $z = Bx^\star$ that is reconstructed from $x^\star$. In addition, display the initial sensed image $y$. Explain your results in one or two sentences.

*Note.* You can view an image $Z \in \mathbf{R}^{d \times d}$ from a vector $z \in \mathbf{R}^m$ with $m = d^2$ by reshaping and displaying. A few commands to view $z \in \mathbf{R}^m$ as an image follow.

- In Julia, assuming you are using PyPlot, use
  `imshow(reshape(z, (d, d)), cmap = "gray", interpolation="nearest")`
  If you are using Plots and Images, you can use
  `display(Gray.(reshape(z, (d, d))))`

- In Matlab use
  `imshow(reshape(z, d, d))`

- In Python assuming you are using `Matplotlib.pyplot as plt`, use
  `plt.imshow(np.reshape(z, (d,d)).T, "gray", interpolation="nearest")`

**6.27** Let $x^\star$ be optimal for the least-$p$-norm problem

$$\begin{array}{ll} \text{minimize} & \|x\|_p \\ \text{subject to} & Ax = b, \end{array}$$

with variable $x \in \mathbf{R}^n$, where $A \in \mathbf{R}^{m \times n}$, with $m \ll n$. (And of course, $p \in [1, \infty]$.) Determine if the statements below are reasonable or unreasonable.

(a) For $p = 2$, we would expect to see many components of $x^\star$ equal to zero.

(b) For $p = 1$, we would expect to see many components of $x^\star$ equal to zero.

(c) For $p = \infty$, we would expect many components of $x^\star$ to take on the values $\pm \|x^\star\|_\infty$.

**6.28** *Predicting complete rankings.* A (complete) ranking of $K$ items consists of an ordering of the items from rank 1 to rank $K$. For example, these could be $K$ candidates, ranked from 1 (best) to $K$ (worst), or the order in which $K$ horses cross the finish line in a race. We represent a ranking of $K$ items as a vector $\pi \in \mathbf{R}^K$, with $\pi_i$ the rank of item $i$. In the vector $\pi$, the numbers $1, \ldots, K$

each appear exactly once (so it can also be considered a permutation), so there are $K!$ different rankings. We will let $\mathcal{P} \subset \mathbf{R}^K$ denote the set of all $K!$ rankings.

For example with $K = 3$, $(2, 3, 1)$ and $(1, 3, 2)$ are two of the six possible rankings. In the first ranking, item 1 has rank 2, whereas in the second ranking, item 1 has rank 1. Both rankings agree that item 2 has rank 3.

There are many ways to assign a distance between two rankings $\pi$ and $\sigma$, but we will use a simple one, $(1/2)\|\pi - \sigma\|_1$. This distance is zero if and only if $\pi = \sigma$, and one if and only if $\pi$ and $\sigma$ assign the same rank to all items except two, whose ranks are off by one. The maximum possible distance is $K^2/4$ for $K$ even and $(K^2 - 1)/4$ for $K$ odd, achieved by, *e.g.*, $\pi = (1, 2, \ldots, K)$ and $\sigma = (K, K - 1, \ldots, 1)$. The average distance between two randomly chosen rankings is $(K^2 - 1)/6$. (These observations are not relevant for this problem, but only meant to give you an idea of the range and scale of the distance between rankings.)

We wish to build a predictor of an outcome which is a ranking, based on a vector of features. We denote the predictor as $P : \mathbf{R}^d \to \mathcal{P}$, where $P(x)$ is the ranking we predict when the feature vector is $x \in \mathbf{R}^d$. We will judge a predictor by the average distance between the true ranking and the predicted one, on a test set of data $(x_i^{\text{test}}, \pi_i^{\text{test}})$, $i = 1, \ldots, N^{\text{test}}$ (that presumably was not used to develop or fit the predictor):

$$\frac{1}{2N^{\text{test}}} \sum_{i=1}^{N^{\text{test}}} \left\| \pi_i^{\text{test}} - P(x_i^{\text{test}}) \right\|_1 .$$

We refer to this quantity as the average test error of the predictor. (The smaller this is, the better the predictor performs on the test data set.)

We will consider a simple predictor of the form $P(x) = \Pi(\theta x)$, where $\theta \in \mathbf{R}^{K \times d}$ is the predictor coefficient matrix, and $\Pi : \mathbf{R}^K \to \mathcal{P}$ is Euclidean projection onto $\mathcal{P}$. (We will describe this projection in more detail below, but for now we note that if there are multiple rankings that are closest to $\theta x$, we arbitrarily choose one.)

We choose the predictor parameter matrix $\theta$ to minimize

$$\frac{1}{2N} \sum_{i=1}^{N} \|\pi_i - \theta x_i\|_1,$$

where $(x_i, \pi_i)$, $i = 1, \ldots, N$, is some given training data. (Note that this objective would become the average distance between the true and predicted rankings if we replace $\theta x_i$ with $\Pi(\theta x_i)$, but then the objective is no longer convex.)

*Projection onto rankings.* You can use the following, without deriving or justifying it. The projection $\pi = \Pi(y)$ is the vector of rank orders of the entries of $y$ in nondecreasing order. For example with $y = (1.1, -0.3, 0.5, 0.4)$, we have $\Pi(y) = (4, 1, 3, 2)$, since the first entry of $y$ is the largest (*i.e.*, has rank 4), the second entry of $y$ is the smallest (*i.e.*, has rank 1), and so on. So we can compute $\Pi(y)$ by sorting the entries of $y$ (breaking any ties arbitrarily), keeping track of the sort ordering.

Explain how to fit the predictor using the training data with convex optimization.

The data file `ranking_est_data.*` contains functions that generate synthetic training and test data, as well as a function that implements $\Pi$. The data are in the matrices `X_train`, `pi_train`, `X_test`, `pi_test`, and the projection $\Pi$ is given in `Pi()`. Fit the predictor using the training data,

and give the average distance between the true and predicted ranking on both the training and test data sets.

# 7    Statistical estimation

**7.1** *Maximum likelihood estimation of x and noise mean and covariance.* Consider the maximum likelihood estimation problem with the linear measurement model

$$y_i = a_i^T x + v_i, \quad i = 1, \dots, m.$$

The vector $x \in \mathbf{R}^n$ is a vector of unknown parameters, $y_i$ are the measurement values, and $v_i$ are independent and identically distributed measurement errors.

In this problem we make the assumption that the *normalized* probability density function of the errors is given (normalized to have zero mean and unit variance), but not their mean and variance. In other words, the density of the measurement errors $v_i$ is

$$p(z) = \frac{1}{\sigma} f\left(\frac{z - \mu}{\sigma}\right),$$

where $f$ is a given, normalized density. The parameters $\mu$ and $\sigma$ are the mean and standard deviation of the distribution $p$, and are not known.

The maximum likelihood estimates of $x$, $\mu$, $\sigma$ are the maximizers of the log-likelihood function

$$\sum_{i=1}^{m} \log p(y_i - a_i^T x) = -m \log \sigma + \sum_{i=1}^{m} \log f\left(\frac{y_i - a_i^T x - \mu}{\sigma}\right),$$

where $y$ is the observed value. Show that if $f$ is log-concave, then the maximum likelihood estimates of $x$, $\mu$, $\sigma$ can be determined by solving a convex optimization problem.

**7.2** *Mean and covariance estimation with conditional independence constraints.* Let $X \in \mathbf{R}^n$ be a Gaussian random variable with density

$$p(x) = \frac{1}{(2\pi)^{n/2}(\det S)^{1/2}} \exp(-(x - a)^T S^{-1}(x - a)/2).$$

The conditional density of a subvector $(X_i, X_j) \in \mathbf{R}^2$ of $X$, given the remaining variables, is also Gaussian, and its covariance matrix $R_{ij}$ is equal to the Schur complement of the $2 \times 2$ submatrix

$$\begin{bmatrix} S_{ii} & S_{ij} \\ S_{ij} & S_{jj} \end{bmatrix}$$

in the covariance matrix $S$. The variables $X_i$, $X_j$ are called *conditionally independent* if the covariance matrix $R_{ij}$ of their conditional distribution is diagonal.

Formulate the following problem as a convex optimization problem. We are given $N$ independent samples $y_1, \dots, y_N \in \mathbf{R}^n$ of $X$. We are also given a list $\mathcal{N} \in \{1, \dots, n\} \times \{1, \dots, n\}$ of pairs of conditionally independent variables: $(i, j) \in \mathcal{N}$ means $X_i$ and $X_j$ are conditionally independent. The problem is to compute the maximum likelihood estimate of the mean $a$ and the covariance matrix $S$, subject to the constraint that $X_i$ and $X_j$ are conditionally independent for $(i, j) \in \mathcal{N}$.

**7.3** *Maximum likelihood estimation for exponential family.* A probability distribution or density on a set $\mathcal{D}$, parametrized by $\theta \in \mathbf{R}^n$, is called an *exponential family* if it has the form

$$p_\theta(x) = a(\theta) \exp(\theta^T c(x)),$$

for $x \in \mathcal{D}$, where $c : \mathcal{D} \to \mathbf{R}^n$, and $a(\theta)$ is a normalizing function. Here we interpret $p_\theta(x)$ as a density function when $\mathcal{D}$ is a continuous set, and a probability distribution when $\mathcal{D}$ is discrete. Thus we have

$$a(\theta) = \left( \int_{\mathcal{D}} \exp(\theta^T c(x)) \, dx \right)^{-1}$$

when $p_\theta$ is a density, and

$$a(\theta) = \left( \sum_{x \in \mathcal{D}} \exp(\theta^T c(x)) \right)^{-1}$$

when $p_\theta$ represents a distribution. We consider only values of $\theta$ for which the integral or sum above is finite. Many families of distributions have this form, for appropriate choice of the parameter $\theta$ and function $c$.

(a) When $c(x) = x$ and $\mathcal{D} = \mathbf{R}^n_+$, what is the associated family of densities? What is the set of valid values of $\theta$?

(b) Consider the case with $\mathcal{D} = \{0, 1\}$, with $c(0) = 0$, $c(1) = 1$. What is the associated exponential family of distributions? What are the valid values of the parameter $\theta \in \mathbf{R}$?

(c) Explain how to represent the normal family $\mathcal{N}(\mu, \Sigma)$ as an exponential family. *Hint.* Use parameter $(z, Y) = (\Sigma^{-1}\mu, \Sigma^{-1})$. With this parameter, $\theta^T c(x)$ has the form $z^T c_1(x) + \mathbf{tr}\, Y C_2(x)$, where $C_2(x) \in \mathbf{S}^n$.

(d) *Log-likelihood function.* Show that for any $x \in \mathcal{D}$, the log-likelihood function $\log p_\theta(x)$ is concave in $\theta$. This means that maximum-likelihood estimation for an exponential family leads to a convex optimization problem. You don't have to give a formal proof of concavity of $\log p_\theta(x)$ in the general case: You can just consider the case when $\mathcal{D}$ is finite, and state that the other cases (discrete but infinite $\mathcal{D}$, continuous $\mathcal{D}$) can be handled by taking limits of finite sums.

(e) *Optimality condition for ML estimation.* Let $\ell_\theta(x_1, \ldots, x_K)$ be the log-likelihood function for $K$ IID samples, $x_1, \ldots, x_k$, from the distribution or density $p_\theta$. Assuming $\log p_\theta$ is differentiable in $\theta$, show that

$$(1/K)\nabla_\theta \ell_\theta(x_1, \ldots, x_K) = \frac{1}{K} \sum_{i=1}^{K} c(x_i) - \underset{\theta}{\mathbf{E}}\, c(x).$$

(The subscript under $\mathbf{E}$ means the expectation under the distribution or density $p_\theta$.)

*Interpretation.* The ML estimate of $\theta$ is characterized by the empirical mean of $c(x)$ being equal to the expected value of $c(x)$, under the density or distribution $p_\theta$. (We assume here that the maximizer of $\ell$ is characterized by the gradient vanishing.)

**7.4** *Maximum likelihood prediction of team ability.* A set of $n$ teams compete in a tournament. We model each team's ability by a number $a_j \in [0, 1]$, $j = 1, \ldots, n$. When teams $j$ and $k$ play each other, the probability that team $j$ wins is equal to $\mathbf{prob}(a_j - a_k + v > 0)$, where $v \sim \mathcal{N}(0, \sigma^2)$.

You are given the outcome of $m$ past games. These are organized as

$$(j^{(i)}, k^{(i)}, y^{(i)}), \quad i = 1, \ldots, m,$$

meaning that game $i$ was played between teams $j^{(i)}$ and $k^{(i)}$; $y^{(i)} = 1$ means that team $j^{(i)}$ won, while $y^{(i)} = -1$ means that team $k^{(i)}$ won. (We assume there are no ties.)

(a) Formulate the problem of finding the maximum likelihood estimate of team abilities, $\hat{a} \in \mathbf{R}^n$, given the outcomes, as a convex optimization problem. You will find the *game incidence matrix* $A \in \mathbf{R}^{m \times n}$, defined as

$$
A_{il} = \begin{cases} y^{(i)} & l = j^{(i)} \\ -y^{(i)} & l = k^{(i)} \\ 0 & \text{otherwise,} \end{cases}
$$

useful.

The prior constraints $\hat{a}_i \in [0,1]$ should be included in the problem formulation. Also, we note that if a constant is added to all team abilities, there is no change in the probabilities of game outcomes. This means that $\hat{a}$ is determined only up to a constant, like a potential. But this doesn't affect the ML estimation problem, or any subsequent predictions made using the estimated parameters.

(b) Find $\hat{a}$ for the team data given in `team_data.m`, in the matrix `train`. (This matrix gives the outcomes for a tournament in which each team plays each other team once.) You may find the CVX function `log_normcdf` helpful for this problem.

You can form $A$ using the commands

```
A = sparse(1:m,train(:,1),train(:,3),m,n) + ...
sparse(1:m,train(:,2),-train(:,3),m,n);
```

(c) Use the maximum likelihood estimate $\hat{a}$ found in part (b) to predict the outcomes of next year's tournament games, given in the matrix `test`, using $\hat{y}^{(i)} = \mathbf{sign}(\hat{a}_{j^{(i)}} - \hat{a}_{k^{(i)}})$. Compare these predictions with the actual outcomes, given in the third column of `test`. Give the fraction of correctly predicted outcomes.

The games played in `train` and `test` are the same, so another, simpler method for predicting the outcomes in `test` it to just assume the team that won last year's match will also win this year's match. Give the percentage of correctly predicted outcomes using this simple method.

**7.5** *Estimating a vector with unknown measurement nonlinearity.* (A specific instance of exercise 7.9 in *Convex Optimization*.) We want to estimate a vector $x \in \mathbf{R}^n$, given some measurements

$$
y_i = \phi(a_i^T x + v_i), \quad i = 1, \dots, m.
$$

Here $a_i \in \mathbf{R}^n$ are known, $v_i$ are IID $\mathcal{N}(0, \sigma^2)$ random noises, and $\phi : \mathbf{R} \to \mathbf{R}$ is an unknown monotonic increasing function, known to satisfy

$$
\alpha \le \phi'(u) \le \beta,
$$

for all $u$. (Here $\alpha$ and $\beta$ are known positive constants, with $\alpha < \beta$.) We want to find a maximum likelihood estimate of $x$ and $\phi$, given $y_i$. (We also know $a_i$, $\sigma$, $\alpha$, and $\beta$.)

This sounds like an infinite-dimensional problem, since one of the parameters we are estimating is a function. In fact, we only need to know the $m$ numbers $z_i = \phi^{-1}(y_i)$, $i = 1, \dots, m$. So by estimating $\phi$ we really mean estimating the $m$ numbers $z_1, \dots, z_m$. (These numbers are not arbitrary; they must be consistent with the prior information $\alpha \le \phi'(u) \le \beta$ for all $u$.)

(a) Explain how to find a maximum likelihood estimate of $x$ and $\phi$ (*i.e.*, $z_1, \ldots, z_m$) using convex optimization.

(b) Carry out your method on the data given in `nonlin_meas_data.*`, which includes a matrix $A \in \mathbf{R}^{m \times n}$, with rows $a_1^T, \ldots, a_m^T$. Give $\hat{x}_{\mathrm{ml}}$, the maximum likelihood estimate of $x$. Plot your estimated function $\hat{\phi}_{\mathrm{ml}}$. (You can do this by plotting $(\hat{z}_{\mathrm{ml}})_i$ versus $y_i$, with $y_i$ on the vertical axis and $(\hat{z}_{\mathrm{ml}})_i$ on the horizontal axis.)

*Hint.* You can assume the measurements are numbered so that $y_i$ are sorted in nondecreasing order, *i.e.*, $y_1 \le y_2 \le \cdots \le y_m$. (The data given in the problem instance for part (b) is given in this order.)

**7.6** *Maximum likelihood estimation of an increasing nonnegative signal.* We wish to estimate a scalar signal $x(t)$, for $t = 1, 2, \ldots, N$, which is known to be nonnegative and monotonically nondecreasing:

$$0 \le x(1) \le x(2) \le \cdots \le x(N).$$

This occurs in many practical problems. For example, $x(t)$ might be a measure of wear or deterioration, that can only get worse, or stay the same, as time $t$ increases. We are also given that $x(t) = 0$ for $t \le 0$.

We are given a noise-corrupted moving average of $x$, given by

$$y(t) = \sum_{\tau=1}^{k} h(\tau) x(t - \tau) + v(t), \quad t = 2, \ldots, N + 1,$$

where $v(t)$ are independent $\mathcal{N}(0, 1)$ random variables.

(a) Show how to formulate the problem of finding the maximum likelihood estimate of $x$, given $y$, taking into account the prior assumption that $x$ is nonnegative and monotonically nondecreasing, as a convex optimization problem. Be sure to indicate what the problem variables are, and what the problem data are.

(b) We now consider a specific instance of the problem, with problem data (*i.e.*, $N$, $k$, $h$, and $y$) given in the file `ml_estim_incr_signal_data.*`. (This file contains the true signal `xtrue`, which of course you cannot use in creating your estimate.) Find the maximum likelihood estimate $\hat{x}_{\mathrm{ml}}$, and plot it, along with the true signal. Also find and plot the maximum likelihood estimate $\hat{x}_{\mathrm{ml,free}}$ *not taking into account the signal nonnegativity and monotonicity.*

*Hints.*

- Matlab: The function `conv` (convolution) is overloaded to work with CVX.
- Python: Numpy has a function `convolve` which performs convolution. CVXPY has `conv` which does the same thing for variables.
- Julia: The function `conv` is overloaded to work with Convex.jl.

**7.7** *Relaxed and discrete A-optimal experiment design.* This problem concerns the $A$-optimal experiment design problem, described on page 387, with data generated as follows.

```
n = 5; % dimension of parameters to be estimated
p = 20; % number of available types of measurements
m = 30; % total number of measurements to be carried out
randn('state', 0);
V=randn(n,p); % columns are vi, the possible measurement vectors
```

Solve the relaxed $A$-optimal experiment design problem,

$$\begin{array}{ll} \text{minimize} & (1/m)\,\mathbf{tr}\left(\sum_{i=1}^{p} \lambda_i v_i v_i^T\right)^{-1} \\ \text{subject to} & \mathbf{1}^T \lambda = 1, \quad \lambda \succeq 0, \end{array}$$

with variable $\lambda \in \mathbf{R}^p$. Find the optimal point $\lambda^\star$ and the associated optimal value of the relaxed problem. This optimal value is a lower bound on the optimal value of the discrete $A$-optimal experiment design problem,

$$\begin{array}{ll} \text{minimize} & \mathbf{tr}\left(\sum_{i=1}^{p} m_i v_i v_i^T\right)^{-1} \\ \text{subject to} & m_1 + \cdots + m_p = m, \quad m_i \in \{0, \ldots, m\}, \quad i = 1, \ldots, p, \end{array}$$

with variables $m_1, \ldots, m_p$. To get a suboptimal point for this discrete problem, round the entries in $m\lambda^\star$ to obtain integers $\hat{m}_i$. If needed, adjust these by hand or some other method to ensure that they sum to $m$, and compute the objective value obtained. This is, of course, an upper bound on the optimal value of the discrete problem. Give the gap between this upper bound and the lower bound obtained from the relaxed problem. Note that the two objective values can be interpreted as mean-square estimation error $\mathbf{E}\,\|\hat{x} - x\|_2^2$.

**7.8** *Optimal detector design.* We adopt here the notation of §7.3 of the book. Explain how to design a (possibly randomized) detector that minimizes the worst-case probability of our estimate being off by more than one,

$$P_{\text{wc}} = \max_\theta \mathbf{prob}(|\hat{\theta} - \theta| \geq 2).$$

(The probability above is under the distribution associated with $\theta$.)

Carry out your method for the problem instance with data in `off_by_one_det_data.m`. Give the optimal detection probability matrix $D$. Compare the optimal worst-case probability $P_{\text{wc}}^\star$ with the worst-case probability $P_{\text{wc}}^{\text{ml}}$ obtained using a maximum-likelihood detector.

**7.9** *Experiment design with condition number objective.* Explain how to solve the experiment design problem (§7.5) with the condition number $\mathbf{cond}(E)$ of $E$ (the error covariance matrix) as the objective to be minimized.

**7.10** *Worst-case probability of loss.* Two investments are made, with random returns $R_1$ and $R_2$. The total return for the two investments is $R_1 + R_2$, and the probability of a loss (including breaking even, *i.e.*, $R_1 + R_2 = 0$) is $p^{\text{loss}} = \mathbf{prob}(R_1 + R_2 \leq 0)$. The goal is to find the worst-case (*i.e.*, maximum possible) value of $p^{\text{loss}}$, consistent with the following information. Both $R_1$ and $R_2$ have Gaussian marginal distributions, with known means $\mu_1$ and $\mu_2$ and known standard deviations $\sigma_1$ and $\sigma_2$. In addition, it is known that $R_1$ and $R_2$ are correlated with correlation coefficient $\rho$, *i.e.*,

$$\mathbf{E}(R_1 - \mu_1)(R_2 - \mu_2) = \rho\sigma_1\sigma_2.$$

Your job is to find the worst-case $p^{\text{loss}}$ over any joint distribution of $R_1$ and $R_2$ consistent with the given marginals and correlation coefficient.

We will consider the specific case with data

$$\mu_1 = 8, \quad \mu_2 = 20, \quad \sigma_1 = 6, \quad \sigma_2 = 17.5, \quad \rho = -0.25.$$

We can compare the results to the case when $R_1$ and $R_2$ are jointly Gaussian. In this case we have

$$R_1 + R_2 \sim \mathcal{N}(\mu_1 + \mu_2, \sigma_1^2 + \sigma_2^2 + 2\rho\sigma_1\sigma_2),$$

which for the data given above gives $p^{\text{loss}} = 0.050$. Your job is to see how much larger $p^{\text{loss}}$ can possibly be.

This is an infinite-dimensional optimization problem, since you must maximize $p^{\text{loss}}$ over an infinite-dimensional set of joint distributions. To (approximately) solve it, we discretize the values that $R_1$ and $R_2$ can take on, to $n = 100$ values $r_1, \ldots, r_n$, uniformly spaced from $r_1 = -30$ to $r_n = +70$. We use the discretized marginals $p^{(1)}$ and $p^{(2)}$ for $R_1$ and $R_2$, given by

$$p_i^{(k)} = \mathbf{prob}(R_k = r_i) = \frac{\exp\left(-(r_i - \mu_k)^2/(2\sigma_k^2)\right)}{\sum_{j=1}^n \exp\left(-(r_j - \mu_k)^2/(2\sigma_k^2)\right)},$$

for $k = 1, 2$, $i = 1, \ldots, n$.

Formulate the (discretized) problem as a convex optimization problem, and solve it. Report the maximum value of $p^{\text{loss}}$ you find. Plot the joint distribution that yields the maximum value of $p^{\text{loss}}$ using the Matlab commands `mesh` and `contour`.

*Remark.* You might be surprised at both the maximum value of $p^{\text{loss}}$, and the joint distribution that achieves it.

**7.11** *Minimax linear fitting.* Consider a linear measurement model $y = Ax + v$, where $x \in \mathbf{R}^n$ is a vector of parameters to be estimated, $y \in \mathbf{R}^m$ is a vector of measurements, $v \in \mathbf{R}^m$ is a set of measurement errors, and $A \in \mathbf{R}^{m \times n}$ with rank $n$, with $m \geq n$. We know $y$ and $A$, but we don't know $v$; our goal is to estimate $x$. We make only one assumption about the measurement error $v$: $\|v\|_\infty \leq \epsilon$.

We will estimate $x$ using a linear estimator $\hat{x} = By$; we must choose the estimation matrix $B \in \mathbf{R}^{n \times m}$. The estimation error is $e = \hat{x} - x$. We will choose $B$ to minimize the maximum possible value of $\|e\|_\infty$, where the maximum is over all values of $x$ and all values of $v$ satisfying $\|v\|_\infty \leq \epsilon$.

(a) Show how to find $B$ via convex optimization.

(b) *Numerical example.* Solve the problem instance given in `minimax_fit_data.m`. Display the $\hat{x}$ you obtain and report $\|\hat{x} - x^{\text{true}}\|_\infty$. Here $x^{\text{true}}$ is the value of $x$ used to generate the measurement $y$; it is given in the data file.

**7.12** *Cox proportional hazards model.* Let $T$ be a continuous random variable taking on values in $\mathbf{R}_+$. We can think of $T$ as modeling an event that takes place at some unknown future time, such as the death of a living person or a machine failure.

The *survival function* is $S(t) = \mathbf{prob}(T \geq t)$, which satisfies $S(0) = 1$, $S'(t) \leq 0$, and $\lim_{t \to \infty} S(t) = 0$. The *hazard rate* is given by $\lambda(t) = -S'(t)/S(t) \in \mathbf{R}_+$, and has the following interpretation: For

small $\delta > 0$, $\lambda(t)\delta$ is approximately the probability of the event occurring in $[t, t + \delta]$, given that it has not occurred up to time $t$. The survival function can be expressed in terms of the hazard rate:

$$S(t) = \exp\left(-\int_0^t \lambda(\tau)\, d\tau\right).$$

(The hazard rate must have infinite integral over $[0, \infty)$.)

The *Cox proportional hazards model* gives the hazard rate as a function of some features or explanatory variables (assumed constant in time) $x \in \mathbf{R}^n$. In particular, $\lambda$ is given by

$$\lambda(t) = \lambda_0(t)\exp(w^T x),$$

where $\lambda_0$ (which is nonnegative, with infinite integral) is called the *baseline hazard rate*, and $w \in \mathbf{R}^n$ is a vector of model parameters. (The name derives from the fact that $\lambda(t)$ is proportional to $\exp(w_i x_i)$, for each $i$.)

Now suppose that we have observed a set of independent samples, with event times $t^j$ and feature values $x^j$, for $j = 1, \ldots, N$. In other words, we observe that the event with features $x^j$ occurred at time $t^j$. You can assume that the baseline hazard rate $\lambda_0$ is known. Show that maximum likelihood estimation of the parameter $w$ is a convex optimization problem.

*Remarks.* Regularization is typically included in Cox proportional hazards fitting; for example, adding $\ell_1$ regularization yields a sparse model, which selects the features to be used. The basic Cox proportional hazards model described here is readily extended to include discrete times of the event, censored measurements (which means that we only observe $T$ to be in an interval), and the effects of features that can vary with time.

**7.13** *Maximum likelihood estimation for an affinely transformed distribution.* Let $z$ be a random variable on $\mathbf{R}^n$ with density $p_z(u) = \exp -\phi(\|u\|_2)$, where $\phi : \mathbf{R} \to \mathbf{R}$ is convex and increasing. Examples of such distributions include the standard normal $\mathcal{N}(0, \sigma^2 I)$, with $\phi(u) = (u)_+^2 + \alpha$, and the multivariable Laplacian distribution, with $\phi(u) = (u)_+ + \beta$, where $\alpha$ and $\beta$ are normalizing constants, and $(a)_+ = \max\{a, 0\}$. Now let $x$ be the random variable $x = Az + b$, where $A \in \mathbf{R}^{n \times n}$ is nonsingular. The distribution of $x$ is parametrized by $A$ and $b$.

Suppose $x_1, \ldots, x_N$ are independent samples from the distribution of $x$. Explain how to find a maximum likelihood estimate of $A$ and $b$ using convex optimization. If you make any further assumptions about $A$ and $b$ (beyond invertiblility of $A$), you must justify it.

*Hint.* The density of $x = Az + b$ is given by

$$p_x(v) = \frac{1}{|\det A|} p_z(A^{-1}(v - b)).$$

**7.14** *A simple MAP problem.* We seek to estimate a point $x \in \mathbf{R}_+^2$, with exponential prior density $p(x) = \exp -(x_1 + x_2)$, based on the measurements

$$y_1 = x_1 + v_1, \quad y_2 = x_2 + v_2, \quad y_3 = x_1 - x_2 + v_3,$$

where $v_1, v_2, v_3$ are IID $\mathcal{N}(0, 1)$ random variables (also independent of $x$). A naïve estimate of $x$ is given by $\hat{x}_{\text{naive}} = (y_1, y_2)$.

(a) Explain how to find the MAP estimate of $x$, given the observations $y_1, y_2, y_3$.

(b) Generate 100 random instances of $x$ and $y$, from the given distributions. For each instance, find the MAP estimate $\hat{x}_{\mathrm{map}}$ and the naïve estimate $x_{\mathrm{naive}}$. Give a scatter plot of the MAP estimation error, *i.e.*, $\hat{x}_{\mathrm{map}} - x$, and another scatter plot of the naïve estimation error, $\hat{x}_{\mathrm{naive}} - x$.

**7.15** *Minimum possible maximum correlation.* Let $Z$ be a random variable taking values in $\mathbf{R}^n$, and let $\Sigma \in \mathbf{S}_{++}^n$ be its covariance matrix. We do not know $\Sigma$, but we do know the variance of $m$ linear functions of $Z$. Specifically, we are given nonzero vectors $a_1, \ldots, a_m \in \mathbf{R}^n$ and $\sigma_1, \ldots, \sigma_m > 0$ for which

$$\mathbf{var}(a_i^T Z) = \sigma_i^2, \quad i = 1, \ldots, m.$$

For $i \neq j$ the correlation of $Z_i$ and $Z_j$ is defined to be

$$\rho_{ij} = \frac{\Sigma_{ij}}{\sqrt{\Sigma_{ii}\Sigma_{jj}}}.$$

Let $\rho^{\mathrm{max}} = \max_{i \neq j} |\rho_{ij}|$ be the maximum (absolute value) of the correlation among entries of $Z$. If $\rho^{\mathrm{max}}$ is large, then at least two components of $Z$ are highly correlated (or anticorrelated).

(a) Explain how to find the smallest value of $\rho^{\mathrm{max}}$ that is consistent with the given information, using convex or quasiconvex optimization. If your formulation involves a change of variables or other transformation, justify it.

(b) The file `correlation_bounds_data.*` contains $\sigma_1, \ldots, \sigma_m$ and the matrix $A$ with columns $a_1, \ldots, a_m$. Find the minimum value of $\rho^{\mathrm{max}}$ that is consistent with this data. Report your minimum value of $\rho^{\mathrm{max}}$, and give a corresponding covariance matrix $\Sigma$ that achieves this value. You can report the minimum value of $\rho^{\mathrm{max}}$ to an accuracy of 0.01.

**7.16** *Direct standardization.* Consider a random variable $(x, y) \in \mathbf{R}^n \times \mathbf{R}$, and $N$ samples $(x_1, y_1), \ldots, (x_N, y_N) \in \mathbf{R}^n \times \mathbf{R}$, which we will use to estimate the (marginal) distribution of $y$. If the given samples were chosen according to the joint distribution of $(x, y)$, a reasonable estimate for the distribution of $y$ would be the uniform empirical distribution, which takes on values $y_1, \ldots, y_N$ each with probability $1/N$. (If $y$ is Boolean, *i.e.*, $y \in \{0, 1\}$, we are using the fraction of samples with $y = 1$ as our estimate of $\mathbf{prob}(y = 1)$.)

The bad news is that the samples $(x_1, y_1), \ldots, (x_N, y_N) \in \mathbf{R}^n \times \mathbf{R}$ were *not* chosen from the distribution of $(x, y)$, but instead from another (unknown, but presumably similar) distribution. The good news is that we know $\mathbf{E}\, x$, the expected value of $x$. We will use our knowledge of $\mathbf{E}\, x$, together with the samples, to estimate the distribution of $y$. *Direct standardization* replaces the uniform empirical distribution with a weighted one, which takes on values $y_i$ with probability $\pi_i$, where $\pi \succeq 0$, $\mathbf{1}^T \pi = 1$. The weights or sample probabilities $\pi$ are found by maximizing the entropy $-\sum_{i=1}^N \pi_i \log \pi_i$, subject to the requirement that the weighted sample expected value of $x$ matches the known probabilities of $x$ in the distribution, $\mathbf{E}\, x$. This can be expressed as $\sum_{i=1}^N \pi_i x_i = \mathbf{E}\, x$. (Both $x_i$ and $\mathbf{E}\, x$ are known.)

(a) Explain why choosing $\pi$ is a convex optimization problem.

(b) Consider the simple case with $n = 1$, and $x \in \{0, 1\}$, so $\mathbf{E}\, x = \mathbf{prob}(x = 1)$. Find the optimal sample weights $\pi_i^\star$ (analytically). Explain your solution in the following case. The samples are people, with $x = 0$ meaning the person is male, and $x = 1$ meaning the person is female. The

overall population is known to have equal numbers of females and males, but in the sample population the male : female proportions are 0.7 : 0.3.

(c) The data in `direct_std_data.*` contain the samples $x^{(i)}$ and $y^{(i)}$, as well as $\mathbf{E}\,x$. Find the weights $\pi^\star$, and report the weighted empirical distribution. On the same plot, compare the cumulative distributions of

  - the uniform empirical distribution,
  - the weighted empirical distribution using $\pi^\star$, and
  - the true distribution of $y$.

  The true and empirical distributions are provided in the data file. (For example, the 20 elements of `p_true` give $\mathbf{prob}(y = 1)$ up to $\mathbf{prob}(y = 20)$, in order).

  **Note:** Julia users might want to use the ECOS solver, by including `using ECOS`, and solving by using `solve!(prob, ECOSSolver())`.

**Note:** You don't need to know this to solve the problem, but the data for part (c) are real. The random variable $x$ is a vector of a student's gender, age, and mother's and father's educational attainment, and $y$ is the student's score on a standardized test.

**7.17** *Maximum likelihood estimation of a discrete log-concave distribution.* Suppose random variable $X \in \{1, \ldots, n\}$ has unknown probability mass function $p \in \mathbf{R}^n$, where $\mathbf{prob}(X = k) = p_k$, $k = 1, \ldots, n$. Suppose we know that the probability mass function is log-concave, which means

$$\mathbf{prob}(X = k) \geq \sqrt{\mathbf{prob}(X = k - 1)\,\mathbf{prob}(X = k + 1)}, \quad k = 2, \ldots, n - 1.$$

Let $x^{(1)}, \ldots, x^{(N)}$ be $N$ independent and identically distributed (IID) samples of $X$.

(a) Explain how to compute a maximum likelihood estimate of the log-concave probability mass function $p$, given the $N$ observations described above.

(b) Carry out your procedure on the data found in `logccv_mle_data.*`. Plot the empirical probability mass function (which is the maximum likelihood estimate without the log-concave assumption), your maximum likelihood estimate (with the log-concave assumption), and the true probability mass function found in the data file. Comment briefly on the result.

**7.18** *Maximum likelihood estimation of a log-concave distribution.* We have a random variable $X$ which takes values in $\{1, \ldots, n\}$. It has a distribution $p \in \mathbf{R}^n$, with $\mathbf{prob}(X = i) = p_i$. However, we do not know $p$, and would like to determine it based on $N$ independent samples of $X$. In those $N$ samples, let $m_i$ denote the number of samples for which $X = i$, so $\sum_i m_i = N$. The likelihood function is then

$$l(p) = \prod_{i=1}^{n} p_i^{m_i}.$$

We know that the distribution $p$ is log-concave. Recall a discrete function $f : \mathbf{Z} \to \mathbf{R}$ is called concave if $f(i) \geq (1/2)(f(i - 1) + f(i + 1))$. For functions $f$ defined on $\{1, \ldots, n\}$ we require this constraint to hold at $i = 2, \ldots, n - 1$. The function $p$ is called log-concave if $\log p$ is concave. Given $m_1, \ldots, m_n$, we would like to find the log-concave distribution $p$ of maximum likelihood.

(a) Formulate this problem as a convex optimization problem.

(b) We have $n = 13$ and observe

$$m = \begin{pmatrix} 1, & 5, & 6, & 15, & 18, & 20, & 22, & 11, & 22, & 8, & 9, & 4, & 2 \end{pmatrix}.$$

Carry out your method from part (a) on this data. Plot $m_i/N$ (the empirical distribution) and your estimate of $p$.

**7.19** *Rank one nonnegative matrix approximation.* We are given *some* entries of an $m \times n$ matrix $A$ with positive entries, and wish to approximate it as the outer product of vectors $x$ and $y$ with positive entries, *i.e.*, $xy^T$. We will use the average relative deviation between the entries of $A$ and $xy^T$ as our approximation criterion,

$$\frac{1}{mn} \sum_{i=1}^{m} \sum_{j=1}^{n} R(A_{ij}, x_i y_j),$$

where $R$ is the relative deviation of two positive numbers, defined as

$$R(u, v) = \max\{u/v, v/u\} - 1.$$

If we scale $x$ by the positive number $\alpha$, and $y$ by $1/\alpha$, the outer product $(\alpha x)(y/\alpha)^T$ is the same as $xy^T$, so we will normalize $x$ as $\mathbf{1}^T x = 1$.

The data in the problem consists of *some* of the values of $A$. Specifically, we are given $A_{ij}$ for $(i,j) \in \Omega \subseteq \{1, \ldots, m\} \times \{1, \ldots, n\}$. Thus, your goal is to find $x \in \mathbf{R}_{++}^m$ (which satisfies $\mathbf{1}^T x = 1$), $y \in \mathbf{R}_{++}^n$, and $A_{ij} > 0$ for $(i,j) \notin \Omega$, to minimize the average relative deviation between the entries of $A$ and $xy^T$.

(a) Explain how to solve this problem using convex or quasiconvex optimization.

(b) Solve the problem for the data given in `rank_one_nmf_data.*`. This includes a matrix `A`, and a set of indexes `Omega` for the given entries. (The other entries of `A` are filled in with zeros.) Report the optimal average relative deviation between $A$ and $xy^T$. Give your values for $x_1$, $y_1$, and $A_{11} = x_1 y_1$.

**7.20** *Transforming to a normal distribution.* We are given $n$ samples $x_i \in \mathbf{R}$ from an unknown distribution. We seek an increasing piecewise-affine function $\varphi : \mathbf{R} \to \mathbf{R}$ for which $y_i = \varphi(x_i)$ has a distribution close to $\mathcal{N}(0, 1)$. In other words, the nonlinear transformation $x \mapsto y = \varphi(x)$ (approximately) transforms the given distribution to a standard normal distribution.

You can assume that the samples are distinct and sorted, *i.e.*, $x_1 < x_2 < \cdots < x_n$, and therefore we also have $y_1 < y_2 < \cdots < y_n$. The empirical CDF (cumulative distribution function) of $y_i$ is the piecewise-constant function $F : \mathbf{R} \to \mathbf{R}$ given by

$$F(z) = \begin{cases} 0 & z < y_1, \\ k/n & y_k \leq z < y_{k+1}, \quad k = 1, \ldots, n-1, \\ 1 & z \geq y_n. \end{cases}$$

The *Kolmogorov-Smirnov* distance between the empirical distribution of $y_i$ and the standard normal distribution is given by

$$D = \sup_z |F(z) - \Phi(z)|,$$

where $\Phi$ is the CDF of an $\mathcal{N}(0,1)$ random variable. We will use $D$ as our measure of how close the transformed distribution is to normal. Note that $D$ can be as small as $1/(2n)$ (but no smaller), by choosing $y_i = \Phi^{-1}((i-1/2)/n)$.

Note that $D$ only depends on the $n$ numbers $y_1, \ldots, y_n$. From these numbers we extend $\varphi$ to a function on $\mathbf{R}$ using linear interpolation between these values, and extending outside the interval $[x_1, x_n]$ using the same slopes as the first and last segments, respectively. So $y_1, \ldots, y_n$ determine $\varphi$.

Our regularization (measure of complexity) of $\varphi$ is

$$ R = \sum_{i=2}^{n-1} \left| \frac{y_{i+1} - y_i}{x_{i+1} - x_i} - \frac{y_i - y_{i-1}}{x_i - x_{i-1}} \right|. $$

This is the sum of the absolute values of the change in slope of $\varphi$. Note that $R = 0$ if and only if $\varphi$ has no kinks, *i.e.*, is affine.

We will choose $y_i$ (which defines $\varphi$) by minimizing $R$, subject to $D \leq D^{\max}$, where $D^{\max} \geq 1/(2n)$ is a parameter. It can be shown that the condition $y_i < y_{i+1}$ will hold automatically; but if you are nervous about this, you are welcome to add the constraint $y_i + \epsilon \leq y_{i+1}$, where $\epsilon$ is a small positive number.

(a) Explain how to solve this problem using convex or quasiconvex optimization. If your formulation involves a change of variables or other transformation, justify it.

(b) The file `transform_to_normal_data.*` contains the vector $x$ (in sorted order) and its length $n$. Use the method of part (a) to find the optimal $\varphi$ (*i.e.*, $y$) for $D^{\max} = 0.05$. Plot the empirical CDF of the original data $x$ and the normal CDF $\Phi$ on one plot, the empirical CDF of the transformed data $y$ and the normal CDF $\Phi$ on another plot, and the optimal transformation $\varphi$ on a third plot. Report the optimal value of $R$.

*Hints.* In Python and Julia, you should use the (default) ECOS solver to avoid warnings about inaccurate solutions. You can evaluate the normal CDF $\Phi$ using `normcdf.m`/`norminv.m` (Matlab), `scipy.stats.norm.cdf/ppf` (Python), or `normcdf`/`norminvcdf` in StatsFuns.jl (Julia). To plot the empirical CDFs of $x$ and $y$, you are welcome to use the basic plot functions, which connect adjacent points with lines. But if you'd like to create step function style plots, you can use `ecdf.m` (Matlab), `matplotlib.pyplot.step` (Python), or `step` in PyPlot.jl (Julia).

**7.21** *ARX model with sparse excitation.* Consider a time series $y = (y_1, \ldots, y_T)$. The auto-regressive with excitation (ARX) model has the form

$$ y_{t+1} = \beta_1 y_t + \cdots + \beta_M y_{t-M+1} + x_{t+1}, \quad t = M, \ldots, T-1, $$

where $\beta \in \mathbf{R}^M$ are the coefficients, and $x_{M+1}, \ldots, x_T$ is the *excitation* or *input* signal. Neither $\beta$ nor $x \in \mathbf{R}^T$ are known. (The excitation values $x_1, \ldots, x_M$ do not enter the model.)

(a) The classical assumption is that $x_t$ are IID $\mathcal{N}(0, \sigma^2)$ random variables. Explain how to find the maximum likelihood estimate of $\beta \in \mathbf{R}^M$, given $y$.

(b) Now assume that the excitation signal $x$ is sparse. Suggest a simple method, based on convex optimization, for estimating $\beta$. *Remark.* This is a common model of various phenomena. In one example $y$ is an acoustic signal of a voiced phoneme, and $x$ is the glottal excitation. And no, you do not need to know this.

(c) Apply the methods of parts (a) and (b) to the signal given in `arx_fit_data.*`, with $M = 10$ and $T = 200$. The data file also contains the "true" coefficient $\beta^{\text{true}}$ from which the data is generated. Compare the two estimates of $\beta$ with the true value, by plotting all three.

*Hint.* You may use the fact that $x$ can be expressed in terms of the convolution of $b = (1, -\beta)$ and $y$, defined as

$$(b * y)_i = \sum_{j=1}^{\min\{i,M\}} b_j y_{i-j+1}, \quad i = 1, \ldots, T + M.$$

The function `conv(b,y)` is overloaded to work with CVX*. (Warning: $b * y$ is *not* $x$; but $x$ can be written in terms of $b * y$.)

**7.22** *Blending overlapping covariance matrices.* We consider the problem of constructing a covariance matrix $R \in \mathbf{S}_+^n$ from two (not necessarily consistent) estimates of submatrices $S$ and $T$. We order the indices in the underlying random variable so that the first $n_1$ entries correspond to those in the first submatrix but not the second, the next $n_2$ entries correspond to the entries in both submatrices, and the last $n_3$ entries are those in the second submatrix but not the first. We have $n_1 + n_2 + n_3 = n$, and we assume all three are positive. We partition the matrix $R$ as

$$R = \begin{bmatrix} R_{11} & R_{12} & R_{13} \\ R_{12}^T & R_{22} & R_{23} \\ R_{13}^T & R_{23}^T & R_{33} \end{bmatrix}.$$

We wish to choose $R \in \mathbf{S}_+^n$ so that

$$R^{(1)} = \begin{bmatrix} R_{11} & R_{12} \\ R_{12}^T & R_{22} \end{bmatrix} \approx S = \begin{bmatrix} S_{11} & S_{12} \\ S_{12}^T & S_{22} \end{bmatrix}$$

and

$$R^{(2)} = \begin{bmatrix} R_{22} & R_{23} \\ R_{23}^T & R_{33} \end{bmatrix} \approx T = \begin{bmatrix} T_{22} & T_{23} \\ T_{23}^T & T_{33} \end{bmatrix}.$$

(Note the non-standard labeling of the block indices in $T$.) You can assume that $S \in \mathbf{S}_+^{n_1+n_2}$ and $T \in \mathbf{S}_+^{n_2+n_3}$ are given.

Roughly speaking, your job is to guess the six submatrices $R_{ij}$ for $i \leq j$. For four of these, $R_{11}, R_{12}, R_{23}$, and $R_{33}$, you have only one piece of data to work with, *i.e.*, $S_{11}, S_{12}, T_{23}$, and $T_{33}$, respectively. For one of them, $R_{22}$, you have two pieces of data to work with, *i.e.*, $S_{22}$ and $T_{22}$. For one submatrix, $R_{13}$, you have no pieces of data to work with.

(a) *A simple method.* Based on the given data $S$ and $T$, our guess of $R$ is

$$R_{11} = S_{11}, \qquad\qquad R_{12} = S_{12}, \quad R_{13} = 0,$$
$$R_{22} = (1/2)(S_{22} + T_{22}), \quad R_{23} = T_{23}, \quad R_{33} = T_{33}.$$

For the four submatrices for which you have only one piece of data, we simply use that data as our guess. For the one submatrix for which we have two pieces of data, we average the two values. For the one submatrix for which we have no data, we guess the zero matrix.

Show by a specific numerical example that this simple method can yield an *unacceptable* value of $R$. (No, we will not be more specific about what we mean by this; part of the problem is to figure out what we mean. Also, we will deduct points from examples that are more complicated than they need to be.)

104

(b) *Convex optimization to the rescue.* Suppose we choose $R$ by solving the convex optimization problem

$$\begin{array}{ll} \text{minimize} & \|R^{(1)} - S\|_F^2 + \|R^{(2)} - T\|_F^2 + \|R_{13}\|_F^2 \\ \text{subject to} & R \succeq 0. \end{array}$$

Here the variable is $R \in \mathbf{S}^n$, and $\|U\|_F = (\mathbf{tr}(U^T U))^{1/2}$ is the Frobenius norm of a matrix. Let $R^{\text{sim}}$ be the estimate of $R$ obtained using the simple method in part (a). Show that if $R^{\text{sim}} \succeq 0$, then it is the solution of this problem.

(c) Apply the method described in part (b) to the specific numerical example you provided in part (a), and check (numerically) that the result $R^\star$ is now acceptable.

**7.23** *Fitting a periodic Poisson distribution to data.* We model the (random) number of times that some type of event occurs in each hour of the day as independent Poisson variables, with

$$\mathbf{prob}(k \text{ events occur}) = e^{-\lambda_t} \frac{\lambda_t^k}{k!}, \quad k = 0, 1, \dots,$$

with parameter $\lambda_t \geq 0$, $t = 1, \dots, 24$. (For $\lambda_t = 0$, $k = 0$ events occur with probability one.) Here $t$ denotes the hour, with $t = 1$ corresponding to the hour from midnight to 1AM, and $t = 24$ the hour between 11PM and midnight. (This is the periodic Poisson distribution in the title.) The parameter $\lambda_t$ is the expected value of the number of events that occur in hour $t$; it can be thought of as the rate of occurence of the events in hour $t$.

Over one day we observe the numbers of events $N_1, \dots, N_{24}$.

(a) *Maximum likelihood estimate of parameters.* What is the maximum likelihood estimate of the parameters $\lambda_1, \dots, \lambda_{24}$? *Hint.* There is a simple analytical solution. You should consider the cases $N_t > 0$ and $N_t = 0$ separately.

(b) *Regularized maximum likelihood estimate of parameters.* In many applications it is reasonable to assume that $\lambda_t$ varies smoothly over the day; for example, the rate of occurence of events for 3PM–4PM is not too different from the rate of occurence for 4PM–5PM. To obtain a smooth estimate of $\lambda_t$ we maximize the log likelihood minus the regularization term

$$\rho \left( \sum_{t=1}^{23} (\lambda_{t+1} - \lambda_t)^2 + (\lambda_1 - \lambda_{24})^2 \right),$$

where $\rho \geq 0$. Explain how to find the values $\lambda_1, \dots, \lambda_{24}$ using convex optimization. If you change variables, explain.

(c) What happens as $\rho \to \infty$? You can give a very short answer, with an informal argument. *Hint.* As in part (a), there is a simple analytical solution.

(d) *Numerical example.* Over one day, we observe

$$N = (0, 4, 2, 2, 3, 0, 4, 5, 6, 6, 4, 1, 4, 4, 0, 1, 3, 4, 2, 0, 3, 2, 0, 1).$$

Find the regularized maximum likelihood parameters for $\rho \in \{0.1, 1, 10, 100\}$ using CVX*, and plot $\lambda_t$ versus $t$ for each value of $\rho$.

(e) *Choosing the hyper-parameter value by out-of-sample test.* One way to choose the value of $\rho$ is to see which of the models found in part (d) has the highest log likelihood on a test set, *i.e.*, another day's data, that was not used to create the model. For each of the 4 values of the parameters you estimated in part (d), evaluate the log likelihood of another day's number of events,

$$N^{\text{test}} = (0, 1, 3, 2, 3, 1, 4, 5, 3, 1, 4, 3, 5, 5, 2, 1, 1, 1, 2, 0, 1, 2, 1, 0).$$

Which hyper-parameter value $\rho$ would you choose?

**7.24** *Morphing between two discrete distributions.* Consider two distributions for a random variable that takes values in $\{1, 2, \ldots, n\}$, given by $q, r \in \mathbf{R}^n$, with $q \succeq 0$, $\mathbf{1}^T q = 1$, and $r \succeq 0$, $\mathbf{1}^T r = 1$. We seek a sequence of distributions $p^{(i)}$, $i = 1, \ldots, N$, that 'morph' between $q$ and $r$. This means that $p^{(1)} = q$, $p^{(N)} = r$, and $p^{(i+1)}$ is close to $p^{(i)}$ for $i = 1, \ldots, (N-1)$, in some sense. Specifically we will minimize

$$\sum_{i=1}^{N-1} d(p^{(i)}, p^{(i+1)})$$

where $d$ is a distance function.

(a) *Euclidean morphing.* What is the solution when the distance function is the sum of squares, $d^{\text{sq}}(u, v) = \|u - v\|_2^2$? The solution is simple; you can just give it without justification.

(b) *Hellinger morphing.* Now we use the Hellinger distance function

$$d^{\text{hel}}(u, v) = \sum_{i=1}^{n} (\sqrt{u_i} - \sqrt{v_i})^2.$$

Explain how to solve the Hellinger morphing problem using convex optimization.

(c) *Kolmogorov morphing.* Now we use the Kolmogorov distance function

$$d^{\text{kol}}(u, v) = \max_{i=1,\ldots,n} \left| \sum_{j=1}^{i} u_j - \sum_{j=1}^{i} v_j \right|,$$

which is the $\ell_\infty$ distance between the respective cumulative distributions (using the order of the outcomes). Explain how to solve the Kolmogorov morphing problem using convex optimization.

(d) Find the Euclidean, Hellinger, and Kolmogorov morphings for $N = 10$, $n = 100$. Use $q$ and $r$ provided in `morphing_data.*`. Plot each $p^{(i)}$ versus $n$. Produce one figure for each choice of distance function.

*Note.* In Python and Julia, you should use the ECOS solver.

**7.25** *Constrained maximum likelihood estimation of mean and covariance.* You are given some independent samples $x_1, \ldots, x_N \in \mathbf{R}^n$ from a Gaussian distribution $\mathcal{N}(\mu, \Sigma)$.

(a) Explain how to find the maximum-likelihood estimate of $\mu$ and $\Sigma$, subject to the constraint that $\Sigma^{-1}\mu \succeq 0$, using convex optimization. You must fully justify any change of variables.

*Finance interpretation.* (Not needed to solve the problem.) Suppose $x \sim \mathcal{N}(\mu, \Sigma)$ is the return of $n$ assets. The portfolio vector $h$ that maximizes the risk-adjusted return $\mu^T h - \gamma h^T \Sigma h$, where $\gamma > 0$ is the risk aversion parameter, is $h = (1/2\gamma)\Sigma^{-1}\mu$. So the constraint in the problem above is that the optimal portfolio has nonnegative entries, *i.e.*, is a long-only portfolio. The constrained maximum-likelihood estimate finds the maximum likelihood mean and covariance of the return distribution, subject to the constraint that the associated optimal portfolio is long-only.

*Probability interpretation.* (Not needed to solve the problem.) The constraint $\Sigma^{-1}\mu \succeq 0$ is the same as $\nabla p(0) \succeq 0$, where $p$ is the density of the $\mathcal{N}(\mu, \Sigma)$ distribution. In other words, at 0, the density is nondecreasing in each coordinate.

(b) Use your method on the data in `long_only_ml_data.*`. The data file also contains the 'true' mean and covariance, from the which the data are generated. (Of course in any practical application, you would not know these.) Report the $\ell_2$ distance between your estimated mean and the true mean, and also the Frobenius norm of the difference between your estimamted covariance and the true covariance.

Repeat for the maximum likelihood estimate of $\mu$ and $\Sigma$ *without* the constraint $\Sigma^{-1}\mu \succeq 0$. (That is, find the maximum likelihood estimates and give the distances to the true mean and covariance.) *Hint.* The unconstrained maximum likelihood estimates are the empirical mean and covariance of the data, when the empirical covariance is positive definite.

**7.26** *c-Optimal experiment design* [Harman and Jurík]. The optimization problem

$$
\begin{array}{ll}
\text{minimize} & c^T \left( A \operatorname{\mathbf{diag}}(x) A^T \right)^{-1} c \\
\text{subject to} & x \succeq 0 \\
& \mathbf{1}^T x = 1,
\end{array}
\tag{32}
$$

with variable $x \in \mathbf{R}^n$, where $c$ is a nonzero $m$-vector and $A$ an $m \times n$ matrix, is known in statistics as the *c-optimal* experiment design problem. Here we show that it can be reformulated as an LP.

Since $x \succeq 0$, the matrix $A \operatorname{\mathbf{diag}}(x) A^T$ is at least positive semidefinite. If it is not positive definite, we interpret the cost function as $c^T (A \operatorname{\mathbf{diag}}(x) A^T)^\dagger c$ if $c$ is in the range of $A \operatorname{\mathbf{diag}}(x) A^T$, and as $+\infty$ otherwise.

(a) Show that (32) is equivalent to

$$
\begin{array}{ll}
\text{minimize} & \sum_{k=1}^{n} h(x_k, y_k) \\
\text{subject to} & Ay + c = 0 \\
& \mathbf{1}^T x = 1,
\end{array}
\tag{33}
$$

with variables $x$, $y$, where $h$ is the quadratic-over-linear function

$$
h(x_k, y_k) = \begin{cases} y_k^2/x_k & x_k > 0 \\ 0 & y_k = x_k = 0 \\ +\infty & \text{otherwise.} \end{cases}
$$

*Hint.* To show the equivalence between (32) and (33), assume $x$ is fixed in (33), with $x \succeq 0$ and $c$ in the range of $A \operatorname{\mathbf{diag}}(x) A^T$. The minimization problem over $y$ is an equality-constrained quadratic optimization problem. Use the optimality conditions to find the optimal $y$ as a function of $x$.

(b) Use the result of part (a) to show that the solution of (32) is $x_k = |\hat{y}_k|/\|\hat{y}\|_1$, where $\hat{y}$ is the solution of

$$\begin{array}{ll} \text{minimize} & \|y\|_1^2 \\ \text{subject to} & Ay + c = 0. \end{array} \qquad (34)$$

This can be further reduced to an LP.

*Hint.* Follow a similar idea as in the hint of part (a), but now assume $y$ is fixed in (33) and optimize over $x$.

**7.27** *Estimating a time-dependent covariance scaling.* Consider a vector time series $x_t \in \mathbf{R}^n$, $t = 1, 2, \ldots$. We want to fit a model of the form $x_t \sim \mathcal{N}(0, a_t \Sigma)$, where $\Sigma \in \mathbf{S}_{++}^n$ is given, and $a_t > 0$. (We assume $x_t$ and $x_s$ are independent for $t \neq s$.) Roughly speaking, the covariance matrix of $x_t$ scales up and down with time; $a_t$ is the scale factor at time $t$.

We are given the base covariance matrix $\Sigma$, and a sample sequence $x_1, \ldots, x_T$. We are to find the scale factor time series $a_t$, $t = 1, \ldots, T$.

We will fit the scale factor times series by minimizing the negative log likelihood, plus a term that regularizes the variation in $a(t)$,

$$\lambda \sum_{t=1}^{T-1} (\log a_{t+1} - \log a_t)^2,$$

where $\lambda > 0$ is a given hyper-parameter. (Note that $\log a_{t+1} - \log a_t$ can be interpreted as the fractional change in the scaling parameter from $t$ to $t+1$.)

(a) Show how to solve this fitting problem using convex or quasiconvex optimization. Fully justify any changes of variables, or relaxations, that your method uses.

(b) Carry out your method on the data given in `covar_series_data.*`, for the three hyper-parameter values $\lambda = 0.01$, $\lambda = 1$, $\lambda = 100$. (This gives three different estimates of the scale factor time series.) Plot these three estimates versus $t$.

(c) *Validation.* The data `covar_series_data.*` contains another time series $y_1, \ldots, y_T$ from the same source. Evaluate the negative log likelihood of your three models obtained in part (b) on this validation data set. Which of the three hyper-parameter values achieves the smallest negative log-likelihood?

**7.28** *Elliptical distributions.* An *elliptical distribution* on $\mathbf{R}^n$ has a probability density function of the form

$$p(x) = Cg((x - \mu)^T \Sigma^{-1} (x - \mu)),$$

where $\mu \in \mathbf{R}^n$ and $\Sigma \in \mathbf{S}_{++}^n$ are parameters, and $g : \mathbf{R} \to \mathbf{R}$ is an unnormalized density function. The constant $C$ normalizes the density:

$$C = \left( \int g((x - \mu)^T \Sigma^{-1} (x - \mu)) \, dx \right)^{-1}.$$

(We assume $g$ is such that the integral is finite for any choice of $\Sigma \in \mathbf{S}_{++}^n$ and $\mu \in \mathbf{R}^n$.) When $g(u) = \exp(-u)$, the elliptical distribution reduces to a Gaussian.

You are given independent samples $x_1, \ldots, x_N \in \mathbf{R}^n$ from an elliptical distribution. Suppose that $g$ is log-concave and decreasing. Explain how to find the maximum-likelihood estimate of $\mu$ and $\Sigma$ using convex optimization.

*Hint.* Define $z = \Sigma^{-1/2}(x - \mu)$. Then

$$
\begin{aligned}
C &= \det \Sigma^{-1/2} \left( \int g(z^T z)\, dz \right)^{-1} \\
&= \det \Sigma^{-1/2} \left( \int g(u^2) V u^{n-1}\, du \right)^{-1},
\end{aligned}
$$

where $u = \|z\|_2$ and $V = \frac{\pi^{n/2}}{\Gamma(\frac{n}{2}+1)}$ is the hyper-volume of the unit sphere in $\mathbf{R}^n$.

**7.29** *Maximum likelihood prediction of team ability.* (A more CVX-friendly tweak of problem 7.4.) A set of $n$ teams compete in a tournament. We model each team's ability by a number $a_j \in [0,1]$, $j = 1, \ldots, n$. When teams $j$ and $k$ play each other, the probability that team $j$ wins is equal to $\mathbf{prob}(a_j - a_k + v > 0)$, where $v$ is a symmetric random variable with density

$$
p(v) = \frac{2\sigma^{-1}}{(e^{v/\sigma} + e^{-v/\sigma})^2},
$$

where $\sigma$ controls the standard deviation of $v$. For this question, you will likely find it useful that the cumulative distribution function (CDF) of $v$ is

$$
F(t) = \int_{-\infty}^{t} p(v)\, dv = \frac{e^{t/\sigma}}{e^{t/\sigma} + e^{-t/\sigma}}.
$$

You are given the outcome of $m$ past games. These are organized as

$$
(j^{(i)}, k^{(i)}, y^{(i)}), \quad i = 1, \ldots, m,
$$

meaning that game $i$ was played between teams $j^{(i)}$ and $k^{(i)}$; $y^{(i)} = 1$ means that team $j^{(i)}$ won, while $y^{(i)} = -1$ means that team $k^{(i)}$ won. (We assume there are no ties.)

(a) Formulate the problem of finding the maximum likelihood estimate of team abilities, $\hat{a} \in \mathbf{R}^n$, given the outcomes, as a convex optimization problem. You will find the *game incidence matrix* $A \in \mathbf{R}^{m \times n}$, defined as

$$
A_{il} = \begin{cases}
y^{(i)} & l = j^{(i)} \\
-y^{(i)} & l = k^{(i)} \\
0 & \text{otherwise},
\end{cases}
$$

useful.

The prior constraints $\hat{a}_i \in [0,1]$ should be included in the problem formulation. Also, we note that if a constant is added to all team abilities, there is no change in the probabilities of game outcomes. This means that $\hat{a}$ is determined only up to a constant, like a potential. But this doesn't affect the ML estimation problem, or any subsequent predictions made using the estimated parameters.

(b) Find $\hat{a}$ for the team data given in `team_data.jl`, in the matrix `train`. (This matrix gives the outcomes for a tournament in which each team plays each other team once.)

You can form $A$ using the commands

```
using SparseArrays;
A1 = sparse(1:m, train[:, 1], train[:,3], m, n);
A2 = sparse(1:m, train[:, 2], -train[:,3], m, n);
A = A1 + A2;
```

(c) Use the maximum likelihood estimate $\hat{a}$ found in part (b) to predict the outcomes of next year's tournament games, given in the matrix `test`, using $\hat{y}^{(i)} = \mathbf{sign}(\hat{a}_{j^{(i)}} - \hat{a}_{k^{(i)}})$. Compare these predictions with the actual outcomes, given in the third column of `test`. Give the fraction of correctly predicted outcomes.

The games played in `train` and `test` are the same, so another, simpler method for predicting the outcomes in `test` it to just assume the team that won last year's match will also win this year's match. Give the percentage of correctly predicted outcomes using this simple method.

**7.30** *Duals of some multiclass classification problems.* In the $k$-class multiclass classification problem, we are given data pairs $\{x_i, y_i\} \in \mathbf{R}^n \times \{1, \ldots, k\}$, where $x_i \in \mathbf{R}^n$ are covariates with which we wish to predict the label $y_i \in \{1, \ldots, k\}$, and $i = 1, \ldots, m$. A typical approach is to seek a classifier represented by a matrix

$$\Theta \in \mathbf{R}^{k \times n}, \quad \Theta = \begin{bmatrix} \theta_1^T \\ \theta_2^T \\ \vdots \\ \theta_k^T \end{bmatrix}$$

and find $\Theta$ so that $\theta_{y_i}^T x_i \gg \theta_j^T x_i$ for all $j \neq y_i$ and $i = 1, \ldots, m$, that is, the correct label is assigned a much higher score than incorrect labels. In this problem, you will compute duals for different approaches for the multiclass classification problem.

(a) For a set of scores $z_1, \ldots, z_k \in \mathbf{R}$ and a label $y \in \{1, \ldots, k\}$, the multiclass logistic loss is

$$\ell_{\mathrm{mc}}(z, y) = \log \left( \sum_{j=1}^k \exp(z_j - z_y) \right),$$

which is convex in $z$. Show that if $z_y \leq z_j$ for some index $j \neq y$, $\ell_{\mathrm{mc}}(z, y) \geq \log 2$, while $\inf_z \ell_{\mathrm{mc}}(z, y) = 0$.

(b) Let $\|\cdot\|$ be an arbitrary norm on matrices and $\lambda \geq 0$. Give a dual problem for the regularized multiclass logistic regression problem

$$\text{minimize} \sum_{i=1}^m \ell_{\mathrm{mc}}(\Theta x_i, y_i) + \lambda \|\Theta\|.$$

Your dual may depend on the dual norm $\|\cdot\|^*$ of $\|\cdot\|$, but all other functions should be explicit.

(c) Instead of a general matrix norm, it is often useful to regularize individual rows of $\Theta$. Give a dual problem for

$$\text{minimize} \quad \sum_{i=1}^{m} \ell_{\text{mc}}(\Theta x_i, y_i) + \lambda \sum_{j=1}^{k} \|\theta_j\|.$$

Your dual may depend on the dual norm $\|\cdot\|^*$ of $\|\cdot\|$, but all other functions should be explicit.

(d) Instead of the multiclass logistic loss, it is sometimes useful to have a loss that decomposes across all indices. Let $\phi : \mathbf{R} \to \mathbf{R}_+$ be a non-increasing convex function. Give a dual problem for

$$\text{minimize} \quad \sum_{i=1}^{m} \sum_{j=1}^{k} \phi(x_i^T \theta_j - x_i^T \theta_{y_i}) + \lambda \|\Theta\|.$$

Your dual problem should be written in terms of the conjugates $\phi^*$ and the dual norm $\|\cdot\|^*$.

**7.31** *The kernel trick.* Consider a binary classification problem with data in pairs $(x_i, y_i) \in \mathbf{R}^n \times \{-1, 1\}$, where we represent a classifer mapping $x \in \mathbf{R}^n$ to $\{\pm 1\}$ by $\theta \in \mathbf{R}^n$, predicting $\hat{y} = \text{sign}(x^T \theta)$. Given $m$ observations $(x_i, y_i)$, $i = 1, \ldots, m$, we solve the convex optimization problem

$$\text{minimize} \quad \sum_{i=1}^{m} f(y_i x_i^T \theta) + \frac{\lambda}{2} \|\theta\|_2^2 \tag{35}$$

to find a classifier $\theta$, where $\lambda > 0$ is a regularization parameter and $f : \mathbf{R} \to \mathbf{R}_+$ is a non-increasing convex function. Let $X = [x_1 \ \cdots \ x_m]^T \in \mathbf{R}^{m \times n}$ denote the data matrix.

(a) Show that a dual of problem (35) is

$$\text{maximize} \quad -\sum_{i=1}^{m} f^*(\alpha_i) - \frac{1}{2\lambda} \|X^T \mathbf{diag}(y)\alpha\|_2^2,$$

with variable $\alpha \in \mathbf{R}^m$. *Hint.* Introduce the equality constraints $z_i = y_i x_i^T \theta$.

(b) Using duality, show that the solution $\theta^*$ to the original problem is of the form

$$\theta^* = \sum_{i=1}^{m} \nu_i x_i = X^T \nu$$

for some vector $\nu \in \mathbf{R}^m$. Specify your vector $\nu$.

In many scenarios, it is useful to consider functions of $x$, including (but not limited to) polynomials, Fourier transforms, or other nonlinearities. In this case, for a *feature mapping* $\varphi : \mathbf{R}^n \to \mathbf{R}^N$ we instead predict with $\theta \in \mathbf{R}^N$ and use $\hat{y} = \mathbf{sign}(\theta^T \varphi(x))$. For example, if

$$\varphi(x) = (1, x_1, \ldots, x_n, x_1^2, x_1 x_2, x_1 x_3, \ldots, x_1 x_n, x_2 x_1, \ldots, x_{n-1} x_n, x_n^2) \in \mathbf{R}^{1+n+n^2},$$

we can represent all quadratic functions of the input vector $x \in \mathbf{R}^n$. Instead of solving problem (35), we wish to find a classifier based on a (nonlinear) transformation of the $x_i$ vectors, replacing $x_i$ by $\varphi(x_i) \in \mathbf{R}^N$, that is, we wish to solve

$$\text{minimize} \quad \sum_{i=1}^{m} f(y_i \varphi(x_i)^T \theta) + \frac{\lambda}{2} \|\theta\|_2^2. \tag{36}$$

By part (b), the solution to this must satisfy $\theta^\star = \sum_{i=1}^{m} \nu_i \varphi(x_i)$ for some $\nu \in \mathbf{R}^m$, and therefore we may classify a new instance $x$ by evaluating

$$\varphi(x)^T \theta^\star = \sum_{i=1}^{m} \varphi(x)^T \varphi(x_i) \nu_i.$$

The *kernel trick* works as follows. In statistical machine learning parlance, a *kernel function* is a symmetric function $K : \mathbf{R}^n \times \mathbf{R}^n \to \mathbf{R}$ that can be written as $K(x,z) = \varphi(x)^T \varphi(z)$ for some mapping $\varphi : \mathbf{R}^n \to \mathbf{R}^N$, where $N$ may even be infinite. In many cases, our choice of $\varphi(\theta)$ in problem (36) may be efficiently evaluated by such a kernel, even when $N$ is large. These mappings can allow one to introduce nonlinearities in classification rules that are quite effective.

(c) Suppose we have a kernel $K$ for $\varphi$, so that we can write $\varphi(x)^T \theta^\star = \sum_{i=1}^{m} K(x, x_i) \nu_i$. Let $G \in \mathbf{S}_+^m$ be the *Gram matrix* whose entries are $G_{i,j} = K(x_i, x_j)$. Show how to implicitly find $\theta^\star$ using this Gram matrix and the dual problem in part (a). More specifically, show how to find the parameters $\nu$ in part (b) without ever explicitly computing $\varphi(x_i)$.

For completeness, we enumerate a few different kernel functions to highlight why these ideas may be important. For $k \in \mathbf{Z}_+$ and $x \in \mathbf{R}^n$ define the tensor

$$X = x^{\otimes k} \in \underbrace{\mathbf{R}^n \times \mathbf{R}^n \times \cdots \times \mathbf{R}^n}_{k \text{ times}}$$

to have entries $X_{i_1,\ldots,i_k} = x_{i_1} x_{i_2} \cdots x_{i_k}$, and let $\mathbf{vec}(X) \in \mathbf{R}^{n^k}$ be the vectorized version of $X$, that is, we simply stack all entries of $X$ on one another. (We say $x^{\otimes 0} = 1$.) Then for any $x, z \in \mathbf{R}^n$ and degree $d \in \mathbf{Z}_+$ we have

$$(1 + x^T z)^d = \varphi(x)^T \varphi(z) \quad \text{where} \quad \varphi(x) = \left[ \sqrt{\binom{d}{k}} \mathbf{vec}(x^{\otimes k}) \right]_{k=0}^{d}.$$

Note that the dimension of $\varphi(x)$ is $\sum_{i=0}^{d} n^i = \frac{n^{d+1}-1}{n-1}$, and the structure of $\varphi$ shows that the kernel $K(x,z) = (1 + x^T z)^d$ can represent *all* polynomials of $x$ up to degree $d$.

(d) Compare the computational time to evaluate $\varphi(x)^T \theta^\star = \sum_{i=1}^{m} \varphi(x)^T \varphi(x_i) \nu_i$ by explicitly using the vector representation $\varphi(x)$ to that using the kernel $K(x,z) = (1 + x^T z)^d$.

**7.32** *Maximum likelihood estimation with conditional independence priors.* Let $X \in \mathbf{R}^n$ be a zero mean Gaussian random vector with covariance matrix $\Sigma \in \mathbf{S}_{++}^n$, *i.e.*, with density

$$p(x) = \frac{\exp\left(-x^T \Sigma^{-1} x / 2\right)}{(2\pi)^{n/2} (\det \Sigma)^{1/2}}.$$

For $i \neq j$, the scalar random variables $X_i$ and $X_j$ are conditionally independent given the other entries if and only if $\left(\Sigma^{-1}\right)_{ij} = 0$. We have prior information that some pairs of entries of $X$ are conditionally independent given the others, specified as a set $\mathcal{P} \subseteq \{1, \ldots, n\} \times \{1, \ldots, n\}$.

Given IID observations $x^{(1)}, \ldots, x^{(m)}$ of $X$, we seek $\hat{\Sigma}$, the maximum likelihood estimate of $\Sigma$ subject to the conditional independence constraints. You can assume that the empirical covariance $Y = \frac{1}{m} \sum_{k=1}^{m} (x^{(k)})(x^{(k)})^T$ is positive definite. (The empirical covariance $Y$ is the maximum likelihood estimate of $\Sigma$ without the conditional independence constraints.)

(a) Explain how to solve this problem using convex optimization. If your method involves a change of variables, be sure to explain how to recover $\hat{\Sigma}$ from a solution of your problem.

(b) Solve the instance of the problem with data given in `mle_cond_ind_data.*` and prior conditional independence information

$$\mathcal{P} = \{(1,3), \ (1,5), \ (2,4), \ (3,5)\}.$$

Give the maximum likelihood estimate $\hat{\Sigma}$ and verify numerically that the conditional independence constraint is satisfied.

The data file includes the 'true' covariance matrix $\Sigma_{\text{true}}$, stored in `Sigma_true`. (Of course, in any practical application you would not have $\Sigma_{\text{true}}$.) Give $\|\hat{\Sigma} - \Sigma_{\text{true}}\|_F$. Compare with $\|Y - \Sigma_{\text{true}}\|_F$, the estimation error obtained without the conditional independence constraints.

**7.33** *Maximum entropy distribution with quartile constraints.* Let $X$ be a random variable on $[-1, 1]$ with mean $\mu$, variance $\sigma^2$, 25th percentile $q_{25}$, median $q_{50}$, and 75th percentile $q_{75}$. Your goal is to find a density function $f : [-1, 1] \to \mathbf{R}_+$ that maximizes the entropy,

$$H(f) = -\int_{-1}^{1} f(x) \log f(x) \, dx,$$

subject to the given mean, variance, and quartiles. (In the formula above, we define $f(x) \log f(x)$ as 0 when $f(x) = 0$.)

You will work with a discretized version of the problem. We take $x_i = -1 + 2i/N$, for $i = 1, \ldots, N$, where $N$ is the number of points in the discretization. You will specify the density $f$ by its values at $x_i$, $p_i = f(x_i)$, $i = 1, \ldots, N$, so the density function $f$ is given by a vector $p \in \mathbf{R}^N$. You can use the Riemann sum approximation of any integral, *i.e.*, for any function $g : [-1, 1] \to \mathbf{R}$ you can replace

$$\int_{-1}^{1} g(x) \, dx$$

with the approximation

$$\frac{2}{N} \sum_{i=1}^{N} g(x_i).$$

(a) Solve the problem with $N = 300$ and the given data

$$\mu = -0.1, \quad \sigma = 0.35, \quad q_{25} = -0.3, \quad q_{50} = -0.05, \quad q_{75} = 0.1.$$

Plot the resulting probability distribution and its cumulative distribution function. Add dots to the CDF plot at $(-0.3, 0.25)$, $(-0.05, 0.5)$, and $(0.1, 0.75)$. (Your CDF should pass through these points.)

(b) Repeat part (a) *without* the quartile constraints, *i.e.*, find the maximum likelihood density subject only to the mean and variance given in part (a). *Hint*: The maximum entropy distribution on $\mathbf{R}$ with mean $\mu$ and variance $\sigma^2$ is the Gaussian distribution $\mathcal{N}(\mu, \sigma^2)$. Your distribution should look like $\mathcal{N}(\mu, \sigma^2)$, truncated to $[-1, 1]$.

**7.34** *Time varying regression model.* We are given data of the form $(x, t)$, where $x \in \mathbf{R}^n$ is a vector of features, and $t \in \{1, \ldots, T\}$ is a time stamp (which you can also consider to be a feature). We are also given the corresponding label or outcome $y \in \mathbf{R}$. The data set has the form

$$(x^i, t^i), \quad y^i, \quad i = 1, \ldots, m.$$

We allow for the possibility that multiple data points can have the same time stamp. We also allow for the possibility that for some values of $t$, we have *no* data points.

We will fit the data with a time-varying regression model, $\hat{y} = \theta_t^T x$, where $\theta_t \in \mathbf{R}^n$ is the regression parameter vector for time period $t$. Unless we have many data points for each time stamp, this model will likely be very overfit.

To combat this, we add regularization that encourages $\theta_t$ and $\theta_{t+1}$ to be near each other. In other words, we want the regression model to vary smoothly over time. We choose $\theta_1, \ldots, \theta_T$ to minimize

$$\sum_{i=1}^{m} p(\hat{y}^i - y^i) + \lambda \sum_{t=1}^{T-1} q(\theta_{t+1} - \theta_t),$$

where $p : \mathbf{R} \to \mathbf{R}$ is a convex penalty function, $q : \mathbf{R}^n \to \mathbf{R}$ is a convex regularization function, and $\lambda > 0$ is a hyper-parameter. Here $\hat{y}^i$ is our prediction of $y^i$, *i.e.*, $\hat{y}^i = \theta_{t^i}^T x^i$.

You will use the data given in `time_reg_data.*`, which includes one data set to use for training (*i.e.*, fitting your model) with $m$ data points, and one to use for testing with $M$ data points. Use the square penalty function $p(u) = u^2$, and smoothness regularizer $q(z) = \|z\|_2$ (which we note is *not* squared). Fit the model for 50 values of $\lambda$ logarithmically spaced between $10^{-2}$ and $10^2$. For each value of $\lambda$, find the test error, defined as $\sum_{i=1}^{M} p(\hat{y}^i - y^i)$, where the sum is over the test data.

Plot the test error versus $\lambda$ and suggest a good value of $\lambda$ to use. Call this value $\lambda^\star$. Plot the optimal $\theta^\star = [\theta_1^\star \; \cdots \; \theta_T^\star] \in \mathbf{R}^{n \times T}$ (all on one graph, with one line for each row $i = 1, \ldots, n$) when $\lambda = \lambda^\star$. Repeat for $\lambda = 5\lambda^\star$ and $\lambda = \lambda^\star/5$. How do the curves change with different $\lambda$?

**7.35** *Meta learning.* In the *meta-learning* or *one-shot learning* problem, one is given $m$ tasks represented by loss functions $f_i : \mathbf{R}^n \to \mathbf{R}$, $i = 1, \ldots, m$, and wishes to find a point $x$ from which it is easy for a given algorithm initialized at $x$ to find a minimizer of $f_i$. (Here the interpretation of *meta-learning* is that it is easy to "learn" from the initialization $x$.)

We formulate this as follows. For a point $x \in \mathbf{R}^n$, convex $f : \mathbf{R}^n \to \mathbf{R}$, and $\lambda > 0$ the *proximal mapping* is

$$\mathbf{prox}_f^\lambda(x) = \underset{y}{\operatorname{argmin}} \left\{ f(y) + \frac{\lambda}{2} \|y - x\|_2^2 \right\}.$$

We measure the performance of a point $x$ for task $i$ by its distance to the proximal point update $\mathbf{prox}_{f_i}^\lambda(x)$ and the loss $f_i(\mathbf{prox}_{f_i}^\lambda(x))$ at this updated point. Accordingly, we seek $x$ minimizing

$$h(x) = \frac{\lambda}{2} \sum_{i=1}^{m} \|x - \mathbf{prox}_{f_i}^\lambda(x)\|_2^2 + \sum_{i=1}^{m} f_i \left( \mathbf{prox}_{f_i}^\lambda(x) \right).$$

In this problem, the $f_i$ are closed convex functions.

(a) Formulate the problem of minimizing $h(x)$ as a convex optimization problem. You may introduce new variables.

(b) Suppose the loss for task $i$ is the squared error

$$f_i(x) = \frac{1}{2}(a_i^T x - b_i)^2,$$

where $a_i \in \mathbf{R}^n, b_i \in \mathbf{R}$. Formulate minimizing $h$ as a quadratic program with the single variable $x \in \mathbf{R}^n$. Be as explicit as you can.

**7.36** Let $x^{(1)}, \ldots, x^{(N)}$ be independent samples from an $\mathcal{N}(\mu, \Sigma)$ distribution, where it is known that $\Sigma^{\min} \preceq \Sigma \preceq \Sigma^{\max}$, where $\Sigma^{\min}$ and $\Sigma^{\max}$ are given positive definite matrices. Roughly speaking, we are given lower and upper bounds on the covariance matric.

Explain how to find the maximum likelihood of $\mu$ and $\Sigma$ (including the constraint on $\Sigma$) using convex optimization. Explain any change of variables you use.

**7.37** *Estimating mixture coefficients.* We are given $N$ IID samples $x_1, \ldots, x_N \in \mathbf{R}^m$ from a distribution with mixture density

$$p(x; \lambda) = \sum_{j=1}^k \lambda_j p_j(x),$$

where $\lambda \in \mathbf{R}_+^k$, with $\mathbf{1}^T \lambda = 1$, are the mixture coefficients, and $p_1, \ldots, p_k$ are given densities on $\mathbf{R}^m$.

(a) Explain how to use convex optimization to find the maximum likelihood estimate of the mixture coefficients $\lambda^{\mathrm{ml}} \in \mathbf{R}_+^k$. (You can assume that the maximum likelihood problem is well posed, *i.e.*, there is an optimal $\lambda^{\mathrm{ml}} \in \mathbf{R}_+^k$.) If you change variables, or form a relaxation, be sure to fully justify it.

*Note.* We will not accept methods or algorithms from other courses or fields, even if they work.

(b) The data files `mixture_coeffs_data.*` contain code that generates $N = 100$ samples from a mixture of $k = 3$ distributions on $\mathbf{R}$,

$$\mathcal{N}(3, 4), \quad \mathcal{U}(-1, 2), \quad \mathcal{L}(-2, 3),$$

with mixture coefficients $\lambda^{\mathrm{true}} = (0.3, 0.5, 0.2)$. The first distribution is Gaussian with mean 3 and variance 4; the second is a uniform distribution on $[-1, 2]$, and the third is a Laplace or double-sided exponential distribution with mean $-2$ and shape parameter 3, which has density $p(x) = \frac{1}{6} \exp(-|x + 2|/3)$. The data file contains code for evaluating the density values at the sample points, *i.e.*, $p_j(x_i)$, $j = 1, 2, 3$ and $i = 1, \ldots, N$.

Carry out the method of part (a) on this data. Compare the ML estimate of the mixture coefficients with their true values. Plot the true and estimated mixture densities on the same plot. The data file also contains code for these plots; you just have to plug in your $\lambda^{\mathrm{ml}}$. (Of course, in any real problem you would not have a 'true' distribution.)

**7.38** *Bounding the median.* We consider a random variable $X$ on $[-3, 3]$, with moments

$$\mathbf{E}\,X = 0, \qquad \mathbf{E}\,X^2 = 1, \qquad \mathbf{E}\,X^3 = 1.$$

The first two state that $X$ is standardized; the last tells us that $X$ has significant positive skew. Our goal is to find the range of possible values of $\mathbf{med}(X)$, its median or 50th percentile, over all distributions consistent with the three moment constraints above.

We consider a simple discretization of this problem, where $X$ takes on $N$ values uniformly spaced on $[-3, 3]$, *i.e.*, $x_k = -3 + (k-1)(6/(N-1))$, $k = 1, \ldots, N$. We take the median to be $\mathbf{med}(X) = \min\{x_k \mid \mathbf{prob}(X \le x_k) \ge 1/2\}$.

(a) Explain how to use convex optimization, or quasiconvex optimization, to find the range of possible values of $\mathbf{med}(X)$.

(b) Solve the problem for $N = 300$. Give the minimum possible value and maximum possible values of $\mathbf{med}(X)$, and plot the associated cumulative distribution functions.

**7.39** *Linear classifier for one Gaussian versus others.* We consider $m$ independent Gaussian random variables in $\mathbf{R}^n$, $Z_i \sim \mathcal{N}(\mu_i, \Sigma_i)$, $i = 1, \ldots, m$. Our goal is to find a halfspace $\mathcal{H} = \{x \mid c^T x + d \ge 0\}$, with $c \ne 0$, that separates $Z_1$ from $Z_2$, $\ldots$, $Z_m$ in the sense that $\mathbf{prob}(Z_1 \in \mathcal{H})$ is large, while $\mathbf{prob}(Z_i \in \mathcal{H})$ is small for $i = 2, \ldots, m$. We do this by solving the problem

$$\begin{array}{ll} \text{maximize} & \mathbf{prob}(Z_1 \in \mathcal{H}) \\ \text{subject to} & \mathbf{prob}(Z_i \in \mathcal{H}) \le \eta, \quad i = 2, \ldots, m, \end{array}$$

where $\eta \in (0, 1/2)$ is a given upper limit. You can assume that there exists a feasible hyperplane with $\mathbf{prob}(Z_1 \in \mathcal{H}) \ge 1/2$. The variables are the vector $c$ and constant $d$ that define $\mathcal{H}$. (The solution is not unique, since we can multiply $c$ and $d$ by any positive scale factor without affecting $\mathcal{H}$.)

*Remark.* (Not needed to solve the problem.) For $m = 2$, the classifier found by this method is the same as Fisher's linear discriminant analysis (LDA). So the method described above can be considered a generalization of LDA to multiple Gaussians in one of the classes.

(a) Explain how to use convex or quasiconvex optimization to solve the problem above. Justify any relaxations or change of variables.

(b) Solve the problem instance with data given in `linear_classifier_gaussian_data.*`. Give the optimal value, and an optimal $c$ and $d$ (which are not unique). The data file contains a function that will plot the hyperplane you find, along with the one-$\sigma$ ellipsoids for the Gaussian distributions. Create this plot and submit it.

*Coding help.* The normal distribution's CDF is $\Phi(t) = \mathbf{prob}(\mathcal{N}(0, 1) \le t)$. In Python, you can compute the normal distribution's inverse CDF $\Phi^{-1}$ via `scipy.stats.norm.ppf`. In Julia, you can use `quantile.(Normal(),·)` while using the packages `Random` and `Distributions`.

**7.40** *Estimating a sparse covariance matrix.* We are given independent samples $x_i \sim \mathcal{N}(0, \Sigma)$, $i = 1, \ldots, N$, and wish to estimate $\Sigma \in \mathbf{S}_{++}^n$, taking into account prior information that $\Sigma$ is sparse.

To do this we minimize the negative log-likelihood of the samples, plus a sparsifying regularizer of the form

$$r(\Sigma) = \lambda \sum_{i<j} |\Sigma_{ij}|,$$

where $\lambda > 0$. Note that we do not penalize the diagonal entries of $\Sigma$.

*Remark.* Sparse $\Sigma$ means that many pairs of components of $x$ are uncorrelated and therefore independent. A closely related problem is to estimate $\Sigma$ with the prior assumption that its *inverse* $\Sigma^{-1}$ (the precision matrix) is sparse. This means that many pairs of components of $x$ are conditionally independent, given the others.

(a) Explain how to approximately solve this estimation problem using the convex-concave procedure. If you use a change of variables or relaxation, explain and justify it. Give the linearization of the concave term, and the optimization problem you solve to find the update.

(b) Carry out the method of part (a) on the problem instance given in
`estim_sparse_cov_data.*`, which also gives a specific value for $\lambda$. Plot the convergence of the objective versus iteration for a few different initial guesses $\Sigma^1$. Print out your estimate of the covariance matrix, and use the plotting helper in the data file to plot the true, estimated, and emprirical covariance matrices.

The data is generated from a true distribution $\Sigma^{\text{true}}$. Give the error,

$$\|\Sigma^{\text{true}} - \hat{\Sigma}\|_1,$$

where $\hat{\Sigma}$ is your approximate solution of the regularized maximum-likelihood problem obtained from the convex-concave procedure, and $\|A\|_1 = \sum_{i,j} |A_{ij}|$. Compare to the error obtained using the unregularized estimate, *i.e.*, the empirical covariance $\Sigma^{\text{emp}} = (1/N) \sum_{i=1}^{N} x_i x_i^T$. (Of course in any real application you would not have the true covariance.)

**7.41** *Autogressive process with Poisson conditionals.* We consider a stochastic process $X_1, X_2, \ldots$ with each $X_t$ having Poisson distribution,

$$\mathbf{prob}(X_t = k) = \frac{e^{-\lambda_t} \lambda_t^k}{k!}, \quad k = 0, 1, 2, \ldots,$$

where $\lambda_t > 0$ is the rate or mean. In the formula above, we take $\lambda_t^0 = 1$ and $0! = 1$, so $\mathbf{prob}(X_t = 0) = e^{-\lambda_t}$. The process is autoregressive (AR), with

$$\lambda_t = \nu \omega^{X_{t-1}}, \quad t = 2, 3, \ldots,$$

where $\nu$ and $\omega$ are positive parameters that define the process. You can assume that $\lambda_1 = \nu$, which is the same as assuming that $X_0 = 0$.

This AR process can model excitatory and inhibitory behavior. When $\omega = 1$, the values $X_t$ are independent and identically distributed Poisson random variables with mean $\nu$. With $\omega > 1$, whenever $X_t > 0$, the mean of the following value $X_{t+1}$ increases. This is called *excitatory*, since it typically leads to bursts of positive values of $X_t$. (The term self-exciting is sometimes used to describe such a process.) With $\omega < 1$, whenever $X_t > 0$, the mean of the following value $X_{t+1}$

decreases. This is called *inhibitory*, since it typically leads to zero values of $X_t$ following a positive value. (These interpretations are not needed to solve this problem.)

Suppose we have data $x_1, \ldots, x_T \in \mathbf{Z}_+$ (the nonnegative integers) and wish to fit the process described above to it, *i.e.*, choose $\nu$ and $\omega$, using maximum likelihood estimation.

(a) Explain how to do this using convex optimization. If you use a change of variable or introduce new variables, explain your reasoning.

*Remark.* This particular problem involves only two variables, $\nu$ and $\omega$. We can easily solve such a problem in practice by just plotting the likelihood function. But simple generalizations of it, for example increasing the memory of the AR process, leads to a problem with more than two variables, which is worthy of a convex optimization formulation.

(b) Carry out the method from part (a) on the data given in `poisson_ar_data.*`. Give your estimated values of $\nu$ and $\omega$. Your are welcome to compare these to the true values from which we generate the data, $\nu^{\text{true}} = 0.3$ and $\omega^{\text{true}} = 1.5$.

**7.42** *Computational bounds on the values of a copula.* A *copula* $C : [0,1]^d \to [0,1]$ is the cumulative distribution function of a random variable $X \in [0,1]^d$, where each marginal $X_i$ has a uniform distribution. Copulas are used in areas like insurance to estimate the probability of a big loss. (You don't need to know this to solve this problem.)

We will focus on the case $d = 2$, where

$$C(u) = \mathbf{prob}(X_1 \le u_1, \ X_2 \le u_2).$$

The copula $C$ satisfies

$$C(a, 0) = C(0, a) = 0, \quad C(a, 1) = C(1, a) = a, \quad a \in [0, 1].$$

Here are some examples. If $X_1 = X_2$ is uniform on $[0,1]$, then $C(u) = \min\{u_1, u_2\}$. If $X_1 = 1 - X_2$, with $X_1$ uniform on $[0, 1]$, we have $C(u) = \max\{u_1 + u_2 - 1, 0\}$. If $X_1$ and $X_2$ are independent and uniform on $[0, 1]$, then $C(u) = u_1 u_2$.

We are given the value of a copula at $N$ points $u^{(i)} \in [0, 1]^2$,

$$C(u^{(i)}) = c_i, \quad i = 1, \ldots, N.$$

Our goal is to find the range of possible values of $C(0.5, 0.5)$, over all possible copulas consistent with these given values. (You can assume that there is at least one copula consistent with the given values.)

To carry out the computation we will discretize the values of $u$ to an $M \times M$ uniform grid,

$$\frac{1}{M-1}(i - 1, j - 1), \quad i, j = 1, \ldots, M.$$

With this discretization we can represent $C$ as an $M \times M$ matrix. You can assume that $(0.5, 0.5)$ and the given points $u_i$ are all on this grid. The matrix $C$ represents a copula if and only if the following three conditions hold:

- $C_{M,i} = C_{i,M} = (i-1)/(M-1)$ for $i = 1, \ldots, M$,

- $C_{1,i} = C_{i,1} = 0$ for $i = 1, \ldots, M$, and
- $C_{i+1,j+1} - C_{i,j+1} - C_{i+1,j} + C_{i,j} \geq 0$ for $i, j = 1, \ldots, M - 1$.

(The lefthand quantity in the last condition is the probability that $X$ is in the rectangle with lower and upper limits $(i - 1, j - 1)/(M - 1)$ and $(i, j)/(M - 1)$.)

(a) Explain how to find the minimum and maximum possible values of $C(0.5, 0.5)$ consistent with the given values, using convex optimization. Explain any change of variables or relaxation you use.

(b) Carry out the method of part (a) for the specific case $M = 101$ and

$$
\begin{aligned}
C(0.5, 0.9) &= 0.5 \times 0.9, & C(0.1, 0.6) &= 0.1 \times 0.6, \\
C(0.3, 0.3) &= 0.3 \times 0.3, & C(0.6, 0.2) &= 0.6 \times 0.2.
\end{aligned}
$$

These constraints mean that the copula $C$ agrees with the copula when $X_1$ and $X_2$ are independent, at the four given points.

Report the minimum and maximum values of $C(0.5, 0.5)$.

**7.43** *Consistent decile regression.* We model the 9 deciles (*i.e.*, 10%, ..., 90% quantiles) of the conditional distribution of an outcome $y \in \mathbf{R}$ as a function of a feature vector $x \in \mathbf{R}^n$, using the regression model

$$\hat{q} = v + \theta x,$$

where $\hat{q} \in \mathbf{R}^9$ is the vector of our estimates of the 10%, ..., 90% quantiles, and the regression model parameters are $v \in \mathbf{R}^9$ and $\theta \in \mathbf{R}^{9 \times n}$.

For given model parameters $v$ and $\theta$ and feature vector $x$, we say that the decile estimates are *consistent* if they are in the correct order, *i.e.*,

$$\hat{q}_1 \leq \hat{q}_2 \leq \cdots \leq \hat{q}_9.$$

(It's always socially awkward when you estimate the 30% quantile to be smaller than the 20% quantile.) We can write consistency as $D\hat{q} \succeq 0$, where $D \in \mathbf{R}^{8 \times 9}$ is the first difference matrix, *i.e.*, $Du = (u_2 - u_1, \ldots, u_9 - u_8)$.

We will assume that the features have been constructed in such a way that $x_i \in [-1, 1]$ always holds, *i.e.*, $\|x\|_\infty \leq 1$. We will require that for any such feature vector $x$, we have consistency, *i.e.*, $D\hat{q} \succeq 0$. This imposes a constraint on $(v, \theta)$, which we write as $(v, \theta) \in \mathcal{C}$. *Note that this constraint requires consistency for all possible feature vectors (that satisfy $\|x\|_\infty \leq 1$), not just on the given data. In particular, $\mathcal{C}$ does not depend on the given data.*

We will fit the decile regression model to given training data with features and outcomes

$$x_1, \ldots, x_N \in \mathbf{R}^n, \qquad y_1, \ldots, y_N \in \mathbf{R}.$$

To do this we minimize the sum of the so-called pinball losses,

$$\sum_{i=1}^{N} \sum_{j=1}^{9} \phi_j(v_j + \theta_j^T x_i - y_i),$$

where $\phi_j : \mathbf{R} \to \mathbf{R}$ are given by

$$\phi_j(u) = \begin{cases} -0.1ju & u < 0 \\ (1 - 0.1j)u & u \geq 0 \end{cases} = (1/2)|u| + (1/2 - 0.1j)u,$$

and $\theta_j^T$ is the $j$th row of $\theta$. This loss is minimized subject to $(v, \theta) \in \mathcal{C}$.

(a) Explain how to use convex optimization to carry out the fitting method described above, *i.e.*, consistent decile regression. In particular, give an explicit description of $\mathcal{C}$, that can be used in CVXPY.

(b) Carry out the method of part (a) on the data found in `consistent_decile_data.py`, where $x_i^T$ are given as the rows of an $N \times n$ matrix `X`. Give your estimates $\hat{v}$ and the first row of $\hat{\theta}$, $\hat{\theta}_1^T$ (so you don't have to include the whole matrix). Find the fraction of the data samples $i$ for which $y_i \leq (\hat{q}_i)_j$, where $\hat{q}_i = \hat{v} + \hat{\theta} x_i$ is the vector of decile predictions for data sample $i$, and $(\hat{q}_i)_j$ is the prediction of the $j$th decile on the $i$th data sample. We expect the fraction of samples for which $y_i \leq (\hat{q}_i)_j$ holds to be around $0.1j$, $j = 1, \ldots, 9$.

(c) Fit the decile regression model *without* the constraint $(v, \theta) \in \mathcal{C}$, by simply minimizing the sum of the pinball losses over the given data. Give the model coefficients $\tilde{v}$ and $\tilde{\theta}_1^T$ (the first row of $\tilde{\theta}$) that you find. (This breaks into 9 independent decile regression problems, but you're welcome to solve it as one.)

Find a feature vector $x^{\text{inc}}$, with $\|x^{\text{inc}}\|_\infty \leq 1$, for which this decile regression model is inconsistent, *i.e.*, we have $D\tilde{q} = D(\tilde{v} + \tilde{\theta} x^{\text{inc}}) \not\succeq 0$. (Verify that this holds for the $x^{\text{inc}}$ you find.) The feature vector $x^{\text{inc}}$ need not be one of the given data points; it can be any vector that satisfies $\|x\|_\infty \leq 1$.

# 8 Geometry

**8.1** *Efficiency of maximum volume inscribed ellipsoid.* In this problem we prove the following geometrical result. Suppose $C$ is a polyhedron in $\mathbf{R}^n$, symmetric about the origin, and described as

$$C = \{x \mid -1 \le a_i^T x \le 1, \ i = 1, \dots, p\}.$$

Let

$$\mathcal{E} = \{x \mid x^T Q^{-1} x \le 1\},$$

with $Q \in \mathbf{S}_{++}^n$, be the maximum volume ellipsoid with center at the origin, inscribed in $C$. Then the ellipsoid

$$\sqrt{n}\mathcal{E} = \{x \mid x^T Q^{-1} x \le n\}$$

(*i.e.*, the ellipsoid $\mathcal{E}$, scaled by a factor $\sqrt{n}$ about the origin) *contains* $C$.

(a) Show that the condition $\mathcal{E} \subseteq C$ is equivalent to $a_i^T Q a_i \le 1$ for $i = 1, \dots, p$.

(b) The volume of $\mathcal{E}$ is proportional to $(\det Q)^{1/2}$, so we can find the maximum volume ellipsoid $\mathcal{E}$ inside $C$ by solving the convex problem

$$\begin{array}{ll} \text{minimize} & \log \det Q^{-1} \\ \text{subject to} & a_i^T Q a_i \le 1, \quad i = 1\ldots, p. \end{array} \tag{37}$$

The variable is the matrix $Q \in \mathbf{S}^n$ and the domain of the objective function is $\mathbf{S}_{++}^n$.

Derive the Lagrange dual of problem (37).

(c) Note that Slater's condition for (37) holds ($a_i^T Q a_i < 1$ for $Q = \epsilon I$ and $\epsilon > 0$ small enough), so we have strong duality, and the KKT conditions are necessary and sufficient for optimality. What are the KKT conditions for (37)?

Suppose $Q$ is optimal. Use the KKT conditions to show that

$$x \in C \quad \implies \quad x^T Q^{-1} x \le n.$$

In other words $C \subseteq \sqrt{n}\mathcal{E}$, which is the desired result.

**8.2** *Euclidean distance matrices.* A matrix $X \in \mathbf{S}^n$ is a *Euclidean distance matrix* if its elements $x_{ij}$ can be expressed as

$$x_{ij} = \|p_i - p_j\|_2^2, \quad i, j = 1, \dots, n,$$

for some vectors $p_1$, …, $p_n$ (of arbitrary dimension). In this exercise we prove several classical characterizations of Euclidean distance matrices, derived by I. Schoenberg in the 1930s.

(a) Show that $X$ is a Euclidean distance matrix if and only if

$$X = \mathbf{diag}(Y)\mathbf{1}^T + \mathbf{1}\,\mathbf{diag}(Y)^T - 2Y \tag{38}$$

for some matrix $Y \in \mathbf{S}_+^n$ (the symmetric positive semidefinite matrices of order $n$). Here, $\mathbf{diag}(Y)$ is the $n$-vector formed from the diagonal elements of $Y$, and $\mathbf{1}$ is the $n$-vector with all its elements equal to one. The equality (38) is therefore equivalent to

$$x_{ij} = y_{ii} + y_{jj} - 2y_{ij}, \quad i, j = 1, \dots, n.$$

*Hint.* $Y$ is the Gram matrix associated with the vectors $p_1$, …, $p_n$, *i.e.*, the matrix with elements $y_{ij} = p_i^T p_j$.

(b) Show that the set of Euclidean distance matrices is a convex cone.

(c) Show that $X$ is a Euclidean distance matrix if and only if

$$\mathbf{diag}(X) = 0, \qquad X_{22} - X_{21}\mathbf{1}^T - \mathbf{1}X_{21}^T \preceq 0. \tag{39}$$

The subscripts refer to the partitioning

$$X = \left[ \begin{array}{cc} x_{11} & X_{21}^T \\ X_{21} & X_{22} \end{array} \right]$$

with $X_{21} \in \mathbf{R}^{n-1}$, and $X_{22} \in \mathbf{S}^{n-1}$.

*Hint.* The definition of Euclidean distance matrix involves only the distances $\|p_i - p_j\|_2$, so the origin can be chosen arbitrarily. For example, it can be assumed without loss of generality that $p_1 = 0$. With this assumption there is a unique Gram matrix $Y$ for a given Euclidean distance matrix $X$. Find $Y$ from (38), and relate it to the lefthand side of the inequality (39).

(d) Show that $X$ is a Euclidean distance matrix if and only if

$$\mathbf{diag}(X) = 0, \qquad (I - \frac{1}{n}\mathbf{11}^T)X(I - \frac{1}{n}\mathbf{11}^T) \preceq 0. \tag{40}$$

*Hint.* Use the same argument as in part (c), but take the mean of the vectors $p_k$ at the origin, *i.e.*, impose the condition that $p_1 + p_2 + \cdots + p_n = 0$.

(e) Suppose $X$ is a Euclidean distance matrix. Show that the matrix $W \in \mathbf{S}^n$ with elements

$$w_{ij} = e^{-x_{ij}}, \quad i,j = 1,\ldots,n,$$

is positive semidefinite.

*Hint.* Use the following identity from probability theory. Define $z \sim \mathcal{N}(0, I)$. Then

$$\mathbf{E}\, e^{iz^T x} = e^{-\frac{1}{2}\|x\|_2^2}$$

for all $x$, where $i = \sqrt{-1}$ and $\mathbf{E}$ denotes expectation with respect to $z$. (This is the characteristic function of a multivariate normal distribution.)

**8.3** *Minimum total covering ball volume.* We consider a collection of $n$ points with locations $x_1, \ldots, x_n \in \mathbf{R}^k$. We are also given a set of $m$ groups or subsets of these points, $G_1, \ldots, G_m \subseteq \{1, \ldots, n\}$. For each group, let $V_i$ be the volume of the smallest Euclidean ball that contains the points in group $G_i$. (The volume of a Euclidean ball of radius $r$ in $\mathbf{R}^k$ is $a_k r^k$, where $a_k$ is known constant that is positive but otherwise irrelevant here.) We let $V = V_1 + \cdots + V_m$ be the total volume of these minimal covering balls.

The points $x_{k+1}, \ldots, x_n$ are fixed (*i.e.*, they are problem data). The variables to be chosen are $x_1, \ldots, x_k$. Formulate the problem of choosing $x_1, \ldots, x_k$, in order to minimize the total minimal covering ball volume $V$, as a convex optimization problem. Be sure to explain any new variables you introduce, and to justify the convexity of your objective and inequality constraint functions.

**8.4** *Maximum-margin multiclass classification.* In an $m$-category pattern classification problem, we are given $m$ sets $C_i \subseteq \mathbf{R}^n$. Set $C_i$ contains $N_i$ examples of feature vectors in class $i$. The learning problem is to find a decision function $f : \mathbf{R}^n \to \{1, 2, \ldots, m\}$ that maps each training example to its class, and also generalizes reliably to feature vectors that are not included in the training sets $C_i$.

(a) A common type of decision function for two-way classification is

$$f(x) = \begin{cases} 1 & \text{if } a^T x + b > 0 \\ 2 & \text{if } a^T x + b < 0. \end{cases}$$

In the simplest form, finding $f$ is equivalent to solving a feasibility problem: find $a$ and $b$ such that

$$a^T x + b > 0 \quad \text{if } x \in C_1$$
$$a^T x + b < 0 \quad \text{if } x \in C_2.$$

Since these strict inequalities are homogeneous in $a$ and $b$, they are feasible if and only if the nonstrict inequalities

$$a^T x + b \geq 1 \quad \text{if } x \in C_1$$
$$a^T x + b \leq -1 \quad \text{if } x \in C_2$$

are feasible. This is a feasibility problem with $N_1 + N_2$ linear inequalities in $n + 1$ variables $a$, $b$.

As an extension that improves the robustness (*i.e.*, generalization capability) of the classifier, we can impose the condition that the decision function $f$ classifies all points in a neighborhood of $C_1$ and $C_2$ correctly, and we can maximize the size of the neighborhood. This problem can be expressed as

$$\begin{array}{ll} \text{maximize} & t \\ \text{subject to} & a^T x + b > 0 \ \ \text{if } \mathbf{dist}(x, C_1) \leq t, \\ & a^T x + b < 0 \ \ \text{if } \mathbf{dist}(x, C_2) \leq t, \end{array}$$

where $\mathbf{dist}(x, C) = \min_{y \in C} \|x - y\|_2$.

This is illustrated in the figure. The centers of the shaded disks form the set $C_1$. The centers of the other disks form the set $C_2$. The set of points at a distance less than $t$ from $C_i$ is the union of disks with radius $t$ and center in $C_i$. The hyperplane in the figure separates the two expanded sets. We are interested in expanding the circles as much as possible, until the two expanded sets are no longer separable by a hyperplane.



Since the constraints are homogeneous in $a$, $b$, we can again replace them with nonstrict inequalities

$$\begin{array}{ll} \text{maximize} & t \\ \text{subject to} & a^T x + b \geq 1 \ \ \text{if } \mathbf{dist}(x, C_1) \leq t, \\ & a^T x + b \leq -1 \ \ \text{if } \mathbf{dist}(x, C_2) \leq t. \end{array} \qquad (41)$$

The variables are $a$, $b$, and $t$.

(b) Next we consider an extension to more than two classes. If $m > 2$ we can use a decision function

$$f(x) = \operatorname*{argmax}_{i=1,\ldots,m} (a_i^T x + b_i),$$

parameterized by $m$ vectors $a_i \in \mathbf{R}^n$ and $m$ scalars $b_i$. To find $f$, we can solve a feasibility problem: find $a_i$, $b_i$, such that

$$a_i^T x + b_i > \max_{j \neq i} (a_j^T x + b_j) \quad \text{if } x \in C_i, \quad i = 1, \ldots, m,$$

or, equivalently,

$$a_i^T x + b_i \geq 1 + \max_{j \neq i} (a_j^T x + b_j) \quad \text{if } x \in C_i, \quad i = 1, \ldots, m.$$

Similarly as in part (a), we consider a robust version of this problem:

$$
\begin{aligned}
\text{maximize} \quad & t \\
\text{subject to} \quad & a_i^T x + b_i \geq 1 + \max_{j \neq i} (a_j^T x + b_j) \text{ if } \mathbf{dist}(x, C_i) \leq t, \\
& i = 1, \ldots, m.
\end{aligned}
\tag{42}
$$

The variables in the problem are $a_i \in \mathbf{R}^n$, $b_i \in \mathbf{R}$, $i = 1, \ldots, m$, and $t$.

Formulate the optimization problems (41) and (42) as SOCPs (if possible), or as quasiconvex optimization problems involving SOCP feasibility problems (otherwise).

**8.5** *Three-way linear classification.* We are given data

$$x^{(1)}, \ldots, x^{(N)}, \quad y^{(1)}, \ldots, y^{(M)}, \quad z^{(1)}, \ldots, z^{(P)},$$

three nonempty sets of vectors in $\mathbf{R}^n$. We wish to find three affine functions on $\mathbf{R}^n$,

$$f_i(z) = a_i^T z - b_i, \quad i = 1, 2, 3,$$

that satisfy the following properties:

$$
\begin{aligned}
f_1(x^{(j)}) &> \max\{f_2(x^{(j)}), f_3(x^{(j)})\}, \quad j = 1, \ldots, N, \\
f_2(y^{(j)}) &> \max\{f_1(y^{(j)}), f_3(y^{(j)})\}, \quad j = 1, \ldots, M, \\
f_3(z^{(j)}) &> \max\{f_1(z^{(j)}), f_2(z^{(j)})\}, \quad j = 1, \ldots, P.
\end{aligned}
$$

In words: $f_1$ is the largest of the three functions on the $x$ data points, $f_2$ is the largest of the three functions on the $y$ data points, $f_3$ is the largest of the three functions on the $z$ data points. We can give a simple geometric interpretation: The functions $f_1$, $f_2$, and $f_3$ partition $\mathbf{R}^n$ into three regions,

$$
\begin{aligned}
R_1 &= \{z \mid f_1(z) > \max\{f_2(z), f_3(z)\}\}, \\
R_2 &= \{z \mid f_2(z) > \max\{f_1(z), f_3(z)\}\}, \\
R_3 &= \{z \mid f_3(z) > \max\{f_1(z), f_2(z)\}\},
\end{aligned}
$$

defined by where each function is the largest of the three. Our goal is to find functions with $x^{(j)} \in R_1$, $y^{(j)} \in R_2$, and $z^{(j)} \in R_3$.

Pose this as a convex optimization problem. You may not use strict inequalities in your formulation.

Solve the specific instance of the 3-way separation problem given in `sep3way_data.m`, with the columns of the matrices `X`, `Y` and `Z` giving the $x^{(j)}$, $j = 1, \ldots, N$, $y^{(j)}$, $j = 1, \ldots, M$ and $z^{(j)}$, $j = 1, \ldots, P$. To save you the trouble of plotting data points and separation boundaries, we have included the plotting code in `sep3way_data.m`. (Note that `a1`, `a2`, `a3`, `b1` and `b2` contain arbitrary numbers; you should compute the correct values using CVX.)

**8.6** *Feature selection and sparse linear separation.* Suppose $x^{(1)}, \ldots, x^{(N)}$ and $y^{(1)}, \ldots, y^{(M)}$ are two given nonempty collections or classes of vectors in $\mathbf{R}^n$ that can be (strictly) separated by a hyperplane, *i.e.*, there exists $a \in \mathbf{R}^n$ and $b \in \mathbf{R}$ such that

$$a^T x^{(i)} - b \geq 1, \quad i = 1, \ldots, N, \qquad a^T y^{(i)} - b \leq -1, \quad i = 1, \ldots, M.$$

This means the two classes are (weakly) separated by the slab

$$S = \{z \mid |a^T z - b| \leq 1\},$$

which has thickness $2/\|a\|_2$. You can think of the components of $x^{(i)}$ and $y^{(i)}$ as *features*; $a$ and $b$ define an affine function that combines the features and allows us to distinguish the two classes.

To find the thickest slab that separates the two classes, we can solve the QP

$$
\begin{array}{ll}
\text{minimize} & \|a\|_2 \\
\text{subject to} & a^T x^{(i)} - b \geq 1, \quad i = 1, \ldots, N \\
& a^T y^{(i)} - b \leq -1, \quad i = 1, \ldots, M,
\end{array}
$$

with variables $a \in \mathbf{R}^n$ and $b \in \mathbf{R}$. (This is equivalent to the problem given in (8.23), p424, §8.6.1; see also exercise 8.23.)

In this problem we seek $(a, b)$ that separate the two classes with a thick slab, and also has $a$ sparse, *i.e.*, there are many $j$ with $a_j = 0$. Note that if $a_j = 0$, the affine function $a^T z - b$ does not depend on $z_j$, *i.e.*, the $j$th feature is not used to carry out classification. So a sparse $a$ corresponds to a classification function that is parsimonious; it depends on just a few features. So our goal is to find an affine classification function that gives a thick separating slab, and also uses as few features as possible to carry out the classification.

This is in general a hard combinatorial (bi-criterion) optimization problem, so we use the standard heuristic of solving

$$
\begin{array}{ll}
\text{minimize} & \|a\|_2 + \lambda \|a\|_1 \\
\text{subject to} & a^T x^{(i)} - b \geq 1, \quad i = 1, \ldots, N \\
& a^T y^{(i)} - b \leq -1, \quad i = 1, \ldots, M,
\end{array}
$$

where $\lambda \geq 0$ is a weight vector that controls the trade-off between separating slab thickness and (indirectly, through the $\ell_1$ norm) sparsity of $a$.

Get the data in `sp_ln_sp_data.m`, which gives $x^{(i)}$ and $y^{(i)}$ as the columns of matrices `X` and `Y`, respectively. Find the thickness of the maximum thickness separating slab. Solve the problem above for 100 or so values of $\lambda$ over an appropriate range (we recommend log spacing). For each value,

record the separation slab thickness $2/\|a\|_2$ and $\mathbf{card}(a)$, the cardinality of $a$ (*i.e.*, the number of nonzero entries). In computing the cardinality, you can count an entry $a_j$ of $a$ as zero if it satisfies $|a_j| \leq 10^{-4}$. Plot these data with slab thickness on the vertical axis and cardinality on the horizontal axis.

Use this data to choose a set of 10 features out of the 50 in the data. Give the indices of the features you choose. You may have several choices of sets of features here; you can just choose one. Then find the maximum thickness separating slab that uses only the chosen features. (This is standard practice: once you've chosen the features you're going to use, you optimize again, using only those features, and without the $\ell_1$ regularization.

**8.7** *Thickest slab separating two sets.* We are given two sets in $\mathbf{R}^n$: a polyhedron

$$C_1 = \{x \mid Cx \preceq d\},$$

defined by a matrix $C \in \mathbf{R}^{m \times n}$ and a vector $d \in \mathbf{R}^m$, and an ellipsoid

$$C_2 = \{Pu + q \mid \|u\|_2 \leq 1\},$$

defined by a matrix $P \in \mathbf{R}^{n \times n}$ and a vector $q \in \mathbf{R}^n$. We assume that the sets are nonempty and that they do not intersect. We are interested in the optimization problem

$$
\begin{array}{ll}
\text{maximize} & \inf_{x \in C_1} a^T x - \sup_{x \in C_2} a^T x \\
\text{subject to} & \|a\|_2 = 1.
\end{array}
$$

with variable $a \in \mathbf{R}^n$.

Explain how you would solve this problem. You can answer the question by reducing the problem to a standard problem class (LP, QP, SOCP, SDP, ...), or by describing an algorithm to solve it.

*Remark.* The geometrical interpretation is as follows. If we choose

$$b = \frac{1}{2}(\inf_{x \in C_1} a^T x + \sup_{x \in C_2} a^T x),$$

then the hyperplane $H = \{x \mid a^T x = b\}$ is the maximum margin separating hyperplane separating $C_1$ and $C_2$. Alternatively, $a$ gives us the thickest slab that separates the two sets.

**8.8** *Bounding object position from multiple camera views.* A small object is located at unknown position $x \in \mathbf{R}^3$, and viewed by a set of $m$ cameras. Our goal is to find a box in $\mathbf{R}^3$,

$$\mathcal{B} = \{z \in \mathbf{R}^3 \mid l \preceq z \preceq u\},$$

for which we can guarantee $x \in \mathcal{B}$. We want the smallest possible such bounding box. (Although it doesn't matter, we can use volume to judge 'smallest' among boxes.)

Now we describe the cameras. The object at location $x \in \mathbf{R}^3$ creates an image on the image plane of camera $i$ at location

$$v_i = \frac{1}{c_i^T x + d_i}(A_i x + b_i) \in \mathbf{R}^2.$$

The matrices $A_i \in \mathbf{R}^{2 \times 3}$, vectors $b_i \in \mathbf{R}^2$ and $c_i \in \mathbf{R}^3$, and real numbers $d_i \in \mathbf{R}$ are known, and depend on the camera positions and orientations. We assume that $c_i^T x + d_i > 0$. The $3 \times 4$ matrix

$$P_i = \begin{bmatrix} A_i & b_i \\ c_i^T & d_i \end{bmatrix}$$

is called the *camera matrix* (for camera $i$). It is often (but not always) the case the that the first 3 columns of $P_i$ (*i.e.*, $A_i$ stacked above $c_i^T$) form an orthogonal matrix, in which case the camera is called *orthographic.*

We do not have direct access to the image point $v_i$; we only know the (square) pixel that it lies in. In other words, the camera gives us a measurement $\hat{v}_i$ (the center of the pixel that the image point lies in); we are guaranteed that

$$\|v_i - \hat{v}_i\|_\infty \le \rho_i/2,$$

where $\rho_i$ is the pixel width (and height) of camera $i$. (We know nothing else about $v_i$; it could be any point in this pixel.)

Given the data $A_i$, $b_i$, $c_i$, $d_i$, $\hat{v}_i$, $\rho_i$, we are to find the smallest box $\mathcal{B}$ (*i.e.*, find the vectors $l$ and $u$) that is guaranteed to contain $x$. In other words, find the smallest box in $\mathbf{R}^3$ that contains all points consistent with the observations from the camera.

(a) Explain how to solve this using convex or quasiconvex optimization. You must explain any transformations you use, any new variables you introduce, etc. If the convexity or quasiconvexity of any function in your formulation isn't obvious, be sure justify it.

(b) Solve the specific problem instance given in the file `camera_data.m`. Be sure that your final numerical answer (*i.e.*, $l$ and $u$) stands out.

**8.9** *Triangulation from multiple camera views.* A projective camera can be described by a linear-fractional function $f : \mathbf{R}^3 \to \mathbf{R}^2$,

$$f(x) = \frac{1}{c^T x + d}(Ax + b), \qquad \mathbf{dom}\, f = \{x \mid c^T x + d > 0\},$$

with

$$\mathbf{rank}\left(\begin{bmatrix} A \\ c^T \end{bmatrix}\right) = 3.$$

The domain of $f$ consists of the points in front of the camera.

Before stating the problem, we give some background and interpretation, most of which will not be needed for the actual problem.

The $3 \times 4$-matrix

$$P = \begin{bmatrix} A & b \\ c^T & d \end{bmatrix}$$

is called the *camera matrix* and has rank 3. Since $f$ is invariant with respect to a scaling of $P$, we can normalize the parameters and assume, for example, that $\|c\|_2 = 1$. The numerator $c^T x + d$ is then the distance of $x$ to the plane $\{z \mid c^T z + d = 0\}$. This plane is called the *principal plane*. The point

$$x_c = - \begin{bmatrix} A \\ c^T \end{bmatrix}^{-1} \begin{bmatrix} b \\ d \end{bmatrix}$$

lies in the principal plane and is called the *camera center*. The ray $\{x_c + \theta c \mid \theta \geq 0\}$, which is perpendicular to the principal plane, is the *principal axis*. We will define the *image plane* as the plane parallel to the principal plane, at a unit distance from it along the principal axis.

The point $x'$ in the figure is the intersection of the image plane and the line through the camera center and $x$, and is given by

$$x' = x_c + \frac{1}{c^T (x - x_c)} (x - x_c).$$

Using the definition of $x_c$ we can write $f(x)$ as

$$f(x) = \frac{1}{c^T (x - x_c)} A(x - x_c) = A(x' - x_c) = Ax' + b.$$

This shows that the mapping $f(x)$ can be interpreted as a projection of $x$ on the image plane to get $x'$, followed by an affine transformation of $x'$. We can interpret $f(x)$ as the point $x'$ expressed in some two-dimensional coordinate system attached to the image plane.

In this exercise we consider the problem of determining the position of a point $x \in \mathbf{R}^3$ from its image in $N$ cameras. Each of the cameras is characterized by a known linear-fractional mapping $f_k$ and camera matrix $P_k$:

$$f_k(x) = \frac{1}{c_k^T x + d_k} (A_k x + b_k), \qquad P_k = \begin{bmatrix} A_k & b_k \\ c_k^T & d_k \end{bmatrix}, \qquad k = 1, \dots, N.$$

128

The image of the point $x$ in camera $k$ is denoted $y^{(k)} \in \mathbf{R}^2$. Due to camera imperfections and calibration errors, we do not expect the equations $f_k(x) = y^{(k)}$, $k = 1, \ldots, N$, to be exactly solvable. To estimate the point $x$ we therefore minimize the maximum error in the $N$ equations by solving

$$\text{minimize} \quad g(x) = \max_{k=1,\ldots,N} \|f_k(x) - y^{(k)}\|_2. \tag{43}$$

(a) Show that (43) is a quasiconvex optimization problem. The variable in the problem is $x \in \mathbf{R}^3$. The functions $f_k$ (*i.e.*, the parameters $A_k$, $b_k$, $c_k$, $d_k$) and the vectors $y^{(k)}$ are given.

(b) Solve the following instance of (43) using CVX (and bisection): $N = 4$,

$$P_1 = \begin{bmatrix} 1 & 0 & 0 & 0 \\ 0 & 1 & 0 & 0 \\ 0 & 0 & 1 & 0 \end{bmatrix}, \qquad P_2 = \begin{bmatrix} 1 & 0 & 0 & 0 \\ 0 & 0 & 1 & 0 \\ 0 & -1 & 0 & 10 \end{bmatrix},$$

$$P_3 = \begin{bmatrix} 1 & 1 & 1 & -10 \\ -1 & 1 & 1 & 0 \\ -1 & -1 & 1 & 10 \end{bmatrix}, \qquad P_4 = \begin{bmatrix} 0 & 1 & 1 & 0 \\ 0 & -1 & 1 & 0 \\ -1 & 0 & 0 & 10 \end{bmatrix},$$

$$y^{(1)} = \begin{bmatrix} 0.98 \\ 0.93 \end{bmatrix}, \qquad y^{(2)} = \begin{bmatrix} 1.01 \\ 1.01 \end{bmatrix}, \qquad y^{(3)} = \begin{bmatrix} 0.95 \\ 1.05 \end{bmatrix}, \qquad y^{(4)} = \begin{bmatrix} 2.04 \\ 0.00 \end{bmatrix}.$$

You can terminate the bisection when a point is found with accuracy $g(x) - p^\star \leq 10^{-4}$, where $p^\star$ is the optimal value of (43).

**8.10** *Projection onto the probability simplex.* In this problem you will work out a simple method for finding the Euclidean projection $y$ of $x \in \mathbf{R}^n$ onto the probability simplex $\mathcal{P} = \{z \mid z \succeq 0, \; \mathbf{1}^T z = 1\}$.

*Hints.* Consider the problem of minimizing $(1/2)\|y - x\|_2^2$ subject to $y \succeq 0$, $\mathbf{1}^T y = 1$. Form the partial Lagrangian

$$L(y, \nu) = (1/2)\|y - x\|_2^2 + \nu(\mathbf{1}^T y - 1),$$

leaving the constraint $y \succeq 0$ implicit. Show that $y = (x - \nu\mathbf{1})_+$ minimizes $L(y, \nu)$ over $y \succeq 0$.

**8.11** *Conformal mapping via convex optimization.* Suppose that $\Omega$ is a closed bounded region in $\mathbf{C}$ with no holes (*i.e.*, it is simply connected). The Riemann mapping theorem states that there exists a conformal mapping $\varphi$ from $\Omega$ onto $D = \{z \in \mathbf{C} \mid |z| \leq 1\}$, the unit disk in the complex plane. (This means that $\varphi$ is an analytic function, and maps $\Omega$ one-to-one onto $D$.)

One proof of the Riemann mapping theorem is based on an infinite dimensional optimization problem. We choose a point $a \in \mathbf{int}\,\Omega$ (the interior of $\Omega$). Among all analytic functions that map $\partial\Omega$ (the boundary of $\Omega$) into $D$, we choose one that maximizes the magnitude of the derivative at $a$. Amazingly, it can be shown that this function is a conformal mapping of $\Omega$ onto $D$.

We can use this theorem to construct an approximate conformal mapping, by sampling the boundary of $\Omega$, and by restricting the optimization to a finite-dimensional subspace of analytic functions. Let $b_1, \ldots, b_N$ be a set of points in $\partial\Omega$ (meant to be a sampling of the boundary). We will search only over polynomials of degree up to $n$,

$$\hat{\varphi}(z) = \alpha_1 z^n + \alpha_2 z^{n-1} + \cdots + \alpha_n z + \alpha_{n+1},$$

where $\alpha_1, \ldots, \alpha_{n+1} \in \mathbf{C}$. With these approximations, we obtain the problem

$$
\begin{array}{ll}
\text{maximize} & |\hat{\varphi}'(a)| \\
\text{subject to} & |\hat{\varphi}(b_i)| \leq 1, \quad i = 1, \ldots, N,
\end{array}
$$

with variables $\alpha_1, \ldots, \alpha_{n+1} \in \mathbf{C}$. The problem data are $b_1, \ldots, b_N \in \partial\Omega$ and $a \in \mathbf{int}\,\Omega$.

(a) Explain how to solve the problem above via convex or quasiconvex optimization.

(b) Carry out your method on the problem instance given in `conf_map_data.m`. This file defines the boundary points $b_i$ and plots them. It also contains code that will plot $\hat{\varphi}(b_i)$, the boundary of the mapped region, once you provide the values of $\alpha_j$; these points should be very close to the boundary of the unit disk. (Please turn in this plot, and give us the values of $\alpha_j$ that you find.) The function `polyval` may be helpful.

*Remarks.*

- We've been a little informal in our mathematics here, but it won't matter.

- You do not need to know any complex analysis to solve this problem; we've told you everything you need to know.

- A basic result from complex analysis tells us that $\hat{\varphi}$ is one-to-one if and only if the image of the boundary does not 'loop over' itself. (We mention this just for fun; we're not asking you to verify that the $\hat{\varphi}$ you find is one-to-one.)

**8.12** *Fitting a vector field to given directions.* This problem concerns a vector field on $\mathbf{R}^n$, *i.e.*, a function $F : \mathbf{R}^n \to \mathbf{R}^n$. We are given the *direction* of the vector field at points $x^{(1)}, \ldots, x^{(N)} \in \mathbf{R}^n$,

$$
q^{(i)} = \frac{1}{\|F(x^{(i)})\|_2} F(x^{(i)}), \quad i = 1, \ldots, N.
$$

(These directions might be obtained, for example, from samples of trajectories of the differential equation $\dot{z} = F(z)$.) The goal is to fit these samples with a vector field of the form

$$
\hat{F} = \alpha_1 F_1 + \cdots + \alpha_m F_m,
$$

where $F_1, \ldots, F_m : \mathbf{R}^n \to \mathbf{R}^n$ are given (basis) functions, and $\alpha \in \mathbf{R}^m$ is a set of coefficients that we will choose.

We will measure the fit using the maximum angle error,

$$
J = \max_{i=1,\ldots,N} \left| \angle(q^{(i)}, \hat{F}(x^{(i)})) \right|,
$$

where $\angle(z, w) = \cos^{-1}((z^T w)/\|z\|_2\|w\|_2)$ denotes the angle between nonzero vectors $z$ and $w$. We are only interested in the case when $J$ is smaller than $\pi/2$.

(a) Explain how to choose $\alpha$ so as to minimize $J$ using convex optimization. Your method can involve solving multiple convex problems. Be sure to explain how you handle the constraints $\hat{F}(x^{(i)}) \neq 0$.

(b) Use your method to solve the problem instance with data given in `vfield_fit_data.m`, with an affine vector field fit, i.e., $\hat{F}(z) = Az + b$. (The matrix $A$ and vector $b$ are the parameters $\alpha$ above.) Give your answer to the nearest degree, as in '$20° < J^\star \le 21°$'.

This file also contains code that plots the vector field directions, and also (but commented out) the directions of the vector field fit, $\hat{F}(x^{(i)})/\|\hat{F}(x^{(i)})\|_2$. Create this plot, with your fitted vector field.

**8.13** *Robust minimum volume covering ellipsoid.* Suppose $z$ is a point in $\mathbf{R}^n$ and $\mathcal{E}$ is an ellipsoid in $\mathbf{R}^n$ with center $c$. The *Mahalanobis distance* of the point to the ellipsoid center is defined as

$$M(z, \mathcal{E}) = \inf\{t \ge 0 \mid z \in c + t(\mathcal{E} - c)\},$$

which is the factor by which we need to scale the ellipsoid about its center so that $z$ is on its boundary. We have $z \in \mathcal{E}$ if and only if $M(z, \mathcal{E}) \le 1$. We can use $(M(z, \mathcal{E}) - 1)_+$ as a measure of the Mahalanobis distance of the point $z$ to the ellipsoid $\mathcal{E}$.

Now we can describe the problem. We are given $m$ points $x_1, \ldots, x_m \in \mathbf{R}^n$. The goal is to find the optimal trade-off between the volume of the ellipsoid $\mathcal{E}$ and the total Mahalanobis distance of the points to the ellipsoid, *i.e.*,

$$\sum_{i=1}^{m} (M(z, \mathcal{E}) - 1)_+ .$$

Note that this can be considered a robust version of finding the smallest volume ellipsoid that covers a set of points, since here we allow one or more points to be outside the ellipsoid.

(a) Explain how to solve this problem. You must say clearly what your variables are, what problem you solve, and why the problem is convex.

(b) Carry out your method on the data given in `rob_min_vol_ellips_data.m`. Plot the optimal trade-off curve of ellipsoid volume versus total Mahalanobis distance. For some selected points on the trade-off curve, plot the ellipsoid and the points (which are in $\mathbf{R}^2$). We are only interested in the region of the curve where the ellipsoid volume is within a factor of ten (say) of the minimum volume ellipsoid that covers all the points.

*Important.* Depending on how you formulate the problem, you might encounter problems that are unbounded below, or where CVX encounters numerical difficulty. Just avoid these by appropriate choice of parameter.

*Very important.* If you use Matlab version 7.0 (which is filled with bugs) you might find that functions involving determinants don't work in CVX. If you use this version of Matlab, then you must download the file `blkdiag.m` on the course website and put it in your Matlab path before the default version (which has a bug).

**8.14** *Isoperimetric problem.* We consider the problem of choosing a curve in a two-dimensional plane that encloses as much area as possible between itself and the $x$-axis, subject to constraints. For simplicity we will consider only curves of the form

$$\mathcal{C} = \{(x, y) \mid y = f(x)\},$$

where $f : [0, a] \to \mathbf{R}$. This assumes that for each $x$-value, there can only be a single $y$-value, which need not be the case for general curves. We require that at the end points (which are given), the

curve returns to the $x$-axis, so $f(0) = 0$, and $f(a) = 0$. In addition, the length of the curve cannot exceed a budget $L$, so we must have

$$\int_0^a \sqrt{1 + f'(x)^2} \, dx \le L.$$

The objective is the area enclosed, which is given by

$$\int_0^a f(x) \, dx.$$

To pose this as a finite dimensional optimization problem, we discretize over the $x$-values. Specifically, we take $x_i = h(i-1)$, $i = 1, \ldots, N+1$, where $h = a/N$ is the discretization step size, and we let $y_i = f(x_i)$. Thus our objective becomes

$$h \sum_{i=1}^N y_i,$$

and our constraints can be written as

$$h \sum_{i=1}^N \sqrt{1 + ((y_{i+1} - y_i)/h)^2} \le L, \quad y_1 = 0, \quad y_{N+1} = 0.$$

In addition to these constraints, we will also require that our curve passes through a set of pre-specified points. Let $\mathcal{F} \subseteq \{1, \ldots, N+1\}$ be an index set. For $j \in \mathcal{F}$, we require $y_j = y_j^{\text{fixed}}$, where $y^{\text{fixed}} \in \mathbf{R}^{N+1}$ (the entries of $y^{\text{fixed}}$ whose indices are not in $\mathcal{F}$ can be ignored). Finally, we add a constraint on maximum curvature,

$$-C \le (y_{i+2} - 2y_{i+1} + y_i)/h^2 \le C, \quad i = 1, \ldots, N-1.$$

Explain how to find the curve, *i.e.*, $y_1, \ldots, y_{N+1}$, that maximizes the area enclosed subject to these constraints, using convex optimization. Carry out your method on the problem instance with data given in `iso_perim_data.m`. Report the optimal area enclosed, and use the commented out code in the data file to plot your curve.

*Remark (for your amusement only).* The isoperimetric problem is an ancient problem in mathematics with a history dating all the way back to the tragedy of queen Dido and the founding of Carthage. The story (which is mainly the account of the poet Virgil in his epic volume *Aeneid*), goes that Dido was a princess forced to flee her home after her brother murdered her husband. She travels across the mediterranean and arrives on the shores of what is today modern Tunisia. The natives weren't very happy about the newcomers, but Dido was able to negotiate with the local King: in return for her fortune, the King promised to cede her as much land as she could mark out with the skin of a bull.

The king thought he was getting a good deal, but Dido outmatched him in mathematical skill. She broke down the skin into thin pieces of leather and sewed them into a long piece of string. Then, taking the seashore as an edge, they laid the string in a semicircle, carving out a piece of land larger than anyone imagined; and on this land, the ancient city of Carthage was born. When the king saw what she had done, he was so impressed by Dido's talent that he asked her to marry him. Dido refused, so the king built a university in the hope that he could find another woman with similar talent.

**8.15** *Dual of maximum volume ellipsoid problem.* Consider the problem of computing the maximum volume ellipsoid inscribed in a nonempty bounded polyhedron

$$C = \{x \mid a_i^T x \le b_i, i = 1, \ldots, m\}.$$

Parametrizing the ellipsoid as $\mathcal{E} = \{Bu + d \mid \|u\|_2 \le 1\}$, with $B \in \mathbf{S}_{++}^n$ and $d \in \mathbf{R}^n$, the optimal ellipsoid can be found by solving the convex optimization problem

$$
\begin{array}{ll}
\text{minimize} & -\log \det B \\
\text{subject to} & \|Ba_i\|_2 + a_i^T d \le b_i, \quad i = 1, \ldots, m
\end{array}
$$

with variables $B \in \mathbf{S}^n$, $d \in \mathbf{R}^n$. Derive the Lagrange dual of the equivalent problem

$$
\begin{array}{ll}
\text{minimize} & -\log \det B \\
\text{subject to} & \|y_i\|_2 + a_i^T d \le b_i, \quad i = 1, \ldots, m \\
& Ba_i = y_i, \quad i = 1, \ldots, m
\end{array}
$$

with variables $B \in \mathbf{S}^n$, $d \in \mathbf{R}^n$, $y_i \in \mathbf{R}^n$, $i = 1, \ldots, m$.

**8.16** *Fitting a sphere to data.* Consider the problem of fitting a sphere $\{x \in \mathbf{R}^n \mid \|x - c\|_2 = r\}$ to $m$ points $u_1, \ldots, u_m \in \mathbf{R}^n$, by minimizing the loss function

$$\sum_{i=1}^m \left( \|u_i - c\|_2^2 - r^2 \right)^2$$

over the variables $c \in \mathbf{R}^n$, $r \in \mathbf{R}$.

(a) Explain how to solve this problem using convex optimization. *Hint.* Consider the change of variables from $(c, r)$ to $(c, t)$, with $t = r^2 - \|c\|_2^2$. You'll need to argue that you can recover $r^\star$ from $t^\star$ once you solve the problem with these transformed variables.

(b) Use your method to solve the problem instance with data given in the file `sphere_fit_data.*`, with $n = 2$. This file creates $u_i$ as a $2 \times m$ matrix U. Plot the fitted circle and the data points.

**8.17** The *polar* of a set $C \subseteq \mathbf{R}^n$ is defined as

$$C^\circ = \{x \mid u^T x \le 1 \ \forall u \in C\}.$$

(a) Show that $C^\circ$ is convex, regardless of the properties of $C$.

(b) Let $C_1$ and $C_2$ be two nonempty polyhedra defined by sets of linear inequalities:

$$C_1 = \{u \in \mathbf{R}^n \mid A_1 u \preceq b_1\}, \qquad C_2 = \{v \in \mathbf{R}^n \mid A_2 v \preceq b_2\}$$

with $A_1 \in \mathbf{R}^{m_1 \times n}$, $A_2 \in \mathbf{R}^{m_2 \times n}$, $b_1 \in \mathbf{R}^{m_1}$, $b_2 \in \mathbf{R}^{m_2}$. Formulate the problem of finding the Euclidean distance between $C_1^\circ$ and $C_2^\circ$,

$$
\begin{array}{ll}
\text{minimize} & \|x_1 - x_2\|_2^2 \\
\text{subject to} & x_1 \in C_1^\circ \\
& x_2 \in C_2^\circ,
\end{array}
$$

as a QP. Your formulation should be efficient, *i.e.*, the dimensions of the QP (number of variables and constraints) should be linear in $m_1$, $m_2$, $n$. (In particular, formulations that require enumerating the extreme points of $C_1$ and $C_2$ are to be avoided.)

**8.18** *Polyhedral cone questions.* You are given matrices $A \in \mathbf{R}^{n \times k}$ and $B \in \mathbf{R}^{n \times p}$.

Explain how to solve the following two problems using convex optimization. Your solution can involve solving multiple convex problems, as long as the number of such problems is no more than linear in the dimensions $n$, $k$, $p$.

(a) How would you determine whether $A\mathbf{R}_+^k \subseteq B\mathbf{R}_+^p$? This means that every nonnegative linear combination of the columns of $A$ can be expressed as a nonnegative linear combination of the columns of $B$.

(b) How would you determine whether $A\mathbf{R}_+^k = \mathbf{R}^n$? This means that every vector in $\mathbf{R}^n$ can be expressed as a nonnegative linear combination of the columns of $A$.

**8.19** *Projection on convex hull of union of ellipsoids.* Let $E_1, \ldots, E_m$ be $m$ ellipsoids in $\mathbf{R}^n$ defined as

$$E_i = \{A_i u + b_i \mid \|u\|_2 \leq 1\}, \quad i = 1, \ldots, m,$$

with $A_i \in \mathbf{R}^{n \times n}$ and $b_i \in \mathbf{R}^n$. Consider the problem of projecting a point $a \in \mathbf{R}^n$ on the convex hull of the union of the ellipsoids:

$$
\begin{array}{ll}
\text{minimize} & \|x - a\|_2 \\
\text{subject to} & x \in \mathbf{conv}(E_1 \cup \cdots \cup E_m).
\end{array}
$$

Formulate this as a second order cone program.

**8.20** *Bregman divergences.* Let $f : \mathbf{R}^n \to \mathbf{R}$ be strictly convex and differentiable. Then the *Bregman divergence* associated with $f$ is the function $D_f : \mathbf{R}^n \times \mathbf{R}^n \to \mathbf{R}$ given by

$$D_f(x, y) = f(x) - f(y) - \nabla f(y)^T (x - y).$$

(a) Show that $D_f(x, y) \geq 0$ for all $x$, $y \in \mathbf{dom}\, f$.

(b) Show that if $f = \|\cdot\|_2^2$, then $D_f(x, y) = \|x - y\|_2^2$.

(c) Show that if $f(x) = \sum_{i=1}^n x_i \log x_i$ (negative entropy), with $\mathbf{dom}\, f = \mathbf{R}_+^n$ (with $0 \log 0$ taken to be 0), then

$$D_f(x, y) = \sum_{i=1}^n \left( x_i \log(x_i/y_i) - x_i + y_i \right),$$

the *Kullback-Leibler divergence* between $x$ and $y$.

(d) *Bregman projection.* The previous parts suggest that Bregman divergences can be viewed as generalized 'distances', *i.e.*, functions that measure how similar two vectors are. This suggests solving geometric problems that measure distance between vectors using a Bregman divergence rather than Euclidean distance.

Explain whether

$$
\begin{array}{ll}
\text{minimize} & D_f(x, y) \\
\text{subject to} & x \in \mathcal{C},
\end{array}
$$

with variable $x \in \mathbf{R}^n$, is a convex optimization problem (assuming $\mathcal{C}$ is convex).

(e) *Duality.* Show that $D_g(y^*, x^*) = D_f(x, y)$, where $g = f^*$ and $z^* = \nabla f(z)$. You can assume that $\nabla f^* = (\nabla f)^{-1}$ and that $f$ is closed.

**8.21** *Ellipsoidal peeling.* In this problem, you will implement an outlier identification technique using Löwner-John ellipsoids. Given a set of points $\mathcal{D} = \{x_1, \ldots, x_N\}$ in $\mathbf{R}^n$, the goal is to identify a set $\mathcal{O} \subseteq \mathcal{D}$ that are anomalous in some sense. Roughly speaking, we think of an outlier as a point that is far away from most of the points, so we would like the points in $\mathcal{D} \setminus \mathcal{O}$ to be relatively close together, and to be relatively far apart from the points in $\mathcal{O}$.

We describe a heuristic technique for identifying $\mathcal{O}$. We start with $\mathcal{O} = \emptyset$ and find the minimum volume (Löwner-John) ellipsoid $\mathcal{E}$ containing all $x_i \notin \mathcal{O}$ (which is all $x_i$ in the first step). Each iteration, we flag (*i.e.*, add to $\mathcal{O}$) the point that corresponds to the largest dual variable for the constraint $x_i \in \mathcal{E}$; this point will be one of the points on the boundary of $\mathcal{E}$, and intuitively, it will be the one for whom the constraint is 'most' binding. We then plot **vol** $\mathcal{E}$ (on a log scale) versus **card** $\mathcal{O}$ and hope that we see a sharp drop in the curve. We use the value of $\mathcal{O}$ after the drop.

The hope is that after removing a relatively small number of points, the volume of the minimum volume ellipsoid containing the remaining points will be much smaller than the minimum volume ellipsoid for $\mathcal{D}$, which means the removed points are far away from the others.

For example, suppose we have 100 points that lie in the unit ball and 3 points with (Euclidean) norm 1000. Intuitively, it is clear that it is reasonable to consider the three large points outliers. The minimum volume ellipsoid of all 103 points will have very large volume. The three points will be the first ones removed, and as soon as they are, the volume of the ellipsoid ellipsoid will drop dramatically and be on the order of the volume of the unit ball.

Run 6 iterations of the algorithm on the data given in `ellip_anomaly_data.m`. Plot **vol** $\mathcal{E}$ (on a log scale) versus **card** $\mathcal{O}$. In addition, on a single plot, plot all the ellipses found with the function `ellipse_draw(A,b)` along with the outliers (in red) and the remaining points (in blue).

Of course, we have chosen an example in $\mathbf{R}^2$ so the ellipses can be plotted, but one can detect outliers in $\mathbf{R}^2$ simply by inspection. In dimension much higher than 3, however, detecting outliers by plotting will become substantially more difficult, while the same algorithm can be used.

*Note.* In CVX, you should use `det_rootn` (which is SDP-representable and handled exactly) instead of `log_det` (which is handled using an inefficient iterative procedure).

**8.22** *Urban planning.* An urban planner would like to choose the location $x \in \mathbf{R}^2$ for a new warehouse. This should be close to $n$ distribution centers located at $y_1, \ldots, y_n \in \mathbf{R}^2$. The objective is to minimize the worst-case distance, *i.e.*, solve

$$\text{minimize} \ \max_{k=1,\ldots,n} \|y_k - x\|_2.$$

(a) Explain in one sentence why this is a convex optimization problem.

(b) Construct an equivalent second-order cone program.

(c) Find the Langrange dual to the problem you found in part (b). Does strong duality hold?

(d) Suppose that the primal SOCP and the dual SOCP each have a unique optimum. Give a relationship between the primal optimal point and the optimal dual variables. In particular, we would like you to say as much as you can about the optimal dual variables given the primal optimal solution.

**8.23** *Optimizing a set of disks.* A disk $D \subset \mathbf{R}^2$ is parametrized by its center $c \in \mathbf{R}^2$ and its radius $r \geq 0$, with the form $D = \{x \mid \|x - c\|_2 \leq r\}$. (We allow $r = 0$, in which case the disk reduces to a single

point $\{c\}$.) The goal is to choose a set of $n$ disks $D_1, \ldots, D_n$ (*i.e.*, specify their centers and radii), to minimize an objective subject to some constraints.

One constraint is that the first $k$ disks are fixed, *i.e.*,

$$c_i = c_i^{\text{fix}}, \quad r_i = r_i^{\text{fix}}, \quad i = 1, \ldots, k,$$

where $c_i^{\text{fix}}$ and $r_i^{\text{fix}}$ are given.

The second constraint is an overlap or intersection constraint, which requires some pairs of disks to intersect:

$$D_i \cap D_j \neq \emptyset, \quad (i, j) \in \mathcal{I},$$

where $\mathcal{I} \subset \{1, \ldots, n\}^2$ is given. You can assume that for each $(i, j) \in \mathcal{I}$, $i < j$.

We consider two objectives: The sum of the disk areas, and the sum of the disk perimeters. These two objectives result in two different problems.

(a) Explain how to solve these two problems using convex optimization.

(b) Solve both problems for the problem data given in `disks_data.*`. Give the optimal total area, and the optimal total perimeter. Plot the two optimal disk arrangements, using the code included in the data file. Give a *very brief* comment on the results, especially the distribution of disk radii each problem obtains.

**8.24** *Minimum-volume ellipsoid around intersection of two ellipsoids.* We work out a simple method for computing the minimum-volume ellipsoid

$$\mathcal{E}_0 = \{x \mid x^T A x \leq 1\}$$

that covers the intersection of two ellipsoids $\mathcal{E}_1$ and $\mathcal{E}_2$ centered at the origin. The problem can be written as an optimization problem

$$\begin{array}{ll} \text{minimize} & \log \det A^{-1} \\ \text{subject to} & x^T A x \leq 1 \quad \text{for all } x \in \mathcal{E}_1 \cap \mathcal{E}_2. \end{array} \tag{44}$$

The variable is the matrix $A \in \mathbf{S}^n$. As usual, we define the domain of $\log \det A^{-1}$ as $\mathbf{S}_{++}^n$. It can be shown that it is sufficient to consider the problem for the special case

$$\mathcal{E}_1 = \{x \mid x^T x \leq 1\}, \qquad \mathcal{E}_2 = \{x \mid x^T \mathbf{diag}(d) x \leq 1\}, \tag{45}$$

where $d$ is a positive vector. The figure shows a two-dimensional example.



136

(a) We first show that the optimal $A$ is diagonal. Suppose $A$ is feasible for (44), with $\mathcal{E}_1$ and $\mathcal{E}_2$ defined in (45).

    (i) Verify that $\mathbf{diag}(s)A\,\mathbf{diag}(s)$, where $s$ is an $n$-vector with elements $s_i = \pm 1$, is also feasible.

    (ii) Show that the matrix

$$B = \frac{1}{2^n} \sum_{s_i \in \{-1,+1\},\ i=1,\ldots,n} \mathbf{diag}(s)A\,\mathbf{diag}(s),$$

    is also feasible for (44). The sum is over all $n$-vectors $s$ with elements $s_i = \pm 1$.

    (iii) Show that $\log \det B^{-1} \le \log \det A^{-1}$.

Since $B$ is diagonal (each off-diagonal element $B_{ij}$ is the sum of terms $\pm A_{ij}$, with an equal number of positive and negative signs in the sum) and the cost function in (44) is strictly convex, this implies that the optimal solution is diagonal.

(b) Hence, we can take $A = \mathbf{diag}(a)$ and write the problem as

$$
\begin{aligned}
\text{minimize} \quad & -\sum_{i=1}^{n} \log a_i \\
\text{subject to} \quad & x^T \mathbf{diag}(a)x \le 1 \quad \text{for all } x \in \mathcal{E}_1 \cap \mathcal{E}_2.
\end{aligned}
\tag{46}
$$

The constraint means that

$$x_1^2 + \cdots + x_n^2 \le 1, \quad d_1 x_1^2 + \cdots + d_n x_n^2 \le 1 \quad \implies \quad a_1 x_1^2 + \cdots + a_n x_n^2 \le 1.$$

Show that this is true if and only if there exist scalars $\lambda$ and $\mu$ that satisfy

$$\lambda + \mu \le 1, \qquad \lambda \mathbf{1} + \mu d \succeq a, \qquad \lambda \ge 0, \qquad \mu \ge 0. \tag{47}$$

(c) Replace the constraint in (46) by the equivalent set of constraints (47) and simplify the problem. Show that the optimal $a$ is given by $a = \mathbf{1} + \mu(d-\mathbf{1})$ where $\mu$ is the solution of a simple convex optimization problem with one variable,

$$
\begin{aligned}
\text{minimize} \quad & -\sum_{i=1}^{n} \log(1 + \mu(d_i - 1)) \\
\text{subject to} \quad & 0 \le \mu \le 1.
\end{aligned}
$$

**8.25** *Probabilistic centers.* Let $C \subset \mathbf{R}^n$ be a bounded convex set. For a vector $w \in \mathbf{R}^n$, the distance of $x$ to the boundary of $C$ in the direction $w$ is

$$d_C(x,w) = \sup_{y \in C} \left| w^T(y-x) \right| / \|w\|_2.$$

For a given probability density $p$ on $w \in \mathbf{R}^n$, we let

$$f(x) := \mathbf{E}\, d_C(x,w) = \int d_C(x,w)p(w)dw$$

be the expected distance. (We could easily define this for discrete random variables $w$ as well.) The *p-centers of $C$* are all points $x^\star \in C$ minimizing $f(x)$, i.e., satisfying $f(x^\star) = \inf_{x \in C} f(x)$.

(a) Let $w_1, \ldots, w_m \in \mathbf{R}^n$ and consider the empirical average

$$f_m(x) = \frac{1}{m} \sum_{i=1}^{m} d_C(x, w_i).$$

(48)

Formulate minimizing $f_m$ as a convex optimization problem using the support functions $\sigma_C(w) = \sup_{y \in C} y^T w$.

(b) If $C$ is convex and symmetric (*i.e.* $C = -C$) and $p$ is an arbitrary distribution on $w$, is $x^\star = 0$ a minimizer of $f$? If so, why? If not, give a counterexample.

(c) Suppose that the set $C$ is a polyhedron, that is,

$$C = \{x \in \mathbf{R}^n \mid Ax \preceq b\}$$

for some $A \in \mathbf{R}^{k \times n}, b \in \mathbf{R}^k$. Formulate minimizing $f_m$ over $C$ as a linear program.

(d) Suppose that $p$ is the uniform distribution over $\{w \in \mathbf{R}^n \mid \|w\| = 1\}$, where $n = 10$, and let $C = \{x \in \mathbf{R}^n_+ \mid \mathbf{1}^T x \leq 1\}$ be the unit simplex. Repeat the following experiment 20 times for each of the values of $m \in \{10, 20, 40, 80, 160, 320, 640, 1280, 2560\}$.

 (i) Draw $m$ samples $w_1, \ldots, w_m$, where each $w_i$ is uniform on the sphere, then
 (ii) Solve problem (48) to get a (random) minimizer $\hat{x}_m = \operatorname{argmin}_{x \in C} f_m(x)$.

Plot the average of the errors $\|\hat{x}_m - \mathbf{1}/n\|_2$ you get in each experiment against $m$, the sample size. (Be sure to include your code in your solution.)

**8.26** *Some problems involving a polyhedron and a point.* Let $\mathcal{P} \subset \mathbf{R}^n$ be a polyhedron described by a set of (a modest number of) linear inequalities, and $a$ a point in $\mathbf{R}^n$. Are the following problems easy or hard? (Easy means the solution can be found by solving one or a modest number of convex optimization problems.)

(a) Find a point in $\mathcal{P}$ that is closest to $a$ in Euclidean norm.

(b) Find a point in $\mathcal{P}$ that is closest to $a$ in $\ell_\infty$ norm.

(c) Find a point in $\mathcal{P}$ that is farthest from $a$ in Euclidean norm.

(d) Find a point in $\mathcal{P}$ that is farthest from $a$ in $\ell_\infty$ norm.

**8.27** *Minimum volume ellipsoid that contains points and is inside a polyhedron.* We seek the minimum volume ellipsoid in $\mathbf{R}^n$, centered at 0, that contains the points $x_1, \ldots, x_K \in \mathbf{R}^n$, and is itself contained in (*i.e.*, a subset of) a polyhedron $\mathcal{P} = \{x \mid Ax \preceq b\}$, where $A \in \mathbf{R}^{m \times n}$ and $b \in \mathbf{R}^m$. This combines two of the extremal volume problems studied in the book. The data are the points $x_i$, and the matrix $A$ and vector $b$ that define the polyhedron. You can assume that $b \succeq 0$, which means $0 \in \mathcal{P}$.

Explain how to use convex optimization to find this ellipsoid, or to determine that no such ellipsoid exists. Be sure to explain how you parametrize the ellipsoid, how the constraints on the ellipsoid are expressed in your problem, and why the problem you propose is convex.

# 9 Unconstrained minimization

**9.1** *Gradient descent and nondifferentiable functions.*

(a) Let $\gamma > 1$. Show that the function

$$
f(x_1, x_2) = \begin{cases} \sqrt{x_1^2 + \gamma x_2^2} & |x_2| \leq x_1 \\[2ex] \dfrac{x_1 + \gamma|x_2|}{\sqrt{1 + \gamma}} & \text{otherwise} \end{cases}
$$

is convex. You can do this, for example, by verifying that

$$
f(x_1, x_2) = \sup \left\{ x_1 y_1 + \sqrt{\gamma} x_2 y_2 \ \middle|\ y_1^2 + y_2^2 \leq 1, \ y_1 \geq 1/\sqrt{1+\gamma} \right\}.
$$

Note that $f$ is unbounded below. (Take $x_2 = 0$ and let $x_1$ go to $-\infty$.)

(b) Consider the gradient descent algorithm applied to $f$, with starting point $x^{(0)} = (\gamma, 1)$ and an exact line search. Show that the iterates are

$$
x_1^{(k)} = \gamma \left( \frac{\gamma - 1}{\gamma + 1} \right)^k, \qquad x_2^{(k)} = \left( -\frac{\gamma - 1}{\gamma + 1} \right)^k.
$$

Therefore $x^{(k)}$ converges to $(0,0)$. However, this is not the optimum, since $f$ is unbounded below.

**9.2** *Suggestions for exercise 9.30 in* Convex Optimization. We recommend the following to generate a problem instance:

```
n = 100;
m = 200;
randn('state',1);
A=randn(m,n);
```

Of course, you should try out your code with different dimensions, and different data as well.

In all cases, be sure that your line search *first* finds a step length for which the tentative point is in **dom** $f$; if you attempt to evaluate $f$ outside its domain, you'll get complex numbers, and you'll never recover.

To find expressions for $\nabla f(x)$ and $\nabla^2 f(x)$, use the chain rule (see Appendix A.4); if you attempt to compute $\partial^2 f(x)/\partial x_i \partial x_j$, you will be sorry.

To compute the Newton step, you can use `vnt=-H\g`.

**9.3** *Suggestions for exercise 9.31 in* Convex Optimization. For 9.31a, you should try out $N = 1$, $N = 15$, and $N = 30$. You might as well compute and store the Cholesky factorization of the Hessian, and then back solve to get the search directions, even though you won't really see any speedup in Matlab for such a small problem. After you evaluate the Hessian, you can find the Cholesky factorization as `L=chol(H,'lower')`. You can then compute a search step as `-L'\(L\g)`, where `g` is the gradient at the current point. Matlab will do the right thing, *i.e.*, it will first solve

`L\g` using forward substitution, and then it will solve `-L'\(L\g)` using backward substitution. Each substitution is order $n^2$.

To fairly compare the convergence of the three methods (*i.e.*, $N = 1$, $N = 15$, $N = 30$), the horizontal axis should show the approximate total number of flops required, and not the number of iterations. You can compute the approximate number of flops using $n^3/3$ for each factorization, and $2n^2$ for each solve (where each 'solve' involves a forward substitution step and a backward substitution step).

**9.4** *Efficient numerical method for a regularized least-squares problem.* We consider a regularized least squares problem with smoothing,

$$\text{minimize} \quad \sum_{i=1}^{k}(a_i^T x - b_i)^2 + \delta \sum_{i=1}^{n-1}(x_i - x_{i+1})^2 + \eta \sum_{i=1}^{n} x_i^2,$$

where $x \in \mathbf{R}^n$ is the variable, and $\delta, \eta > 0$ are parameters.

(a) Express the optimality conditions for this problem as a set of linear equations involving $x$. (These are called the normal equations.)

(b) Now assume that $k \ll n$. Describe an efficient method to solve the normal equations found in part (a). Give an approximate flop count for a general method that does not exploit structure, and also for your efficient method.

(c) *A numerical instance.* In this part you will try out your efficient method. We'll choose $k = 100$ and $n = 4000$, and $\delta = \eta = 1$. First, randomly generate $A$ and $b$ with these dimensions. Form the normal equations as in part (a), and solve them using a generic method. Next, write (short) code implementing your efficient method, and run it on your problem instance. Verify that the solutions found by the two methods are nearly the same, and also that your efficient method is much faster than the generic one.

*Note:* You'll need to know some things about Matlab to be sure you get the speedup from the efficient method. Your method should involve solving linear equations with tridiagonal coefficient matrix. In this case, both the factorization and the back substitution can be carried out very efficiently. The Matlab documentation says that banded matrices are recognized and exploited, when solving equations, but we found this wasn't always the case. To be sure Matlab knows your matrix is tridiagonal, you can declare the matrix as sparse, using `spdiags`, which can be used to create a tridiagonal matrix. You could also create the tridiagonal matrix conventionally, and then convert the resulting matrix to a sparse one using `sparse`.

One other thing you need to know. Suppose you need to solve a group of linear equations with the same coefficient matrix, *i.e.*, you need to compute $F^{-1}a_1, ..., F^{-1}a_m$, where $F$ is invertible and $a_i$ are column vectors. By concatenating columns, this can be expressed as a single matrix

$$\begin{bmatrix} F^{-1}a_1 & \cdots & F^{-1}a_m \end{bmatrix} = F^{-1} \begin{bmatrix} a_1 & \cdots & a_m \end{bmatrix}.$$

To compute this matrix using Matlab, you should collect the righthand sides into one matrix (as above) and use Matlab's backslash operator: `F\A`. This will do the right thing: factor the matrix $F$ once, and carry out multiple back substitutions for the righthand sides.

In Python, `np.linalg.solve` is unable to recognize banded matrices, and will therefore take a long time to solve the resulting system of equations. Instead, you can use `scipy.linalg.solve_banded` with `(l, u) = (1, 1)` for a tridiagonal matrix to solve it more efficiently. In Julia, you can use `spdiagm` in the SparseArrays package to generate banded matrices; Julia will solve these efficiently.

**9.5** *Newton method for approximate total variation de-noising.* Total variation de-noising is based on the bi-criterion problem with the two objectives

$$\|x - x^{\text{cor}}\|_2, \qquad \phi_{\text{tv}}(x) = \sum_{i=1}^{n-1} |x_{i+1} - x_i|.$$

Here $x^{\text{cor}} \in \mathbf{R}^n$ is the (given) corrupted signal, $x \in \mathbf{R}^n$ is the de-noised signal to be computed, and $\phi_{\text{tv}}$ is the total variation function. This bi-criterion problem can be formulated as an SOCP, or, by squaring the first objective, as a QP. In this problem we consider a method used to approximately formulate the total variation de-noising problem as an unconstrained problem with twice differentiable objective, for which Newton's method can be used.

We first observe that the Pareto optimal points for the bi-criterion total variation de-noising problem can found as the minimizers of the function

$$\|x - x^{\text{cor}}\|_2^2 + \mu \phi_{\text{tv}}(x),$$

where $\mu \geq 0$ is parameter. (Note that the Euclidean norm term has been squared here, and so is twice differentiable.) In *approximate total variation de-noising*, we substitute a twice differentiable approximation of the total variation function,

$$\phi_{\text{atv}}(x) = \sum_{i=1}^{n-1} \left( \sqrt{\epsilon^2 + (x_{i+1} - x_i)^2} - \epsilon \right),$$

for the total variation function $\phi_{\text{tv}}$. Here $\epsilon > 0$ is parameter that controls the level of approximation. In approximate total variation de-noising, we use Newton's method to minimize

$$\psi(x) = \|x - x^{\text{cor}}\|_2^2 + \mu \phi_{\text{atv}}(x).$$

(The parameters $\mu > 0$ and $\epsilon > 0$ are given.)

(a) Find expressions for the gradient and Hessian of $\psi$.

(b) Explain how you would exploit the structure of the Hessian to compute the Newton direction for $\psi$ efficiently. (Your explanation can be brief.) Compare the approximate flop count for your method with the flop count for a generic method that does not exploit any structure in the Hessian of $\psi$.

(c) Implement Newton's method for approximate total variation de-noising. Get the corrupted signal $x^{\text{cor}}$ from the file `approx_tv_denoising_data.m`, and compute the de-noised signal $x^\star$, using parameters $\epsilon = 0.001$, $\mu = 50$ (which are also in the file). Use line search parameters $\alpha = 0.01$, $\beta = 0.5$, initial point $x^{(0)} = 0$, and stopping criterion $\lambda^2/2 \leq 10^{-8}$. Plot the Newton decrement versus iteration, to verify asymptotic quadratic convergence. Plot the final smoothed signal $x^\star$, along with the corrupted one $x^{\text{cor}}$.

**9.6** Derive the Newton equation for the unconstrained minimization problem

$$\text{minimize} \quad (1/2)x^T x + \log \sum_{i=1}^{m} \exp(a_i^T x + b_i).$$

Give an efficient method for solving the Newton system, assuming the matrix $A \in \mathbf{R}^{m \times n}$ (with rows $a_i^T$) is dense with $m \ll n$. Give an approximate flop count of your method.

**9.7** *Estimation of a vector from one-bit measurements.* A system of $m$ sensors is used to estimate an unknown parameter $x \in \mathbf{R}^n$. Each sensor makes a noisy measurement of some linear combination of the unknown parameters, and quantizes the measured value to one bit: it returns $+1$ if the measured value exceeds a certain threshold, and $-1$ otherwise. In other words, the output of sensor $i$ is given by

$$y_i = \mathbf{sign}(a_i^T x + v_i - b_i) = \begin{cases} 1 & a_i^T x + v_i \geq b_i \\ -1 & a_i^T x + v_i < b_i, \end{cases}$$

where $a_i$ and $b_i$ are known, and $v_i$ is measurement error. We assume that the measurement errors $v_i$ are independent random variables with a zero-mean unit-variance Gaussian distribution (*i.e.*, with a probability density $\phi(v) = (1/\sqrt{2\pi})e^{-v^2/2}$). As a consequence, the sensor outputs $y_i$ are random variables with possible values $\pm 1$. We will denote $\mathbf{prob}(y_i = 1)$ as $P_i(x)$ to emphasize that it is a function of the unknown parameter $x$:

$$P_i(x) = \mathbf{prob}(y_i = 1) = \mathbf{prob}(a_i^T x + v_i \geq b_i) = \frac{1}{\sqrt{2\pi}} \int_{b_i - a_i^T x}^{\infty} e^{-t^2/2} dt$$

$$1 - P_i(x) = \mathbf{prob}(y_i = -1) = \mathbf{prob}(a_i^T x + v_i < b_i) = \frac{1}{\sqrt{2\pi}} \int_{-\infty}^{b_i - a_i^T x} e^{-t^2/2} dt.$$

The problem is to estimate $x$, based on observed values $\bar{y}_1, \bar{y}_2, \ldots, \bar{y}_m$ of the $m$ sensor outputs.

We will apply the maximum likelihood (ML) principle to determine an estimate $\hat{x}$. In maximum likelihood estimation, we calculate $\hat{x}$ by maximizing the *log-likelihood function*

$$l(x) = \log \left( \prod_{\bar{y}_i=1} P_i(x) \prod_{\bar{y}_i=-1} (1 - P_i(x)) \right) = \sum_{\bar{y}_i=1} \log P_i(x) + \sum_{\bar{y}_i=-1} \log(1 - P_i(x)).$$

(a) Show that the maximum likelihood estimation problem

$$\text{maximize } l(x)$$

is a convex optimization problem. The variable is $x$. The measured vector $\bar{y}$, and the parameters $a_i$ and $b_i$ are given.

(b) Solve the ML estimation problem with data defined in `one_bit_meas_data.m`, using Newton's method with backtracking line search. This file will define a matrix $A$ (with rows $a_i^T$), a vector $b$, and a vector $\bar{y}$ with elements $\pm 1$.

*Remark.* The Matlab functions `erfc` and `erfcx` are useful to evaluate the following functions:

$$\frac{1}{\sqrt{2\pi}} \int_{-\infty}^{u} e^{-t^2/2} \, dt = \frac{1}{2}\mathbf{erfc}(-\frac{u}{\sqrt{2}}), \qquad \frac{1}{\sqrt{2\pi}} \int_{u}^{\infty} e^{-t^2/2} \, dt = \frac{1}{2}\mathbf{erfc}(\frac{u}{\sqrt{2}})$$

$$\frac{1}{\sqrt{2\pi}} e^{u^2/2} \int_{-\infty}^{u} e^{-t^2/2} \, dt = \frac{1}{2}\mathbf{erfcx}(-\frac{u}{\sqrt{2}}), \qquad \frac{1}{\sqrt{2\pi}} e^{u^2/2} \int_{u}^{\infty} e^{-t^2/2} \, dt = \frac{1}{2}\mathbf{erfcx}(\frac{u}{\sqrt{2}}).$$

**9.8** *Functions with bounded Newton decrement.* Let $f : \mathbf{R}^n \to \mathbf{R}$ be a convex function with $\nabla^2 f(x) \succ 0$ for all $x \in \mathbf{dom}\, f$ and Newton decrement bounded by a positive constant $c$:

$$\lambda(x)^2 \leq c \quad \forall x \in \mathbf{dom}\, f.$$

Show that the function $g(x) = \exp(-f(x)/c)$ is concave.

**9.9** *Monotone convergence of Newton's method.* Suppose $f : \mathbf{R} \to \mathbf{R}$ is strongly convex and smooth, and in addition, $f''' \leq 0$. Let $x^\star$ minimize $f$, and suppose Newton's method is initialized with $x^{(0)} < x^\star$. Show that the iterates $x^{(k)}$ converge to $x^\star$ monotonically, and that a backtracking line search always takes a step size of one, *i.e.*, $t^{(k)} = 1$.

**9.10** *True or false.*

   (a) In descent methods, the particular choice of search direction does not matter so much.

   (b) In descent methods, the particular choice of line search does not matter so much.

   (c) When the gradient method is started from a point near the solution, it will converge very quickly.

   (d) When Newton's method is started from a point near the solution, it will converge very quickly.

   (e) Newton's method with step size $h = 1$ always works; damping (*i.e.*, using $h < 1$) is used only to improve the speed of convergence.

   (f) Using the gradient method to minimize $f(Ty)$, where $Ty = x$ and $T$ is nonsingular, can greatly improve the convergence speed when $T$ is chosen appropriately.

   (g) Using Newton's method to minimize $f(Ty)$, where $Ty = x$ and $T$ is nonsingular, can greatly improve the convergence speed when $T$ is chosen appropriately.

**9.11** *Self-concordance.* Determine whether the following statements are true or false.

   (a) If $f$ is self-concordant, its Hessian is Lipschitz continuous.

   (b) If the Hessian of $f$ is Lipschitz continuous, then $f$ is self-concordant.

   (c) Newton's method should only be used to minimize self-concordant functions.

   (d) $f(x) = \exp x$ is self-concordant.

   (e) $f(x) = -\log x$ is self-concordant.

**9.12** *Gradient versus Newton's method.* Consider the problem of minimizing

$$f(x) = (c^T x)^4 + \sum_{i=1}^{n} w_i \exp x_i,$$

over $x \in \mathbf{R}^n$, where $w \succ 0$. We wish to solve it to high accuracy, *i.e.*, we seek a point $x$ for which $\nabla f(x)$ is very small. Determine whether the following statements are true or false, with a short justification or explanation.

   (a) Newton's method would probably require fewer iterations than the gradient method.

   (b) But each iteration of Newton's method would be far more costly than an iteration of the gradient method.

(c) So it's not clear which method would be better for this problem.

**9.13** *Newton's method in machine learning problems.* Newton's method is seldom used to solve large unconstrained problems with smooth objective that arise in machine learning. Choose the most reasonable explanation from among the ones below.

(a) Common loss functions are not self-concordant.

(b) Newton's method does not work well on noisy data.

(c) Machine learning researchers don't really understand linear algebra.

(d) Due to the large problem size, it is generally not practical to form or store the Hessian, let alone compute the Newton step.

# 10    Equality constrained minimization

**10.1** *A characterization of the Newton decrement.* Let $f : \mathbf{R}^n \to \mathbf{R}$ be convex and twice differentiable, and let $A$ be a $p \times n$-matrix with rank $p$. Suppose $\hat{x}$ is feasible for the equality constrained problem

$$\begin{array}{ll} \text{minimize} & f(x) \\ \text{subject to} & Ax = b. \end{array}$$

Recall that the Newton step $\Delta x$ at $\hat{x}$ can be computed from the linear equations

$$\begin{bmatrix} \nabla^2 f(\hat{x}) & A^T \\ A & 0 \end{bmatrix} \begin{bmatrix} \Delta x \\ u \end{bmatrix} = \begin{bmatrix} -\nabla f(\hat{x}) \\ 0 \end{bmatrix},$$

and that the Newton decrement $\lambda(\hat{x})$ is defined as

$$\lambda(\hat{x}) = (-\nabla f(\hat{x})^T \Delta x)^{1/2} = (\Delta x^T \nabla^2 f(\hat{x}) \Delta x)^{1/2}.$$

Assume the coefficient matrix in the linear equations above is nonsingular and that $\lambda(\hat{x})$ is positive. Express the solution $y$ of the optimization problem

$$\begin{array}{ll} \text{minimize} & \nabla f(\hat{x})^T y \\ \text{subject to} & Ay = 0 \\ & y^T \nabla^2 f(\hat{x}) y \leq 1 \end{array}$$

in terms of Newton step $\Delta x$ and the Newton decrement $\lambda(\hat{x})$.

**10.2** We consider the equality constrained problem

$$\begin{array}{ll} \text{minimize} & \mathbf{tr}(CX) - \log \det X \\ \text{subject to} & \mathbf{diag}(X) = \mathbf{1}. \end{array}$$

The variable is the matrix $X \in \mathbf{S}^n$. The domain of the objective function is $\mathbf{S}^n_{++}$. The matrix $C \in \mathbf{S}^n$ is a problem parameter. This problem is similar to the analytic centering problem discussed in lecture 11 (p.18–19) and pages 553-555 of the textbook. The differences are the extra linear term $\mathbf{tr}(CX)$ in the objective, and the special form of the equality constraints. (Note that the equality constraints can be written as $\mathbf{tr}(A_i X) = 1$ with $A_i = e_i e_i^T$, a matrix of zeros except for the $i, i$ element, which is equal to one.)

(a) Show that $X$ is optimal if and only if

$$X \succ 0, \qquad X^{-1} - C \text{ is diagonal}, \qquad \mathbf{diag}(X) = \mathbf{1}.$$

(b) The Newton step $\Delta X$ at a feasible $X$ is defined as the solution of the Newton equations

$$X^{-1} \Delta X X^{-1} + \mathbf{diag}(w) = -C + X^{-1}, \qquad \mathbf{diag}(\Delta X) = 0,$$

with variables $\Delta X \in \mathbf{S}^n$, $w \in \mathbf{R}^n$. (Note the two meanings of the **diag** function: $\mathbf{diag}(w)$ is the diagonal matrix with the vector $w$ on its diagonal; $\mathbf{diag}(\Delta X)$ is the vector of the diagonal elements of $\Delta X$.) Eliminating $\Delta X$ from the first equation gives an equation

$$\mathbf{diag}(X \mathbf{diag}(w) X) = \mathbf{1} - \mathbf{diag}(XCX).$$

This is a set of $n$ linear equations in $n$ variables, so it can be written as $Hw = g$. Give a simple expression for the coefficients of the matrix $H$.

(c) Implement the feasible Newton method in Matlab. You can use $X = I$ as starting point. The code should terminate when $\lambda(X)^2/2 \leq 10^{-6}$, where $\lambda(X)$ is the Newton decrement.

You can use the Cholesky factorization to evaluate the cost function: if $X = LL^T$ where $L$ is triangular with positive diagonal then $\log \det X = 2 \sum_i \log L_{ii}$.

To ensure that the iterates remain feasible, the line search has to consist of two phases. Starting at $t = 1$, you first need to backtrack until $X + t\Delta X \succ 0$. Then you continue the backtracking until the condition of sufficient decrease

$$f_0(X + t\Delta X) \leq f_0(X) + \alpha t \, \mathbf{tr}(\nabla f_0(X)\Delta X)$$

is satisfied. To check that a matrix $X + t\Delta X$ is positive definite, you can use the Cholesky factorization with two output arguments ([R, p] = chol(A) returns $p > 0$ if $A$ is not positive definite).

Test your code on randomly generated problems of sizes $n = 10, \ldots, 100$ (for example, using n = 100; C = randn(n); C = C + C').

**10.3** *Estimation of a vector from one-bit measurements.* A system of $m$ sensors is used to estimate an unknown parameter $x \in \mathbf{R}^n$. Each sensor makes a noisy measurement of some linear combination of the unknown parameters, and quantizes the measured value to one bit: it returns $+1$ if the measured value exceeds a certain threshold, and $-1$ otherwise. In other words, the output of sensor $i$ is given by

$$y_i = \mathbf{sign}(a_i^T x + v_i - b_i) = \begin{cases} 1 & a_i^T x + v_i \geq b_i \\ -1 & a_i^T x + v_i < b_i, \end{cases}$$

where $a_i$ and $b_i$ are known, and $v_i$ is measurement error. We assume that the measurement errors $v_i$ are independent random variables with a zero-mean unit-variance Gaussian distribution (*i.e.*, with a probability density $\phi(v) = (1/\sqrt{2\pi})e^{-v^2/2}$). As a consequence, the sensor outputs $y_i$ are random variables with possible values $\pm 1$. We will denote $\mathbf{prob}(y_i = 1)$ as $P_i(x)$ to emphasize that it is a function of the unknown parameter $x$:

$$P_i(x) \;\; = \;\; \mathbf{prob}(y_i = 1) = \mathbf{prob}(a_i^T x + v_i \geq b_i) = \frac{1}{\sqrt{2\pi}} \int_{b_i - a_i^T x}^{\infty} e^{-t^2/2} dt$$

$$1 - P_i(x) \;\; = \;\; \mathbf{prob}(y_i = -1) = \mathbf{prob}(a_i^T x + v_i < b_i) = \frac{1}{\sqrt{2\pi}} \int_{-\infty}^{b_i - a_i^T x} e^{-t^2/2} dt.$$

The problem is to estimate $x$, based on observed values $\bar{y}_1, \bar{y}_2, \ldots, \bar{y}_m$ of the $m$ sensor outputs.

We will apply the maximum likelihood (ML) principle to determine an estimate $\hat{x}$. In maximum likelihood estimation, we calculate $\hat{x}$ by maximizing the *log-likelihood function*

$$l(x) = \log \left( \prod_{\bar{y}_i=1} P_i(x) \prod_{\bar{y}_i=-1} (1 - P_i(x)) \right) = \sum_{\bar{y}_i=1} \log P_i(x) + \sum_{\bar{y}_i=-1} \log(1 - P_i(x)).$$

(a) Show that the maximum likelihood estimation problem

$$\text{maximize } l(x)$$

is a convex optimization problem. The variable is $x$. The measured vector $\bar{y}$, and the parameters $a_i$ and $b_i$ are given.

(b) Solve the ML estimation problem with data defined in `one_bit_meas_data.m`, using Newton's method with backtracking line search. This file will define a matrix $A$ (with rows $a_i^T$), a vector $b$, and a vector $\bar{y}$ with elements $\pm 1$.

*Remark.* The Matlab functions `erfc` and `erfcx` are useful to evaluate the following functions:

$$\frac{1}{\sqrt{2\pi}} \int_{-\infty}^{u} e^{-t^2/2}\, dt = \frac{1}{2}\mathbf{erfc}(-\frac{u}{\sqrt{2}}), \qquad \frac{1}{\sqrt{2\pi}} \int_{u}^{\infty} e^{-t^2/2}\, dt = \frac{1}{2}\mathbf{erfc}(\frac{u}{\sqrt{2}})$$

$$\frac{1}{\sqrt{2\pi}} e^{u^2/2} \int_{-\infty}^{u} e^{-t^2/2}\, dt = \frac{1}{2}\mathbf{erfcx}(-\frac{u}{\sqrt{2}}), \qquad \frac{1}{\sqrt{2\pi}} e^{u^2/2} \int_{u}^{\infty} e^{-t^2/2}\, dt = \frac{1}{2}\mathbf{erfcx}(\frac{u}{\sqrt{2}}).$$

**10.4** *Infeasible start Newton method for LP centering problem.* Implement the infeasible start Newton method for solving the centering problem arising in the standard form LP,

$$\begin{array}{ll} \text{minimize} & c^T x - \sum_{i=1}^{n} \log x_i \\ \text{subject to} & Ax = b, \end{array}$$

with variable $x$. The data are $A \in \mathbf{R}^{m \times n}$, with $m < n$, $c \in \mathbf{R}^n$, and $b \in \mathbf{R}^m$. You can assume that $A$ is full rank. This problem cannot be solved when it is infeasible or unbounded below.

Your code should accept $A$, $b$, $c$, and $x_0$, and return $x^\star$, the primal optimal point, $\nu^\star$, a dual optimal point, and the number of Newton steps executed. The initial point $x^{(0)}$ must satisfy $x^{(0)} \succ 0$, but it need not satisfy the equality constraints.

Use the block elimination method to compute the Newton step. (You can also compute the Newton step via the KKT system, and compare the result to the Newton step computed via block elimination. The two steps should be close, but if any $x_i$ is very small, you might get a warning about the condition number of the KKT matrix.)

Plot $\|r(x,\nu)\|_2$, the norm of the concatenated primal and dual residuals, versus iteration $k$ for various problem data and initial points, to verify that your implementation achieves quadratic convergence. As stopping criterion, you can use $\|r(x,\nu)\|_2 \leq 10^{-6}$ (which means the problem was solved) or some maximum number of iterations (say, 50) was reached, which means it was not solved (likely because the problem is either infeasible or unbounded below).

For a fixed problem instance, experiment with varying the algorithm parameters $\alpha$ and $\beta$, observing the effect on the total number of Newton steps required.

To generate problem data (*i.e.*, $A$, $b$, $c$, $x_0$) that are feasible, you can first generate $A$, then random positive vector $p$, and set $b = Ap$. You can be sure that the problem is not unbounded by making one row of $A$ have positive entries. You may also want to check that $A$ is full rank.

Test the behavior of your implementation on data instances that are not feasible, and also ones that are unbounded below.

# 11 Interior-point methods

**11.1** *Dual feasible point from analytic center.* We consider the problem

$$
\begin{aligned}
&\text{minimize} && f_0(x) \\
&\text{subject to} && f_i(x) \le 0, \quad i = 1, \dots, m,
\end{aligned}
\tag{49}
$$

where the functions $f_i$ are convex and differentiable. For $u > p^\star$, define $x_{\mathrm{ac}}(u)$ as the analytic center of the inequalities

$$
f_0(x) \le u, \qquad f_i(x) \le 0, \quad i = 1, \dots, m,
$$

*i.e.,*

$$
x_{\mathrm{ac}}(u) = \operatorname{argmin} \left( -\log(u - f_0(x)) - \sum_{i=1}^{m} \log(-f_i(x)) \right).
$$

Show that $\lambda \in \mathbf{R}^m$, defined by

$$
\lambda_i = \frac{u - f_0(x_{\mathrm{ac}}(u))}{-f_i(x_{\mathrm{ac}}(u))}, \quad i = 1, \dots, m
$$

is dual feasible for the problem above. Express the corresponding dual objective value in terms of $u$, $x_{\mathrm{ac}}(u)$ and the problem parameters.

**11.2** *Efficient solution of Newton equations.* Explain how you would solve the Newton equations in the barrier method applied to the quadratic program

$$
\begin{aligned}
&\text{minimize} && (1/2)x^T x + c^T x \\
&\text{subject to} && Ax \preceq b
\end{aligned}
$$

where $A \in \mathbf{R}^{m \times n}$ is dense. Distinguish two cases, $m \gg n$ and $n \gg m$, and give the most efficient method in each case.

**11.3** *Efficient solution of Newton equations.* Describe an efficient method for solving the Newton equation in the barrier method for the quadratic program

$$
\begin{aligned}
&\text{minimize} && (1/2)(x - a)^T P^{-1}(x - a) \\
&\text{subject to} && 0 \preceq x \preceq \mathbf{1},
\end{aligned}
$$

with variable $x \in \mathbf{R}^n$. The matrix $P \in \mathbf{S}^n$ and the vector $a \in \mathbf{R}^n$ are given.

Assume that the matrix $P$ is large, positive definite, and sparse, and that $P^{-1}$ is dense. 'Efficient' means that the complexity of the method should be much less than $O(n^3)$.

**11.4** *Dual feasible point from incomplete centering.* Consider the SDP

$$
\begin{aligned}
&\text{minimize} && \mathbf{1}^T x \\
&\text{subject to} && W + \mathbf{diag}(x) \succeq 0,
\end{aligned}
$$

with variable $x \in \mathbf{R}^n$, and its dual

$$
\begin{aligned}
&\text{maximize} && -\operatorname{\mathbf{tr}} WZ \\
&\text{subject to} && Z_{ii} = 1, \quad i = 1, \dots, n \\
& && Z \succeq 0,
\end{aligned}
$$

with variable $X \in \mathbf{S}^n$. (These problems arise in a relaxation of the two-way partitioning problem, described on page 219; see also exercises 5.39 and 11.23.)

Standard results for the barrier method tell us that when $x$ is on the central path, *i.e.*, minimizes the function

$$\phi(x) = t\mathbf{1}^T x + \log \det(W + \mathbf{diag}(x))^{-1}$$

for some parameter $t > 0$, the matrix

$$Z = \frac{1}{t}(W + \mathbf{diag}(x))^{-1}$$

is dual feasible, with objective value $-\mathbf{tr}\, WZ = \mathbf{1}^T x - n/t$.

Now suppose that $x$ is strictly feasible, but not necessarily on the central path. (For example, $x$ might be the result of using Newton's method to minimize $\phi$, but with early termination.) Then the matrix $Z$ defined above will not be dual feasible. In this problem we will show how to construct a dual feasible $\hat{Z}$ (which agrees with $Z$ as given above when $x$ is on the central path), from any point $x$ that is *near* the central path. Define $X = W + \mathbf{diag}(x)$, and let $v = -\nabla^2\phi(x)^{-1}\nabla\phi(x)$ be the Newton step for the function $\phi$ defined above. Define

$$\hat{Z} = \frac{1}{t}\left(X^{-1} - X^{-1}\mathbf{diag}(v)X^{-1}\right).$$

(a) Verify that when $x$ is on the central path, we have $\hat{Z} = Z$.

(b) Show that $\hat{Z}_{ii} = 1$, for $i = 1, \ldots, n$.

(c) Let $\lambda(x) = \nabla\phi(x)^T\nabla^2\phi(x)^{-1}\nabla\phi(x)$ be the Newton decrement at $x$. Show that

$$\lambda(x) = \mathbf{tr}(X^{-1}\mathbf{diag}(v)X^{-1}\mathbf{diag}(v)) = \mathbf{tr}(X^{-1/2}\mathbf{diag}(v)X^{-1/2})^2.$$

(d) Show that $\lambda(x) < 1$ implies that $\hat{Z} \succ 0$. Thus, when $x$ is near the central path (meaning, $\lambda(x) < 1$), $Z$ is dual feasible.

**11.5** *Standard form LP barrier method.* In the following three parts of this exercise, you will implement a barrier method for solving the standard form LP

$$\begin{array}{ll} \text{minimize} & c^T x \\ \text{subject to} & Ax = b, \quad x \succeq 0, \end{array}$$

with variable $x \in \mathbf{R}^n$, where $A \in \mathbf{R}^{m \times n}$, with $m < n$. Throughout these exercises we will assume that $A$ is full rank, and the sublevel sets $\{x \mid Ax = b, \ x \succeq 0, \ c^T x \leq \gamma\}$ are all bounded. (If this is not the case, the centering problem is unbounded below.)

(a) *Centering step.* Implement Newton's method for solving the centering problem

$$\begin{array}{ll} \text{minimize} & c^T x - \sum_{i=1}^n \log x_i \\ \text{subject to} & Ax = b, \end{array}$$

with variable $x$, given a strictly feasible starting point $x_0$.

Your code should accept $A$, $b$, $c$, and $x_0$, and return $x^\star$, the primal optimal point, $\nu^\star$, a dual optimal point, and the number of Newton steps executed.

Use the block elimination method to compute the Newton step. (You can also compute the Newton step via the KKT system, and compare the result to the Newton step computed via block elimination. The two steps should be close, but if any $x_i$ is very small, you might get a warning about the condition number of the KKT matrix.)

Plot $\lambda^2/2$ versus iteration $k$, for various problem data and initial points, to verify that your implementation gives asymptotic quadratic convergence. As stopping criterion, you can use $\lambda^2/2 \leq 10^{-6}$. Experiment with varying the algorithm parameters $\alpha$ and $\beta$, observing the effect on the total number of Newton steps required, for a fixed problem instance. Check that your computed $x^\star$ and $\nu^\star$ (nearly) satisfy the KKT conditions.

To generate some random problem data (*i.e.*, $A$, $b$, $c$, $x_0$), we recommend the following approach. First, generate $A$ randomly. (You might want to check that it has full rank.) Then generate a random positive vector $x_0$, and take $b = Ax_0$. (This ensures that $x_0$ is strictly feasible.) The parameter $c$ can be chosen randomly. To be sure the sublevel sets are bounded, you can add a row to $A$ with all positive elements. If you want to be able to repeat a run with the same problem data, be sure to set the state for the uniform and normal random number generators.

Here are some hints that may be useful.

- We recommend computing $\lambda^2$ using the formula $\lambda^2 = -\Delta x_{\mathrm{nt}}^T \nabla f(x)$. You don't really need $\lambda$ for anything; you can work with $\lambda^2$ instead. (This is important for reasons described below.)

- There can be small numerical errors in the Newton step $\Delta x_{\mathrm{nt}}$ that you compute. When $x$ is nearly optimal, the computed value of $\lambda^2$, *i.e.*, $\lambda^2 = -\Delta x_{\mathrm{nt}}^T \nabla f(x)$, can actually be (slightly) negative. If you take the squareroot to get $\lambda$, you'll get a complex number, and you'll never recover. Moreover, your line search will never exit. However, this only happens when $x$ is nearly optimal. So if you exit on the condition $\lambda^2/2 \leq 10^{-6}$, everything will be fine, even when the computed value of $\lambda^2$ is negative.

- For the line search, you must first multiply the step size $t$ by $\beta$ until $x + t\Delta x_{\mathrm{nt}}$ is feasible (*i.e.*, strictly positive). If you don't, when you evaluate $f$ you'll be taking the logarithm of negative numbers, and you'll never recover.

(b) *LP solver with strictly feasible starting point.* Using the centering code from part (a), implement a barrier method to solve the standard form LP

$$\begin{array}{ll} \text{minimize} & c^T x \\ \text{subject to} & Ax = b, \quad x \succeq 0, \end{array}$$

with variable $x \in \mathbf{R}^n$, given a strictly feasible starting point $x_0$. Your LP solver should take as argument $A$, $b$, $c$, and $x_0$, and return $x^\star$.

You can terminate your barrier method when the duality gap, as measured by $n/t$, is smaller than $10^{-3}$. (If you make the tolerance much smaller, you might run into some numerical trouble.) Check your LP solver against the solution found by CVX*, for several problem instances.

The comments in part (a) on how to generate random data hold here too.

Experiment with the parameter $\mu$ to see the effect on the number of Newton steps per centering step, and the total number of Newton steps required to solve the problem.

Plot the progress of the algorithm, for a problem instance with $n = 500$ and $m = 100$, showing duality gap (on a log scale) on the vertical axis, versus the cumulative total number of Newton steps (on a linear scale) on the horizontal axis.

Your algorithm should return a $2 \times k$ matrix `history`, (where $k$ is the total number of centering steps), whose first row contains the number of Newton steps required for each centering step, and whose second row shows the duality gap at the end of each centering step. In order to get a plot that looks like the ones in the book (*e.g.*, figure 11.4, page 572), you should use the following code:

```
[xx, yy] = stairs(cumsum(history(1,:)),history(2,:));
semilogy(xx,yy);
```

(c) *LP solver.* Using the code from part (b), implement a general standard form LP solver, that takes arguments $A$, $b$, $c$, determines (strict) feasibility, and returns an optimal point if the problem is (strictly) feasible.

You will need to implement a phase I method, that determines whether the problem is strictly feasible, and if so, finds a strictly feasible point, which can then be fed to the code from part (b). In fact, you can use the code from part (b) to implement the phase I method.

To find a strictly feasible initial point $x_0$, we solve the phase I problem

$$
\begin{array}{ll}
\text{minimize} & t \\
\text{subject to} & Ax = b \\
& x \succeq (1-t)\mathbf{1}, \quad t \geq 0,
\end{array}
$$

with variables $x$ and $t$. If we can find a feasible $(x, t)$, with $t < 1$, then $x$ is strictly feasible for the original problem. The converse is also true, so the original LP is strictly feasible if and only if $t^\star < 1$, where $t^\star$ is the optimal value of the phase I problem.

We can initialize $x$ and $t$ for the phase I problem with any $x^0$ satisfying $Ax^0 = b$, and $t^0 = 2 - \min_i x_i^0$. (Here we can assume that $\min x_i^0 \leq 0$; otherwise $x^0$ is already a strictly feasible point, and we are done.) You can use a change of variable $z = x + (t-1)\mathbf{1}$ to transform the phase I problem into the form in part (b).

Check your LP solver against CVX* on several numerical examples, including both feasible and infeasible instances.

**11.6** *Primal and dual feasible points in the barrier method for LP.* Consider a standard form LP and its dual

$$
\begin{array}{ll}
\text{minimize} & c^T x \\
\text{subject to} & Ax = b \\
& x \succeq 0
\end{array}
\qquad
\begin{array}{ll}
\text{maximize} & b^T y \\
\text{subject to} & A^T y \preceq c,
\end{array}
$$

with $A \in \mathbf{R}^{m \times n}$ and $\mathbf{rank}(A) = m$. In the barrier method the (feasible) Newton method is applied to the equality constrained problem

$$
\begin{array}{ll}
\text{minimize} & tc^T x + \phi(x) \\
\text{subject to} & Ax = b,
\end{array}
$$

where $t > 0$ and $\phi(x) = -\sum_{i=1}^{n} \log x_i$. The Newton equation at a strictly feasible $\hat{x}$ is given by

$$
\begin{bmatrix} \nabla^2 \phi(\hat{x}) & A^T \\ A & 0 \end{bmatrix} \begin{bmatrix} \Delta x \\ w \end{bmatrix} = \begin{bmatrix} -tc - \nabla\phi(\hat{x}) \\ 0 \end{bmatrix}.
$$

Suppose $\lambda(\hat{x}) \leq 1$ where $\lambda(\hat{x})$ is the Newton decrement at $\hat{x}$.

(a) Show that $\hat{x} + \Delta x$ is primal feasible.

(b) Show that $y = -(1/t)w$ is dual feasible.

(c) Let $p^\star$ be the optimal value of the LP. Show that

$$c^T \hat{x} - p^\star \leq \frac{n + \lambda(\hat{x})\sqrt{n}}{t}.$$

**11.7** Consider a convex optimization problem and its dual

$$
\begin{array}{lll}
\text{minimize} & f_0(x) & \qquad\qquad \text{maximize} \quad g(\lambda) \qquad\qquad (50) \\
\text{subject to} & f_i(x) \leq 0, \quad i = 1, \ldots, m, & \qquad\qquad \text{subject to} \quad \lambda \succeq 0.
\end{array}
$$

The centering problem in the barrier method is

$$\text{minimize} \quad t f_0(x) - \sum_{i=1}^{m} \log(-f_i(x)), \qquad\qquad (51)$$

where $t$ is a positive parameter.

(a) The centering problem can be written as

$$
\begin{array}{ll}
\text{minimize} & t f_0(x) - \sum_{i=1}^{m} \log(y_i) \\
\text{subject to} & f_i(x) + y_i \leq 0, \quad i = 1, \ldots, m,
\end{array}
$$

with variables $x$ and $y$. Derive the Lagrange dual of this problem and express it in terms of the dual function $g(\lambda)$ in (50).

(b) Suppose the feasible set of the dual problem in (50) contains strictly positive $\lambda$. Show that the centering problem (51) is bounded below for any positive $t$.

**11.8** *Standard form LP barrier method with infeasible start Newton method.* Implement the barrier method for the standard form LP,

$$
\begin{array}{ll}
\text{minimize} & c^T x \\
\text{subject to} & Ax = b, \quad x \succeq 0,
\end{array}
$$

with variable $x \in \mathbf{R}^n$, where $A \in \mathbf{R}^{m \times n}$, with $m < n$, with $A$ full rank. (Your method will of course fail if the problem is not strictly feasible, or if it is unbounded.)

Use the centering code that you developed in exercise 10.4. Your LP solver should take as argument $A$, $b$, $c$, and return primal and dual optimal points $x^\star$, $\nu^\star$, and $\lambda^\star$.

You can terminate your barrier method when the duality gap, as measured by $n/t$, is smaller than $10^{-3}$. (If you make the tolerance much smaller, you might run into some numerical trouble.)

Check your LP solver against the solution found by CVX* for several problem instances. The comments in exercise 10.4 on how to generate random data hold here too.

Experiment with the parameter $\mu$ to see the effect on the number of Newton steps per centering step, and the total number of Newton steps required to solve the problem.

Plot the progress of the algorithm, for a problem instance with $n = 500$ and $m = 100$, showing duality gap (on a log scale) on the vertical axis, versus the cumulative total number of Newton steps (on a linear scale) on the horizontal axis.

Your algorithm should return a $2 \times k$ matrix `history`, (where $k$ is the total number of centering steps), whose first row contains the number of Newton steps required for each centering step, and whose second row shows the duality gap at the end of each centering step. In order to get a plot that looks like the ones in the book (*e.g.*, figure 11.4, page 572), in Julia, with PyPlot you can use the following:

```
using PyPlot
step(cumsum(history[1,:]'),history[2,:]')
yscale("log")
```

In Python, also with PyPlot you should use:

```
import matplotlib.pyplot as plt
plt.step(np.cumsum(history[0,:]),history[1,:],where="post")
plt.yscale("log")
plt.show()
```

**11.9** Consider an optimization problem

$$\begin{array}{ll} \text{minimize} & f_0(x) \\ \text{subject to} & f_i(x) \le 0, \quad i = 1, \ldots, m, \end{array}$$

with $f_0, \ldots, f_m$ convex and differentiable.

(a) Show that the Karush-Kuhn-Tucker (KKT) conditions are equivalent to the two conditions

$$\lambda_i = \max\{\lambda_i + f_i(x), 0\}, \quad i = 1, \ldots, m, \qquad \nabla f_0(x) + \sum_{i=1}^{m} \lambda_i \nabla f_i(x) = 0.$$

(b) The function $\max\{u, 0\}$ can be approximated by the smooth function $(u + \sqrt{u^2 + 4t})/2$, where $t$ is a positive constant that determines the quality of the approximation.



153

If we use this approximation in the KKT conditions of part (a), we obtain

$$\lambda_i = \frac{\lambda_i + f_i(x) + \sqrt{(\lambda_i + f_i(x))^2 + 4t}}{2}, \quad i = 1, \ldots, m, \qquad \nabla f_0(x) + \sum_{i=1}^{m} \lambda_i \nabla f_i(x) = 0. \quad (52)$$

Solving this set of nonlinear equations for a small value of $t$, gives an approximate solution of the KKT conditions. Show that this is another interpretation of the central path: if $x$, $\lambda$ satisfy (52), then $x$ minimizes $f_0(x) - t \sum_{i=1}^{m} \log(-f_i(x))$ and $\lambda_i = -t/f_i(x)$.

**11.10** Suppose $\hat{x}$ is on the central path of the linear program

$$\begin{array}{ll} \text{minimize} & c^T x \\ \text{subject to} & Ax \preceq b, \end{array}$$

where $A \in \mathbf{R}^{m \times n}$, $b \in \mathbf{R}^m$. We assume $m \geq 2$ and $\mathbf{rank}(A) = n$.

(a) Show that the set

$$C = \{x \mid Ax \preceq b, \ c^T x \leq c^T \hat{x}\}$$

is contained in the ellipsoid

$$E = \{x \mid (x - \hat{x})^T \nabla^2 \phi(\hat{x})(x - \hat{x}) \leq m(m - 1)\}.$$

In this expression, $\phi$ is the logarithmic barrier function $\phi(x) = -\sum_{i=1}^{m} \log(b_i - a_i^T x)$, where $a_i^T$ denotes the $i$th row of $A$. To simplify the notation you can assume (without loss of generality) that $b = \mathbf{1}$ and $\hat{x} = 0$.

(b) The dual problem of the linear program is

$$\begin{array}{ll} \text{maximize} & -b^T z \\ \text{subject to} & A^T z + c = 0 \\ & z \succeq 0, \end{array}$$

with variable $z \in \mathbf{R}^m$. Use the result of part (a) to show that the optimal $z_k$ must be zero if

$$a_k^T \hat{x} + \sqrt{m(m-1)} \sqrt{a_k^T \nabla^2 \phi(\hat{x})^{-1} a_k} < b_k.$$

**11.11** Consider the quadratic program that arises in the Markowitz portfolio selection problem:

$$\begin{array}{ll} \text{minimize} & x^T P x + q^T x \\ \text{subject to} & x \succeq 0 \\ & \mathbf{1}^T x = 1. \end{array}$$

The variable is $x \in \mathbf{R}^n$. We assume $P$ is positive definite.

(a) The barrier method applied to this problem requires the repeated solution of equality-constrained optimization problems

$$\begin{array}{ll} \text{minimize} & t(x^T P x + q^T x) - \sum_{k=1}^{n} \log x_k \\ \text{subject to} & \mathbf{1}^T x = 1, \end{array}$$

where $t$ is a positive constant. Give the set of linear equations that defines the Newton step $\Delta x$.

(b) Suppose $P = FF^T + D$ where $D$ is positive diagonal and $F$ is an $n \times p$ matrix with $n \gg p$. Describe an efficient method for solving the Newton equation in part (a). How does the complexity of your method depend on $n$? Is it a linear, quadratic, or cubic function?

**11.12** *Self concordance and a logarithmic barrier for the exponential cone.* Let $C \subset \mathbf{R}_+^n$ be an open convex set and $f : C \to \mathbf{R}$ be three times continuously differentiable and convex. Recall the notation that if for a vector $v \in \mathbf{R}^n$ we define $g(t) = f(x + tv)$ for $t \in \mathbf{R}$, then

$$\nabla^3 f(x)[v, v, v] = g'''(0) = \lim_{t \to 0} \frac{v^T \nabla^2 f(x + tv)v - v^T \nabla^2 f(x)v}{t}.$$

Assume the following condition, which generalizes inequality (9.43) in the book:

$$|\nabla^3 f(x)[v, v, v]| \le 3v^T \nabla^2 f(x)v \sqrt{\sum_{i=1}^n \frac{v_i^2}{x_i^2}}. \tag{53}$$

(a) Show that

$$\psi(t, x) = -\log(t - f(x)) - \sum_{i=1}^n \log x_i$$

is self-concordant on $\{(x, t) \mid x \in C, t > f(x)\}$. Recall that in our notation, self-concordance of a function $\psi$ is equivalent to

$$|\nabla^3 \psi(y)[v, v, v]| \le 2(v^T \nabla^2 \psi(y)v)^{3/2}.$$

*Hint.* As in exercise 9.14 in the book, you may use the inequality $\frac{3}{2}a^2 c + b^3 + c^3 + \frac{3}{2}a^2 b \le 1$ for $a^2 + b^2 + c^2 = 1$. As a side note—and you should not need to use this!—a *3-way tensor* $A \in \mathbf{R}^{n \times n \times n}$ is a collection indexed by $(i, j, k)$, and $A[v, v, v] = \sum_{i,j,k} A_{ijk} v_i v_j v_k$. In this case the $(i, j, k)$ entry of $\nabla^3 f(x) \in \mathbf{R}^{n \times n \times n}$ is $[\nabla^3 f(x)]_{ijk} = \frac{\partial^3}{\partial x_i \partial x_j \partial x_k} f(x)$, and the tensor is symmetric (it does not matter what order one takes the derivatives). Then we have

$$f(x + v) = f(x) + \nabla f(x)^T v + \frac{1}{2} v^T \nabla^2 f(x)v + \frac{1}{6} \nabla^3 f(x)[v, v, v] + o(\|v\|^3)$$

for $v$ small.

(b) Show that the relative entropy

$$f : \mathbf{R}_{++}^2 \to \mathbf{R}, \quad f(y, z) = y \log \frac{y}{z}$$

satisfies condition (53).

(c) Use the preceding parts of the exercise to argue that that

$$\psi(x, y, z) = -\log y - \log z - \log\left(y \log \frac{z}{y} - x\right)$$

is self-concordant on the perspective-transformed exponential cone

$$K = \{(x, y, z) \mid ye^{x/y} < z, y > 0\}.$$

Show also that $\psi$ is a generalized logarithm of degree 3, meaning that $\psi(s(x, y, z)) = \psi(x, y, z) - 3 \log s$ for $s > 0$.

It turns out that $\psi$ is a *barrier for* $K$, meaning that $\|\nabla\psi(x,y,z)\| \to +\infty$ as $(x,y,z) \to \mathbf{bd}\,K$, and that it is the optimal (in a sense we will not make precise) such self-concordant barrier; such logarithmically-homogeneous barriers are useful for bounding the complexity of Newton methods for solving convex problems.

**11.13** *Educational testing problem.* The educational testing problem (ETP) has the following form:

$$
\begin{array}{ll}
\text{maximize} & \mathbf{1}^T x \\
\text{subject to} & \Sigma - \mathbf{diag}(x) \succeq 0 \\
& x \succeq 0,
\end{array}
\tag{54}
$$

with variable $x \in \mathbf{R}^n$; the problem data is $\Sigma \in \mathbf{S}^n_{++}$.

(a) *Dual of the ETP.* Form the Lagrangian, and derive an explicit expression for the dual function $g$. Show that the Lagrange dual can be simplified as

$$
\begin{array}{ll}
\text{minimize} & \mathbf{tr}\,\Sigma Z \\
\text{subject to} & Z \succeq 0 \\
& Z_{ii} \geq 1, \ i = 1,\dots,n,
\end{array}
\tag{55}
$$

with variable $Z \in \mathbf{S}^n$. Note that $Z = I$ is dual feasible. What is the corresponding bound on the optimal value of the ETP? Can you derive this bound directly (*i.e.*, without any duality theory)?

(b) *Central path for ETP.* We will use the standard logarithmic barrier for the positive definite cone, *i.e.*, $\log\det X^{-1}$ for $X \in \mathbf{S}^n_{++}$. Derive and simplify the conditions under which a strictly feasible $x$ is on the central path. Show explicitly how to find a matrix $Z$ that is feasible for the dual (55), given a central point $x^\star(t)$.

(c) *Barrier method for ETP.* Write code that solves the ETP, with a guaranteed accuracy of 1%, by which we mean that on exit your solution must satisfy

$$
p^\star - \mathbf{1}^T x \leq 0.01 p^\star,
$$

where $p^\star$ is the optimal value of (54).

Along with your code, give formulas for the gradient and Hessian of barrier and related functions, how you find an initial strictly feasible $x$, what starting value you use for $t$, and how your stopping criterion guarantees the required 1% accuracy. You can use a backtracking line search.

Test your code on a variety of simple instances (diagonal, $2 \times 2$, ... ). Then test it on some larger problems, with random (positive definite symmetric) $\Sigma$.

For a moderate sized problem (say, $n = 30$), experiment with the effect of $\mu$ on the total number of Newton steps required to solve the problem.

*Hint.* The gradient and Hessian of the logarithmic barrier $\phi(x) = \log\det F(x)^{-1}$ for the linear matrix inequality

$$
F(x) = F_0 + \sum_{i=1}^m x_i F_i \succeq 0, \quad F_i = F_i^T \in \mathbf{R}^{n\times n}, \ i = 0,\dots,m
$$

are given by

$$
\nabla\phi(x)_i = -\mathbf{tr}\,F_i F(x)^{-1}, \quad \nabla^2\phi(x)_{ij} = \mathbf{tr}\,F_i F(x)^{-1} F_j F(x)^{-1}, \quad i,j = 1,\dots,m.
$$

156

# 12 Mathematical background

**12.1** *Some famous inequalities.* The Cauchy-Schwarz inequality states that

$$|a^T b| \leq \|a\|_2 \|b\|_2$$

for all vectors $a, b \in \mathbf{R}^n$ (see page 633 of the textbook).

(a) Prove the Cauchy-Schwarz inequality.

*Hint.* A simple proof is as follows. With $a$ and $b$ fixed, consider the function $g(t) = \|a + tb\|_2^2$ of the scalar variable $t$. This function is nonnegative for all $t$. Find an expression for $\inf_t g(t)$ (the minimum value of $g$), and show that the Cauchy-Schwarz inequality follows from the fact that $\inf_t g(t) \geq 0$.

(b) The 1-norm of a vector $x$ is defined as $\|x\|_1 = \sum_{k=1}^{n} |x_k|$. Use the Cauchy-Schwarz inequality to show that

$$\|x\|_1 \leq \sqrt{n}\|x\|_2$$

for all $x$.

(c) The *harmonic mean* of a positive vector $x \in \mathbf{R}_{++}^n$ is defined as

$$\left( \frac{1}{n} \sum_{k=1}^{n} \frac{1}{x_k} \right)^{-1}.$$

Use the Cauchy-Schwarz inequality to show that the arithmetic mean $(\sum_k x_k)/n$ of a positive $n$-vector is greater than or equal to its harmonic mean.

**12.2** *Schur complements.* Consider a matrix $X = X^T \in \mathbf{R}^{n \times n}$ partitioned as

$$X = \left[ \begin{array}{cc} A & B \\ B^T & C \end{array} \right],$$

where $A \in \mathbf{R}^{k \times k}$. If $\det A \neq 0$, the matrix $S = C - B^T A^{-1} B$ is called the *Schur complement* of $A$ in $X$. Schur complements arise in many situations and appear in many important formulas and theorems. For example, we have $\det X = \det A \det S$. (You don't have to prove this.)

(a) The Schur complement arises when you minimize a quadratic form over some of the variables. Let $f(u, v) = (u, v)^T X (u, v)$, where $u \in \mathbf{R}^k$. Let $g(v)$ be the minimum value of $f$ over $u$, *i.e.*, $g(v) = \inf_u f(u, v)$. Of course $g(v)$ can be $-\infty$.

Show that if $A \succ 0$, we have $g(v) = v^T S v$.

(b) The Schur complement arises in several characterizations of positive definiteness or semidefiniteness of a block matrix. As examples we have the following three theorems:

- $X \succ 0$ if and only if $A \succ 0$ and $S \succ 0$.
- If $A \succ 0$, then $X \succeq 0$ if and only if $S \succeq 0$.
- $X \succeq 0$ if and only if $A \succeq 0$, $B^T (I - AA^\dagger) = 0$ and $C - B^T A^\dagger B \succeq 0$, where $A^\dagger$ is the pseudo-inverse of $A$. ($C - B^T A^\dagger B$ serves as a generalization of the Schur complement in the case where $A$ is positive semidefinite but singular.)

Prove *one* of these theorems. (You can choose which one.)

**12.3** *Von Neumann's trace inequality.*

(a) The set $\mathcal{P}$ of doubly stochastic matrices (often called the *Birkhoff polytope*) are those matrices $P \in \mathbf{R}_+^{n \times n}$ satisfying $P\mathbf{1} = \mathbf{1}$ and $P^T\mathbf{1} = \mathbf{1}$. For a vector $x \in \mathbf{R}^n$, we let $x_{[i]}$ denote the $i$th largest component of $x$. Show that for any two vectors $x, y \in \mathbf{R}^n$,

$$x^T P y \le \sum_{i=1}^{n} x_{[i]} y_{[i]}.$$

*Hint.* You may use the result that if $\mathcal{S}^n = \{A \in \{0,1\}^{n \times n} \mid A\mathbf{1} = \mathbf{1}, A^T\mathbf{1} = \mathbf{1}\}$ is the set of permutation matrices, then $\mathcal{P} = \mathbf{conv}\{\mathcal{S}^n\}$, that is, the Birkhoff polytope is the convex hull of $\mathcal{S}^n$.

(b) Prove Von Neumann's trace inequality, that is, that for any matrices $X, Y \in \mathbf{S}^n$,

$$\mathbf{tr}(XY) \le \sum_{i=1}^{n} \lambda_i(X) \lambda_i(Y), \tag{56}$$

where $\lambda_i(X), \lambda_i(Y)$ are the eigenvalues of $X, Y$ in sorted order. *Hint.* Argue that it is no loss of generality to assume $X$ is diagonal, and use that you may write $Y = U\Lambda U^T$ for an orthogonal $U$ and diagonal $\Lambda$.

(c) Give a sufficient condition for equality in Eq. (56).

**12.4** *Von Neumann's trace inequality revisited.* In this question, you prove the full version of Von Neumann's trace inequality, that is, that for matrices $X, Y \in \mathbf{R}^{n \times m}$,

$$\mathbf{tr}(X^T Y) \le \sum_{i=1}^{\min\{n,m\}} \sigma_i(X) \sigma_i(Y), \tag{57}$$

where $\sigma_i(X)$ and $\sigma_i(Y)$ are the singular values of $X$ and $Y$, with $\sigma_1 \ge \sigma_2 \ge \cdots$.

(a) Show that it is no loss of generality to assume that $m \le n$.

(b) Show that inequality (57) holds.

(c) Give a sufficient condition for equality in inequality (57) to hold.

(d) Show that if $\|\cdot\|$ denotes the operator norm of a matrix, $\|X\| = \sigma_1(X)$ (the maximum singular value), then

$$\|Y\|^* = \sup\{\mathbf{tr}(X^T Y) \mid \|X\| \le 1\} = \sum_{i=1}^{\min\{m,n\}} \sigma_i(Y).$$

That is, the dual norm to the $\ell_2$-operator norm is the trace norm (or sum of singular values).

*Hint.* See exercise 12.3.

# 13  Numerical linear algebra

**13.1** *Time to solve one or multiple sets of linear equations.*

  (a) About how long does it take a 10 Gflop/s computer to solve a system of 100 linear equations (with 100 variables)? Choose one below.

  - Ten microseconds.
  - One hundred microseconds.
  - One millisecond.
  - Ten milliseconds.
  - One hundred milliseconds.
  - One second.

  (b) About how long does it take a 10 Gflop/s computer to solve 10 systems of 100 linear equations, with the same coefficient matrix but 10 different righthand sides?

  - Ten microseconds.
  - One hundred microseconds.
  - One millisecond.
  - Ten milliseconds.
  - One hundred milliseconds.
  - One second.

**13.2** *True or false.*

  (a) Algorithm flop counts allow for very accurate prediction of running time on a given computer.

  (b) Since matrix multiplication is associative, the flop count for multiplying three or more matrices doesn't depend on the order in which you multiply them.

  (c) Suppose $A \in \mathbf{R}^{n \times n}$ is lower triangular. The flop count for computing $Ab$ is the same order as the flop count for computing $A^{-1}b$.

**13.3** *Ridge regression.* Suppose $A \in \mathbf{R}^{m \times n}$, and we need to compute $x$ that minimizes $\|Ax - b\|_2^2 + (\rho/2)\|x\|_2^2$, where $\rho > 0$. (This is the problem of using ridge regression to fit a regression model, but that doesn't matter here.)

  (a) *Tall matrix.* For $m \geq n$, the flop count (order) of a good method is (choose one)

  - $m^3$.
  - $m^2 n$.
  - $mn^2$.
  - $n^3$.

  (b) *Wide matrix.* For $m \leq n$, the flop count (order) of a good method is (choose one)

  - $m^3$.
  - $m^2 n$.
  - $mn^2$.
  - $n^3$.

# 14  Circuit design

**14.1** *Interconnect sizing.* In this problem we will size the interconnecting wires of the simple circuit shown below, with one voltage source driving three different capacitive loads $C_{\text{load1}}, C_{\text{load2}}$, and $C_{\text{load3}}$.



We divide the wires into 6 segments of fixed length $l_i$; our variables will be the widths $w_i$ of the segments. (The height of the wires is related to the particular IC technology process, and is fixed.) The total area used by the wires is, of course,

$$A = \sum_i w_i l_i.$$

We'll take the lengths to be one, for simplicity. The wire widths must be between a minimum and maximum allowable value:

$$W_{\min} \leq w_i \leq W_{\max}.$$

For our specific problem, we'll take $W_{\min} = 0.1$ and $W_{\max} = 10$.

Each of the wire segments will be modeled by a simple simple RC circuit, with the resistance inversely proportional to the width of the wire and the capacitance proportional to the width. (A far better model uses an extra constant term in the capacitance, but this complicates the equations.) The capacitance and resistance of the $i$th segment is thus

$$C_i = k_0 w_i, \qquad R_i = \rho/w_i,$$

where $k_0$ and $\rho$ are positive constants, which we take to be one for simplicity. We also have $C_{\text{load1}} = 1.5$, $C_{\text{load2}} = 1$, and $C_{\text{load3}} = 5$.

Using the RC model for the wire segments yields the circuit shown below.

We will use the Elmore delay to model the delay from the source to each of the loads. The Elmore delay to loads 1, 2, and 3 are given by

$$
\begin{aligned}
T_1 &= (C_3 + C_{\text{load1}})(R_1 + R_2 + R_3) + C_2(R_1 + R_2) + \\
&\quad +(C_1 + C_4 + C_5 + C_6 + C_{\text{load2}} + C_{\text{load3}})R_1 \\
T_2 &= (C_5 + C_{\text{load2}})(R_1 + R_4 + R_5) + C_4(R_1 + R_4) + \\
&\quad +(C_6 + C_{\text{load3}})(R_1 + R_4) + (C_1 + C_2 + C_3 + C_{\text{load1}})R_1 \\
T_3 &= (C_6 + C_{\text{load3}})(R_1 + R_4 + R_6) + C_4(R_1 + R_4) + \\
&\quad +(C_1 + C_2 + C_3 + C_{\text{load1}})R_1 + (C_5 + C_{\text{load2}})(R_1 + R_4).
\end{aligned}
$$

Our main interest is in the maximum of these delays,

$$
T = \max\{T_1, T_2, T_3\}.
$$

(a) Explain how to find the optimal trade-off curve between area $A$ and delay $T$.

(b) *Optimal area-delay sizing.* For the specific problem parameters given, plot the area-delay trade-off curve, together with the individual Elmore delays. Comment on the results you obtain.

(c) *The simple method.* Plot the area-delay trade-off obtained when you assign all wire widths to be the same width (which varies between $W_{\min}$ and $W_{\max}$). Compare this curve to the optimal one, obtained in part (b). How much better does the optimal method do than the simple method? *Note:* for a large circuit, say with 1000 wires to size, the difference is *far larger*.

For this problem you can use the CVX in GP mode. We've also made available the function `elm_del_example.m`, which evaluates the three delays, given the widths of the wires.

**14.2** *Optimal sizing of power and ground trees.* We consider a system or VLSI device with many subsystems or subcircuits, each of which needs one or more power supply voltages. In this problem we consider the case where the power supply network has a tree topology with the power supply (or external pin connection) at the root. Each node of the tree is connected to some subcircuit that draws power.

We model the power supply as a constant voltage source with value $V$. The $m$ subcircuits are modeled as current sources that draw currents $i_1(t), \ldots, i_m(t)$ from the node (to ground) (see the figure below).



The subcircuit current draws have two components:

$$i_k(t) = i_k^{\mathrm{dc}} + i_k^{\mathrm{ac}}(t)$$

where $i_k^{\mathrm{dc}}$ is the DC current draw (which is a positive constant), and $i_k^{\mathrm{ac}}(t)$ is the AC draw (which has zero average value). We characterize the AC current draw by its RMS value, defined as

$$\mathrm{RMS}(i_k^{\mathrm{ac}}) = \left( \lim_{T \to \infty} \frac{1}{T} \int_0^T i_k^{\mathrm{ac}}(t)^2 \, dt \right)^{1/2}.$$

For each subcircuit we are given maximum values for the DC and RMS AC currents draws, $i.e.$, constants $I_k^{\mathrm{dc}}$ and $I_k^{\mathrm{ac}}$ such that

$$0 \le i_k^{\mathrm{dc}} \le I_k^{\mathrm{dc}}, \qquad \mathrm{RMS}(i_k^{\mathrm{ac}}) \le I_k^{\mathrm{ac}}. \tag{58}$$

The $n$ wires that form the distribution network are modeled as resistors $R_k$ (which, presumably, have small value). (Since the circuit has a tree topology, we can use the following labeling convention: node $k$ and the current source $i_k(t)$ are immediately following resistor $R_k$.) The resistance of the wires is given by

$$R_i = \alpha l_i / w_i,$$

where $\alpha$ is a constant and $l_i$ are the lengths of the wires, which are known and fixed. The variables in the problem are the width of the wires, $w_1, \ldots, w_n$. Obviously by making the wires very wide, the resistances become very low, and we have a nearly ideal power network. The purpose of this problem is to optimally select wire widths, to minimize area while meeting certain specfications. Note that in this problem we ignore dynamics, $i.e.$, we do not model the capacitance or inductance of the wires.

As a result of the current draws and the nonzero resistance of the wires, the voltage at node $k$ (which supplies subcircuit $k$) has a DC value less than the supply voltage, and also an AC voltage (which is called power supply ripple or noise). By superposition these two effects can be analyzed separately.

- The DC voltage drop $V - v_k^{\text{dc}}$ at node $k$ is equal to the sum of the voltage drops across wires on the (unique) path from node $k$ to the root. It can be expressed as

$$V - v_k^{\text{dc}} = \sum_{j=1}^{m} i_j^{\text{dc}} \sum_{i \in \mathcal{N}(j,k)} R_i, \tag{59}$$

where $\mathcal{N}(j,k)$ consists of the indices of the branches upstream from nodes $j$ and $k$, i.e., $i \in \mathcal{N}(j,k)$ if and only if $R_i$ is in the path from node $j$ to the root and in the path from node $k$ to the root.

- The power supply noise at a node can be found as follows. The AC voltage at node $k$ is equal to

$$v_k^{\text{ac}}(t) = -\sum_{j=1}^{m} i_j^{\text{ac}}(t) \sum_{i \in \mathcal{N}(j,k)} R_i.$$

We assume the AC current draws are independent, so the RMS value of $v_k^{\text{ac}}(t)$ is given by the squareroot of the sum of the squares of the RMS value of the ripple due to each other node, i.e.,

$$\text{RMS}(v_k^{\text{ac}}) = \left( \sum_{j=1}^{m} \left( \text{RMS}(i_j^{\text{ac}}) \sum_{i \in \mathcal{N}(j,k)} R_i \right)^2 \right)^{1/2}. \tag{60}$$

The problem is to choose wire widths $w_i$ that minimize the total wire area $\sum_{i=k}^{n} w_k l_k$ subject to the following specifications:

- maximum allowable DC voltage drop at each node:

$$V - v_k^{\text{dc}} \leq V_{\text{max}}^{\text{dc}}, \quad k = 1, \ldots, m, \tag{61}$$

where $V - v_k^{\text{dc}}$ is given by (59), and $V_{\text{max}}^{\text{dc}}$ is a given constant.

- maximum allowable power supply noise at each node:

$$\text{RMS}(v_k^{\text{ac}}) \leq V_{\text{max}}^{\text{ac}}, \quad k = 1, \ldots, m, \tag{62}$$

where $\text{RMS}(v_k^{\text{ac}})$ is given by (60), and $V_{\text{max}}^{\text{ac}}$ is a given constant.

- upper and lower bounds on wire widths:

$$w_{\text{min}} \leq w_i \leq w_{\text{max}}, \quad i = 1, \ldots, n, \tag{63}$$

where $w_{\text{min}}$ and $w_{\text{max}}$ are given constants.

- maximum allowable DC current density in a wire:

$$\left( \sum_{j \in \mathcal{M}(k)} i_j^{\text{dc}} \right) \Big/ w_k \leq \rho_{\text{max}}, \quad k = 1, \ldots, n, \tag{64}$$

where $\mathcal{M}(k)$ is the set of all indices of nodes downstream from resistor $k$, i.e., $j \in \mathcal{M}(k)$ if and only if $R_k$ is in the path from node $j$ to the root, and $\rho_{\text{max}}$ is a given constant.

163

- maximum allowable total DC power dissipation in supply network:

$$\sum_{k=1}^{n} R_k \left( \sum_{j \in \mathcal{M}(k)} i_j^{\text{dc}} \right)^2 \le P_{\text{max}}, \tag{65}$$

where $P_{\text{max}}$ is a given constant.

These specifications must be satisfied for all possible $i_k(t)$ that satisfy (58).

Formulate this as a convex optimization problem in the standard form

$$\begin{array}{ll} \text{minimize} & f_0(x) \\ \text{subject to} & f_i(x) \le 0, \quad i = 1, \ldots, p \\ & Ax = b. \end{array}$$

You may introduce new variables, or use a change of variables, but you must say very clearly

- what the optimization variable $x$ is, and how it corresponds to the problem variables $w$ (*i.e.*, is $x$ equal to $w$, does it include auxiliary variables, ...?)

- what the objective $f_0$ and the constraint functions $f_i$ are, and how they relate to the objectives and specifications of the problem description

- why the objective and constraint functions are convex

- what $A$ and $b$ are (if applicable).

**14.3** *Optimal amplifier gains.* We consider a system of $n$ amplifiers connected (for simplicity) in a chain, as shown below. The variables that we will optimize over are the gains $a_1, \ldots, a_n > 0$ of the amplifiers. The first specification is that the overall gain of the system, *i.e.*, the product $a_1 \cdots a_n$, is equal to $A^{\text{tot}}$, which is given.



We are concerned about two effects: noise generated by the amplifiers, and amplifier overload. These effects are modeled as follows.

We first describe how the noise depends on the amplifier gains. Let $N_i$ denote the noise level (RMS, or root-mean-square) at the output of the $i$th amplifier. These are given recursively as

$$N_0 = 0, \quad N_i = a_i \left( N_{i-1}^2 + \alpha_i^2 \right)^{1/2}, \quad i = 1, \ldots, n$$

where $\alpha_i > 0$ (which is given) is the ('input-referred') RMS noise level of the $i$th amplifier. The *output noise level* $N_{\text{out}}$ of the system is given by $N_{\text{out}} = N_n$, *i.e.*, the noise level of the last amplifier. Evidently $N_{\text{out}}$ depends on the gains $a_1, \ldots, a_n$.

Now we describe the amplifier overload limits. $S_i$ will denote the signal level at the output of the $i$th amplifier. These signal levels are related by

$$S_0 = S_{\text{in}}, \qquad S_i = a_i S_{i-1}, \quad i = 1, \ldots, n,$$

where $S_{\text{in}} > 0$ is the *input signal level*. Each amplifier has a maximum allowable output level $M_i > 0$ (which is given). (If this level is exceeded the amplifier will distort the signal.) Thus we have the constraints $S_i \leq M_i$, for $i = 1, \ldots, n$. (We can ignore the noise in the overload condition, since the signal levels are much larger than the noise levels.)

The *maximum output signal level* $S_{\text{max}}$ is defined as the maximum value of $S_n$, over all input signal levels $S_{\text{in}}$ that respect the the overload constraints $S_i \leq M_i$. Of course $S_{\text{max}} \leq M_n$, but it can be smaller, depending on the gains $a_1, \ldots, a_n$.

The *dynamic range D* of the system is defined as $D = S_{\text{max}}/N_{\text{out}}$. Evidently it is a (rather complicated) function of the amplifier gains $a_1, \ldots, a_n$.

The goal is to choose the gains $a_i$ to maximize the dynamic range $D$, subject to the constraint $\prod_i a_i = A^{\text{tot}}$, and upper bounds on the amplifier gains, $a_i \leq A_i^{\text{max}}$ (which are given).

Explain how to solve this problem as a convex (or quasiconvex) optimization problem. If you introduce new variables, or transform the variables, explain. Clearly give the objective and inequality constraint functions, explaining why they are convex if it is not obvious. If your problem involves equality constraints, give them explicitly.

Carry out your method on the specific instance with $n = 4$, and data

$$
\begin{aligned}
A^{\text{tot}} &= 10000, \\
\alpha &= (10^{-5}, 10^{-2}, 10^{-2}, 10^{-2}), \\
M &= (0.1, 5, 10, 10), \\
A^{\text{max}} &= (40, 40, 40, 20).
\end{aligned}
$$

Give the optimal gains, and the optimal dynamic range.

**14.4** *Blending existing circuit designs.* In circuit design, we must select the widths of a set of $n$ components, given by the vector $w = (w_1, \ldots, w_n)$, which must satisfy width limits

$$W^{\text{min}} \leq w_i \leq W^{\text{max}}, \quad i = 1, \ldots, n,$$

where $W^{\text{min}}$ and $W^{\text{max}}$ are given (positive) values. (You can assume there are no other constraints on $w$.) The design is judged by three objectives, each of which we would like to be small: the circuit power $P(w)$, the circuit delay $D(w)$, and the total circuit area $A(w)$. These three objectives are (complicated) posynomial functions of $w$.

You *do not know* the functions $P$, $D$, or $A$. (That is, you do not know the coefficients or exponents in the posynomial expressions.) You *do know* a set of $k$ designs, given by $w^{(1)}, \ldots, w^{(k)} \in \mathbf{R}^n$, and their associated objective values

$$P(w^{(j)}), \quad D(w^{(j)}), \quad A(w^{(j)}), \quad j = 1, \ldots, k.$$

You can assume that these designs satisfy the width limits. The goal is to find a design $w$ that satisfies the width limits, and the design specifications

$$P(w) \leq P_{\text{spec}}, \quad D(w) \leq D_{\text{spec}}, \quad A(w) \leq A_{\text{spec}},$$

where $P_{\text{spec}}$, $D_{\text{spec}}$, and $A_{\text{spec}}$ are given.

Now consider the specific data given in `blend_design_data.*`. Give the following.

- A feasible design (*i.e.*, $w$) that satisfies the specifications.
- A clear argument as to how you know that your design satisfies the specifications, even though you do not know the formulas for $P$, $D$, and $A$.
- Your method for finding $w$, including any code that you write.

*Hints/comments.*

- You do not need to know *anything* about circuit design to solve this problem.
- See the title of this problem.

**14.5** *Solving nonlinear circuit equations using convex optimization.* An electrical circuit consists of $b$ two-terminal devices (or branches) connected to $n$ nodes, plus a so-called ground node. The goal is to compute several sets of physical quantities that characterize the circuit operation. The vector of *branch voltages* is $v \in \mathbf{R}^b$, where $v_j$ is the voltage appearing across device $j$. The vector of *branch currents* is $i \in \mathbf{R}^b$, where $i_j$ is the current flowing through device $j$. (The symbol $i$, which is often used to denote an index, is unfortunately the standard symbol used to denote current.) The vector of *node potentials* is $e \in \mathbf{R}^n$, where $e_k$ is the potential of node $k$ with respect to the ground node. (The ground node has potential zero by definition.)

The circuit variables $v$, $i$, and $e$ satisfy several physical laws. Kirchhoff's current law (KCL) can be expressed as $Ai = 0$, and Kirchhoff's voltage law (KVL) can be expressed as $v = A^T e$, where $A \in \mathbf{R}^{n \times b}$ is the reduced incidence matrix, which describes the circuit topology:

$$A_{kj} = \begin{cases} -1 & \text{branch } j \text{ enters node } k \\ +1 & \text{branch } j \text{ leaves node } k \\ 0 & \text{otherwise,} \end{cases}$$

for $k = 1, \ldots, n$, $j = 1, \ldots, b$. (KCL states that current is conserved at each node, and KVL states that the voltage across each branch is the difference of the potentials of the nodes it is connected to.)

The branch voltages and currents are related by

$$v_j = \phi_j(i_j), \quad j = 1, \ldots, b,$$

where $\phi_j$ is a given function that depends on the *type* of device $j$. We will assume that these functions are continuous and nondecreasing. We give a few examples. If device $j$ is a resistor with resistance $R_j > 0$, we have $\phi_j(i_j) = R_j i_j$ (which is called Ohm's law). If device $j$ is a voltage source with voltage $V_j$ and internal resistance $r_j > 0$, we have $\phi_j(i_j) = V_j + r_j i_j$. And for a more interesting example, if device $j$ is a diode, we have $\phi_j(i_j) = V_T \log(1 + i_j/I_S)$, where $I_S$ and $V_T$ are known positive constants.

(a) Find a method to solve the circuit equations, *i.e.*, find $v$, $i$, and $e$ that satisfy KCL, KVL, and the branch equations, that relies on convex optimization. State the optimization problem clearly, indicating what the variables are. Be sure to explain how solving the convex optimization problem you propose leads to choices of the circuit variables that satisfy all of the circuit

equations. You can assume that no pathologies occur in the problem that you propose, for example, it is feasible, a suitable constraint qualification holds, and so on.

*Hint.* You might find the function $\psi : \mathbf{R}^b \to \mathbf{R}$,

$$\psi(i_1,\ldots,i_b) = \sum_{j=1}^{b} \int_0^{i_j} \phi_j(u_j) \, du_j,$$

useful.

(b) Consider the circuit shown in the diagram below. Device 1 is a voltage source with parameters $V_1 = 1000$, $r_1 = 1$. Devices 2 and 5 are resistors with resistance $R_2 = 1000$, and $R_5 = 100$ respectively. Devices 3 and 4 are identical diodes with parameters $V_T = 26$, $I_S = 1$. (The units are mV, mA, and $\Omega$.)

The nodes are labeled $N_1, N_2$, and $N_3$; the ground node is at the bottom. The incidence matrix $A$ is

$$A = \begin{bmatrix} 1 & 1 & 0 & 0 & 0 \\ 0 & -1 & 1 & 1 & 0 \\ 0 & 0 & 0 & -1 & 1 \end{bmatrix}.$$

(The reference direction for each edge is down or to the right.)

Use the method in part (a) to compute $v$, $i$, and $e$. Verify that all the circuit equations hold.

# 15 Signal processing and communications

**15.1** *FIR low-pass filter design.* Consider the (symmetric, linear phase) finite impulse response (FIR) filter described by its frequency response

$$H(\omega) = a_0 + \sum_{k=1}^{N} a_k \cos k\omega,$$

where $\omega \in [0, \pi]$ is the frequency. The design variables in our problems are the real coefficients $a = (a_0, \ldots, a_N) \in \mathbf{R}^{N+1}$, where $N$ is called the order or length of the FIR filter. In this problem we will explore the design of a low-pass filter, with specifications:

- For $0 \le \omega \le \pi/3$, $0.89 \le H(\omega) \le 1.12$, *i.e.*, the filter has about $\pm 1\text{dB}$ ripple in the 'passband' $[0, \pi/3]$.

- For $\omega_c \le \omega \le \pi$, $|H(\omega)| \le \alpha$. In other words, the filter achieves an attenuation given by $\alpha$ in the 'stopband' $[\omega_c, \pi]$. Here $\omega_c$ is called the filter 'cutoff frequency'.

(It is called a low-pass filter since low frequencies are allowed to pass, but frequencies above the cutoff frequency are attenuated.) These specifications are depicted graphically in the figure below.



For parts (a)–(c), explain how to formulate the given problem as a convex or quasiconvex optimization problem.

(a) *Maximum stopband attenuation.* We fix $\omega_c$ and $N$, and wish to maximize the stopband attenuation, *i.e.*, minimize $\alpha$.

(b) *Minimum transition band.* We fix $N$ and $\alpha$, and want to minimize $\omega_c$, *i.e.*, we set the stopband attenuation and filter length, and wish to minimize the 'transition' band (between $\pi/3$ and $\omega_c$).

(c) *Shortest length filter.* We fix $\omega_c$ and $\alpha$, and wish to find the smallest $N$ that can meet the specifications, *i.e.*, we seek the shortest length FIR filter that can meet the specifications.

(d) *Numerical filter design.* Use CVX to find the shortest length filter that satisfies the filter specifications with

$$\omega_c = 0.4\pi, \quad \alpha = 0.0316.$$

(The attenuation corresponds to $-30$dB.) For this subproblem, you may sample the constraints in frequency, which means the following. Choose $K$ large (say, 500; an old rule of thumb is that $K$ should be at least $15N$), and set $\omega_k = k\pi/K$, $k = 0, \ldots, K$. Then replace the specifications with

- For $k$ with $0 \le \omega_k \le \pi/3$, $0.89 \le H(\omega_k) \le 1.12$.
- For $k$ with $\omega_c \le \omega_k \le \pi$, $|H(\omega_k)| \le \alpha$.

Plot $H(\omega)$ versus $\omega$ for your design.

**15.2** *SINR maximization.* Solve the following instance of problem 4.20: We have $n = 5$ transmitters, grouped into two groups: $\{1, 2\}$ and $\{3, 4, 5\}$. The maximum power for each transmitter is 3, the total power limit for the first group is 4, and the total power limit for the second group is 6. The noise $\sigma$ is equal to 0.5 and the limit on total received power is 5 for each receiver. Finally, the path gain matrix is given by

$$G = \begin{bmatrix} 1.0 & 0.1 & 0.2 & 0.1 & 0.0 \\ 0.1 & 1.0 & 0.1 & 0.1 & 0.0 \\ 0.2 & 0.1 & 2.0 & 0.2 & 0.2 \\ 0.1 & 0.1 & 0.2 & 1.0 & 0.1 \\ 0.0 & 0.0 & 0.2 & 0.1 & 1.0 \end{bmatrix}.$$

Find the transmitter powers $p_1, \ldots, p_5$ that maximize the minimum SINR ratio over all receivers. Also report the maximum SINR value. Solving the problem to an accuracy of 0.05 (in SINR) is fine.

*Hint.* When implementing a bisection method in CVX, you will need to check feasibility of a convex problem. You can do this using `strcmpi(cvx_status, 'Solved')`.

**15.3** *Power control for sum rate maximization in interference channel.* We consider the optimization problem

$$\begin{array}{ll} \text{maximize} & \displaystyle\sum_{i=1}^{n} \log\left(1 + \frac{p_i}{\sum_{j\neq i} A_{ij}p_j + v_i}\right) \\ \text{subject to} & \displaystyle\sum_{i=1}^{n} p_i = 1 \\ & p_i \ge 0, \quad i = 1, \ldots, n \end{array}$$

with variables $p \in \mathbf{R}^n$. The problem data are the matrix $A \in \mathbf{R}^{n \times n}$ and the vector $v \in \mathbf{R}^n$. We assume $A$ and $v$ are componentwise nonnegative ($A_{ij} \ge 0$ and $v_i \ge 0$), and that the diagonal elements of $A$ are equal to one. If the off-diagonal elements of $A$ are zero ($A = I$), the problem has a simple solution, given by the waterfilling method. We are interested in the case where the off-diagonal elements are nonzero.

We can give the following interpretation of the problem, which is not needed below. The variables in the problem are the transmission powers in a communications system. We limit the total power to one (for simplicity; we could have used any other number). The $i$th term in the objective is

the Shannon capacity of the $i$th channel; the fraction in the argument of the log is the signal to interference plus noise ratio.

We can express the problem as

$$
\begin{aligned}
\text{maximize} \quad & \sum_{i=1}^{n} \log\left( \frac{\sum_{j=1}^{n} B_{ij} p_j}{\sum_{j=1}^{n} B_{ij} p_j - p_i} \right) \\
\text{subject to} \quad & \sum_{i=1}^{n} p_i = 1 \\
& p_i \geq 0, \quad i = 1, \ldots, n,
\end{aligned}
\tag{66}
$$

where $B \in \mathbf{R}^{n \times n}$ is defined as $B = A + v\mathbf{1}^T$, i.e., $B_{ij} = A_{ij} + v_i$, $i, j = 1, \ldots, n$. Suppose $B$ is nonsingular and

$$
B^{-1} = I - C
$$

with $C_{ij} \geq 0$. Express the problem above as a convex optimization problem. *Hint.* Use $y = Bp$ as variables.

**15.4** *Radio-relay station placement and power allocation.* Radio relay stations are to be located at positions $x_1, \ldots, x_n \in \mathbf{R}^2$, and transmit at power $p_1, \ldots, p_n \geq 0$. In this problem we will consider the problem of simultaneously deciding on good locations *and* operating powers for the relay stations.

The received signal power $S_{ij}$ at relay station $i$ from relay station $j$ is proportional to the transmit power and inversely proportional to the distance, *i.e.*,

$$
S_{ij} = \frac{\alpha p_j}{\|x_i - x_j\|^2},
$$

where $\alpha > 0$ is a known constant.

Relay station $j$ must transmit a signal to relay station $i$ at the rate (or bandwidth) $R_{ij} \geq 0$ bits per second; $R_{ij} = 0$ means that relay station $j$ does not need to transmit any message (directly) to relay station $i$. The matrix of bit rates $R_{ij}$ is given. Although it doesn't affect the problem, $R$ would likely be sparse, *i.e.*, each relay station needs to communicate with only a few others.

To guarantee accurate reception of the signal from relay station $j$ to $i$, we must have

$$
S_{ij} \geq \beta R_{ij},
$$

where $\beta > 0$ is a known constant. (In other words, the minimum allowable received signal power is proportional to the signal bit rate or bandwidth.)

The relay station positions $x_{r+1}, \ldots, x_n$ are fixed, *i.e.*, problem parameters. The problem variables are $x_1, \ldots, x_r$ and $p_1, \ldots, p_n$. The goal is to choose the variables to minimize the total transmit power, *i.e.*, $p_1 + \cdots + p_n$.

Explain how to solve this problem as a convex or quasiconvex optimization problem. If you introduce new variables, or transform the variables, explain. Clearly give the objective and inequality constraint functions, explaining why they are convex. If your problem involves equality constraints, express them using an affine function.

**15.5** *Power allocation with coherent combining receivers.* In this problem we consider a variation on the power allocation problem described on pages 4-13 and 4-14 of the notes. In that problem we have $m$ transmitters, each of which transmits (broadcasts) to $n$ receivers, so the total number of receivers is $mn$. In this problem we have the converse: multiple transmitters send a signal to each receiver.

More specifically we have $m$ receivers labeled $1, \ldots, m$, and $mn$ transmitters labeled $(j, k)$, $j = 1, \ldots, m$, $k = 1, \ldots, n$. The transmitters $(i, 1), \ldots, (i, n)$ all transmit the same message to the receiver $i$, for $i = 1, \ldots, m$.

Transmitter $(j, k)$ operates at power $p_{jk}$, which must satisfy $0 \le p_{jk} \le P_{\max}$, where $P_{\max}$ is a given maximum allowable transmitter power.

The path gain from transmitter $(j, k)$ to receiver $i$ is $A_{ijk} > 0$ (which are given and known). Thus the power received at receiver $i$ from transmitter $(j, k)$ is given by $A_{ijk} p_{jk}$.

For $i \ne j$, the received power $A_{ijk} p_{jk}$ represents an interference signal. The total interference-plus-noise power at receiver $i$ is given by

$$I_i = \sum_{j \ne i,\ k=1,\ldots,n} A_{ijk} p_{jk} + \sigma$$

where $\sigma > 0$ is the known, given (self) noise power of the receivers. Note that the *powers* of the interference and noise signals add to give the total interference-plus-noise power.

The receivers use *coherent detection and combining* of the desired message signals, which means the effective received signal power at receiver $i$ is given by

$$S_i = \left( \sum_{k=1,\ldots,n} (A_{iik} p_{ik})^{1/2} \right)^2.$$

(Thus, the *amplitudes* of the desired signals add to give the effective signal amplitude.)

The total signal to interference-plus-noise ratio (SINR) for receiver $i$ is given by $\gamma_i = S_i / I_i$.

The problem is to choose transmitter powers $p_{jk}$ that maximize the minimum SINR $\min_i \gamma_i$, subject to the power limits.

Explain in detail how to solve this problem using convex or quasiconvex optimization. If you transform the problem by using a different set of variables, explain completely. Identify the objective function, and all constraint functions, indicating if they are convex or quasiconvex, etc.

**15.6** *Antenna array weight design.* We consider an array of $n$ omnidirectional antennas in a plane, at positions $(x_k, y_k)$, $k = 1, \ldots, n$.

A unit plane wave with frequency $\omega$ is incident from an angle $\theta$. This incident wave induces in the $k$th antenna element a (complex) signal $\exp(i(x_k \cos\theta + y_k \sin\theta - \omega t))$, where $i = \sqrt{-1}$. (For simplicity we assume that the spatial units are normalized so that the wave number is one, *i.e.*, the wavelength is $\lambda = 2\pi$.) This signal is demodulated, *i.e.*, multiplied by $e^{i\omega t}$, to obtain the baseband signal (complex number) $\exp(i(x_k \cos\theta + y_k \sin\theta))$. The baseband signals of the $n$ antennas are combined linearly to form the output of the antenna array

$$
\begin{aligned}
G(\theta) &= \sum_{k=1}^{n} w_k \, e^{i(x_k \cos\theta + y_k \sin\theta)} \\
&= \sum_{k=1}^{n} \left( w_{\mathrm{re},k} \cos\gamma_k(\theta) - w_{\mathrm{im},k} \sin\gamma_k(\theta) \right) + i \left( w_{\mathrm{re},k} \sin\gamma_k(\theta) + w_{\mathrm{im},k} \cos\gamma_k(\theta) \right),
\end{aligned}
$$

if we define $\gamma_k(\theta) = x_k \cos\theta + y_k \sin\theta$. The complex weights in the linear combination,

$$
w_k = w_{\mathrm{re},k} + i w_{\mathrm{im},k}, \quad k = 1, \ldots, n,
$$

are called the *antenna array coefficients* or *shading coefficients*, and will be the design variables in the problem. For a given set of weights, the combined output $G(\theta)$ is a function of the angle of arrival $\theta$ of the plane wave. The design problem is to select weights $w_i$ that achieve a desired directional pattern $G(\theta)$.

We now describe a basic weight design problem. We require unit gain in a target direction $\theta^{\mathrm{tar}}$, *i.e.*, $G(\theta^{\mathrm{tar}}) = 1$. We want $|G(\theta)|$ small for $|\theta - \theta^{\mathrm{tar}}| \geq \Delta$, where $2\Delta$ is our beamwidth. To do this, we can minimize

$$
\max_{|\theta - \theta^{\mathrm{tar}}| \geq \Delta} |G(\theta)|,
$$

where the maximum is over all $\theta \in [-\pi, \pi]$ with $|\theta - \theta^{\mathrm{tar}}| \geq \Delta$. This number is called the sidelobe level for the array; our goal is to minimize the sidelobe level. If we achieve a small sidelobe level, then the array is relatively insensitive to signals arriving from directions more than $\Delta$ away from the target direction. This results in the optimization problem

$$
\begin{array}{ll}
\text{minimize} & \max_{|\theta - \theta^{\mathrm{tar}}| \geq \Delta} |G(\theta)| \\
\text{subject to} & G(\theta^{\mathrm{tar}}) = 1,
\end{array}
$$

with $w \in \mathbf{C}^n$ as variables.

The objective function can be approximated by discretizing the angle of arrival with (say) $N$ values (say, uniformly spaced) $\theta_1, \ldots, \theta_N$ over the interval $[-\pi, \pi]$, and replacing the objective with

$$
\max\{ |G(\theta_k)| \mid |\theta_k - \theta^{\mathrm{tar}}| \geq \Delta \}
$$

(a) Formulate the antenna array weight design problem as an SOCP.

(b) Solve an instance using CVX, with $n = 40$, $\theta^{\mathrm{tar}} = 15°$, $\Delta = 15°$, $N = 400$, and antenna positions generated using

```
rand('state',0);
n = 40;
x = 30 * rand(n,1);
y = 30 * rand(n,1);
```

Compute the optimal weights and make a plot of $|G(\theta)|$ (on a logarithmic scale) versus $\theta$. *Hint.* CVX can directly handle complex variables, and recognizes the modulus `abs(x)` of a complex number as a convex function of its real and imaginary parts, so you do not need to explicitly form the SOCP from part (a). Even more compactly, you can use `norm(x,Inf)` with complex argument.

**15.7** *Power allocation problem with analytic solution.* Consider a system of $n$ transmitters and $n$ receivers. The $i$th transmitter transmits with power $x_i$, $i = 1, \ldots, n$. The vector $x$ will be the variable in this problem. The path gain from each transmitter $j$ to each receiver $i$ will be denoted $A_{ij}$ and is assumed to be known (obviously, $A_{ij} \geq 0$, so the matrix $A$ is elementwise nonnegative, and $A_{ii} > 0$). The signal received by each receiver $i$ consists of three parts: the desired signal, arriving from transmitter $i$ with power $A_{ii}x_i$, the interfering signal, arriving from the other receivers with power $\sum_{j \neq i} A_{ij}x_j$, and noise $\beta_i$ (which are positive and known). We are interested in allocating the powers $x_i$ in such a way that the signal to noise plus interference ratio at each of the receivers exceeds a level $\alpha$. (Thus $\alpha$ is the minimum acceptable SNIR for the receivers; a typical value might be around $\alpha = 3$, *i.e.*, around 10dB). In other words, we want to find $x \succeq 0$ such that for $i = 1, \ldots, n$

$$A_{ii}x_i \geq \alpha \left( \sum_{j \neq i} A_{ij}x_j + \beta_i \right).$$

Equivalently, the vector $x$ has to satisfy

$$x \succeq 0, \quad Bx \succeq \alpha\beta \tag{67}$$

where $B \in \mathbf{R}^{n \times n}$ is defined as

$$B_{ii} = A_{ii}, \quad B_{ij} = -\alpha A_{ij}, \quad j \neq i.$$

(a) Show that (67) is feasible if and only if $B$ is invertible and $z = B^{-1}\mathbf{1} \succeq 0$ ($\mathbf{1}$ is the vector with all components 1). Show how to construct a feasible power allocation $x$ from $z$.

(b) Show how to find the largest possible SNIR, *i.e.*, how to maximize $\alpha$ subject to the existence of a feasible power allocation.

To solve this problem you may need the following:

*Hint.* Let $T \in \mathbf{R}^{n \times n}$ be a matrix with nonnegative elements, and $s \in \mathbf{R}$. Then the following are equivalent:

(a) $s > \rho(T)$, where $\rho(T) = \max_i |\lambda_i(T)|$ is the spectral radius of $T$.

(b) $sI - T$ is nonsingular and the matrix $(sI - T)^{-1}$ has nonnegative elements.

(c) there exists an $x \succeq 0$ with $(sI - T)x \succ 0$.

(For such $s$, the matrix $sI - T$ is called a *nonsingular M-matrix*.)

*Remark.* This problem gives an analytic solution to a very special form of transmitter power allocation problem. Specifically, there are exactly as many transmitters as receivers, and no power limits on the transmitters. One consequence is that the receiver noises $\beta_i$ play no role at all in the solution — just crank up all the transmitters to overpower the noises!

**15.8** *Optimizing rates and time slot fractions.* We consider a wireless system that uses time-domain multiple access (TDMA) to support $n$ communication flows. The flows have (nonnegative) rates $r_1, \ldots, r_n$, given in bits/sec. To support a rate $r_i$ on flow $i$ requires transmitter power

$$p = a_i(e^{br} - 1),$$

where $b$ is a (known) positive constant, and $a_i$ are (known) positive constants related to the noise power and gain of receiver $i$.

TDMA works like this. Time is divided up into periods of some fixed duration $T$ (seconds). Each of these $T$-long periods is divided into $n$ time-slots, with durations $t_1, \ldots, t_n$, that must satisfy $t_1 + \cdots + t_n = T$, $t_i \geq 0$. In time-slot $i$, communications flow $i$ is transmitted at an instantaneous rate $r = Tr_i/t_i$, so that over each $T$-long period, $Tr_i$ bits from flow $i$ are transmitted. The power required during time-slot $i$ is $a_i(e^{bTr_i/t_i} - 1)$, so the average transmitter power over each $T$-long period is

$$P = (1/T)\sum_{i=1}^{n} a_i t_i (e^{bTr_i/t_i} - 1).$$

When $t_i$ is zero, we take $P = \infty$ if $r_i > 0$, and $P = 0$ if $r_i = 0$. (The latter corresponds to the case when there is zero flow, and also, zero time allocated to the flow.)

The problem is to find rates $r \in \mathbf{R}^n$ and time-slot durations $t \in \mathbf{R}^n$ that maximize the log utility function

$$U(r) = \sum_{i=1}^{n} \log r_i,$$

subject to $P \leq P^{\mathrm{max}}$. (This utility function is often used to ensure 'fairness'; each communication flow gets at least some positive rate.) The problem data are $a_i$, $b$, $T$ and $P^{\mathrm{max}}$; the variables are $t_i$ and $r_i$.

(a) Formulate this problem as a convex optimization problem. Feel free to introduce new variables, if needed, or to change variables. Be sure to justify convexity of the objective or constraint functions in your formulation.

(b) Give the optimality conditions for your formulation. Of course we prefer simpler optimality conditions to complex ones. *Note:* We do not expect you to *solve* the optimality conditions; you can give them as a set of equations (and possibly inequalities).

*Hint.* With a log utility function, we cannot have $r_i = 0$, and therefore we cannot have $t_i = 0$; therefore the constraints $r_i \geq 0$ and $t_i \geq 0$ cannot be active or tight. This will allow you to simplify the optimality conditions.

**15.9** *Optimal jamming power allocation.* A set of $n$ jammers transmit with (nonnegative) powers $p_1, \ldots, p_n$, which are to be chosen subject to the constraints

$$p \succeq 0, \qquad Fp \preceq g.$$

The jammers produce interference power at $m$ receivers, given by

$$d_i = \sum_{j=1}^{n} G_{ij} p_j, \quad i = 1, \ldots, m,$$

174

where $G_{ij}$ is the (nonnegative) channel gain from jammer $j$ to receiver $i$.

Receiver $i$ has capacity (in bits/s) given by

$$C_i = \alpha \log(1 + \beta_i/(\sigma_i^2 + d_i)), \quad i = 1, \ldots, m,$$

where $\alpha$, $\beta_i$, and $\sigma_i$ are positive constants. (Here $\beta_i$ is proportional to the signal power at receiver $i$ and $\sigma_i^2$ is the receiver $i$ self-noise, but you won't need to know this to solve the problem.)

Explain how to choose $p$ to *minimize* the sum channel capacity, $C = C_1 + \cdots + C_m$, using convex optimization. (This corresponds to the most effective jamming, given the power constraints.) The problem data are $F$, $g$, $G$, $\alpha$, $\beta_i$, $\sigma_i$.

If you change variables, or transform your problem in any way that is not obvious (for example, you form a relaxation), you must explain fully how your method works, and why it gives the solution. If your method relies on any convex functions that we have not encountered before, you must show that the functions are convex.

*Disclaimer.* The teaching staff does not endorse jamming, optimal or otherwise.

**15.10** *2D filter design.* A symmetric convolution kernel with support $\{-(N-1), \ldots, N-1\}^2$ is characterized by $N^2$ coefficients

$$h_{kl}, \quad k, l = 1, \ldots, N.$$

These coefficients will be our variables. The corresponding 2D frequency response (Fourier transform) $H : \mathbf{R}^2 \to \mathbf{R}$ is given by

$$H(\omega_1, \omega_2) = \sum_{k,l=1,\ldots,N} h_{kl} \cos((k-1)\omega_1) \cos((l-1)\omega_2),$$

where $\omega_1$ and $\omega_2$ are the frequency variables. Evidently we only need to specify $H$ over the region $[0, \pi]^2$, although it is often plotted over the region $[-\pi, \pi]^2$. (It won't matter in this problem, but we should mention that the coefficients $h_{kl}$ above are not exactly the same as the impulse response coefficients of the filter.)

We will design a 2D filter (*i.e.*, find the coefficients $h_{kl}$) to satisfy $H(0,0) = 1$ and to minimize the maximum response $R$ in the rejection region $\Omega_{\mathrm{rej}} \subset [0, \pi]^2$,

$$R = \sup_{(\omega_1, \omega_2) \in \Omega_{\mathrm{rej}}} |H(\omega_1, \omega_2)|.$$

(a) Explain why this 2D filter design problem is convex.

(b) Find the optimal filter for the specific case with $N = 5$ and

$$\Omega_{\mathrm{rej}} = \{(\omega_1, \omega_2) \in [0, \pi]^2 \mid \omega_1^2 + \omega_2^2 \geq W^2\},$$

with $W = \pi/4$.

You can approximate $R$ by sampling on a grid of frequency values. Define

$$\omega^{(p)} = \pi(p-1)/M, \quad p = 1, \ldots, M.$$

(You can use $M = 25$.) We then replace the exact expression for $R$ above with

$$\hat{R} = \max\{|H(\omega^{(p)}, \omega^{(q)})| \mid p, q = 1, \ldots, M, \ (\omega^{(p)}, \omega^{(q)}) \in \Omega_{\mathrm{rej}}\}.$$

Give the optimal value of $\hat{R}$. Plot the optimal frequency response using `plot_2D_filt(h)`, available on the course web site, where `h` is the matrix containing the coefficients $h_{kl}$.

**15.11** *Maximizing log utility in a wireless system with interference.* Consider a wireless network consisting of $n$ data links, labeled $1, \ldots, n$. Link $i$ transmits with power $P_i > 0$, and supports a data rate $R_i = \log(1 + \gamma_i)$, where $\gamma_i$ is the signal-to-interference-plus-noise ratio (SINR). These SINR ratios depend on the transmit powers, as described below.

The system is characterized by the link gain matrix $G \in \mathbf{R}_{++}^{n \times n}$, where $G_{ij}$ is the gain from the transmitter on link $j$ to the receiver for link $i$. The received signal power for link $i$ is $G_{ii}P_i$; the noise plus interference power for link $i$ is given by

$$\sigma_i^2 + \sum_{j \neq i} G_{ij}P_j,$$

where $\sigma_i^2 > 0$ is the receiver noise power for link $i$. The SINR is the ratio

$$\gamma_i = \frac{G_{ii}P_i}{\sigma_i^2 + \sum_{j \neq i} G_{ij}P_j}.$$

The problem is to choose the transmit powers $P_1, \ldots, P_n$, subject to $0 < P_i \leq P_i^{\max}$, in order to maximize the log utility function

$$U(P) = \sum_{i=1}^{n} \log R_i.$$

(This utility function can be argued to yield a fair distribution of rates.) The data are $G$, $\sigma_i^2$, and $P_i^{\max}$.

Formulate this problem as a convex or quasiconvex optimization problem. If you make any transformations or use any steps that are not obvious, explain.

*Hints.*

- The function $\log \log(1 + e^x)$ is concave. (If you use this fact, you must show it.)
- You might find the new variables defined by $z_i = \log P_i$ useful.

**15.12** *Spectral factorization via semidefinite programming.* A Toeplitz matrix is a matrix that has constant values on its diagonals. We use the notation

$$T_m(x_1, \ldots, x_m) = \begin{bmatrix} x_1 & x_2 & x_3 & \cdots & x_{m-1} & x_m \\ x_2 & x_1 & x_2 & \cdots & x_{m-2} & x_{m-1} \\ x_3 & x_2 & x_1 & \cdots & x_{m-3} & x_{m-2} \\ \vdots & \vdots & \vdots & \ddots & \vdots & \vdots \\ x_{m-1} & x_{m-2} & x_{m-2} & \cdots & x_1 & x_2 \\ x_m & x_{m-1} & x_{m-2} & \cdots & x_2 & x_1 \end{bmatrix}$$

to denote the symmetric Toeplitz matrix in $\mathbf{S}^{m \times m}$ constructed from $x_1, \ldots, x_m$. Consider the semidefinite program

$$\begin{array}{ll} \text{minimize} & c^T x \\ \text{subject to} & T_n(x_1, \ldots, x_n) \succeq e_1 e_1^T, \end{array}$$

with variable $x = (x_1, \ldots, x_n)$, where $e_1 = (1, 0, \ldots, 0)$.

(a) Derive the dual of the SDP above. Denote the dual variable as $Z$. (Hence $Z \in \mathbf{S}^n$ and the dual constraints include an inequality $Z \succeq 0$.)

(b) Show that $T_n(x_1, \ldots, x_n) \succ 0$ for every feasible $x$ in the SDP above. You can do this by induction on $n$.

- For $n = 1$, the constraint is $x_1 \geq 1$ which obviously implies $x_1 > 0$.
- In the induction step, assume $n \geq 2$ and that $T_{n-1}(x_1, \ldots, x_{n-1}) \succ 0$. Use a Schur complement argument and the Toeplitz structure of $T_n$ to show that $T_n(x_1, \ldots, x_n) \succeq e_1 e_1^T$ implies $T_n(x_1, \ldots, x_n) \succ 0$.

(c) Suppose the optimal value of the SDP above is finite and attained, and that $Z$ is dual optimal. Use the result of part (b) to show that the rank of $Z$ is at most one, $i.e.$, $Z$ can be expressed as $Z = yy^T$ for some $n$-vector $y$. Show that $y$ satisfies

$$
\begin{aligned}
y_1^2 + y_2^2 + \cdots + y_n^2 &= c_1 \\
y_1 y_2 + y_2 y_3 + \cdots + y_{n-1} y_n &= c_2/2 \\
&\vdots \\
y_1 y_{n-1} + y_2 y_n &= c_{n-1}/2 \\
y_1 y_n &= c_n/2.
\end{aligned}
$$

This can be expressed as an identity $|Y(\omega)|^2 = R(\omega)$ between two functions

$$
\begin{aligned}
Y(\omega) &= y_1 + y_2 e^{-i\omega} + y_3 e^{-3i\omega} + \cdots + y_n e^{-i(n-1)\omega} \\
R(\omega) &= c_1 + c_2 \cos \omega + c_3 \cos(2\omega) + \cdots + c_n \cos((n-1)\omega)
\end{aligned}
$$

(with $i = \sqrt{-1}$). The function $Y(\omega)$ is called a *spectral factor* of the trigonometric polynomial $R(\omega)$.

**15.13** *Bandlimited signal recovery from zero-crossings.* Let $y \in \mathbf{R}^n$ denote a *bandlimited* signal, which means that it can be expressed as a linear combination of sinusoids with frequencies in a band:

$$
y_t = \sum_{j=1}^{B} a_j \cos\left(\frac{2\pi}{n}(f_{\min} + j - 1)t\right) + b_j \sin\left(\frac{2\pi}{n}(f_{\min} + j - 1)t\right), \quad t = 1, \ldots, n,
$$

where $f_{\min}$ is lowest frequency in the band, $B$ is the bandwidth, and $a, b \in \mathbf{R}^B$ are the cosine and sine coefficients, respectively. We are given $f_{\min}$ and $B$, but not the coefficients $a, b$ or the signal $y$.

We do not know $y$, but we are given its sign $s = \mathbf{sign}(y)$, where $s_t = 1$ if $y_t \geq 0$ and $s_t = -1$ if $y_t < 0$. (Up to a change of overall sign, this is the same as knowing the 'zero-crossings' of the signal, $i.e.$, when it changes sign. Hence the name of this problem.)

We seek an estimate $\hat{y}$ of $y$ that is consistent with the bandlimited assumption and the given signs. Of course we cannot distinguish $y$ and $\alpha y$, where $\alpha > 0$, since both of these signals have the same sign pattern. Thus, we can only estimate $y$ up to a positive scale factor. To normalize $\hat{y}$, we will require that $\|\hat{y}\|_1 = n$, $i.e.$, the average value of $|y_i|$ is one. Among all $\hat{y}$ that are consistent with the bandlimited assumption, the given signs, and the normalization, we choose the one that minimizes $\|\hat{y}\|_2$.

(a) Show how to find $\hat{y}$ using convex or quasiconvex optimization.

(b) Apply your method to the problem instance with data in `zero_crossings_data.*`. The data files also include the true signal $y$ (which of course you cannot use to find $\hat{y}$). Plot $\hat{y}$ and $y$, and report the relative recovery error, $\|y - \hat{y}\|_2/\|y\|_2$. Give one short sentence commenting on the quality of the recovery.

**15.14** *Wireless communication power optimization.* A wireless communication system consists of $n$ transmitters and $n$ receivers, where transmitter $i$ is meant to send information to receiver $i$. The variables to be chosen are the transmitter powers $p_i$, which are limited to the range $[p^{\min}, p^{\max}]$, where $p^{\min} > 0$. Receiver $i$ receives power $G_{ij}p_j$ from each transmitter $j$, where $G_{ij} \geq 0$ are known channel gains, with $G_{ii} > 0$. The signal power at receiver $i$ is $G_{ii}p_i$. Receiver $i$ also receives interference power $G_{ij}p_j$ from each of the other transmitters, *i.e.*, for $j \neq i$, and also has a self-noise given by $\sigma_i^2$. The total interference plus noise power at receiver $i$ is $\sigma_i^2 + \sum_{j \neq i} G_{ij}p_j$. The SINR (signal to interference and noise ratio) for receiver $i$ is

$$s_i = \frac{G_{ii}p_i}{\sigma_i^2 + \sum_{j \neq i} G_{ij}p_j}.$$

The SINR $s_i$ determines the data rate $R_i$ (in bits/sec) that receiver $i$ can receive, which has the form $R_i = \alpha \log(1 + s_i)$, where $\alpha$ is a known positive constant. We will use system objective $R = \min_i R_i$, *i.e.*, the minimum data rate of any of the $n$ receivers.

We wish to maximize $R$, while minimizing total system power $P = p_1 + \cdots + p_n$. This is a bi-objective problem.

(a) Explain how to compute the optimal trade-off curve of minimum rate $R$ versus total power $P$, using convex or quasiconvex optimization. (By computing the curve, we mean computing a number of Pareto optimal points.) If you change variables in your formulation, be sure to explain.

*Hint.* In addition to the usual scalarization, there are many ways to compute Pareto optimal points for the bi-criterion problem above.

(b) Find and plot the optimal trade-off curve for the problem instance with data given in `power_control_data.*`, with total power $P$ on the horizontal axis. (It is enough to compute a few tens of points on the Pareto curve. Be sure to check that the end-points of the Pareto curve make sense.)

**15.15** *Sparse blind deconvolution.* We are given a time series observation $y \in \mathbf{R}^T$, and seek a filter (convolution kernel) $w \in \mathbf{R}^k$, so that the convolution $x = w * y \in \mathbf{R}^{T+k-1}$ is sparse after truncating the first and last $k-1$ entries, *i.e.*, $x_{k:T} = (x_k, x_{k+1}, \ldots, x_T)$ is sparse. Here $*$ denotes convolution,

$$x_i = \sum_{j=1}^{k} w_j y_{i-j}, \quad i = 1, \ldots, T+k-1,$$

where we assume that $y_t = 0$ for $t \leq 0$. Typically we have $k \ll T$.

As a convex surrogate for sparsity of $x$, we minimize its $\ell_1$-norm, $\|x\|_1$. To preclude the trivial solution $w = 0$, we normalize $w$ by imposing the constraint $w_1 = 1$.

*Interpretations.* (These are not needed to solve the problem.) In signal processing dialect, we can say that $w$ is a filter which, when applied to the signal $y$, results in $x$, a simpler, sparse signal. As a second interpretation, we can say that $y = w^{-1} * x$, where $w^{-1}$ is the convolution inverse of $w$, defined as

$$w^{-1} = \mathcal{F}^{-1}(1/\mathcal{F}(w)),$$

where $\mathcal{F}$ is discrete Fourier transform at length $N = T + k$ and $\mathcal{F}^{-1}$ is its inverse transform. In this interpretation, we can say that we have decomposed the signal into the convolution of a sparse signal $x$ and a signal with short ($k$-long) inverse, $w^{-1}$.

Carry out blind deconvolution on the signal given in `blind_deconv_data.*`. This file also defines the kernel length $k$. Plot optimal $w$ and $x$, and also the given observation $y$. Also plot the inverse kernel $w^{-1}$, use the function `inverse_ker` that we provided in `blind_deconv_data.*`.

*Hint.* The function `conv(w,y)` is overloaded to work with CVX*.

**15.16** *Recovering a time series corrupted by late reporting.* We consider a scalar time series $y_1, \ldots, y_T$, where $y_t$ represents the total value of some quantity over time interval $t$. We will consider the case where the quantities are nonnegative, *i.e.*, $y_t \geq 0$.

Some of the raw data used to create the time series arrives late, causing it to be erroneously included in the total for the next period. Let $l_t$ be the total amount that arrives late, $t = 1, \ldots, T - 1$. That is, $l_t$ is the total amount that should have been reported in period $t$, but ended up being reported in period $t + 1$. With this late reporting, the time series we observe is $\tilde{y}_1, \ldots, \tilde{y}_T$, with

$$\tilde{y}_1 = y_1 - l_1, \qquad \tilde{y}_t = y_t - l_t + l_{t-1}, \quad t = 2, \ldots, T - 1, \qquad \tilde{y}_T = y_T + l_{T-1}.$$

We assume that $0 \leq l_t \leq y_t$, $t = 1, \ldots, T - 1$. We refer to $y$ as the true time series, and $\tilde{y}$ as the time series corrupted by late reporting. We will assume that

$$\mathbf{1}^T l \leq 0.1(\mathbf{1}^T y) = 0.1(\mathbf{1}^T \tilde{y}),$$

*i.e.*, a total of no more than 10% of the total quantity is reported late.

We observe the corrupted time series $\tilde{y}$ but not the true one $y$. The goal is to find an estimate $\hat{y}$ of the true time series $y$, which we do by minimizing a convex loss function $\ell : \mathbf{R}^T \to \mathbf{R}$, where smaller values of $\ell(\hat{y})$ are more plausible than larger values. (For example, $\ell(\hat{y})$ might be the negative log-likelihood in a statistical model of $y$.)

(a) Explain how to find the estimate $\hat{y}$ by convex optimization.

(b) Carry out the method of part (a) using the data found in `late_reporting_time_series_data.*`, and the simple loss function

$$\ell(\hat{y}) = \sum_{t=2}^{T-1} (\hat{y}_{t+1} - 2\hat{y}_t + \hat{y}_{t-1})^2,$$

the sum of squares of the second difference. Plot your estimated time series $\hat{y}$, as well as the corrupted $\tilde{y}$ and true $y$, which is given in the data file as `y_true`. Report the RMS error between the recovered and true time series, $\|\hat{y} - y\|_2/\sqrt{T}$, and the RMS error between the true and perturbed time series, $\|\tilde{y} - y\|_2/\sqrt{T}$. (Of course in any practical application you would not have access to the true time series.)

**15.17** *Maximizing utility in a wireless network with interference.* A wireless network consists of a set of nodes and a set of $m$ links (between nodes) over which data can be transmitted. There are $n$ routes, each corresponding to a sequence of links from a source to a destination node. Route $j$ has a data flow rate $f_j \in \mathbf{R}_+$ (in units of bits per second, say). The goal is to maximize the total utility

$$U(f) = \sum_{j=1}^{n} U_j(f_j),$$

where the $U_j : \mathbf{R} \to \mathbf{R}$, $j = 1, \ldots, n$, are concave increasing functions.

The network topology is specified by the routing matrix $R \in \mathbf{R}^{m \times n}$, defined by

$$R_{ij} = \begin{cases} 1 & \text{route } j \text{ uses link } i, \\ 0 & \text{otherwise.} \end{cases}$$

The total traffic on a link is the sum of the flows that pass over the link, and can be written as $t = Rf \in \mathbf{R}^m$. The traffic on each link is constrained by the capacity of the link and by interference from traffic on other links. The capacity constraint is simply $t \preceq c$, where $c \in \mathbf{R}_{++}^m$ is the vector of link capacities.

The interference is modeled by rate regions, which are convex regions in which a subset of mutually interfering traffic values can lie. We will describe the rate regions as a single polyhedron, $\mathcal{R} = \{t \mid At \preceq b\}$, with $A \in \mathbf{R}_+^{p \times m}$ and $b \in \mathbf{R}_{++}^p$. Each row $a_k^T t \leq b_k$ specifies a limit on some (nonnegative) linear combination of the link traffic values. Typically, $A$ is sparse, meaning that each link only interferes with a few others.

The data in the problem are the utility functions $U_j$, the route matrix $R$, the link capacity $c$, and the matrix $A$ and vector $b$ that define the rate regions.

(a) Formulate the problem of finding the flow rates that maximize total network utility, subject to the network's interference and capacity constraints, as a convex optimization problem.

(b) Solve the instance of this problem with $m = 20$, $n = 10$, $p = 8$, $U_j(x) = \sqrt{x}$ with other data given in `max_util_wireless_data.py`.

Report the optimal flow $f^\star$ and the associated utility. List the links that operate at full capacity, *i.e.*, $t_i = c_i$. (You can determine this using a reasonable tolerance, such as $c_i - t_i < 0.001$).

(c) For comparison, solve the problem *without* the interference constraints. Report the optimal flow and the associated utility. As above, list the links that operate at full capacity.

**15.18** *Extracting neural signals from an electrophysiological recording.* An electrophysiological (ephys) recording gives the voltage measured by a probe inserted into the brain at regular time intervals, such as every $10^{-4}$ seconds (0.1 milliseconds). Such recordings capture several neurons firing, as well as noise. In this exercise you will use convex optimization to extract the neural signals, which come from the neurons firing, from the noise in an ephys recording.

We represent the ephys recording as a vector $y \in \mathbf{R}^T$, with $y_t$ the voltage in time period $t$, for $t = 1, \ldots, T$. We model $y$ as

$$y = s * a + v,$$

where $*$ denotes convolution, $s \in \mathbf{R}^M$ is the known standard response of a neuron firing (an action potential obtained from the so-called Hodgkin-Huxley model, but you don't need to know that), with $M$ its length, $a \in \mathbf{R}_+^N$ is the unknown activation, and $v \in \mathbf{R}^T$ is the unknown noise signal. The activation signal $a$ is sparse and nonnegative, with $a_t > 0$ meaning that a neuron near the probe fired at time $t$, with amplitude $a_t$. We have $T = M + N - 1$, the length of the convolution $s * a$. Written out explicitly the model above is

$$y_t = \sum_{\tau=1}^{M} a_{t-\tau} s_\tau + v_t, \quad t = 1, \dots, T.$$

where we interpret $a_t$ as 0 for $t < 1$ or $t > N$. We refer to $s * a$ as the neural signal.

We are given $y$ and $s$, and wish to estimate the activation signal $a$. (From $a$ we can construct the extracted or cleaned neural signal $s * a$.) To do this we minimize the mean square value of $v = y - s * a$, plus a regularizer, *i.e.*, solve the problem

$$\begin{array}{ll} \text{minimize} & \frac{1}{T}\|y - s * a\|_2^2 + \lambda r(a) \\ \text{subject to} & a \succeq 0, \end{array}$$

where $r : \mathbf{R}^N \to \mathbf{R}$ is a convex regularizer function and $\lambda$ is a positive parameter that scales the regularization. The variable here is $a$; $s$ and $y$ are given. We let $\hat{a}$ denote a solution of this problem.

(a) Suggest a regularizer $r$ for which the resulting $a$ would typically be sparse. Then simplify $r$ using the fact that here we have $a \succeq 0$.

(b) Carry out the method using the regularizer suggested in part (a), on the data given in `neural_signal_data.*`. This defines synthetic data, which includes the true value $a^{\text{true}}$, which of course you would not have in a real problem. You may use the function `visualize_data`, provided with the data, to plot the given $y$ and the true neural signal $s * a^{\text{true}}$. The data gives $T = 2199$ samples, spaced 0.1 milliseconds apart, so the whole recording covers a little more than 0.2 seconds. The true activation $a^{\text{true}}$ has 10 nonzero entries.

Find $\hat{a}$ using $\lambda = 2$. Using the function `visualize_estimate` provided with the data, plot the estimated and true activations, $\hat{a}$ and $a^{\text{true}}$, and the estimated and true values of the neural signal, $s * \hat{a}$ and $s * a^{\text{true}}$.

Use the function `find_nonzero_entries` provided with the data to find the nonzero entries in $\hat{a}$ (based on the threshold $a_t > 0.01$). How well do the nonzero entries in $\hat{a}$ and $a^{\text{true}}$ match?

*Hint.* CVXPY supports convolution, in its `conv` atom. It returns a $T \times 1$ matrix, so you may need to use `cp.conv(s,a).flatten()` to obtain a vector.

*Remark.* We do not expect the true and estimated nonzero indices to match exactly; in addition, what is really just one nonzero in the true activation can end up as a few contiguous or nearby nonzero entries in the estimated activation.

(c) *Polishing.* Regularization has the effect of making $a$ smaller than it would be without the regularization. (In statistical estimation this phenomenon is called shrinkage, and is a desirable feature. In this case, it is not.) A method called *polishing* can be used to improve the estimate when this is not desirable.

To do this, we first solve the regularized problem in part (b) above. This gives us $\mathcal{T} = \{\tau \mid a_\tau > 0.01\}$, the set of times we think a neuron fires (with our threshold). Then we solve the problem again, *with no regularization*, adding the explicit constraint that $a_\tau = 0$ for $\tau \notin \mathcal{T}$.

Carry out this polishing procedure for the $\hat{a}$ found in part (b) to obtain $\hat{a}^{\text{pol}}$. Use the function `visualize_polished` provided with the data to create the same plots as in part (b), *i.e.*, $\hat{a}^{\text{pol}}$ and $a^{\text{true}}$ and also $s * \hat{a}^{\text{pol}}$ and $s * a^{\text{true}}$. Does polishing improve your estimate of the neural signal?

*Remark.* A more sophisticated version of the polishing step can include logic that combines adjacent or nearby nonzero entries in $\hat{a}$ into just one. Specifically, in this problem, biology dictates that neurons cannot be activated twice within 1ms intervals, providing a natural interval to combine adjacent nonzero entries. But we are not asking you to do this.

# 16 Control and trajectory optimization

**16.1** *Quickest take-off.* This problem concerns the braking and thrust profiles for an airplane during take-off. For simplicity we will use a discrete-time model. The position (down the runway) and the velocity in time period $t$ are $p_t$ and $v_t$, respectively, for $t = 0, 1, \ldots$. These satisfy $p_0 = 0$, $v_0 = 0$, and $p_{t+1} = p_t + hv_t$, $t = 0, 1, \ldots$, where $h > 0$ is the sampling time period. The velocity updates as

$$v_{t+1} = (1 - \eta)v_t + h(f_t - b_t), \quad t = 0, 1, \ldots,$$

where $\eta \in (0, 1)$ is a friction or drag parameter, $f_t$ is the engine thrust, and $b_t$ is the braking force, at time period $t$. These must satisfy

$$0 \le b_t \le \min\{B^{\mathrm{max}}, f_t\}, \quad 0 \le f_t \le F^{\mathrm{max}}, \quad t = 0, 1, \ldots,$$

as well as a constraint on how fast the engine thrust can be changed,

$$|f_{t+1} - f_t| \le S, \quad t = 0, 1, \ldots.$$

Here $B^{\mathrm{max}}$, $F^{\mathrm{max}}$, and $S$ are given parameters. The initial thrust is $f_0 = 0$. The take-off time is $T^{\mathrm{to}} = \min\{t \mid v_t \ge V^{\mathrm{to}}\}$, where $V^{\mathrm{to}}$ is a given take-off velocity. The take-off position is $P^{\mathrm{to}} = p_{T^{\mathrm{to}}}$, the position of the aircraft at the take-off time. The length of the runway is $L > 0$, so we must have $P^{\mathrm{to}} \le L$.

(a) Explain how to find the thrust and braking profiles that minimize the take-off time $T^{\mathrm{to}}$, respecting all constraints. Your solution can involve solving more than one convex problem, if necessary.

(b) Solve the quickest take-off problem with data

$$h = 1, \quad \eta = 0.05, \quad B^{\mathrm{max}} = 0.5, \quad F^{\mathrm{max}} = 4, \quad S = 0.8, \quad V^{\mathrm{to}} = 40, \quad L = 300.$$

Plot $p_t$, $v_t$, $f_t$, and $b_t$ versus $t$. Comment on what you see. Report the take-off time and take-off position for the profile you find.

**16.2** *Optimal spacecraft landing.* We consider the problem of optimizing the thrust profile for a spacecraft to carry out a landing at a target position. The spacecraft dynamics are

$$m\ddot{p} = f - mge_3,$$

where $m > 0$ is the spacecraft mass, $p(t) \in \mathbf{R}^3$ is the spacecraft position, with 0 the target landing position and $p_3(t)$ representing height, $f(t) \in \mathbf{R}^3$ is the thrust force, and $g > 0$ is the gravitational acceleration. (For simplicity we assume that the spacecraft mass is constant. This is not always a good assumption, since the mass decreases with fuel use. We will also ignore any atmospheric friction.) We must have $p(T^{\mathrm{td}}) = 0$ and $\dot{p}(T^{\mathrm{td}}) = 0$, where $T^{\mathrm{td}}$ is the touchdown time. The spacecraft must remain in a region given by

$$p_3(t) \ge \alpha \|(p_1(t), p_2(t))\|_2,$$

where $\alpha > 0$ is a given minimum glide slope. The initial position $p(0)$ and velocity $\dot{p}(0)$ are given.

The thrust force $f(t)$ is obtained from a single rocket engine on the spacecraft, with a given maximum thrust; an attitude control system rotates the spacecraft to achieve any desired direction of thrust. The thrust force is therefore characterized by the constraint $\|f(t)\|_2 \leq F^{\max}$. The fuel use rate is proportional to the thrust force magnitude, so the total fuel use is

$$\int_0^{T^{\mathrm{td}}} \gamma \|f(t)\|_2 \, dt,$$

where $\gamma > 0$ is the fuel consumption coefficient. The thrust force is discretized in time, *i.e.*, it is constant over consecutive time periods of length $h > 0$, with $f(t) = f_k$ for $t \in [(k-1)h, kh)$, for $k = 1, \ldots, K$, where $T^{\mathrm{td}} = Kh$. Therefore we have

$$v_{k+1} = v_k + (h/m)f_k - hge_3, \quad p_{k+1} = p_k + (h/2)(v_k + v_{k+1}),$$

where $p_k$ denotes $p((k-1)h)$, and $v_k$ denotes $\dot{p}((k-1)h)$. We will work with this discrete-time model. For simplicity, we will impose the glide slope constraint only at the times $t = 0, h, 2h, \ldots, Kh$.

(a) *Minimum fuel descent.* Explain how to find the thrust profile $f_1, \ldots, f_K$ that minimizes fuel consumption, given the touchdown time $T^{\mathrm{td}} = Kh$ and discretization time $h$.

(b) *Minimum time descent.* Explain how to find the thrust profile that minimizes the touchdown time, *i.e.*, $K$, with $h$ fixed and given. Your method can involve solving several convex optimization problems.

(c) Carry out the methods described in parts (a) and (b) above on the problem instance with data given in `spacecraft_landing_data.*`. Report the optimal total fuel consumption for part (a), and the minimum touchdown time for part (b). The data files also contain plotting code (commented out) to help you visualize your solution. Use the code to plot the spacecraft trajectory and thrust profiles you obtained for parts (a) and (b).

*Hints.*

- In Julia, the plot will come out rotated.

*Remarks.* If you'd like to see the ideas of this problem in action, watch these videos:

- http://www.youtube.com/watch?v=2t15vP1PyoA
- https://www.youtube.com/watch?v=orUjSkc2pG0
- https://www.youtube.com/watch?v=1B6oiLNyKKI
- https://www.youtube.com/watch?v=ZCBE8ocOkAQ

**16.3** *Feedback gain optimization.* A system (such as an industrial plant) is characterized by $y = Gu + v$, where $y \in \mathbf{R}^n$ is the output, $u \in \mathbf{R}^n$ is the input, and $v \in \mathbf{R}^n$ is a disturbance signal. The matrix $G \in \mathbf{R}^{n \times n}$, which is known, is called the system input-output matrix. The input signal $u$ is found using a linear feedback (control) policy: $u = Fy$, where $F \in \mathbf{R}^{n \times n}$ is the feedback (gain) matrix, which is what we need to determine. From the equations given above, we have

$$y = (I - GF)^{-1}v, \qquad u = F(I - GF)^{-1}v.$$

(You can simply assume that $I - GF$ will be invertible.)

The disturbance $v$ is random, with $\mathbf{E}\, v = 0$, $\mathbf{E}\, vv^T = \sigma^2 I$, where $\sigma$ is known. The objective is to minimize $\max_{i=1,\ldots,n} \mathbf{E}\, y_i^2$, the maximum mean square value of the output components, subject to the constraint that $\mathbf{E}\, u_i^2 \le 1$, $i = 1, \ldots, n$, i.e., each input component has a mean square value not exceeding one. The variable to be chosen is the matrix $F \in \mathbf{R}^{n \times n}$.

(a) Explain how to use convex (or quasi-convex) optimization to find an optimal feedback gain matrix. As usual, you must fully explain any change of variables or other transformations you carry out, and why your formulation solves the problem described above. A few comments:

- You can assume that matrices arising in your change of variables are invertible; you do not need to worry about the special cases when they are not.
- You can assume that $G$ is invertible if you need to, but we will deduct a few points from these answers.

(b) Carry out your method for the problem instance with data

$$
\sigma = 1, \qquad G = \begin{bmatrix} 0.3 & -0.1 & -0.9 \\ -0.6 & 0.3 & -0.3 \\ -0.3 & 0.6 & 0.2 \end{bmatrix}.
$$

Give an optimal $F$, and the associated optimal objective value.

**16.4** *Minimum time speed profile along a road.* A vehicle of mass $m > 0$ moves along a road in $\mathbf{R}^3$, which is piecewise linear with given knot points $p_1, \ldots, p_{N+1} \in \mathbf{R}^3$, starting at $p_1$ and ending at $p_{N+1}$. We let $h_i = (p_i)_3$, the $z$-coordinate of the knot point; these are the heights of the knot points (above sea-level, say). For your convenience, these knot points are equidistant, i.e., $\|p_{i+1} - p_i\|_2 = d$ for all $i$. (The points give an arc-length parametrization of the road.) We let $s_i > 0$ denote the (constant) vehicle speed as it moves along road segment $i$, from $p_i$ to $p_{i+1}$, for $i = 1, \ldots, N$, and $s_{N+1} \ge 0$ denote the vehicle speed after it passes through knot point $p_{N+1}$. Our goal is to minimize the total time to traverse the road, which we denote $T$.

We let $f_i \ge 0$ denote the total fuel burnt while traversing the $i$th segment. This fuel burn is turned into an increase in vehicle energy given by $\eta f_i$, where $\eta > 0$ is a constant that includes the engine efficiency and the energy content of the fuel. While traversing the $i$th road segment the vehicle is subject to a drag force, given by $C_D s_i^2$, where $C_D > 0$ is the coefficient of drag, which results in an energy loss $dC_D s_i^2$.

We derive equations that relate these quantities via energy balance:

$$
\frac{1}{2} m s_{i+1}^2 + m g h_{i+1} = \frac{1}{2} m s_i^2 + m g h_i + \eta f_i - dC_D s_i^2, \quad i = 1, \ldots, N,
$$

where $g = 9.8$ is the gravitational acceleration. The lefthand side is the total vehicle energy (kinetic plus potential) after it passes through knot point $p_{i+1}$; the righthand side is the total vehicle energy after it passes through knot point $p_i$, plus the energy gain from the fuel burn, minus the energy lost to drag. To set up the first vehicle speed $s_1$ requires an additional initial fuel burn $f_0$, with $\eta f_0 = \frac{1}{2} m s_1^2$.

Fuel is also used to power the on-board system of the vehicle. The total fuel used for this purpose is $f_{\mathrm{ob}}$, where $\eta f_{\mathrm{ob}} = TP$, where $P > 0$ is the (constant) power consumption of the on-board system. We have a fuel capacity constraint: $\sum_{i=0}^{N} f_i + f_{\mathrm{ob}} \le F$, where $F > 0$ is the total initial fuel.

The problem data are $m$, $d$, $h_1, \ldots, h_{N+1}$, $\eta$, $C_D$, $P$, and $F$. (You don't need the knot points $p_i$.)

(a) Explain how to find the fuel burn levels $f_0, \ldots, f_N$ that minimize the time $T$, subject to the constraints.

(b) Carry out the method described in part (a) for the problem instance with data given in `min_time_speed_data.m`. Give the optimal time $T^\star$, and compare it to the time $T^{\text{unif}}$ achieved if the fuel for propulsion were burned uniformly, *i.e.*, $f_0 = \cdots = f_N$. For each of these cases, plot speed versus distance along the road, using the plotting code in the data file as a template.

**16.5** *Minimum time maneuver for a crane.* A crane manipulates a load with mass $m > 0$ in two dimensions using two cables attached to the load. The cables maintain angles $\pm\theta$ with respect to vertical, as shown below.



The (scalar) tensions $T^{\text{left}}$ and $T^{\text{right}}$ in the two cables are independently controllable, from 0 up to a given maximum tension $T^{\text{max}}$. The total force on the load is

$$F = T^{\text{left}} \begin{bmatrix} -\sin\theta \\ \cos\theta \end{bmatrix} + T^{\text{right}} \begin{bmatrix} \sin\theta \\ \cos\theta \end{bmatrix} + mg,$$

where $g = (0, -9.8)$ is the acceleration due to gravity. The acceleration of the load is then $F/m$.

We approximate the motion of the load using

$$p_{i+1} = p_i + h v_i, \quad v_{i+1} = v_i + (h/m) F_i, \quad i = 1, 2, \ldots,$$

where $p_i \in \mathbf{R}^2$ is the position of the load, $v_i \in \mathbf{R}^2$ is the velocity of the load, and $F_i \in \mathbf{R}^2$ is the force on the load, at time $t = ih$. Here $h > 0$ is a small (given) time step.

The goal is to move the load, which is initially at rest at position $p^{\text{init}}$ to the position $p^{\text{des}}$, also at rest, in minimum time. In other words, we seek the smallest $k$ for which

$$p_1 = p^{\text{init}}, \quad p_k = p^{\text{des}}, \quad v_1 = v_k = (0,0)$$

is possible, subject to the constraints described above.

(a) Explain how to solve this problem using convex (or quasiconvex) optimization.

(b) Carry out the method of part (a) for the problem instance with

$$m = 0.1, \quad \theta = 15°, \quad T^{\text{max}} = 2, \quad p^{\text{init}} = (0,0), \quad p^{\text{des}} = (10,2),$$

with time step $h = 0.1$. Report the minimum time $k^\star$. Plot the tensions versus time, and the load trajectory, *i.e.*, the points $p_1, \ldots, p_k$ in $\mathbf{R}^2$. Does the load move along the line segment between $p^{\text{init}}$ and $p^{\text{des}}$ (*i.e.*, the shortest path from $p^{\text{init}}$ and $p^{\text{des}}$)? Comment briefly.

**16.6** *Planning an autonomous lane change.* A vehicle is traveling down a highway with two lanes, separated by $L$ meters. At time $t$, its position is $p(t) = (x(t), y(t)) \in \mathbf{R}^2_+$. We require that $y(t) \in [0, L]$, for all $t$. When $y(t) = 0$, it means the vehicle is in lane 1, when $y(t) = L$, it means the vehicle is in lane 2, and when $0 < y(t) < L$, it means the vehicle is passing between lanes. (Notice that since a lane on a highway has traffic moving in a single direction, we require that $x(t)$ is nondecreasing in $t$.)

For simplicity, we discretize the problem. We will consider the position of the vehicle every second, so $p_t = (x_t, y_t)$, $t = 0, 1, \ldots, T$, denotes the vehicles position from 0 to $T$ seconds (in particular, this means $p_t = p(t)$). Initially ($t = 0$), the vehicle lies in lane 1, and we assume $x_0 = 0$. Between $t$ and $t + 1$ seconds, we assume the vehicle travels at constant speed, measured in meters per second (m/s). The speed from time $t$ to $t + 1$ is simply $\|p_{t+1} - p_t\|_2$. We require that these speeds never exceed $S^{\mathrm{max}}$ (for example, the speed limit plus, say, 4 or 5 m/s).

The goal of this problem is to plan a lane change. In particular, after time $T^{\mathrm{start}}$, the vehicle may initiate a lane change from lane 1, and by time $T^{\mathrm{end}}$, the vehicle should have fully entered lane 2.

The vehicle should always travel at a speed of at most $S^{\mathrm{max}}$, measured in meters per second. Additionally, when the vehicle is not allowed to lane change (before $T^{\mathrm{start}}$ and after $T^{\mathrm{end}}$), the vehicle must be driving with at least a given minimum speed, $S^{\mathrm{min}}$, which is also given. (You may assume that $T^{\mathrm{start}}$ and $T^{\mathrm{end}}$ are integers.)

Your goal is to determine the smoothest possible lane change, subject to the constraints described above. By smooth, we simply mean that you should minimize the total acceleration of the vehicle, which can be approximated by

$$\sum_{t=1}^{T-1} \|(p_{t+1} - p_t) - (p_t - p_{t-1})\|_2^2.$$

(a) Explain how to plan this autonomous lane change using convex or quasiconvex optimization, given $T$, $T^{\mathrm{start}}$, $T^{\mathrm{end}}$, $S^{\mathrm{min}}$, $S^{\mathrm{max}}$, and $L$. If you introduce new variables or make any transformations you must justify them.

(b) Carry out this method on the data below,

$$T = 30, \quad T^{\mathrm{start}} = 15, \quad T^{\mathrm{end}} = 20, \quad S^{\mathrm{min}} = 25, \quad S^{\mathrm{max}} = 35, \quad L = 3.7.$$

Produce a plot the speed of the vehicle against time, as well as the position of the vehicle in $\mathbf{R}^2$ for the plan you produce.

*Remark.* In fact, many highways have lanes separated by 3.7 meters. Additionally, on average, a lane change for a vehicle on a standard US freeway takes 5 to 6 seconds, and the speed limits we impose here correspond to a vehicle driving between 55 mph, and 75 mph, which aren't unreasonable for a standard US highway.

**16.7** *Optimal racing of an energy-limited vehicle.* We have an energy-limited vehicle, such as a solar car, moving along a fixed straight track. We'd like to design a control system to move the vehicle from the starting point to the finishing point using minimum energy in the time interval $[0, T]$. (There are other related natural formulations of this problem, such as traversing the track in the minimum time subject to a maximum energy usage. We will not consider these here, but the same techniques are applicable.)

At time $t$ the car has position $x(t) \in \mathbf{R}$, velocity $v(t) \in \mathbf{R}$ and acceleration $a(t) \in \mathbf{R}$. The car starts with $x(0) = 0$ and $v(0) = 0$ and must finish with $x(T) \geq x^{\text{final}}$.

At time $t$ the kinetic energy of the vehicle is $k(t) = \frac{1}{2}mv(t)^2$, where $m$ is the mass. Let the energy delivered from the battery to the drivetrain be $p(t)$, which is nonnegative (there is no regenerative braking.) Then

$$\dot{k}(t) = p(t) - p^{\text{brake}}(t) - p^{\text{loss}}(t)$$

where $p^{\text{brake}}(t) \geq 0$ is an input that the control system (*i.e.*, your optimization) chooses, and losses due to drag are modeled via

$$p^{\text{loss}}(t) = c^{\text{loss}}v(t)^3$$

Here $c^{\text{loss}}$ is a positive constant that depends on the shape of the vehicle and the density of the air.

The vehicle must move according to the following requirements. Tire traction limits acceleration so that $\dot{v}(t) \leq a^{\text{max}}$. Note that there is no lower bound on the acceleration. The vehicle cannot move backwards and must stay within the speed limit, and so $0 \leq v(t) \leq v^{\text{max}}$. The final velocity of the vehicle must satisfy $v(T) \leq v^{\text{final}}$.

We will use period $h > 0$ and sample position according to $x_i = x(ih)$, and similarly for velocity, acceleration and kinetic energy. The vehicle dynamics $\dot{x}(t) = v(t)$ and $\dot{v}(t) = a(t)$ are then discretized according to

$$x_{i+1} = x_i + \frac{h}{2}(v_i + v_{i+1}), \quad v_{i+1} = v_i + ha_i$$

and the rate of change of kinetic energy is discretized according to

$$\frac{1}{h}(k_{i+1} - k_i) = p_i - p_i^{\text{brake}} - p_i^{\text{loss}}$$

We would like to minimize the total energy used, which is discretized as

$$E = h\sum_{i=0}^{n} p_i$$

where $T = nh$. The parameters are

$$m = 10 \quad x^{\text{final}} = 10 \quad v^{\text{final}} = 1 \quad v^{\text{max}} = 10 \quad a^{\text{max}} = 2 \quad c^{\text{loss}} = 2 \quad h = 0.1 \quad T = 5$$

(a) Formulate this problem as an optimization problem with variables $p_i, x_i, v_i, k_i$ (and others if necessary) for $i = 0, \ldots, n$. If this problem is not convex, explain briefly why.

(b) By relaxing the energy constraint $k(t) = \frac{1}{2}mv(t)^2$ to

$$k(t) \geq \frac{1}{2}mv(t)^2$$

state a convex optimization problem whose solution provides an optimal trajectory $x$, $v$, $p$, and $k$ for part (a). Explain why the relaxation is tight. By tight, we mean that the solution to your problem has the same optimal value as that of part (a).

(c) Carry out your method from part (b). Report the optimal value of the total energy $E$. Plot the position $x$, velocity $v$ and power used $p$ of the vehicle as functions of time.

**16.8** *Well that was a bit roundabout.* You're late for the last lecture of Convex Optimization and you need to get the lecture hall. You get on your bike, and proceed directly to class.

At time $t$ the bike has position $x(t) \in \mathbf{R}^2$, velocity $v(t) \in \mathbf{R}^2$, and acceleration $a(t) \in \mathbf{R}^2$. You start at position $x(0) = x^{\text{initial}}$ and finish at time $T$ with $x(T) = x^{\text{final}}$. Your initial velocity is $v(0) = v^{\text{initial}}$.

We will use period $h > 0$ and sample position according to $x_i = x(ih)$, and similarly for velocity and acceleration. Fortunately your bicycle is a point mass, and so the vehicle dynamics are $\dot{x}(t) = v(t)$ and $\dot{v}(t) = a(t)$. These are then discretized according to

$$
\begin{aligned}
x_{i+1} &= x_i + \tfrac{h}{2}(v_i + v_{i+1}) \\
v_{i+1} &= v_i + h a_i
\end{aligned}
$$

Despite your desire to arrive at class on time, you cycle somewhat leisurely, avoiding unnecessary exertion. So you choose to minimize

$$
J = h \sum_{i=0}^{n} \|a_i\|_2^2
$$

where $T = nh$. We have

$$
x^{\text{initial}} = \begin{bmatrix} -5 \\ 0 \end{bmatrix}, \quad x^{\text{final}} = \begin{bmatrix} 6 \\ 1 \end{bmatrix}, \quad v^{\text{initial}} = \begin{bmatrix} 2 \\ 0 \end{bmatrix}, \quad T = 12, \quad h = 0.1.
$$

(a) Find and plot the optimal trajectory of the bicycle. Report the optimal value $J$.

(b) Unfortunately, somebody has built a roundabout in the way. The roundabout is a disk of radius 1 centered at the origin

$$
R = \{x \in \mathbf{R}^2 \mid \|x\|_2 \le 1\}
$$

The constable observing your path advises you that he fears that your trajectory has the unfortunate property of failing to correctly circumnavigate the roundabout.

Unfortunately, the constraint that you should avoid the roundabout is not convex. After considering this, you arrive at a new strategy. Let the previous solution be $x^{\text{prev}}$. You construct a new optimization problem, where at each time step $i$ you add the constraint that $c_i^T x_i \ge 1$, where

$$
c_i = x_i^{\text{prev}} / \|x_i^{\text{prev}}\|_2.
$$

Give a brief interpretation of these constraints. Solve the optimization problem again, with these new constraints. Plot the optimal trajectory and report the optimal cost.

(c) Repeat part (b) until the trajectory converges. Plot the final trajectory along with the the trajectories from part (a),(b) and the roundabout $R$. Note that each optimization only uses constraints generated by the previous solution. What is the final cost $J$ achieved?

**16.9** *Path planning with contingencies.* A vehicle path down a (straight, for simplicity) road is specified by a vector $p \in \mathbf{R}^N$, where $p_i$ gives the position perpendicular to the centerline at the point $ih$ meters down the road, where $h > 0$ is a given discretization size. (Throughout this problem, indexes on $N$-vectors will correspond to positions on the road.) We normalize $p$ so $-1 \le p_i \le 1$ gives the road boundaries. (We are modeling the vehicle as a point, by adjusting for its width.) You are

given the initial two positions $p_1 = a$ and $p_2 = b$ (which give the initial road position and angle), as well as the final two positions $p_{N-1} = c$ and $p_N = d$.

You know there may be an obstruction at position $i = O$. This will require the path to either go around the obstruction on the left, which requires $p_O \geq 0.5$, or on the right, which requires $p_O \leq -0.5$, or possibly the obstruction will clear, and the obstruction does not place any additional constraint on the path. These are the three *contingencies* in the problem title, which we label as $k = 1, 2, 3$.

You will plan three paths for these contingencies, $p^{(i)} \in \mathbf{R}^N$ for $i = 1, 2, 3$. They must each satisfy the given initial and final two road positions and the constraint of staying within the road boundaries. Paths $p^{(1)}$ and $p^{(2)}$ must satisfy the (different) obstacle avoidance constraints given above. Path $p^{(3)}$ does not need to satisfy an avoidance constraint.

Now we add a twist: You will not learn which of the three contingencies will occur until the vehicle arrives at position $i = S$, when the sensors will determine which contingency holds. We model this with the *information constraints* (also called *causality constraints* or *non-anticipatory constraints*),

$$p_i^{(1)} = p_i^{(2)} = p_i^{(3)}, \quad i = 1, \ldots, S,$$

which state that before you know which contingency holds, the three paths must be the same.

The objective to be minimized is

$$\sum_{k=1}^{3} \sum_{i=2}^{N-1} (p_{i-1}^{(k)} - 2p_i^{(k)} + p_{i+1}^{(k)})^2,$$

the sum of the squares of the second differences, which gives smooth paths.

(a) Explain how to solve this problem using convex optimization.

(b) Solve the problem with data given in `path_plan_contingencies_data.*`. The data files include code to plot the results, which you should use to plot (on one plot) the optimal paths. Report the optimal objective value. Give a *very brief* informal explanation for what you see happening for $i = 1, \ldots, S$.

*Hint.* In Python, use the (default) solver ECOS to avoid warnings about inaccurate solutions.

**16.10** *Control with various objectives.* We consider a standard optimal control problem, with dynamics $x_{t+1} = Ax_t + Bu_t$, $t = 0, 1, \ldots, T - 1$. Here $x_t \in \mathbf{R}^n$ is the state, and $u_t \in \mathbf{R}^m$ is the control or input, at time period $t$, $A \in \mathbf{R}^{n \times n}$ is the dynamics matrix, and $B \in \mathbf{R}^{n \times m}$ is the input matrix. We are given the initial state, $x_0 = x^{\text{init}}$, and we require that the final state be zero, $x_T = 0$. (In applications, the state 0 corresponds to some desirable state.) Your job is to choose the sequence of inputs $u_0, \ldots, u_{T-1}$ that minimize an objective. Values for $x^{\text{init}}$, $A$, $B$, and $T$ are given in `various_obj_regulator_data.*`.

We consider various objectives, all of which measure the size of the inputs (or, in control dialect, the *control effort*).

(a) *Sum of squares of 2-norms.* $\sum_{t=0}^{T-1} \|u_t\|_2^2$. This is the traditional objective.

(b) *Sum of 2-norms.* $\sum_{t=0}^{T-1} \|u_t\|_2$.

(c) *Max of 2-norms.* $\max_{t=0,\dots,T-1} \|u_t\|_2$.

(d) *Sum of 1-norms.* $\sum_{t=0}^{T-1} \|u_t\|_1$. In some applications this is an approximation of the fuel use.

For each objective, plot (the components of) optimal input, as well as $\|u_t\|_2$, versus $t$. Make a very brief comment on each plot of optimal control inputs, explaining why you might expect what happened.

**16.11** *Multi-period liability clearing.* We consider a financial system with $n$ financial entities or agents, such as banks, who make payments to each other over discrete time periods $t = 1, 2, \dots$. We let $c_t \in \mathbf{R}^n_+$ denote the cash held at the beginning of time period $t$, where $(c_t)_i$ is the amount held by the $i$th entity in dollars.

We let $L_t \in \mathbf{R}^{n \times n}_+$ denote the liability between the entities at the beginning of time period $t$, where $(L_t)_{ij}$ is the amount in dollars that entity $i$ owes entity $j$. You can assume that $(L_t)_{ii} = 0$, *i.e.*, the entities do not owe anything to themselves. Note that $L_t \mathbf{1}$ is the vector of total liabilities of the entities, *i.e.*, the total amount owed to other entities, and $L_t^T \mathbf{1}$ is the vector of total amount owed to the entities by others, at time period $t$.

We let $P_t \in \mathbf{R}^{n \times n}_+$ denote the amount paid between each entity during time period $t$, where $(P_t)_{ij}$ is the amount, in dollars, paid from entity $i$ to entity $j$. Thus $P_t \mathbf{1}$ is the vector of total cash payments made by the entities to others in period $t$ (*i.e.*, $(P_t \mathbf{1})_i$ is the total payments from entity $i$ to all other entities), and $P_t^T \mathbf{1}$ is the vector of total cash received by the entities from others in period $t$.

The liabilities and cash follows the dynamics

$$L_{t+1} = L_t - P_t, \quad t = 1, 2, \dots,$$
$$c_{t+1} = c_t - P_t \mathbf{1} + P_t^T \mathbf{1}, \quad t = 1, 2, \dots.$$

Each entity cannot pay more than the cash that it has on hand, so we have the constraint

$$P_t \mathbf{1} \preceq c_t, \quad t = 1, 2, \dots.$$

We are given the initial cash held $c_1$ and the initial liabilities $L_1$. You can assume that for each entity, the cash held plus the cash owed to it are at least as much as the amount it owes, *i.e.*, $c_1 - L_1 \mathbf{1} + L_1^T \mathbf{1} \succeq 0$.

(a) *Minimum time to clear the liabilities.* Explain how to find the minimum $T$ for which there is a feasible sequence of payments $P_1, \dots, P_{T-1}$ that results in $L_T = 0$. (Reducing the liabilities to zero is called *clearing* them.) Your method can involve solving a reasonable number of convex problems.

(b) Carry out the method of part (a) on the data given in `clearing_data.*`.

**16.12** *Lyapunov analysis of a dynamical system.* We consider a discrete-time time-varying linear dynamical system with state $x_t \in \mathbf{R}^n$. The state propagates according to the linear recursion $x_{t+1} = A_t x_t$, for $t = 0, 1, \dots$, where the matrices $A_t$ are unknown but satisfy $A_t \in \mathcal{A} = \{A^{(1)}, \dots, A^{(K)}\}$, where $A^{(1)}, \dots, A^{(K)}$ are known. (In computer science, this would be called a non-deterministic linear automaton.) We call the sequence $x_0, x_1, \dots$ a *trajectory* of the system. There are infinitely many trajectories, one for each sequence $A_0, A_1, \dots$.

The *Lyapunov exponent* $\kappa$ of the system is defined as

$$\kappa = \sup_{A_0, A_1, \ldots} \limsup_{t \to \infty} \|x_t\|_2^{1/t}.$$

(If you don't know what sup and lim sup mean, you can replace them with max and lim, respectively.) Roughly speaking, this means that all trajectories grow no faster than $\kappa^t$. When $\kappa < 1$, the system is called *exponentially stable*.

It is a hard problem to determine the Lyapunov exponent of the system, or whether the system is exponentially stable, given the data $A^{(1)}, \ldots, A^{(K)}$. In this problem we explore a powerful method for computing an upper bound on the Lyapunov exponent.

(a) Let $P \in \mathbf{S}_{++}^n$ and define $V(x) = x^T P x$. Suppose $V$ satisfies

$$V(A^{(i)}x) \leq \gamma^2 V(x) \text{ for all } x \in \mathbf{R}^n, \ i = 1, \ldots, K.$$

Show that $\kappa \leq \gamma$. Thus $\gamma$ is an upper bound on the Lyapunov exponent $\kappa$. (The function $V$ is called a quadratic *Lyapunov function* for the system.)

(b) Explain how to use convex or quasiconvex optimization to find a matrix $P \in \mathbf{S}_{++}^n$ with the smallest value of $\gamma$, *i.e.*, with the best upper bound on $\kappa$. You must justify your formulation.

(c) Carry out the method of part (b) for the specific problem with data given in `lyap_exp_bound_data.m`. Report the best upper bound on $\kappa$, to a tolerance of 0.01. The data $A^{(i)}$ are given as a cell array; `A{i}` gives $A^{(i)}$.

(d) *Approximate worst-case trajectory simulation.* The quadratic Lyapunov function found in part (c) can be used to generate sequences of $A_t$ that tend to result in large values of $\|x_t\|_2^{1/t}$. Start from a random vector $x_0$. At each $t$, generate $x_{t+1}$ by choosing $A_t = A^{(i)}$ that maximizes $V(A^{(i)}x_t)$, where $P$ is computed from part (c). Do this for 50 time steps, and generate 5 such trajectories. Plot $\|x_t\|_2^{1/t}$ and $\gamma$ against $t$ to verify that the bound you obtained in the previous part is valid. Report the lower bound on the Lyapunov exponent that the trajectories suggest.

**16.13** *Optimal evacuation planning.* We consider the problem of evacuating people from a dangerous area in a way that minimizes risk exposure. We model the area as a connected graph with $n$ nodes and $m$ edges; people can assemble or collect at the nodes, and travel between nodes (in either direction) over the edges. We let $q_t \in \mathbf{R}_+^n$ denote the vector of the numbers of people at the nodes, in time period $t$, for $t = 1, \ldots, T$, where $T$ is the number of periods we consider. (We will consider the entries of $q_t$ as real numbers, not integers.) The initial population distribution $q_1$ is given. The nodes have capacity constraints, given by $q_t \preceq Q$, where $Q \in \mathbf{R}_+^n$ is the vector of node capacities.

We use the incidence matrix $A \in \mathbf{R}^{n \times m}$ to describe the graph. We assign an arbitrary reference direction to each edge, and take

$$A_{ij} = \begin{cases} +1 & \text{if edge } j \text{ enters node } i \\ -1 & \text{if edge } j \text{ exits node } i \\ 0 & \text{otherwise.} \end{cases}$$

The population dynamics are given by $q_{t+1} = Af_t + q_t$, $t = 1, \ldots, T-1$ where $f_t \in \mathbf{R}^m$ is the vector of population movement (flow) across the edges, for $t = 1, \ldots, T-1$. A positive flow

denotes movement in the direction of the edge; negative flow denotes population flow in the reverse direction. Each edge has a capacity, *i.e.*, $|f_t| \preceq F$, where $F \in \mathbf{R}_+^m$ is the vector of edge capacities, and $|f_t|$ denotes the elementwise absolute value of $f_t$.

An *evacuation plan* is a sequence $q_1, q_2, \ldots, q_T$ and $f_1, f_2, \ldots, f_{T-1}$ obeying the constraints above. The goal is to find an evacuation plan that minimizes the total risk exposure, defined as

$$
R_{\text{tot}} = \sum_{t=1}^{T} \left( r^T q_t + s^T q_t^2 \right) + \sum_{t=1}^{T-1} \left( \tilde{r}^T |f_t| + \tilde{s}^T f_t^2 \right),
$$

where $r, s \in \mathbf{R}_+^n$ are given vectors of risk exposure coefficients associated with the nodes, and $\tilde{r}, \tilde{s} \in \mathbf{R}_+^m$ are given vectors of risk exposure coefficients associated with the edges. The notation $q_t^2$ and $f_t^2$ refers to elementwise squares of the vectors. Roughly speaking, the risk exposure is a quadratic function of the occupancy of a node, or the (absolute value of the) flow of people along an edge. The linear terms can be interpreted as the risk exposure per person; the quadratic terms can be interpreted as the additional risk associated with crowding.

A subset of nodes have zero risk ($r_i = s_i = 0$), and are designated as *safe nodes*. The population is considered *evacuated* at time $t$ if $r^T q_t + s^T q_t^2 = 0$. The *evacuation time* $t_{\text{evac}}$ of an evacuation plan is the smallest such $t$. We will assume that $T$ is sufficiently large and that the total capacity of the safe nodes exceeds the total initial population, so evacuation is possible.

Use CVX* to find an optimal evacuation plan for the problem instance with data given in `opt_evac_data.*`. (We display the graph below, with safe nodes denoted as squares.)



Report the associated optimal risk exposure $R_{\text{tot}}^\star$. Plot the time period risk

$$
R_t = r^T q_t + s^T q_t^2 + \tilde{r}^T |f_t| + \tilde{s}^T f_t^2
$$

versus time. (For $t = T$, you can take the edge risk to be zero.) Plot the node occupancies $q_t$, and edge flows $f_t$ versus time. Briefly comment on the results you see. Give the evacuation time $t_{\text{evac}}$ (considering any $r^T q_t + s^T q_t^2 \leq 10^{-4}$ to be zero).

*Hint.* With CVXPY, use the ECOS solver with `p.solve(solver=cvxpy.ECOS)`.

**16.14** *Dual of an optimal control problem.* We consider the optimal control problem

$$
\begin{array}{ll}
\text{minimize} & \sum_{t=1}^{T} \frac{1}{2} \|u_t\|^2 \\
\text{subject to} & x_{t+1} = A x_t + B u_t \qquad t = 1, \ldots, T \\
& x_1 = x_{\text{init}}, \qquad x_{T+1} = x_{\text{term}},
\end{array}
$$

with variables $x_1, \ldots, x_{T+1} \in \mathbf{R}^n$ (the state trajectory) and $u_1, \ldots, u_T \in \mathbf{R}^m$ (the input or control trajectory). The matrices $A \in \mathbf{R}^{n \times n}$ and $B \in \mathbf{R}^{n \times m}$ are given, as are the initial state $x_{\text{init}} \in \mathbf{R}^n$ and final or terminal state $x_{\text{term}} \in \mathbf{R}^n$. The norm appearing in the objective is an arbitrary norm on $\mathbf{R}^m$, with dual norm denoted $\| \cdot \|_*$.

We will use $\nu_1, \ldots, \nu_T \in \mathbf{R}^n$ as the dual variables associated with the dynamics equality constraints $x_{t+1} = Ax_t + Bu_t$, $t = 1, \ldots, T$. We associate the dual variable $\nu_0 \in \mathbf{R}^n$ with the initial state constraint $x_1 = x_{\text{init}}$, and the dual variable $\nu_{T+1} \in \mathbf{R}^n$ with the terminal state constraint $x_{T+1} = x_{\text{term}}$.

(a) Give the Lagrangian for this optimal control problem, using the dual variables $\nu_0, \ldots, \nu_{T+1}$ described above.

(b) Derive the dual function $g$. Be sure to specify its domain, *i.e.*, conditions on the dual variables under which $g(\nu_0, \ldots, \nu_{T+1}) > -\infty$. *Hint.* The conjugate of $\frac{1}{2}\| \cdot \|^2$ is $\frac{1}{2}\| \cdot \|_*^2$.

(c) Give the Lagrange dual of the optimal control problem. Express the implicit constraints in $g$ (*i.e.*, its domain) as explicit constraints.

# 17   Finance

**17.1** *Transaction cost.* Consider a market for some asset or commodity, which we assume is infinitely divisible, *i.e.*, can be bought or sold in quantities of shares that are real numbers (as opposed to integers). The *order book* at some time consists of a set of offers to sell or buy the asset, at a given price, up to a given quantity of shares. The $N$ offers to sell the asset have positive prices per share $p_1^{\text{sell}}, \ldots, p_N^{\text{sell}}$, sorted in increasing order, in positive share quantities $q_1^{\text{sell}}, \ldots, q_N^{\text{sell}}$. The $M$ offers to buy the asset have positive prices $p_1^{\text{buy}}, \ldots, p_N^{\text{buy}}$, sorted in decreasing order, and positive quantities $q_1^{\text{buy}}, \ldots, q_M^{\text{buy}}$. The price $p_1^{\text{sell}}$ is called the (current) *ask price* for the asset; $p_1^{\text{buy}}$ is the *bid price* for the asset. The ask price is larger than the bid price; the difference is called the *spread*. The average of the ask and bid prices is called the *mid-price*, denoted $p^{\text{mid}}$.

Now suppose that you want to purchase $q > 0$ shares of the asset, where $q \le q_1^{\text{sell}} + \cdots + q_N^{\text{sell}}$, *i.e.*, your purchase quantity does not exceed the total amount of the asset currently offered for sale. Your purchase proceeds as follows. Suppose that

$$q_1^{\text{sell}} + \cdots + q_k^{\text{sell}} < q \le q_1^{\text{sell}} + \cdots + q_{k+1}^{\text{sell}}.$$

Then you pay an amount

$$A = p_1^{\text{sell}} q_1^{\text{sell}} + \cdots + p_k^{\text{sell}} q_k^{\text{sell}} + p_{k+1}^{\text{sell}} (q - q_1^{\text{sell}} - \cdots - q_k^{\text{sell}}).$$

Roughly speaking, you work your way through the offers in the order book, from the least (ask) price, and working your way up the order book until you fill the order. We define the *transaction cost* as

$$T(q) = A - p^{\text{mid}} q.$$

This is the difference between what you pay, and what you would have paid had you been able to purchase the shares at the mid-price. It is always positive.

We handle the case of selling the asset in a similar way. Here we take $q < 0$ to mean that we sell $-q$ shares of the asset. Here you sell shares at the bid price, up to the quantity $q^{\text{buy}}$ (or $-q$, whichever is smaller); if needed, you sell shares at the price $p_2^{\text{buy}}$, and so on, until all $-q$ shares are sold. Here we assume that $-q \le q_1^{\text{buy}} + \cdots + q_M^{\text{buy}}$, *i.e.*, you are not selling more shares than the total quantity of offers to buy. Let $A$ denote the amount you receive from the sale. Here we define the transaction cost as

$$T(q) = -p^{\text{mid}} q - A,$$

the difference between the amount you would have received had you sold the shares at the mid-price, and the amount you received. It is always positive. We set $T(0) = 0$.

(a) Show that $T$ is a convex piecewise linear function.

(b) Show that $T(q) \ge (s/2)|q|$, where $s$ is the spread. When would we have $T(q) = (s/2)|q|$ for all $q$ (in the range between the total shares offered to purchase or sell)?

(c) Give an interpretation of the conjugate function $T^*(y) = \sup_q (yq - T(q))$. *Hint.* Suppose you can purchase or sell the asset in another market, at the price $p^{\text{other}}$.

**17.2** *Risk-return trade-off in portfolio optimization.* We consider the portfolio risk-return trade-off problem of page 185, with the following data:

$$\bar{p} = \begin{bmatrix} 0.12 \\ 0.10 \\ 0.07 \\ 0.03 \end{bmatrix}, \quad \Sigma = \begin{bmatrix} 0.0064 & 0.0008 & -0.0011 & 0 \\ 0.0008 & 0.0025 & 0 & 0 \\ -0.0011 & 0 & 0.0004 & 0 \\ 0 & 0 & 0 & 0 \end{bmatrix}.$$

(a) Solve the quadratic program

$$\begin{array}{ll} \text{minimize} & -\bar{p}^T x + \mu x^T \Sigma x \\ \text{subject to} & \mathbf{1}^T x = 1, \quad x \succeq 0 \end{array}$$

for a large number of positive values of $\mu$ (for example, 100 values logarithmically spaced between 1 and $10^7$). Plot the optimal values of the expected return $\bar{p}^T x$ versus the standard deviation $(x^T \Sigma x)^{1/2}$. Also make an area plot of the optimal portfolios $x$ versus the standard deviation (as in figure 4.12).

(b) Assume the price change vector $p$ is a Gaussian random variable, with mean $\bar{p}$ and covariance $\Sigma$. Formulate the problem

$$\begin{array}{ll} \text{maximize} & \bar{p}^T x \\ \text{subject to} & \mathbf{prob}(p^T x \leq 0) \leq \eta \\ & \mathbf{1}^T x = 1, \quad x \succeq 0, \end{array}$$

as a convex optimization problem, where $\eta < 1/2$ is a parameter. In this problem we maximize the expected return subject to a constraint on the probability of a negative return. Solve the problem for a large number of values of $\eta$ between $10^{-4}$ and $10^{-1}$, and plot the optimal values of $\bar{p}^T x$ versus $\eta$. Also make an area plot of the optimal portfolios $x$ versus $\eta$.

*Hint:* The Matlab functions `erfc` and `erfcinv` can be used to evaluate

$$\Phi(x) = (1/\sqrt{2\pi}) \int_{-\infty}^{x} e^{-t^2/2} \, dt$$

and its inverse:

$$\Phi(u) = \frac{1}{2}\mathbf{erfc}(-u/\sqrt{2}).$$

Since you will have to solve this problem for a large number of values of $\eta$, you may find the command `cvx_quiet(true)` helpful.

(c) *Monte Carlo simulation.* Let $x$ be the optimal portfolio found in part (b), with $\eta = 0.05$. This portfolio maximizes the expected return, subject to the probability of a loss being no more than 5%. Generate 10000 samples of $p$, and plot a histogram of the returns. Find the empirical mean of the return samples, and calculate the percentage of samples for which a loss occurs.

*Hint:* You can generate samples of the price change vector using

```
p=pbar+sqrtm(Sigma)*randn(4,1);
```

**17.3** *Simple portfolio optimization.* We consider a portfolio optimization problem as described on pages 155 and 185–186 of *Convex Optimization*, with data that can be found in the file `simple_portfolio_data.*`.

(a) Find minimum-risk portfolios with the same expected return as the uniform portfolio ($x = (1/n)\mathbf{1}$), with risk measured by portfolio return variance, and the following portfolio constraints (in addition to $\mathbf{1}^T x = 1$):

- No (additional) constraints.
- Long-only: $x \succeq 0$.
- Limit on total short position: $\mathbf{1}^T(x_-) \leq 0.5$, where $(x_-)_i = \max\{-x_i, 0\}$.

Compare the optimal risk in these portfolios with each other and the uniform portfolio.

(b) Plot the optimal risk-return trade-off curves for the long-only portfolio, and for total short-position limited to 0.5, in the same figure. Follow the style of figure 4.12 (top), with horizontal axis showing standard deviation of portfolio return (which is $(x^\Sigma x)^{1/2}$), and vertical axis showing mean return.

**17.4** *Bounding portfolio risk with incomplete covariance information.* Consider the following instance of the problem described in §4.6, on p171–173 of *Convex Optimization*. We suppose that $\Sigma_{ii}$, which are the squares of the price volatilities of the assets, are known. For the off-diagonal entries of $\Sigma$, all we know is the sign (or, in some cases, nothing at all). For example, we might be given that $\Sigma_{12} \geq 0$, $\Sigma_{23} \leq 0$, etc. This means that we do not know the correlation between $p_1$ and $p_2$, but we do know that they are nonnegatively correlated (*i.e.*, the prices of assets 1 and 2 tend to rise or fall together).

Compute $\sigma_{\mathrm{wc}}^2$, the worst-case variance of the portfolio return, for the specific case

$$
x = \begin{bmatrix} 0.1 \\ 0.2 \\ -0.05 \\ 0.1 \end{bmatrix}, \quad
\Sigma = \begin{bmatrix}
0.2 & + & + & \pm \\
+ & 0.1 & - & - \\
+ & - & 0.3 & + \\
\pm & - & + & 0.1
\end{bmatrix},
$$

where a "+" entry means that the element is nonnegative, a "−" means the entry is nonpositive, and "$\pm$" means we don't know anything about the entry. (The negative value in $x$ represents a *short position*: you sold stocks that you didn't have, but must produce at the end of the investment period.) In addition to $\sigma_{\mathrm{wc}}^2$, give the covariance matrix $\Sigma_{\mathrm{wc}}$ associated with the maximum risk. Compare the worst-case risk with the risk obtained when $\Sigma$ is diagonal.

**17.5** *Log-optimal investment strategy.* In this problem you will solve a specific instance of the log-optimal investment problem described in exercise 4.60, with $n = 5$ assets and $m = 10$ possible outcomes in each period. The problem data are defined in `log_opt_invest.*`, with the rows of the matrix `P` giving the asset return vectors $p_j^T$. The outcomes are equiprobable, *i.e.*, we have $\pi_j = 1/m$. Each column of the matrix `P` gives the return of the associated asset in the different posible outcomes. You can examine the columns to get an idea of the types of assets. For example, the last asset gives a fixed and certain return of 1%; the first asset is a very risky one, with occasional large return, and (more often) substantial loss.

Find the log-optimal investment strategy $x^\star$, and its associated long term growth rate $R_{\mathrm{lt}}^\star$. Compare this to the long term growth rate obtained with a uniform allocation strategy, *i.e.*, $x = (1/n)\mathbf{1}$, and also with a pure investment in each asset.

For the optimal investment strategy, and also the uniform investment strategy, plot 10 sample trajectories of the accumulated wealth, *i.e.*, $W(T) = W(0) \prod_{t=1}^{T} \lambda(t)$, for $T = 0, \ldots, 200$, with initial wealth $W(0) = 1$.

To save you the trouble of figuring out how to simulate the wealth trajectories or plot them nicely, we've included the simulation and plotting code in `log_opt_invest.*`; you just have to add the code needed to find $x^\star$.

*Hint (Matlab users only):* The current version of CVX handles the logarithm via an iterative method, which can be slow and unreliable. You're better off using `geo_mean()`, which is directly handled by CVX, to solve the problem.

**17.6** *Optimality conditions and dual for log-optimal investment problem.*

(a) Show that the optimality conditions for the log-optimal investment problem described in exercise 4.60 can be expressed as: $\mathbf{1}^T x = 1$, $x \succeq 0$, and for each $i$,

$$x_i > 0 \;\Rightarrow\; \sum_{j=1}^m \pi_j \frac{p_{ij}}{p_j^T x} = 1, \quad x_i = 0 \;\Rightarrow\; \sum_{j=1}^m \pi_j \frac{p_{ij}}{p_j^T x} \leq 1.$$

We can interpret this as follows. $p_{ij}/p_j^T x$ is a random variable, which gives the ratio of the investment gain with asset $i$ only, to the investment gain with our mixed portfolio $x$. The optimality condition is that, for each asset we invest in, the expected value of this ratio is one, and for each asset we do not invest in, the expected value cannot exceed one. Very roughly speaking, this means our portfolio does as well as any of the assets that we choose to invest in, and cannot do worse than any assets that we do not invest in.

*Hint.* You can start from the simple criterion given in §4.2.3 or the KKT conditions.

(b) In this part we will derive the dual of the log-optimal investment problem. We start by writing the problem as

$$\begin{array}{ll} \text{minimize} & -\sum_{j=1}^m \pi_j \log y_j \\ \text{subject to} & y = P^T x, \quad x \succeq 0, \quad \mathbf{1}^T x = 1. \end{array}$$

Here, $P$ has columns $p_1, \ldots, p_m$, and we have the introduced new variables $y_1, \ldots, y_m$, with the implicit constraint $y \succ 0$. We will associate dual variables $\nu$, $\lambda$ and $\nu_0$ with the constraints $y = P^T x$, $x \succeq 0$, and $\mathbf{1}^T x = 1$, respectively. Defining $\tilde\nu_j = \nu_j/\nu_0$ for $j = 1, \ldots, m$, show that the dual problem can be written as

$$\begin{array}{ll} \text{maximize} & \sum_{j=1}^m \pi_j \log(\tilde\nu_j/\pi_j) \\ \text{subject to} & P\tilde\nu \preceq \mathbf{1}, \end{array}$$

with variable $\tilde\nu$. The objective here is the (negative) Kullback-Leibler divergence between the given distribution $\pi$ and the dual variable $\tilde\nu$.

**17.7** *Arbitrage and theorems of alternatives.* Consider an event (for example, a sports game, political elections, the evolution of the stock market over a certain period) with $m$ possible outcomes. Suppose that $n$ wagers on the outcome are possible. If we bet an amount $x_j$ on wager $j$, and the outcome of the event is $i$ $(i = 1, \ldots, m)$, then our return will be equal to $r_{ij}x_j$. The return $r_{ij}x_j$ is the net gain: we pay $x_j$ initially, and receive $(1 + r_{ij})x_j$ if the outcome of the event is $i$. We allow the bets $x_j$ to be positive, negative, or zero. The interpretation of a negative bet is as follows. If $x_j < 0$, then initially we *receive* an amount of money $|x_j|$, with an obligation to *pay* $(1 + r_{ij})|x_j|$ if outcome $i$ occurs. In that case, we lose $r_{ij}|x_j|$, *i.e.*, our net is gain $r_{ij}x_j$ (a negative number).

| Country | Odds | | Country | Odds |
|---|---|---|---|---|
| Holland | 3.5 | | Czech Republic | 17.0 |
| Italy | 5.0 | | Romania | 18.0 |
| Spain | 5.5 | | Yugoslavia | 20.0 |
| France | 6.5 | | Portugal | 20.0 |
| Germany | 7.0 | | Norway | 20.0 |
| England | 10.0 | | Denmark | 33.0 |
| Belgium | 14.0 | | Turkey | 50.0 |
| Sweden | 16.0 | | Slovenia | 80.0 |

Table 1: Odds for the 2000 European soccer championships.

We call the matrix $R \in \mathbf{R}^{m \times n}$ with elements $r_{ij}$ the *return matrix*. A *betting strategy* is a vector $x \in \mathbf{R}^n$, with as components $x_j$ the amounts we bet on each wager. If we use a betting strategy $x$, our total return in the event of outcome $i$ is equal to $\sum_{j=1}^n r_{ij} x_j$, *i.e.*, the $i$th component of the vector $Rx$.

(a) *The arbitrage theorem.* Suppose you are given a return matrix $R$. Prove the following theorem: there is a betting strategy $x \in \mathbf{R}^n$ for which

$$Rx \succ 0$$

if and only if there exists no vector $p \in \mathbf{R}^m$ that satisfies

$$R^T p = 0, \qquad p \succeq 0, \qquad p \neq 0.$$

We can interpret this theorem as follows. If $Rx \succ 0$, then the betting strategy $x$ guarantees a positive return for all possible outcomes, *i.e.*, it is a sure-win betting scheme. In economics, we say there is an *arbitrage opportunity*.

If we normalize the vector $p$ in the second condition, so that $\mathbf{1}^T p = 1$, we can interpret it as a probability vector on the outcomes. The condition $R^T p = 0$ means that

$$\mathbf{E}\, Rx = p^T Rx = 0$$

for all $x$, *i.e.*, the expected return is zero for all betting strategies. In economics, $p$ is called a risk neutral probability.

We can therefore rephrase the arbitrage theorem as follows: There is no sure-win betting strategy (or arbitrage opportunity) if and only if there is a probability vector on the outcomes that makes all bets fair (*i.e.*, the expected gain is zero).

(b) *Betting.* In a simple application, we have exactly as many wagers as there are outcomes ($n = m$). Wager $i$ is to bet that the outcome will be $i$. The returns are usually expressed as *odds*. For example, suppose that a bookmaker accepts bets on the result of the 2000 European soccer championships. If the odds against Belgium winning are 14 to one, and we bet $100 on Belgium, then we win $1400 if they win the tournament, and we lose $100 otherwise.

In general, if we have $m$ possible outcomes, and the odds against outcome $i$ are $\lambda_i$ to one, then the return matrix $R \in \mathbf{R}^{m \times m}$ is given by

$$
\begin{aligned}
r_{ij} &= \lambda_i & \text{if } j = i \\
r_{ij} &= -1 & \text{otherwise.}
\end{aligned}
$$

Show that there is no sure-win betting scheme (or arbitrage opportunity) if

$$
\sum_{i=1}^{m} \frac{1}{1 + \lambda_i} = 1.
$$

In fact, you can verify that if this equality is not satisfied, then the betting strategy

$$
x_i = \frac{1/(1 + \lambda_i)}{1 - \sum_{i=1}^{m} 1/(1 + \lambda_i)}
$$

always results in a profit.

The common situation in real life is

$$
\sum_{i=1}^{m} \frac{1}{1 + \lambda_i} > 1,
$$

because the bookmakers take a cut on all bets.

(c) *Option pricing.* The arbitrage theorem is a key result in mathematical finance, where it is used to determine prices of contracts. As a simple example, suppose we can invest in two assets: a stock and an option.

The current unit price of the stock is $S$. The price $\bar{S}$ of the stock at the end of the investment period is unknown, but it will be either $\bar{S} = Su$ or $\bar{S} = Sd$, where $u > 1$ and $d < 1$ are given numbers. In other words the price either goes up by a factor $u$, or down by a factor $d$. If the current interest rate over the investment period is $r$, then the present value of the stock price $\bar{S}$ at the end of the period is equal to $\bar{S}/(1 + r)$, and our unit return is

$$
\frac{Su}{1 + r} - S = S\frac{u - r}{1 + r}
$$

if the stock goes up, and

$$
\frac{Sd}{1 + r} - S = S\frac{d - r}{1 + r}
$$

if the stock goes down.

We can also buy options, at a unit price of $C$. An option gives us the right to purchase one stock at a fixed price $K$ at the end of the period. Whether we exercise the option or not depends on the price of the stock at the end of the period. If the stock price $\bar{S}$ at the end of the period is greater than $K$, we exercise the option, buy the stock and sell it immediately, so we receive an amount $\bar{S} - K$. If the stock price $\bar{S}$ is less than $K$, we do not exercise the option and receive nothing. Combining both cases, we can say that the value of the option at the end of the period is $\max\{0, \bar{S} - K\}$, and the present value is $\max\{0, \bar{S} - K\}/(1 + r)$. If we pay a price $C$ per option, then our return is

$$
\frac{1}{1 + r} \max\{0, \bar{S} - K\} - C
$$

per option.

We can summarize the situation with the return matrix

$$R = \begin{bmatrix} \dfrac{u-1-r}{1+r} & \dfrac{\max\{0, Su-K\}}{(1+r)C} - 1 \\[4mm] \dfrac{d-1-r}{1+r} & \dfrac{\max\{0, Sd-K\}}{(1+r)C} - 1 \end{bmatrix}.$$

The elements of the first row are the (present values of the) returns in the event that the stock price goes up. The second row are the returns in the event that the stock price goes down. The first column gives the returns per unit investment in the stock. The second column gives the returns per unit investment in the option.

In this simple example the arbitrage theorem allows us to determine the price of the option, given the other information $S$, $K$, $u$, $d$, and $r$. Show that if there is no arbitrage, then the price of the option $C$ must be equal to

$$\frac{1}{1+r}\left(p \max\{0, Su-K\} + (1-p)\max\{0, Sd-K\}\right)$$

where

$$p = \frac{1+r-d}{u-d}.$$

**17.8** *Log-optimal investment.* We consider an instance of the log-optimal investment problem described in exercise 4.60 of *Convex Optimization*. In this exercise, however, we allow $x$, the allocation vector, to have negative components. Investing a negative amount $x_i W(t)$ in an asset is called *shorting* the asset. It means you borrow the asset, sell it for $|x_i W(t)|$, and have an obligation to purchase it back later and return it to the lender.

(a) Let $R$ be the $n \times m$-matrix with columns $r_j$:

$$R = \begin{bmatrix} r_1 & r_2 & \cdots & r_m \end{bmatrix}.$$

We assume that the elements $r_{ij}$ of $R$ are all positive, which implies that the log-optimal investment problem is feasible. Show the following property: if there exists a $v \in \mathbf{R}^n$ with

$$\mathbf{1}^T v = 0, \qquad R^T v \succeq 0, \qquad R^T v \neq 0 \tag{68}$$

then the log-optimal investment problem is unbounded (assuming that the probabilities $p_j$ are all positive).

(b) Derive a Lagrange dual of the log-optimal investment problem (or an equivalent problem of your choice). Use the Lagrange dual to show that the condition in part a is also necessary for unboundedness. In other words, the log-optimal investment problem is bounded if and only if there does not exist a $v$ satisfying (68).

(c) Consider the following small example. We have four scenarios and three investment options. The return vectors for the four scenarios are

$$r_1 = \begin{bmatrix} 2 \\ 1.3 \\ 1 \end{bmatrix}, \qquad r_2 = \begin{bmatrix} 2 \\ 0.5 \\ 1 \end{bmatrix}, \qquad r_3 = \begin{bmatrix} 0.5 \\ 1.3 \\ 1 \end{bmatrix}, \qquad r_4 = \begin{bmatrix} 0.5 \\ 0.5 \\ 1 \end{bmatrix}.$$

The probabilities of the three scenarios are

$$p_1 = 1/3, \qquad p_2 = 1/6, \qquad p_3 = 1/3, \qquad p_4 = 1/6.$$

The interpretation is as follows. We can invest in two stocks. The first stock doubles in value in each period with a probability $1/2$, or decreases by $50\%$ with a probability $1/2$. The second stock either increases by $30\%$ with a probability $2/3$, or decreases by $50\%$ with a probability $1/3$. The fluctuations in the two stocks are independent, so we have four scenarios: both stocks go up (probability $2/6$), stock 1 goes up and stock 2 goes down (probability $1/6$), stock 1 goes down and stock 2 goes up (probability $1/3$), both stocks go down (probability $1/6$). The fractions of our capital we invest in stocks 1 and 2 are denoted by $x_1$ and $x_2$, respectively. The rest of our capital, $x_3 = 1 - x_1 - x_2$ is not invested.

What is the expected growth rate of the log-optimal strategy $x$? Compare with the strategies $(x_1, x_2, x_3) = (1, 0, 0)$, $(x_1, x_2, x_3) = (0, 1, 0)$ and $(x_1, x_2, x_3) = (1/2, 1/2, 0)$. (Obviously the expected growth rate for $(x_1, x_2, x_3) = (0, 0, 1)$ is zero.)

*Remark.* The figure below shows a simulation that compares three investment strategies over 200 periods. The solid line shows the log-optimal investment strategy. The dashed lines show the growth for strategies $x = (1, 0, 0)$, $(0, 1, 0)$, and $(0, 0, 1)$.



**17.9** *Maximizing house profit in a gamble and imputed probabilities.* A set of $n$ participants bet on which one of $m$ outcomes, labeled $1, \ldots, m$, will occur. Participant $i$ offers to purchase up to $q_i > 0$ gambling contracts, at price $p_i > 0$, that the true outcome will be in the set $S_i \subset \{1, \ldots, m\}$. The house then sells her $x_i$ contracts, with $0 \le x_i \le q_i$. If the true outcome $j$ is in $S_i$, then participant $i$ receives \$1 per contract, *i.e.*, $x_i$. Otherwise, she loses, and receives nothing. The house collects a total of $x_1 p_1 + \cdots + x_n p_n$, and pays out an amount that depends on the outcome $j$,

$$\sum_{i:\, j \in S_i} x_i.$$

202

The difference is the house profit.

(a) *Optimal house strategy.* How should the house decide on $x$ so that its worst-case profit (over the possible outcomes) is maximized? (The house determines $x$ after examining all the participant offers.)

(b) *Imputed probabilities.* Suppose $x^\star$ maximizes the worst-case house profit. Show that there exists a probability distribution $\pi$ on the possible outcomes (*i.e.*, $\pi \in \mathbf{R}_+^m$, $\mathbf{1}^T \pi = 1$) for which $x^\star$ also maximizes the expected house profit. Explain how to find $\pi$.

*Hint.* Formulate the problem in part (a) as an LP; you can construct $\pi$ from optimal dual variables for this LP.

*Remark.* Given $\pi$, the 'fair' price for offer $i$ is $p_i^{\text{fair}} = \sum_{j \in S_i} \pi_j$. All offers with $p_i > p_i^{\text{fair}}$ will be completely filled (*i.e.*, $x_i = q_i$); all offers with $p_i < p_i^{\text{fair}}$ will be rejected (*i.e.*, $x_i = 0$).

*Remark.* This exercise shows how the probabilities of outcomes (*e.g.*, elections) can be guessed from the offers of a set of gamblers.

(c) *Numerical example.* Carry out your method on the simple example below with $n = 5$ participants, $m = 5$ possible outcomes, and participant offers

| Participant $i$ | $p_i$ | $q_i$ | $S_i$ |
|---|---|---|---|
| 1 | 0.50 | 10 | {1,2} |
| 2 | 0.60 | 5 | {4} |
| 3 | 0.60 | 5 | {1,4,5} |
| 4 | 0.60 | 20 | {2,5} |
| 5 | 0.20 | 10 | {3} |

Compare the optimal worst-case house profit with the worst-case house profit, if all offers were accepted (*i.e.*, $x_i = q_i$). Find the imputed probabilities.

**17.10** *Optimal investment to fund an expense stream.* An organization (such as a municipality) knows its operating expenses over the next $T$ periods, denoted $E_1, \ldots, E_T$. (Normally these are positive; but we can have negative $E_t$, which corresponds to income.) These expenses will be funded by a combination of investment income, from a mixture of bonds purchased at $t = 0$, and a cash account.

The bonds generate investment income, denoted $I_1, \ldots, I_T$. The cash balance is denoted $B_0, \ldots, B_T$, where $B_0 \geq 0$ is the amount of the initial deposit into the cash account. We can have $B_t < 0$ for $t = 1, \ldots, T$, which represents borrowing.

After paying for the expenses using investment income and cash, in period $t$, we are left with $B_t - E_t + I_t$ in cash. If this amount is positive, it earns interest at the rate $r_+ > 0$; if it is negative, we must pay interest at rate $r_-$, where $r_- \geq r_+$. Thus the expenses, investment income, and cash balances are linked as follows:

$$B_{t+1} = \begin{cases} (1 + r_+)(B_t - E_t + I_t) & B_t - E_t + I_t \geq 0 \\ (1 + r_-)(B_t - E_t + I_t) & B_t - E_t + I_t < 0, \end{cases}$$

for $t = 1, \ldots, T - 1$. We take $B_1 = (1 + r_+)B_0$, and we require that $B_T - E_T + I_T = 0$, which means the final cash balance, plus income, exactly covers the final expense.

The initial investment will be a mixture of bonds, labeled $1, \ldots, n$. Bond $i$ has a price $P_i > 0$, a coupon payment $C_i > 0$, and a maturity $M_i \in \{1, \ldots, T\}$. Bond $i$ generates an income stream

given by

$$a_t^{(i)} = \begin{cases} C_i & t < M_i \\ C_i + 1 & t = M_i \\ 0 & t > M_i, \end{cases}$$

for $t = 1, \ldots, T$. If $x_i$ is the number of units of bond $i$ purchased (at $t = 0$), the total investment cash flow is

$$I_t = x_1 a_t^{(1)} + \cdots + x_n a_t^{(n)}, \quad t = 1, \ldots, T.$$

We will require $x_i \geq 0$. (The $x_i$ can be fractional; they do not need to be integers.)

The total initial investment required to purchase the bonds, and fund the initial cash balance at $t = 0$, is $x_1 P_1 + \cdots + x_n P_n + B_0$.

(a) Explain how to choose $x$ and $B_0$ to minimize the total initial investment required to fund the expense stream.

(b) Solve the problem instance given in `opt_funding_data.m`. Give optimal values of $x$ and $B_0$. Give the optimal total initial investment, and compare it to the initial investment required if no bonds were purchased (which would mean that all the expenses were funded from the cash account). Plot the cash balance (versus period) with optimal bond investment, and with no bond investment.

**17.11** *Planning production with uncertain demand.* You must order (nonnegative) amounts $r_{\mathrm{I}}, \ldots, r_m$ of raw materials, which are needed to manufacture (nonnegative) quantities $q_1, \ldots, q_n$ of $n$ different products. To manufacture one unit of product $j$ requires at least $A_{ij}$ units of raw material $i$, so we must have $r \succeq Aq$. (We will assume that $A_{ij}$ are nonnegative.) The per-unit cost of the raw materials is given by $c \in \mathbf{R}_+^m$, so the total raw material cost is $c^T r$.

The (nonnegative) demand for product $j$ is denoted $d_j$; the number of units of product $j$ sold is $s_j = \min\{q_j, d_j\}$. (When $q_j > d_j$, $q_j - d_j$ is the amount of product $j$ produced, but not sold; when $d_j > q_j$, $d_j - q_j$ is the amount of unmet demand.) The revenue from selling the products is $p^T s$, where $p \in \mathbf{R}_+^n$ is the vector of product prices. The profit is $p^T s - c^T r$. (Both $d$ and $q$ are real vectors; their entries need not be integers.)

You are given $A$, $c$, and $p$. The product demand, however, is not known. Instead, a set of $K$ possible demand vectors, $d^{(1)}, \ldots, d^{(K)}$, with associated probabilities $\pi_1, \ldots, \pi_K$, is given. (These satisfy $\mathbf{1}^T \pi = 1$, $\pi \succeq 0$.)

You will explore two different optimization problems that arise in choosing $r$ and $q$ (the variables).

**I. Choose $r$ and $q$ ahead of time.** You must choose $r$ and $q$, knowing only the data listed above. (In other words, you must order the raw materials, and commit to producing the chosen quantities of products, before you know the product demand.) The objective is to maximize the expected profit.

**II. Choose $r$ ahead of time, and $q$ after $d$ is known.** You must choose $r$, knowing only the data listed above. Some time after you have chosen $r$, the demand will become known to you. This means that you will find out which of the $K$ demand vectors is the true demand. Once you know this, you must choose the quantities to be manufactured. (In other words, you must order

the raw materials before the product demand is known; but you can choose the mix of products to manufacture after you have learned the true product demand.) The objective is to maximize the expected profit.

(a) Explain how to formulate each of these problems as a convex optimization problem. Clearly state what the variables are in the problem, what the constraints are, and describe the roles of any auxiliary variables or constraints you introduce.

(b) Carry out the methods from part (a) on the problem instance with numerical data given in `planning_data.m`. This file will define A, D, K, c, m, n, p and pi. The $K$ columns of $D$ are the possible demand vectors. For both of the problems described above, give the optimal value of $r$, and the expected profit.

**17.12** *Gini coefficient of inequality.* Let $x_1, \ldots, x_n$ be a set of nonnegative numbers with positive sum, which typically represent the wealth or income of $n$ individuals in some group. The *Lorentz curve* is a plot of the fraction $f_i$ of total wealth held by the $i$ poorest individuals,

$$f_i = (1/\mathbf{1}^T x) \sum_{j=1}^{i} x_{(j)}, \quad i = 0, \ldots, n,$$

versus $i/n$, where $x_{(j)}$ denotes the $j$th smallest of the numbers $\{x_1, \ldots, x_n\}$, and we take $f_0 = 0$. The Lorentz curve starts at $(0,0)$ and ends at $(1,1)$. Interpreted as a continuous curve (as, say, $n \to \infty$) the Lorentz curve is convex and increasing, and lies on or below the straight line joining the endpoints. The curve coincides with this straight line, *i.e.*, $f_i = (i/n)$, if and only if the wealth is distributed equally, *i.e.*, the $x_i$ are all equal.

The *Gini coefficient* is defined as twice the area between the straight line corresponding to uniform wealth distribution and the Lorentz curve:

$$G(x) = (2/n) \sum_{i=1}^{n} ((i/n) - f_i).$$

The Gini coefficient is used as a measure of wealth or income inequality: It ranges between 0 (for equal distribution of wealth) and $1 - 1/n$ (when one individual holds all wealth).

(a) Show that $G$ is a quasiconvex function on $x \in \mathbf{R}^n_+ \setminus \{0\}$.

(b) *Gini coefficient and marriage.* Suppose that individuals $i$ and $j$ get married ($i \neq j$) and therefore pool wealth. This means that $x_i$ and $x_j$ are both replaced with $(x_i + x_j)/2$. What can you say about the change in Gini coefficient caused by this marriage?

**17.13** *Internal rate of return for cash streams with a single initial investment.* We use the notation of example 3.34 in the textbook. Let $x \in \mathbf{R}^{n+1}$ be a cash flow over $n$ periods, with $x$ indexed from 0 to $n$, where the index denotes period number. We assume that $x_0 < 0$, $x_j \geq 0$ for $j = 1, \ldots, n$, and $x_0 + \cdots + x_n > 0$. This means that there is an initial positive investment; thereafter, only payments are made, with the total of the payments exceeding the initial investment. (In the more general setting of example 3.34, we allow additional investments to be made after the initial investment.)

(a) Show that $\text{IRR}(x)$ is quasilinear in this case.

(b) *Blending initial investment only streams.* Use the result in part (a) to show the following. Let $x^{(i)} \in \mathbf{R}^{n+1}$, $i = 1, \dots, k$, be a set of $k$ cash flows over $n$ periods, each of which satisfies the conditions above. Let $w \in \mathbf{R}_+^k$, with $\mathbf{1}^T w = 1$, and consider the blended cash flow given by $x = w_1 x^{(1)} + \cdots + w_k x^{(k)}$. (We can think of this as investing a fraction $w_i$ in cash flow $i$.) Show that $\mathrm{IRR}(x) \le \max_i \mathrm{IRR}(x^{(i)})$. Thus, blending a set of cash flows (with initial investment only) will not improve the IRR over the best individual IRR of the cash flows.

**17.14** *Efficient solution of basic portfolio optimization problem.* This problem concerns the simplest possible portfolio optimization problem:

$$
\begin{array}{ll}
\text{maximize} & \mu^T w - (\lambda/2) w^T \Sigma w \\
\text{subject to} & \mathbf{1}^T w = 1,
\end{array}
$$

with variable $w \in \mathbf{R}^n$ (the normalized portfolio, with negative entries meaning short positions), and data $\mu$ (mean return), $\Sigma \in \mathbf{S}_{++}^n$ (return covariance), and $\lambda > 0$ (the risk aversion parameter). The return covariance has the factor form $\Sigma = FQF^T + D$, where $F \in \mathbf{R}^{n \times k}$ (with rank $K$) is the *factor loading matrix*, $Q \in \mathbf{S}_{++}^k$ is the factor covariance matrix, and $D$ is a diagonal matrix with positive entries, called the *idiosyncratic risk* (since it describes the risk of each asset that is independent of the factors). This form for $\Sigma$ is referred to as a '$k$-factor risk model'. Some typical dimensions are $n = 2500$ (assets) and $k = 30$ (factors).

(a) What is the flop count for computing the optimal portfolio, if the low-rank plus diagonal structure of $\Sigma$ is *not* exploited? You can assume that $\lambda = 1$ (which can be arranged by absorbing it into $\Sigma$).

(b) Explain how to compute the optimal portfolio more efficiently, and give the flop count for your method. You can assume that $k \ll n$. You do not have to give the best method; any method that has linear complexity in $n$ is fine. You can assume that $\lambda = 1$.

*Hints.* You may want to introduce a new variable $y = F^T w$ (which is called the vector of factor exposures). You may want to work with the matrix

$$
G = \begin{bmatrix} \mathbf{1} & F \\ 0 & -I \end{bmatrix} \in \mathbf{R}^{(n+k) \times (1+k)},
$$

treating it as dense, ignoring the (little) exploitable structure in it.

(c) Carry out your method from part (b) on some randomly generated data with dimensions $n = 2500$, $k = 30$. For comparison (and as a check on your method), compute the optimal portfolio using the method of part (a) as well. Give the (approximate) CPU time for each method, using `tic` and `toc` in Matlab, or by computing the difference of `time.time()` in Python. *Hints.* After you generate $D$ and $Q$ randomly, you might want to add a positive multiple of the identity to each, to avoid any issues related to poor conditioning. Also, to be able to invert a block diagonal matrix efficiently, you'll need to recast it as sparse.

(d) *Risk return trade-off curve.* Now suppose we want to compute the optimal portfolio for $M$ values of the risk aversion parameter $\lambda$. Explain how to do this efficiently, and give the complexity in terms of $M$, $n$, and $k$. Compare to the complexity of using the method of part (b) $M$ times. *Hint.* Show that the optimal portfolio is an affine function of $1/\lambda$.

**17.15** *Sparse index tracking.* The (weekly, say) return of $n$ stocks is given by a random variable $r \in \mathbf{R}^n$, with mean $\bar{r}$ and covariance $\mathbf{E}(r - \bar{r})(r - \bar{r})^T = \Sigma \succ 0$. An index (such as S&P 500 or Wilshire 5000) is a weighted sum of these returns, given by $z = c^T r$, where $c \in \mathbf{R}^n_+$. (For example, the vector $c$ is nonzero only for the stocks in the index, and the coefficients $c_i$ might be proportional to some measure of market capitalization of stock $i$.) We will assume that the index weights $c \in \mathbf{R}^n$, as well as the return mean and covariance $\bar{r}$ and $\Sigma$, are known and fixed.

Our goal is to find a *sparse* weight vector $w \in \mathbf{R}^n$, which can include negative entries (meaning, short positions), so that the RMS index tracking error, defined as

$$E = \left( \frac{\mathbf{E}(z - w^T r)^2}{\mathbf{E}\, z^2} \right)^{1/2},$$

does not exceed 0.10 (*i.e.*, 10%). Of course, taking $w = c$ results in $E = 0$, but we are interested in finding a weight vector with (we hope) many fewer nonzero entries than $c$ has.

*Remark.* This is the idea behind an *index fund*: You find a sparse portfolio that replicates or tracks the return of the index (within some error tolerance). Acquiring (and rebalancing) the sparse tracking portfolio will incur smaller transactions costs than trading in the full index.

(a) Propose a (simple) heuristic method for finding a sparse weight vector $w$ that satisfies $E \le 0.10$.

(b) Carry out your method on the problem instance given in `sparse_idx_track_data.m`. Give $\mathbf{card}(w)$, the number of nonzero entries in $w$. (To evaluate $\mathbf{card}(w)$, use `sum(abs(w)>0.01)`, which treats weight components smaller than 0.01 as zero.) (You might want to compare the index weights and the weights you find by typing `[c w]`. No need to print or turn in the resulting output, though.)

**17.16** *Option price bounds.* In this problem we use the methods and results of example 5.10 to give bounds on the arbitrage-free price of an option. (See exercise 5.38 for a simple version of option pricing.) We will use all the notation and definitions from example 5.10.

We consider here options on an underlying asset (such as a stock); these have a payoff or value that depends on $S$, the value of the underlying asset at the end of the investment period. We will assume that the underlying asset can only take on $m$ different values, $S^{(1)}, \ldots, S^{(m)}$. These correspond to the $m$ possible scenarios or outcomes described in example 5.10.

A risk-free asset has value (or payoff) $r > 1$ in every scenario. (We refer to $r - 1$ as the risk-free interest rate.) The value of the underlying asset is simply $S$.

A *put option* at *strike price* $K$ gives the owner the right to sell one unit of the underlying stock at price $K$. At the end of the investment period, if the stock is trading at a price $S$, then the put option has payoff $(K - S)_+ = \max\{0, K - S\}$ (since the option is exercised only if $K > S$). Similarly a *call option* at strike price $K$ gives the buyer the right to buy a unit of stock at price $K$. A call option has payoff $(S - K)_+ = \max\{0, S - K\}$.

A *collar* is an option with payoff

$$\phi(S) = \min(C, \max(F, S)) = \begin{cases} C & S > C \\ S & F \le S \le C \\ F & S < F \end{cases}$$

where $F$ is the *floor* and $C$ is the *cap*, with $0 < F < C$. A collar option limits both the upside and downside of payoff.

These payoffs, which are functions of $S$ (the price of the underlying stock at the end of the period) are listed in the table below.

| Asset/option | Payoff/value |
|---|---|
| Risk-free asset | $r$ |
| Underlying stock | $S$ |
| Put option with strike price $K$ | $(K - S)_+$ |
| Call option with strike price $K$ | $(S - K)_+$ |
| Collar with floor $F$ and cap $C$ | $\min(C, \max(F, S))$ |

Now we consider a specific problem. The price of the risk-free asset, with $r = 1.05$, is 1. The price of the underlying asset is $S_0 = 1$. We will use $m = 200$ scenarios, with $S^{(i)}$ uniformly spaced from $S^{(1)} = 0.5$ to $S^{(200)} = 2$. The following options are traded on an exchange, with prices listed below.

| Type | Strike | Price |
|---|---|---|
| Call | 1.1 | 0.06 |
| Call | 1.2 | 0.03 |
| Put | 0.8 | 0.02 |
| Put | 0.7 | 0.01. |

A collar with floor $F = 0.9$ and cap $C = 1.15$ is not traded on an exchange, so we do not know its market price. We wish to determine what prices for it would be appropriate. Find the range of prices for this collar, consistent with the absence of arbitrage and the prices of the call and put options above above.

There are 7 assets in total: The risk-free one, the underlying stock, two call options, two put options, and one collar. We are given the prices of each of these except the last.

**17.17** *Portfolio optimization with qualitative return forecasts.* We consider the risk-return portfolio optimization problem described on pages 155 and 185 of the book, with one twist: We don't precisely know the mean return vector $\bar{p}$. Instead, we have a range of possible values for each asset, *i.e.*, we have $l$, $u \in \mathbf{R}^n$ with $l \preceq \bar{p} \preceq u$. We use $l$ and $u$ to encode various qualitative forecasts we have about the mean return vector $\bar{p}$. For example, $l_7 = 0.02$ and $u_7 = 0.20$ means that we believe the mean return for asset 7 is between 2% and 20%.

Define the *worst-case mean return* $R^{\mathrm{wc}}$, as a function of portfolio vector $x$, as the worst (minimum) value of $\bar{p}^T x$, over all $\bar{p}$ consistent with the given bounds $l$ and $u$.

(a) Explain how to find a portfolio $x$ that maximizes $R^{\mathrm{wc}}$, subject to a budget constraint and risk limit,
$$\mathbf{1}^T x = 1, \qquad x^T \Sigma x \leq \sigma_{\max}^2,$$
where $\Sigma \in \mathbf{S}_{++}^n$ and $\sigma_{\max} \in \mathbf{R}_{++}$ are given.

(b) Solve the problem instance given in `port_qual_forecasts_data.m`. Give the optimal worst-case mean return achieved by the optimal portfolio $x^\star$.

In addition, construct a portfolio $x^{\mathrm{mid}}$ that maximizes $c^T x$ subject to the budget constraint and risk limit, where $c = (1/2)(l + u)$. This is the optimal portfolio assuming that the mean return has the midpoint value of the forecasts. Compare the midpoint mean returns $c^T x^{\mathrm{mid}}$ and $c^T x^\star$, and the worst-case mean returns of $x^{\mathrm{mid}}$ and $x^\star$.

Briefly comment on the results.

**17.18** *De-leveraging.* We consider a multi-period portfolio optimization problem, with $n$ assets and $T$ time periods, where $x_t \in \mathbf{R}^n$ gives the holdings (say, in dollars) at time $t$, with negative entries denoting, as usual, short positions. For each time period the return vector has mean $\mu \in \mathbf{R}^n$ and covariance $\Sigma \in \mathbf{S}_{++}^n$. (These are known.)

The initial portfolio $x_0$ maximizes the risk-adjusted expected return $\mu^T x - \gamma x^T \Sigma x$, where $\gamma > 0$, subject to the leverage limit constraint $\|x\|_1 \le L^{\mathrm{init}}$, where $L^{\mathrm{init}} > 0$ is the given initial leverage limit. (There are several different ways to measure leverage; here we use the sum of the total short and long positions.) The final portfolio $x_T$ maximizes the risk-adjusted return, subject to $\|x\|_1 \le L^{\mathrm{new}}$, where $L^{\mathrm{new}} > 0$ is the given final leverage limit (with $L^{\mathrm{new}} < L^{\mathrm{init}}$). This uniquely determines $x_0$ and $x_T$, since the objective is strictly concave.

The question is how to move from $x_0$ to $x_T$, *i.e.*, how to choose $x_1, \dots, x_{T-1}$. We will do this so as to maximize the objective

$$J = \sum_{t=1}^{T} \left( \mu^T x_t - \gamma x_t^T \Sigma x_t - \phi(x_t - x_{t-1}) \right),$$

which is the total risk-adjusted expected return, minus the total transaction cost. The transaction cost function $\phi$ has the form

$$\phi(u) = \sum_{i=1}^{n} \left( \kappa_i |u_i| + \lambda_i u_i^2 \right),$$

where $\kappa \succeq 0$ and $\lambda \succeq 0$ are known parameters. We will require that $\|x_t\|_1 \le L^{\mathrm{init}}$, for $t = 1, \dots, T-1$. In other words, the leverage limit is the initial leverage limit up until the deadline $T$, when it drops to the new lower value.

(a) Explain how to find the portfolio sequence $x_1^\star, \dots, x_{T-1}^\star$ that maximizes $J$ subject to the leverage limit constraints.

(b) Find the optimal portfolio sequence $x_t^\star$ for the problem instance with data given in `deleveraging_data.m`. Compare this sequence with two others: $x_t^{\mathrm{lp}} = x_0$ for $t = 1, \dots, T-1$ (*i.e.*, one that does all trading at the last possible period), and the linearly interpolated portfolio sequence

$$x_t^{\mathrm{lin}} = (1 - t/T)x_0 + (t/T)x_T, \quad t = 1, \dots, T-1.$$

For each of these three portfolio sequences, give the objective value obtained, and plot the risk and transaction cost adjusted return,

$$\mu^T x_t - \gamma x_t^T \Sigma x_t - \phi(x_t - x_{t-1}),$$

and the leverage $\|x_t\|_1$, versus $t$, for $t = 0, \dots, T$. Also, for each of the three portfolio sequences, generate a single plot that shows how the holdings $(x_t)_i$ of the $n$ assets change over time, for $i = 1, \dots, n$.

Give a *very short* (one or two sentence) intuitive explanation of the results.

**17.19** *Worst-case variance.* Suppose $Z$ is a random variable on $\mathbf{R}^n$ with covariance matrix $\Sigma \in \mathbf{S}_+^n$. Let $c \in \mathbf{R}^n$. The variance of $Y = c^T Z$ is $\mathbf{var}(Y) = c^T \Sigma c$. We define the *worst-case variance* of $Y$, denoted $\mathbf{wcvar}(Y)$, as the maximum possible value of $c^T \tilde{\Sigma} c$, over all $\tilde{\Sigma} \in \mathbf{S}_+^n$ that satisfy $\Sigma_{ii} = \tilde{\Sigma}_{ii}$, $i = 1, \ldots, n$. In other words, the worst-case variance of $Y$ is the maximum possible variance, if we are allowed to arbitrarily change the correlations between $Z_i$ and $Z_j$. Of course we have $\mathbf{wcvar}(Y) \geq \mathbf{var}(Y)$.

(a) Find a simple expression for $\mathbf{wcvar}(Y)$ in terms of $c$ and the diagonal entries of $\Sigma$. You must justify your expression.

(b) *Portfolio optimization.* Explain how to find the portfolio $x \in \mathbf{R}^n$ that maximizes the expected return $\mu^T x$ subject to a limit on risk, $\mathbf{var}(r^T x) = x^T \Sigma x \leq R$, and a limit on worst-case risk $\mathbf{wcvar}(r^T x) \leq R^{\text{wc}}$, where $R > 0$ and $R^{\text{wc}} > R$ are given. Here $\mu = \mathbf{E}\, r$ and $\Sigma = \mathbf{E}(r - \mu)(r - \mu)^T$ are the (given) mean and covariance of the (random) return vector $r \in \mathbf{R}^n$.

(c) Carry out the method of part (b) for the problem instance with data given in `wc_risk_portfolio_opt_data.m`. Also find the optimal portfolio when the worst-case risk limit is ignored. Find the expected return and worst-case risk for these two portfolios.

*Remark.* If a portfolio is highly leveraged, and the correlations in the returns change drastically, you (the portfolio manager) can be in big trouble, since you are now exposed to much more risk than you thought you were. And yes, this (almost exactly) has happened.

**17.20** *Risk budget allocation.* Suppose an amount $x_i > 0$ is invested in $n$ assets, labeled $i = 1, \ldots, n$, with asset return covariance matrix $\Sigma \in \mathbf{S}_{++}^n$. We define the *risk* of the investments as the standard deviation of the total return, $R(x) = (x^T \Sigma x)^{1/2}$.

We define the (relative) *risk contribution* of asset $i$ (in the portfolio $x$) as

$$\rho_i = \frac{\partial \log R(x)}{\partial \log x_i} = \frac{\partial R(x)}{R(x)} \frac{x_i}{\partial x_i}, \quad i = 1, \ldots, n.$$

Thus $\rho_i$ gives the fractional increase in risk per fractional increase in investment $i$. We can express the risk contributions as

$$\rho_i = \frac{x_i (\Sigma x)_i}{x^T \Sigma x}, \quad i = 1, \ldots, n,$$

from which we see that $\sum_{i=1}^n \rho_i = 1$. For general $x$, we can have $\rho_i < 0$, which means that a small increase in investment $i$ decreases the risk. Desirable investment choices have $\rho_i > 0$, in which case we can interpret $\rho_i$ as the fraction of the total risk contributed by the investment in asset $i$. Note that the risk contributions are homogeneous of degree zero, *i.e.*, scaling $x$ by a positive constant does not affect $\rho_i$.

In the *risk budget allocation problem*, we are given $\Sigma$ and a set of desired risk contributions $\rho_i^{\text{des}} > 0$ with $\mathbf{1}^T \rho^{\text{des}} = 1$; the goal is to find an investment mix $x \succ 0$, $\mathbf{1}^T x = 1$, with these risk contributions. When $\rho^{\text{des}} = (1/n)\mathbf{1}$, the problem is to find an investment mix that achieves so-called *risk parity*.

(a) Explain how to solve the risk budget allocation problem using convex optimization.
    *Hint.* Minimize $(1/2)x^T \Sigma x - \sum_{i=1}^n \rho_i^{\text{des}} \log x_i$.

(b) Find the investment mix that achieves risk parity for the return covariance matrix

$$
\Sigma = \begin{bmatrix} 6.1 & 2.9 & -0.8 & 0.1 \\ 2.9 & 4.3 & -0.3 & 0.9 \\ -0.8 & -0.3 & 1.2 & -0.7 \\ 0.1 & 0.9 & -0.7 & 2.3 \end{bmatrix}.
$$

For your convenience, this is contained in `risk_alloc_data.m`.

**17.21** *Portfolio rebalancing.* We consider the problem of rebalancing a portfolio of assets over multiple periods. We let $h_t \in \mathbf{R}^n$ denote the vector of our dollar value holdings in $n$ assets, at the beginning of period $t$, for $t = 1, \ldots, T$, with negative entries meaning short positions. We will work with the portfolio weight vector, defined as $w_t = h_t/(\mathbf{1}^T h_t)$, where we assume that $\mathbf{1}^T h_t > 0$, *i.e.*, the total portfolio value is positive.

The *target portfolio weight vector* $w^\star$ is defined as the solution of the problem

$$
\begin{array}{ll}
\text{maximize} & \mu^T w - \frac{\gamma}{2} w^T \Sigma w \\
\text{subject to} & \mathbf{1}^T w = 1,
\end{array}
$$

where $w \in \mathbf{R}^n$ is the variable, $\mu$ is the mean return, $\Sigma \in \mathbf{S}^n_{++}$ is the return covariance, and $\gamma > 0$ is the risk aversion parameter. The data $\mu$, $\Sigma$, and $\gamma$ are given. In words, the target weights maximize the risk-adjusted expected return.

At the beginning of each period $t$ we are allowed to rebalance the portfolio by buying and selling assets. We call the post-trade portfolio weights $\tilde{w}_t$. They are found by solving the (rebalancing) problem

$$
\begin{array}{ll}
\text{maximize} & \mu^T w - \frac{\gamma}{2} w^T \Sigma w - \kappa^T |w - w_t| \\
\text{subject to} & \mathbf{1}^T w = 1,
\end{array}
$$

with variable $w \in \mathbf{R}^n$, where $\kappa \in \mathbf{R}^n_+$ is the vector of (so-called linear) transaction costs for the assets. (For example, these could model bid/ask spread.) Thus, we choose the post-trade weights to maximize the risk-adjusted expected return, minus the transactions costs associated with rebalancing the portfolio. Note that the pre-trade weight vector $w_t$ is known at the time we solve the problem. If we have $\tilde{w}_t = w_t$, it means that no rebalancing is done at the beginning of period $t$; we simply hold our current portfolio. (This happens if $w_t = w^\star$, for example.)

After holding the rebalanced portfolio over the investment period, the dollar value of our portfolio becomes $h_{t+1} = \mathbf{diag}(r_t)\tilde{h}_t$, where $r_t \in \mathbf{R}^n_{++}$ is the (random) vector of asset returns over period $t$, and $\tilde{h}_t$ is the post-trade portfolio given in dollar values (which you do not need to know). The next weight vector is then given by

$$
w_{t+1} = \frac{\mathbf{diag}\,(r_t)\tilde{w}_t}{r_t^T \tilde{w}_t}.
$$

(If $r_t^T \tilde{w}_t \leq 0$, which means our portfolio has negative value after the investment period, we have gone bust, and all trading stops.) The standard model is that $r_t$ are IID random variables with mean and covariance $\mu$ and $\Sigma$, but this is not relevant in this problem.

(a) *No-trade condition.* Show that $\tilde{w}_t = w_t$ is optimal in the rebalancing problem if

$$\gamma \left| \Sigma(w_t - w^\star) \right| \preceq \kappa$$

holds, where the absolute value on the left is elementwise.

*Interpretation.* The lefthand side measures the deviation of $w_t$ from the target portfolio $w^\star$; when this deviation is smaller than the cost of trading, you do not rebalance.

*Hint.* Find dual variables, that with $w = w_t$ satisfy the KKT conditions for the rebalancing problem.

(b) Starting from $w_1 = w^\star$, compute a sequence of portfolio weights $\tilde{w}_t$ for $t = 1, \ldots, T$. For each $t$, find $\tilde{w}_t$ by solving the rebalancing problem (with $w_t$ a known constant); then generate a vector of returns $r_t$ (using our supplied function) to compute $w_{t+1}$ (The sequence of weights is random, so the results won't be the same each time you run your script. But they should look similar.)

Report the fraction of periods in which the no-trade condition holds and the fraction of periods in which the solution has only zero (or negligible) trades, defined as $\|\tilde{w}_t - w_t\|_\infty \leq 10^{-3}$. Plot the sequence $\tilde{w}_t$ for $t = 1, 2, \ldots, T$.

The file `portf_weight_rebalance_data.*` provides the data, a function to generate a (random) vector $r_t$ of market returns, and the code to plot the sequence $\tilde{w}_t$. (The plotting code also draws a dot for every non-negligible trade.)

Carry this out for two values of $\kappa$, $\kappa = \kappa_1$ and $\kappa = \kappa_2$. Briefly comment on what you observe.

*Hint.* In CVXPY we recommend using the solver ECOS. But if you use SCS you should increase the default accuracy, by passing `eps=1e-4` to the `cvxpy.Problem.solve()` method.

**17.22** *Portfolio optimization using multiple risk models.* Let $w \in \mathbf{R}^n$ be a vector of portfolio weights, where negative values correspond to short positions, and the weights are normalized such that $\mathbf{1}^T w = 1$. The expected return of the portfolio is $\mu^T w$, where $\mu \in \mathbf{R}^n$ is the (known) vector of expected asset returns. As usual we measure the risk of the portfolio using the variance of the portfolio return. However, in this problem we do not know the covariance matrix $\Sigma$ of the asset returns; instead we assume that $\Sigma$ is one of $M$ (known) covariance matrices $\Sigma^{(k)} \in \mathbf{S}_{++}^n$, $k = 1, \ldots, M$. We can think of the $\Sigma^{(k)}$ as representing $M$ different risk models, associated with $M$ different market regimes (say). For a weight vector $w$, there are $M$ different possible values of the risk: $w^T \Sigma^{(k)} w$, $k = 1, \ldots, M$. The worst-case risk, across the different models, is given by $\max_{k=1,\ldots,M} w^T \Sigma^{(k)} w$. (This is the same as the worst-case risk over all covariance matrices in the convex hull of $\Sigma^{(1)}, \ldots, \Sigma^{(M)}$.)

We will choose the portfolio weights in order to maximize the expected return, adjusted by the worst-case risk, *i.e.*, as the solution $w^\star$ of the problem

$$\begin{array}{ll} \text{maximize} & \mu^T w - \gamma \max_{k=1,\ldots,M} w^T \Sigma^{(k)} w \\ \text{subject to} & \mathbf{1}^T w = 1, \end{array}$$

with variable $w$, where $\gamma > 0$ is a given risk-aversion parameter. We call this the mean-worst-case-risk portfolio problem.

(a) Show that there exist $\gamma_1, \ldots, \gamma_M \geq 0$ such that $\sum_{k=1}^M \gamma_k = \gamma$ and the solution $w^\star$ of the mean-worst-case-risk portfolio problem is also the solution of the problem

$$\begin{array}{ll} \text{maximize} & \mu^T w - \sum_{k=1}^M \gamma_k w^T \Sigma^{(k)} w \\ \text{subject to} & \mathbf{1}^T w = 1, \end{array}$$

with variable $w$.

*Remark.* The result above has a beautiful interpretation: We can think of the $\gamma_k$ as allocating our total risk aversion $\gamma$ in the mean-worst-case-risk portfolio problem across the $M$ different regimes.

*Hint.* The values $\gamma_k$ are not easy to find: you have to solve the mean-worst-case-risk problem to get them. Thus, this result does not help us solve the mean-worst-case-risk problem; it simply gives a nice interpretation of its solution.

(b) Find the optimal portfolio weights for the problem instance with data given in `multi_risk_portfolio_data.*`. Report the weights and the values of $\gamma_k$, $k = 1, \ldots, M$. Give the $M$ possible values of the risk associated with your weights, and the worst-case risk.

**17.23** *Computing market-clearing prices.* We consider $n$ commodities or goods, with $p \in \mathbf{R}^n_{++}$ the vector of prices (per unit quantity) of them. The (nonnegative) demand for the products is a function of the prices, which we denote $D : \mathbf{R}^n \to \mathbf{R}^n$, so $D(p)$ is the demand when the product prices are $p$. The (nonnegative) supply of the products (*i.e.*, the amounts that manufacturers are willing to produce) is also a function of the prices, which we denote $S : \mathbf{R}^n \to \mathbf{R}^n$, so $S(p)$ is the supply when the product prices are $p$. We say that the market *clears* if $S(p) = D(p)$, *i.e.*, supply equals demand, and we refer to $p$ in this case as a set of *market-clearing prices*.

Elementary economics courses consider the special case $n = 1$, *i.e.*, a single commodity, so supply and demand can be plotted (vertically) against the price (on the horizontal axis). It is assumed that demand decreases with increasing price, and supply increases; the market clearing price can be found 'graphically', as the point where the supply and demand curves intersect. In this problem we examine some cases in which market-clearing prices (for the general case $n > 1$) can be computed using convex optimization.

We assume that the demand function is *Hicksian*, which means it has the form $D(p) = \nabla E(p)$, where $E : \mathbf{R}^n \to \mathbf{R}$ is a differentiable function that is concave and increasing in each argument, called the *expenditure function*. (While not relevant in this problem, Hicksian demand arises from a model in which consumers make purchases by maximizing a concave utility function.)

We will assume that the producers are independent, so $S(p)_i = S_i(p_i)$, $i = 1, \ldots, n$, where $S_i : \mathbf{R} \to \mathbf{R}$ is the supply function for good $i$. We will assume that the supply functions are positive and increasing on their domain $\mathbf{R}_+$.

(a) Explain how to use convex optimization to find market-clearing prices under the assumptions given above. (You do not need to worry about technical details like zero prices, or cases in which there are no market-clearing prices.)

(b) Compute market-clearing prices for the specific case with $n = 4$,

$$E(p) = \left( \prod_{i=1}^{4} p_i \right)^{1/4},$$

$$S(p) = (0.2p_1 + 0.5, 0.02p_2 + 0.1, 0.04p_3, 0.1p_4 + 0.2).$$

Give the market-clearing prices and the demand and supply (which should match) at those prices.

*Hint*: In CVX and CVXPY, `geo_mean` gives the geometric mean of the entries of a vector argument. Julia does not yet have a vector argument `geom_mean` function, but you can get the geometric mean of 4 variables $a$, $b$, $c$, $d$ using `geomean(geomean(a, b), geomean(c, d))`.

**17.24** *Funding an expense stream.* Your task is to fund an expense stream over $n$ time periods. We consider an expense stream $e \in \mathbf{R}^n$, so that $e_t$ is our expenditure at time $t$.

One possibility for funding the expense stream is through our bank account. At time period $t$, the account has balance $b_t$ and we withdraw an amount $w_t$. (A negative withdrawal represents a deposit.) The value of our bank account accumulates with an interest rate $\rho$ per time period, less withdrawals:

$$b_{t+1} = (1 + \rho)b_t - w_t.$$

We assume the account value must be nonnegative, so that $b_t \geq 0$ for all $t$.

We can also use other investments to fund our expense stream, which we purchase at the initial time period $t = 1$, and which pay out over the $n$ time periods. The amount each investment type pays out over the $n$ time periods is given by the *payout matrix* $P$, defined so that $P_{tj}$ is the amount investment type $j$ pays out at time period $t$ per dollar invested. There are $m$ investment types, and we purchase $x_j \geq 0$ dollars of investment type $j$. In time period $t$, the total payout of all investments purchased is therefore given by $(Px)_t$.

In each time period, the sum of the withdrawals and the investment payouts must cover the expense stream, so that

$$w_t + (Px)_t \geq e_t$$

for all $t = 1, \ldots, n$.

The total amount we invest to fund the expense stream is the sum of the initial account balance, and the sum total of the investments purchased: $b_1 + \mathbf{1}^T x$.

(a) Show that the minimum initial investment that funds the expense stream can be found by solving a convex optimization problem.

(b) Using the data in `expense_stream_data.*`, carry out your method in part (a). On three graphs, plot the expense stream, the payouts from the $m$ investment types (so $m$ different curves), and the bank account balance, all as a function of the time period $t$. Report the minimum initial investment, and the initial investment required when no investments are purchased (so $x = 0$).

**17.25** *Yield curve envelope.* The *term structure of interest rates* gives the current value of a future payment at the current time. The value of a \$1 payment in period $t$ is worth $p_t$, with $p_0 = 1$. The curve $p_t$ is called the *discount curve*. It is often described in terms of the *yield curve*, defined as $y_t = p_t^{-1/t} - 1$. We will assume that $p_t$ is positive, nonincreasing, and satisfies $p_0 = 1$. (The nonincreasing assumption means that future payments are worth less than current payments.) We don't know the discount curve (or equivalently, the yield curve) but we do have some additional information about it, beyond the assumptions made above, based on the market prices of some known bonds.

A *bond* is characterized by a future cash flow, called the the coupon payment schedule, given by $c \in \mathbf{R}^T$, where $c_t \geq 0$ is the payment in period $t$, for $t = 1, \ldots, T$. (Bond payment schedules typically

have the form of a constant payment every month, or quarter, or year, and a large payment on its *maturity date*, with no payments after that. But you don't need to know this for this problem.) The present (or discounted) value of the bond is $c^T p$. We assume this is the current market price of the bond, which we know. We have $K$ bonds with known coupon schedules $c^k$ and market prices $b^k$, $k = 1, \ldots, K$. Together with the assumptions above (nonnegativity and monotonicity), this describes a set of possible discount rates which we denote $\mathcal{P} \subset \mathbf{R}^T$. Thus $\mathcal{P}$ is the set of discount curves that are consistent with the known bond market prices and our assumptions.

Define
$$d_t^{\max} = \max_{p \in \mathcal{P}} p_t, \quad d_t^{\min} = \min_{p \in \mathcal{P}} p_t, \quad t = 0, \ldots, T.$$

These functions, called the upper and lower envelopes of the discount curve, give the range of possible values of the discount at each time, over all discounts compatible with our assumptions and the known bond prices. From these we can get the maximum and minimum values of the yield curve,
$$y_t^{\max} = (d_t^{\min})^{-1/t} - 1, \quad y_t^{\min} = (d_t^{\max})^{-1/t} - 1, \quad t = 1, \ldots, T.$$
These are called the upper and lower envelope of the yield curve, respectively.

(a) Explain how to find $d^{\max}$ and $d^{\min}$ using convex or quasiconvex optimization, given $T$, the coupon payment schedules $c^k$, and known prices, $b^k$, of the $K$ bonds. Your solution may involve solving a reasonable number of problems.

(b) Solve the problem you formulated using the problem data found in the file, `yield_curve_data.*`. After computing $d^{\max}$ and $d^{\min}$, you should plot your lower and upper envelopes against time. Create one figure for the yield curve, and another for the discount curve. Besides $t = 0$, are there any time points at which you can be certain what value of the discount curve (or equivalently, the yield curve) is? If so, explain briefly.

**17.26** *Portfolio optimization with a drawdown limit.* You are given the time series of the daily share prices of $n$ assets over $T$ days, $p_1, \ldots, p_T \in \mathbf{R}_{++}^n$. We consider a buy-and-hold portfolio, consisting of $s_i$ shares of asset $i$ (with negative meaning a short position). The value of the portfolio on day $t$ is given by $V_t = p_t^T s$. We will assume that $V_t > 0$ for all $t$. We are interested in choosing $s \in \mathbf{R}^n$, subject to the constraint $V_1 = B$, where $B > 0$ is the total budget to be invested on day 1. The objective is to maximize the ending portfolio value $V_T$, subject to the budget constraint above, and an additional constraint described below related to the maximum drawdown of the portfolio.

The *last high* or *high water mark* at time $t$ is $H_t = \max_{\tau \leq t} V_\tau$, the maximum portfolio value up to time $t$. The *drawdown* $D_t$ at time $t$ is defined as
$$D_t = (H_t - V_t)/H_t.$$

(This is often expressed as a percentage.) Investors get nervous when the drawdown gets too large, say, more than 10%.

(a) Explain how to use convex optimization to find a portfolio $s$ that maximizes final value $V_T$, subject to the budget constraint, and $D_t \leq D^{\max}$, where $D^{\max} \in (0, 1)$ is given. You can change or introduce variables, reformulate the problem, or use quasiconvex optimization. In all cases, you must explain your method, and establish the convexity (or concavity, or quasiconvexity, etc.) of any function for which it is not obvious. The number of variables or constraints you introduce in your formulation should be no more than a small multiple of $T$.

(b) Find optimal portfolios for the problem data given in `drawdown_data.*` and `asset_prices.csv`, under drawdown limits $D^{\max} \in \{0.05, 0.10, 0.20\}$. Report the optimal final value in each case. Plot the portfolio value $V_t$ versus time for each choice of $D^{\max}$.

*Remark.* The optimization problem described here is not immediately useful, since you obviously would not know future returns when you choose your portfolio. Instead we are finding what buy and hold portfolio would have been best over the (past) $T$ periods, had you known future returns. But if you believe the future looks like the past (which it need not), this portfolio could be a good choice for the future, too.

**17.27** *Minimax portfolio optimization.* We consider a portfolio optimization problem with $n$ assets held for a fixed period of time. Let $x_i$ denote the amount of asset $i$ held. The price change of asset $i$ over the period is given by $p_i$. The random vector $p$ has mean $\mu \in \mathbf{R}_+^n$ and covariance $\Sigma \in \mathbf{S}_+^n$. The risk adjusted return is defined to be

$$\mu^T x - \gamma x^T \Sigma x$$

where $\gamma \geq 0$ is the risk aversion parameter. Unfortunately we do not know $\Sigma$, but instead we know that $\Sigma \in \mathcal{A}$ where

$$\mathcal{A} = \{\Sigma \mid \Sigma \succeq 0, L_{ij} \leq \Sigma_{ij} \leq U_{ij} \text{ for } i, j = 1, \ldots, n\}$$

We do know the matrices $L$ and $U$, which are symmetric and provide lower and upper bounds on the entries of the matrix $\Sigma$. (Note the two different types of inequality symbols used in the definition of $\mathcal{A}$ above.) We assume that $\Sigma^{\mathrm{mid}} = (L + U)/2 \succ 0$. We require that $x_i \geq 0$ (so all positions are long.)

We intend to maximize the worst-case risk-adjusted return, by solving the optimization problem

$$
\begin{array}{ll}
\text{maximize} & \mu^T x - \gamma \max_{\Sigma \in \mathcal{A}} x^T \Sigma x \\
\text{subject to} & x \succeq 0, \\
& \mathbf{1}^T x = 1,
\end{array}
$$

(a) Show that $\max_{\Sigma \in \mathcal{A}} x^T \Sigma x$ is equal to the optimal value of the following optimization problem with variables $V, W \in \mathbf{R}^{n \times n}$

$$
\begin{array}{ll}
\text{minimize} & \mathbf{tr}\,(VU - WL) \\
\text{subject to} & V_{ij} \geq 0, \quad i, j = 1, \ldots, n, \\
& W_{ij} \geq 0, \quad i, j = 1, \ldots, n, \\
& \begin{bmatrix} V - W & x \\ x^T & 1 \end{bmatrix} \succeq 0.
\end{array}
$$

(b) Explain how the worst-case risk-adjusted return problem can be solved using convex optimization.

(c) The file `minimax_data.m` contains $L$, $U$ and $\mu$. For each $\gamma \in \{2^{-4}, 2^{-3}, \ldots, 2^3, 2^4\}$ apply your method from part (b). Plot the mean return $\mu^T x^\star$ of the optimal portfolio versus $\log_2 \gamma$. Similarly plot the worst-case risk, given by $\max_{\Sigma \in \mathcal{A}} (x^\star)^T \Sigma x^\star$, versus $\log_2 \gamma$.

**17.28** *Maximum Sharpe ratio portfolio.* We consider a portfolio optimization problem with portfolio vector $x \in \mathbf{R}^n$, mean return $\mu \in \mathbf{R}^n$, and return covariance $\Sigma \in \mathbf{S}^n_{++}$. The ratio of portfolio mean return $\mu^T x$ to portfolio standard deviation $\|\Sigma^{1/2} x\|_2$ is called the *Sharpe ratio* of the portfolio. (It is often modified by subtracting a risk-free return from the mean return.) The Sharpe ratio measures how much return you get per risk taken on, and is a widely used single metric that combines return and risk. It is undefined for $\mu^T x \leq 0$.

Consider the problem of choosing the portfolio to maximize the Sharpe ratio, subject to the constraint $\mathbf{1}^T x = 1$, and the leverage constraint $\|x\|_1 \leq L^{\max}$, where $L^{\max} \geq 1$ is a given leverage limit. You can assume there is a feasible $x$ with $\mu^T x > 0$.

   (a) Show that the maximum Sharpe ratio problem is quasiconvex in the variable $x$.

   (b) Show how to solve the maximum Sharpe ratio problem by solving *one* convex optimization problem. You must fully justify any change of variables or problem transformation.

**17.29** *Post-modern portfolio optimization metrics.* Let $r \in \mathbf{R}^T$ denote a time series (say, daily) of investment returns, *i.e.*, the increase in value divided by initial value. The value of the investment (typically, a portfolio) is the time series vector $v \in \mathbf{R}^T$ defined by the recursion

$$v_{t+1} = v_t(1 + r_t), \quad t = 0, \ldots, T-1,$$

with $v_0$ a given positive initial value. Here we are compounding the investment returns. We will assume that all returns satisfy $r_t > -1$, which implies that $v \succ 0$. We define the *high-water value* or *last high value* as

$$h_t = \max_{\tau \leq t} v_\tau, \quad t = 1, \ldots, T.$$

The value and high-water value are functions of $r$.

Portfolio theory as originally developed by Markowitz in the 1950s takes into account the mean return $\mu = \mathbf{1}^T r/T$ and variance (risk) $\sigma^2 = \|r - \mu\mathbf{1}\|_2^2/T$. The idea of using a mathematical approach to choose a portfolio to maximize return and minimize risk came to be called *modern portfolio theory.* Of course, it's not so modern nowadays.

Researchers later suggested various alternative metrics that are (supposedly) closer to what we really care about than the mean return and risk. The use of these metrics was dubbed (or marketed as) *post-modern portfolio theory.* Some of these so-called post-modern portfolio metrics are described below, along with a parenthetical note about whether we'd like to minimize or maximize the metric.

For each metric we wish to minimize, determine if it is a convex or quasiconvex function of $r$, or neither. For each metric we wish to maximize, determine if it is a concave or quasiconcave function of $r$, or neither. For example, the mean return (which we wish to maximize) is a concave function of $r$, and the risk (variance, which we wish to minimize) is a convex function of $r$. When the metric is convex or quasiconvex (or concave or quasiconcave), justify your answer. When it is neither, you can simply state this; you do not need to produce a counterexample. We will deduct some points if your answer is not strong enough, *e.g.*, if you assert that a metric is quasiconvex, but it is in fact convex.

   (a) *Logarithmic or Kelly growth rate.* (Maximize.) $(1/T)\sum_t \log(1 + r_t)$. This is the average growth rate of $v_t$.

(b) *Downside variance.* (Minimize.) The downside variance is $(1/T)\sum_t (r_t - \mu)_-^2$, where $(u)_- = \max\{-u, 0\}$, and $\mu$ is the mean return. This assesses a penalty for a return below the average (the 'downside'), but not for a return above the average.

(c) *Maximum drawdown.* (Minimize.) The *drawdown* at period $t$ is defined as $d_t = (h_t - v_t)/h_t$. The maximum drawdown is defined as $\max_t d_t$.

(d) *Maximum consecutive days under water.* (Minimize.) A time period $t$ is called *under water* if $v_t < h_t$, *i.e.*, the current value is less than the last high. Maximum consecutive days under water means just that, *i.e.*, the maximum number of consecutive days under water.

*Remark.* Many other post-modern metrics can derived be from, or are related to, the ones described above. Examples include the Sortino, Calmar, and Information ratios. You can thank the EE364a staff for refraining from asking about these.

**17.30** *Currency exchange.* An entity (such as a multinational corporation) holds $n = 10$ currencies, with $c_i^{\text{init}} \geq 0$ denoting the number of units of currency $i$. The currencies are, in order, USD, EUR, GBP, CAD, JPY, CNY, RUB, MXN, INR, and BRL. Our goal is to exchange currencies on a market so that, after the exchanges, we hold at least $c_i^{\text{req}}$ units of each currency $i$.

The exchange rates are given by $F \in \mathbf{R}^{n \times n}$, where $F_{ij}$ is the units of currency $j$ it costs to buy one unit of currency $i$. We call $1/F_{ij}$ the bid price for currency $j$ in terms of currency $i$, and $F_{ji}$ the ask price for currency $j$ in terms of currency $i$.

For example, suppose that $F_{12} = 0.88$ and $F_{21} = 1.18$. This means that it takes 0.88 EUR to buy one USD, and it takes 1.18 USD to buy one EUR; the bid and ask prices for EUR in USD are 1.1364 USD and 1.1800 USD, respectively.

We will value a set of currency holdings in USD, by valuing each unit of currency $j$ at the geometric mean of the bid and ask price in USD, $\sqrt{F_{j1}/F_{1j}}$. In our example above, we would value one EUR as $\sqrt{1.1364 \cdot 1.1800} = 1.1580$ USD.

We let $X \in \mathbf{R}_+^{n \times n}$ denote the currency exchanges that we carry out, with $X_{ij} \geq 0$ the amount of currency $j$ we exchange on the market for currency $i$, for which we obtain $X_{ij}/F_{ij}$ of currency $i$. (You can assume that $X_{ii} = 0$.) The total of each currency $j$ that we exchange into other currencies cannot exceed our initial holdings, $c_j^{\text{init}}$. After the currency exchange, we must end up with at least $c_i^{\text{req}}$ of currency $i$. (The post-exchange amount we hold of currency $i$ is our original holding $c_i^{\text{init}}$, minus the total we exchange into other currencies, plus the total amount we obtain from exchanging other currencies into currency $i$.)

The cost of the exchanges is the decrease in value between the currency holdings before and after the exchanges, in USD. The cost can be interpreted as the transaction costs incurred by crossing the bid-ask spread (*i.e.*, if the bid and the ask were the same, there would be no cost.)

Find the currency exchanges $X^\star$ that minimize the currency exchange cost for the data in `currency_exchange_data` (These data are based on real exchange rates, but with artificially large spreads, to make sure that you don't encounter any numerical issues.) Explain your method, and give the optimal value, *i.e.*, the cost obtained.

**17.31** *Minimizing tax liability.* You will liquidate (sell) some stocks that you hold to raise a given amount of cash $C$. The stocks are divided into $n$ tax lots; a tax lot is a group of stocks you bought at the same time. For each tax lot $i$, you have the cost basis $b_i > 0$, the current market value $v_i > 0$ (both

in $), and its short term / long term status. (Long term means that you acquired the stock in the tax lot more than one year ago, and short term means that you acquired it less than one year ago.) We assume that tax lots $i = 1, \ldots, L$ are long term, and tax lots $i = L+1, \ldots, n$ are short term.

The goal is to choose how much of each lot to sell. We let $s_i$ denote the amount of tax lot $i$ we sell (in $). These must satisfy $0 \leq s_i \leq v_i$, and we must have $\mathbf{1}^T s = C$.

When $v_i < b_i$, the sale is called a loss, and when $v_i > b_i$, the sale is called a gain. The amount of the gain or loss is given by $g_i = (s_i/v_i)(v_i - b_i)$, with positive values meaning a gain, and negative values meaning a loss. We define the (net) long and short term gains as

$$N^{\mathrm{l}} = \sum_{i=1}^{L} g_i, \qquad N^{\mathrm{s}} = \sum_{i=L+1}^{n} g_i.$$

When $N^{\mathrm{l}} > 0$ ($N^{\mathrm{l}} < 0$), we say that we have had a long term capital gain (loss), and similary for short term gain.

These two net gains determine the total tax liability. The long and short term net gains are taxed at two different rates, $\rho^{\mathrm{l}}$ and $\rho^{\mathrm{s}}$, respectively, which satisfy $0 < \rho^{\mathrm{l}} < \rho^{\mathrm{s}}$.

The simplest case is when both net gains are nonnegative, in which case the tax is $\rho^{\mathrm{l}} N^{\mathrm{l}} + \rho^{\mathrm{s}} N^{\mathrm{s}}$. Another simple case occurs when both net gains are nonpositive, in which case the tax is zero.

In the case when one of the net gains is positive and the other is negative, you are allowed to use the net loss in one to offset the net gain in the other, up to the value of the net gain. Specifically, if $N^{\mathrm{l}} < 0$ (you have a long term loss), the tax is $\rho^{\mathrm{s}} (N^{\mathrm{s}} + N^{\mathrm{l}})_+$; if $N^{\mathrm{s}} < 0$ (you have a short term loss), the tax is $\rho^{\mathrm{l}} (N^{\mathrm{s}} + N^{\mathrm{l}})_+$. (Here $(u)_+ = \max\{u, 0\}$.) Note that you have zero tax liability if $N^{\mathrm{s}} + N^{\mathrm{l}} \leq 0$, i.e., your total long and short net gains is less than or equal to zero.

*Apology.* Sorry this sounds complicated. In fact, this is a highly simplified version of the way taxes really work.

*Hint.* The tax liability is neither a convex nor quasiconvex function of the long and short term net gains $N^{\mathrm{l}}$ and $N^{\mathrm{s}}$.

(a) Explain how to find $s$ that minimizes the tax liability, subject to the constraints listed above, using convex optimization. Your solution can involve solving a modest number of convex problems.

(b) Suppose you want to raise $C = 2300$ dollars from $n = 10$ tax lots, and the cost basis and values of each lot are given by

$$b = (400, 80, 400, 200, 400, 400, 80, 400, 100, 500),$$
$$v = (500, 100, 500, 200, 700, 300, 120, 300, 150, 600).$$

Carry out your method on this data with $L = 4$, $\rho_l = 0.2$, and $\rho_s = 0.3$. Give optimal values of $s_i$, and the optimal value of the tax liability. Compare this to the tax liability when you liquidate all tax lots proportionally, i.e., $s = (C/\mathbf{1}^T v) v$.

**17.32** *Optimizing the sequence of commitments in an alternative investment.* In an *alternative investment,* the investor makes *commitments* each period for an amount that she will invest. Over the next few

years, the investor puts money into the investment in response to *capital calls*, up to the amount of previous commitments. The investor receives money from the investment in later years through *distributions*. Examples of alternative investments include private equity, venture capital, and infrastructure projects. Alternative investments are found in the portfolios of insurance companies, retirement funds, and university endowments. ('Alternative' refers to the investment not being the more usual stocks, bonds, currencies, and financial derivatives.)

We consider time periods $t = 1, \ldots, T$, which are typically quarters. We first describe some critical quantities.

- $c_t \geq 0$ denotes the amount that the investor commits in period $t$.
- $p_t \geq 0$ denotes the amount that the investor pays in to the investment in response to capital calls in period $t$.
- $d_t \geq 0$ denotes the amount that the investor receives in distributions from the investment in period $t$.
- $n_t \geq 0$ denotes the net asset value (NAV) of the investment in period $t$.
- $u_t \geq 0$ denotes the total amount of uncalled commitments, *i.e.*, the difference between the total so far committed and the total so far that has been called (and paid into the investment).

The units for all of these is typically millions of USD. Among these quantities, the only ones we have direct control over are the commitments $c_t$; the others are functions of these.

A simple dynamical model of these variables is

$$n_{t+1} = (1+r)n_t + p_t - d_t, \quad u_{t+1} = u_t - p_t + c_t, \quad t = 1, \ldots, T,$$

where $r \geq 0$ is the per-period return, with initial conditions $n_1 = u_1 = 0$. (Note that $n$ and $u$ are $(T+1)$-vectors, whereas $c$, $d$, and $p$ are $T$-vectors.) In words: the value of the investment increases by its return, plus the amount paid in, minus the amount distributed; the total uncalled commitments is decreased by the capital calls, and increased by new commitments. The calls and distributions are modeled as

$$p_t = \gamma^{\mathrm{call}} u_t, \quad d_t = \gamma^{\mathrm{dist}} n_t, \quad t = 1, \ldots, T,$$

where $\gamma^{\mathrm{call}} \in (0,1)$ and $\gamma^{\mathrm{dist}} \in (0,1)$ are the call and distribution intensities, respectively. The parameters $r$, $\gamma^{\mathrm{call}}$, and $\gamma^{\mathrm{dist}}$ are given. Your job is to choose the sequence of commitments $c = (c_1, \ldots, c_T)$.

The commitments and the capital calls are limited by $c_t \leq c^{\mathrm{max}}$ and $p_t \leq p^{\mathrm{max}}$, for $t = 1, \ldots, T$, where $c^{\mathrm{max}} > 0$ and $p^{\mathrm{max}} > 0$ are given. In addition we have a total budget $B > 0$ for commitments, with $\mathbf{1}^T c \leq B$. Our objective is to minimize

$$\frac{1}{T+1} \sum_{t=1}^{T+1} (n_t - n^{\mathrm{des}})^2 + \lambda \frac{1}{T-1} \sum_{t=1}^{T-1} (c_{t+1} - c_t)^2,$$

where $n^{\mathrm{des}} > 0$ is a given positive target NAV, and $\lambda > 0$ is a parameter. The first term in the objective is the mean-square tracking error, and the second term, the mean-square difference in commitments, encourages smooth sequences of commitments.

(a) *Optimized commitments.* Explain how to solve this problem with convex optimization. Solve this problem with parameters $T = 40$ (ten years), $r = 0.04$ (4% quarterly return),

$$\gamma^{\text{call}} = .23, \quad \gamma^{\text{dist}} = .15, \quad c^{\max} = 4, \quad p^{\max} = 3, \quad B = 85, \quad n^{\text{des}} = 15, \quad \lambda = 5.$$

Plot $c$, $p$, $d$, $n$, and $u$ versus $t$. Give the root-mean-square (RMS) tracking error, *i.e.*, the squareroot of the mean-square tracking error, for the optimal commitments.

(b) *Constant commitment based on steady-state.* By solving the dynamics equations with all quantities constant, we find that $c^{\text{ss}} = (\gamma^{\text{dist}} - r)n^{\text{des}}$ is the value of a constant commitment (*i.e.*, the same each period) that gives $n_t = n^{\text{des}}$ asymptotically, in steady-state. Plot the same quantities as in part (a) for the constant commitment $c_t = c^{\text{ss}}$ for $t = 1, \ldots, T$. Give the RMS tracking error. *Hint.* A quick and simple (but not computationally efficient) way to do the simulation is to modify the code for part (a), adding the constraint that $c_t = c^{\text{ss}}$, $t = 1, \ldots, T$.

Give a very brief description of what you see, comparing the optimal sequence of commitments found in part (a) and the constant commitments found in part (b).

**17.33** *Maximizing diversification ratio.* Let $x \in \mathbf{R}_+^n$, with $\mathbf{1}^T x = 1$, denote a portfolio of $n$ assets, with $x_i$ the fraction of the total value (assumed positive) invested in asset $i$. Let $\Sigma \in \mathbf{S}_{++}^n$ denote the covariance matrix of the asset returns. The *diversification ratio* of the portfolio is defined as

$$D(x) = \frac{\sigma^T x}{(x^T \Sigma x)^{1/2}},$$

where $\sigma_i = (\Sigma_{ii})^{1/2}$. Note that $D$ is defined for any $x \in \mathbf{R}_+^n$ with $\mathbf{1}^T x = 1$.

We consider the problem of choosing $x$ to maximize the diversification ratio, subject to limits on the weights,

$$\begin{array}{ll} \text{maximize} & D(x) \\ \text{subject to} & \mathbf{1}^T x = 1, \quad 0 \preceq x \preceq M, \end{array}$$

where $M \succ 0$ is a given vector of maximum allowed weights, with $\mathbf{1}^T M > 1$.

*Remark.* (The following is not needed to solve the problem, but gives some background.) For any long-only portfolio $x$ we have $D(x) \geq 1$. To see this we note that

$$x^T \Sigma x = \sum_{ij} x_i x_j \sigma_i \sigma_j \rho_{ij} \leq \sum_{ij} x_i x_j \sigma_i \sigma_j = (\sigma^T x)^2,$$

where $\rho_{ij} = \Sigma_{ij}/(\sigma_i \sigma_j)$ is the correlation, which satisfies $\rho_{ij} \leq 1$. The smallest possible value of diversification $D(x) = 1$ occurs only when $x = e_k$ (the $k$th unit vector), *i.e.*, the portfolio is concentrated in one asset.

(a) Explain how to use convex optimization to solve the problem. We will give half credit for a solution that involves solving a quasiconvex optimization problem, and full credit to one that relies on solving one convex problem. *Hints.* You may need to change variables to get a one-convex-problem method. Note also that $D(tx) = D(x)$ for any $t > 0$.

(b) Use your method from part (a) to solve the problem instance with data given in `max_divers_data.*`. Give an optimal $x^\star$, and the associated diversification ratio $D(x^\star)$.

The (long-only) *minimum variance portfolio* $x^{\text{mv}}$ is the one that minimizes $x^T \Sigma x$ subject to $0 \preceq x \preceq M$, $\mathbf{1}^T x = 1$. Find $D(x^{\text{mv}})$, and compare it to $D(x^\star)$. Compare the maximum diversification and minimum variances portfolios using a bar plot. (The data file contains code for creating such plots.)

**17.34** *Optimal exchange.* We consider a market with $n$ (divisible) goods that a set of $N$ agents or participants can exchange or trade with each other. We let $x_i \in \mathbf{R}^n$ denote the amounts of goods that agent $i$ takes, with $(x_i)_j < 0$ meaning that agent $i$ gives the amount $|(x_i)_j|$. We say that the market *clears* if $x_1 + \cdots + x_N = 0$, which means that for each good, the total amount taken by participants balances the total amount given by other participants. (We assume that each participant starts with an endowment of goods, which allows them to give some away.) The particular choice $x_i = 0$, $i = 1, \ldots, N$, means that no goods are exchanged.

Each participant derives a utility $U_i(x_i)$ (in dollars, say) from the level of goods taken (or given) $x_i$. We will assume that the functions $U_i : \mathbf{R}^n \to \mathbf{R}$ are increasing, strictly concave, and differentiable, with $0 \in \mathbf{dom}\, U_i$, $i = 1, \ldots, N$. (Everything can be made to work when they are just concave, but it gets more complicated.)

Suppose $x_i^\star$, $i = 1, \ldots, N$, maximize the total utility $U_1(x_1) + \cdots + U_N(x_N)$ subject to the market clearing. Unless all of these are are zero, we have (by definition)

$$U_1(x_1^\star) + \cdots + U_N(x_N^\star) > U_1(0) + \cdots + U_N(0),$$

which means that by optimal trading, the total utility increases. In this exercise we discuss how to compensate the participants, or, put another way, how to allocate the increase in total utility to the participants.

To fix the sign convention for the dual variable, we work with the Lagrangian

$$L(x_1, \ldots, x_N, \nu) = U_1(x_1) + \cdots + U_N(x_N) - \nu^T(x_1 + \cdots + x_N),$$

with dual variable $\nu \in \mathbf{R}^n$, and let $p = \nu^\star$ denote an optimal dual variable value. (And yes, you do have strong duality here.)

Not surprisingly, $p$ can be interpreted as a vector of prices for the goods. Below you will show that $p \succ 0$, *i.e.*, the prices for the goods are all positive. The payment by participant $i$ (in dollars) for participating in the exchange is $p^T x_i$. (If this is negative, participant $i$ receives money.) You will work out various properties of this payment scheme.

(a) *Price and marginal utility.* Relate $p$ to $\nabla U_i(x_i^\star)$. The latter is the marginal utility of the goods to participant $i$, at $x_i^\star$. From this relation, conclude that $p \succ 0$.

(b) *Cash balance.* Show that the sum of the payments across the participants is zero. This means that the total cash paid in by participants balances the total cash paid out to participants. In other words, the cash payments also clear.

(c) *Nash equilibrium.* Explain why $x_i^\star$ maximizes $U_i(x_i) - p^T x_i$, which is the net utility for participant $i$. In other words, with the prices of goods fixed at $p$, each participant maximizes their net utility with $x_i = x_i^\star$. This is called a *Nash equilibrium*: No participant is incentivized to change their value of $x_i$ from $x_i^\star$.

(d) *Everyone does better by trading.* Show that for each $i$, $U_i(x_i^\star) - p^T x_i^\star \geq U_i(0)$. (The inequality is strict when $x_i^\star \neq 0$.) The lefthand side is the net utility when the participant trades; the righthand side is the (net) utility when she does not trade.

Your solutions can be brief; we will penalize solutions that are substantially more complicated than they need to be.

**17.35** *Worst case bond portfolio value.* A portfolio of bonds has a known cash flow or sequence of payments the holder will receive, given by the vector $c = (c_1, \ldots, c_T) \in \mathbf{R}^T$, where $c_t \geq 0$ is the cash that will be received in period $t$. (These payments include coupon payments and also the principal for bonds in the portfolio that mature. But you don't need to know these details.)

The (net present) value of the bond portfolio is given by $V = c^T p$, where $p \in \mathbf{R}_{++}^T$ is the vector of discounts for future payments. We interpret $p_t$ as the current value of a payment of \$1 in period $t$. For example, with a constant interest rate $r$ and continuous compounding of interest, we have $p_t = \exp(-tr)$. These discount factors are typically specified by the so-called *yield curve* $y = (y_1, \ldots, y_T)$, where

$$y_t = \frac{\log p_t}{-t}, \quad t = 1, \ldots, T.$$

We interpret $y_t$ as the constant, continuously compounded interest rate $r$ which would yield $p_t = \exp(-ty_t)$. (If you are curious what a real yield curve looks like, search online for 'today's US treasury yield curve'.)

We consider the situation where we know the portfolio cash flow $c$, but not the yield curve $y$. But we do have a set of possible yield curves given by $\mathcal{Y} \subset \mathbf{R}^T$, where $\mathcal{Y}$ is convex. The worst case value of the portfolio, over the set of possible yield curves, is defined as

$$V^{\mathrm{wc}} = \min\{c^T p \mid y \in \mathcal{Y}\}.$$

(a) Explain how to find $V^{\mathrm{wc}}$ using convex optimization. If you change variables or use a relaxation, explain.

(b) Suppose that $\mathcal{Y}$ has a maximum element $y^{\max}$ with respect to the nonnegative cone $\mathbf{R}_+^T$. (This does not always happen, of course.) Give a simple expression or formula for $V^{\mathrm{wc}}$ in terms of $y^{\max}$. Justify your answer.

(c) We now consider a particular form of $\mathcal{Y}$, given by yield curves of the form $y^{\mathrm{nom}} + \delta$ where $y^{\mathrm{nom}} \in \mathbf{R}^T$ is a given nominal yield curve, and $\delta \in \mathbf{R}^T$ is a deviation from the nominal yield curve satisfying

$$\delta_1 = 0, \quad \mathbf{1}^T \delta = 0, \quad \left( \sum_{t=1}^{T-1} (\delta_{t+1} - \delta_t)^2 \right)^{1/2} \leq \rho, \quad -\kappa \leq \delta_t \leq \kappa, \quad t = 1, \ldots, T,$$

where $\rho$ and $\kappa$ are given positive numbers.

Carry out the method of part (a) on the problem instance with data given in `worst_case_bond_price_data.*` Report the worst-case value $V^{\mathrm{wc}}$, and the nominal value $V^{\mathrm{nom}}$, which is the value of the portfolio when the yield curve has the nominal value $y^{\mathrm{nom}}$. Plot the yield curve that results in the worst-case portfolio value, along with the nominal yield curve.

**17.36** *Portfolio optimization with buy/hold/sell recommendations.* We consider the problem of choosing a portfolio of $n$ assets specified by the weight vector $w \in \mathbf{R}^n$, with $\mathbf{1}^T w = 1$, with $w_i$ the fraction of the total portfolio value (assumed to be positive) held in asset $i$, with negative $w_i$ meaning a short position. Markowitz-style portfolio optimization uses the mean return of the assets $\mu \in \mathbf{R}^n$. (Of course, in practice this is always an estimate or forecast of the mean.) In this problem we show how to carry out Markowitz-style optimization with a traditional qualitative estimate of returns, which specifies for each asset whether the investor should buy it (which means the return is thought to be positive), sell it (which means the return is thought to be negative), or hold it (which means the return is not clear). To simplify notation, we assume the assets are sorted with all buy recommendations, then all hold, then all sell, so we can partition the weight vector as $w = (w_b, w_h, w_s)$. These subvectors have positive dimensions $n_b, n_h, n_s$, respectively, with $n_b + n_h + n_s = n$.

We pose the portfolio optimization problem as a robust optimization problem, working with the worst-case portfolio return over asset returns consistent with the buy/hold/sell recommendations. We translate the recommendations into a set of possible returns

$$\mathcal{M} = \{\mu \mid \mu_b \succeq \nu\mathbf{1}, \ -\nu\mathbf{1} \preceq \mu_h \preceq \nu\mathbf{1}, \ \mu_s \preceq -\nu\mathbf{1}\},$$

where the subscripts denote the subvectors associated with buy, hold, and sell recommendations. Here $\nu > 0$ is a parameter that gives the minimum return we expect from a buy recommendation, with $-\nu$ the maximum return we expect for a sell recommendation. We define the worst-case return as $R^{\mathrm{wc}}(w) = \min_{\mu \in \mathcal{M}} \mu^T w$, which is evidently a concave function of $w$. Note that $R^{\mathrm{wc}}(w)$ can be $-\infty$.

We wish to solve the problem

$$\begin{array}{ll} \text{maximize} & R^{\mathrm{wc}}(w) \\ \text{subject to} & \mathbf{1}^T w = 1, \quad \|w\|_1 \leq L, \quad w^T \Sigma w \leq \sigma^2, \end{array}$$

with variable $w$, where $L \geq 1$ is a leverage limit, $\Sigma \in \mathbf{S}_{++}^n$ is the covariance matrix of the asset returns, and $\sigma > 0$ is a maximum allowed portfolio return standard deviation. The parameters $L$, $\Sigma$, and $\sigma$ are given. Since the objective is homogeneous in $\nu$, we can assume that $\nu = 1$. This problem is convex, but not immediately solvable, since the objective cannot be directly handled by standard solvers.

(a) Show how to solve the problem using standard solvers, in a form compatible with CVXPY. Justify any change of variables, or other transformations you use.

(b) Carry out the method in part (a) on the problem instance with data given in `buy_hold_sell_data.py`. Give an optimal $w^\star$ and its associated optimal objective value $R^{\mathrm{wc}}(w^\star)$. Give a $\mu^{\mathrm{wc}} \in \mathcal{M}$ for which $R^{\mathrm{wc}}(w^\star) = (\mu^{\mathrm{wc}})^T w^\star$.

(c) *A naïve method.* A simpler approach to handling buy/hold/sell recommendations is to assume that all buy assets have return $+1$, all sell assets have return $-1$, and all hold assets have return $0$. Solve the problem with this (linear) objective. Give a solution $w^{\mathrm{naïve}}$. What is the associated worst-case return, $R^{\mathrm{wc}}(w^{\mathrm{naïve}})$?

# 18 Mechanical and aerospace engineering

**18.1** *Optimal design of a tensile structure.* A tensile structure is modeled as a set of $n$ masses in $\mathbf{R}^2$, some of which are fixed, connected by a set of $N$ springs. The masses are in equilibrium, with spring forces, connection forces for the fixed masses, and gravity balanced. (This equilibrium occurs when the position of the masses minimizes the total energy, defined below.)

We let $(x_i, y_i) \in \mathbf{R}^2$ denote the position of mass $i$, and $m_i > 0$ its mass value. The first $p$ masses are fixed, which means that $x_i = x_i^{\text{fixed}}$ and $y_i = y_i^{\text{fixed}}$, for $i = 1, \ldots, p$. The gravitational potential energy of mass $i$ is $gm_i y_i$, where $g \approx 9.8$ is the gravitational acceleration.

Suppose spring $j$ connects masses $r$ and $s$. Its elastic potential energy is

$$(1/2)k_j \left( (x_r - x_s)^2 + (y_r - y_s)^2 \right),$$

where $k_j \geq 0$ is the stiffness of spring $j$.

To describe the topology, *i.e.*, which springs connect which masses, we will use the incidence matrx $A \in \mathbf{R}^{n \times N}$, defined as

$$A_{ij} = \begin{cases} 1 & \text{head of spring } j \text{ connects to mass } i \\ -1 & \text{tail of spring } j \text{ connects to mass } i \\ 0 & \text{otherwise.} \end{cases}$$

Here we arbitrarily choose a head and tail for each spring, but in fact the springs are completely symmetric, and the choice can be reversed without any effect. (Hopefully you will discover why it is convenient to use the incidence matrix $A$ to specify the topology of the system.)

The total energy is the sum of the gravitational energies, over all the masses, plus the sum of the elastic energies, over all springs. The equilibrium positions of the masses is the point that minimizes the total energy, subject to the constraints that the first $p$ positions are fixed. (In the equilibrium positions, the total force on each mass is zero.) We let $E_{\min}$ denote the total energy of the system, in its equilibrium position. (We assume the energy is bounded below; this occurs if and only if each mass is connected, through some set of springs with positive stiffness, to a fixed mass.)

The total energy $E_{\min}$ is a measure of the stiffness of the structure, with larger $E_{\min}$ corresponding to stiffer. (We can think of $E_{\min} = -\infty$ as an infinitely unstiff structure; in this case, at least one mass is not even supported against gravity.)

(a) Suppose we know the fixed positions $x_1^{\text{fixed}}, \ldots, x_p^{\text{fixed}}, y_1^{\text{fixed}}, \ldots, y_p^{\text{fixed}}$, the mass values $m_1, \ldots, m_n$, the spring topology $A$, and the constant $g$. You are to choose nonnegative $k_1, \ldots, k_N$, subject to a budget constraint $\mathbf{1}^T k = k_1 + \cdots + k_N = k^{\text{tot}}$, where $k^{\text{tot}}$ is given. Your goal is to maximize $E_{\min}$.

Explain how to do this using convex optimization.

(b) Carry out your method for the problem data given in `tens_struct_data.*`. This file defines all the needed data, and also plots the equilibrium configuration when the stiffness is evenly distributed across the springs (*i.e.*, $k = (k^{\text{tot}}/N)\mathbf{1}$).

Report the optimal value of $E_{\min}$. Plot the optimized equilibrium configuration, and compare it to the equilibrium configuration with evenly distributed stiffness. (The code for doing this is in the file `tens_struct_data.*`, but commented out.)

**18.2** *Equilibrium position of a system of springs.* We consider a collection of $n$ masses in $\mathbf{R}^2$, with locations $(x_1, y_1), \ldots, (x_n, y_n)$, and masses $m_1, \ldots, m_n$. (In other words, the vector $x \in \mathbf{R}^n$ gives the x-coordinates, and $y \in \mathbf{R}^n$ gives the y-coordinates, of the points.) The masses $m_i$ are, of course, positive.

For $i = 1, \ldots, n-1$, mass $i$ is connected to mass $i+1$ by a spring. The potential energy in the $i$th spring is a function of the (Euclidean) distance $d_i = \|(x_i, y_i) - (x_{i+1}, y_{i+1})\|_2$ between the $i$th and $(i+1)$st masses, given by

$$E_i = \begin{cases} 0 & d_i < l_i \\ (k_i/2)(d_i - l_i)^2 & d_i \geq l_i \end{cases}$$

where $l_i \geq 0$ is the rest length, and $k_i > 0$ is the stiffness, of the $i$th spring. The gravitational potential energy of the $i$th mass is $g m_i y_i$, where $g$ is a positive constant. The total potential energy of the system is therefore

$$E = \sum_{i=1}^{n-1} E_i + g m^T y.$$

The locations of the first and last mass are fixed. The equilibrium location of the other masses is the one that minimizes $E$.

(a) Show how to find the equilibrium positions of the masses $2, \ldots, n-1$ using convex optimization. Be sure to justify convexity of any functions that arise in your formulation (if it is not obvious). The problem data are $m_i$, $k_i$, $l_i$, $g$, $x_1$, $y_1$, $x_n$, and $y_n$.

(b) Carry out your method to find the equilibrium positions for a problem with $n = 10$, $m_i = 1$, $k_i = 10$, $l_i = 1$, $x_1 = y_1 = 0$, $x_n = y_n = 10$, with $g$ varying from $g = 0$ (no gravity) to $g = 10$ (say). Verify that the results look reasonable. Plot the equilibrium configuration for several values of $g$.

**18.3** *Elastic truss design.* In this problem we consider a truss structure with $m$ bars connecting a set of nodes. Various external forces are applied at each node, which cause a (small) displacement in the node positions. $f \in \mathbf{R}^n$ will denote the vector of (components of) external forces, and $d \in \mathbf{R}^n$ will denote the vector of corresponding node displacements. (By 'corresponding' we mean if $f_i$ is, say, the $z$-coordinate of the external force applied at node $k$, then $d_i$ is the $z$-coordinate of the displacement of node $k$.) The vector $f$ is called a *loading* or *load*.

The structure is linearly elastic, *i.e.*, we have a linear relation $f = Kd$ between the vector of external forces $f$ and the node displacements $d$. The matrix $K = K^T \succ 0$ is called the *stiffness matrix* of the truss. Roughly speaking, the 'larger' $K$ is (*i.e.*, the stiffer the truss) the smaller the node displacement will be for a given loading.

We assume that the geometry (unloaded bar lengths and node positions) of the truss is fixed; we are to design the cross-sectional areas of the bars. These cross-sectional areas will be the design variables $x_i$, $i = 1, \ldots, m$. The stiffness matrix $K$ is a linear function of $x$:

$$K(x) = x_1 K_1 + \cdots + x_m K_m,$$

where $K_i = K_i^T \succeq 0$ depend on the truss geometry. You can assume these matrices are given or known. The total weight $W_{\text{tot}}$ of the truss also depends on the bar cross-sectional areas:

$$W_{\text{tot}}(x) = w_1 x_1 + \cdots + w_m x_m,$$

where $w_i > 0$ are known, given constants (density of the material times the length of bar $i$). Roughly speaking, the truss becomes stiffer, but also heavier, when we increase $x_i$; there is a tradeoff between stiffness and weight.

Our goal is to design the stiffest truss, subject to bounds on the bar cross-sectional areas and total truss weight:
$$l \le x_i \le u, \quad i = 1, \dots, m, \qquad W_{\text{tot}}(x) \le W,$$
where $l$, $u$, and $W$ are given. You may assume that $K(x) \succ 0$ for all feasible vectors $x$. To obtain a specific optimization problem, we must say how we will measure the stiffness, and what model of the loads we will use.

(a) There are several ways to form a scalar measure of how stiff a truss is, for a given load $f$. In this problem we will use the *elastic stored energy*

$$\mathcal{E}(x, f) = \frac{1}{2} f^T K(x)^{-1} f$$

to measure the stiffness. Maximizing stiffness corresponds to minimizing $\mathcal{E}(x, f)$.

Show that $\mathcal{E}(x, f)$ is a convex function of $x$ on $\{x \mid K(x) \succ 0\}$.

*Hint.* Use Schur complements to prove that the epigraph is a convex set.

(b) We can consider several different scenarios that reflect our knowledge about the possible loadings $f$ that can occur. The simplest is that $f$ is a single, fixed, known loading. In more sophisticated formulations, the loading $f$ might be a random vector with known distribution, or known only to lie in some set $\mathcal{F}$, etc.

Show that each of the following four problems is a convex optimization problem, with $x$ as variable.

- *Design for a fixed known loading.* The vector $f$ is known and fixed. The design problem is

$$
\begin{array}{ll}
\text{minimize} & \mathcal{E}(x, f) \\
\text{subject to} & l \le x_i \le u, \quad i = 1, \dots, m \\
& W_{\text{tot}}(x) \le W.
\end{array}
$$

- *Design for multiple loadings.* The vector $f$ can take any of $N$ known values $f^{(i)}$, $i = 1, \dots, N$, and we are interested in the worst-case scenario. The design problem is

$$
\begin{array}{ll}
\text{minimize} & \max_{i=1,\dots,N} \mathcal{E}(x, f^{(i)}) \\
\text{subject to} & l \le x_i \le u, \quad i = 1, \dots, m \\
& W_{\text{tot}}(x) \le W.
\end{array}
$$

- *Design for worst-case, unknown but bounded load.* Here we assume the vector $f$ can take arbitrary values in a ball $B = \{f \mid \|f\|_2 \le \alpha\}$, for a given value of $\alpha$. We are interested in minimizing the worst-case stored energy, *i.e.*,

$$
\begin{array}{ll}
\text{minimize} & \sup_{\|f\|_2 \le \alpha} \mathcal{E}(x, f^{(i)}) \\
\text{subject to} & l \le x_i \le u, \quad i = 1, \dots, m \\
& W_{\text{tot}}(x) \le W.
\end{array}
$$

- *Design for a random load with known statistics.* We can also use a stochastic model of the uncertainty in the load, and model the vector $f$ as a random variable with known mean and covariance:

$$\mathbf{E}\, f = f^{(0)}, \quad \mathbf{E}(f - f^{(0)})(f - f^{(0)})^T = \Sigma.$$

In this case we would be interested in minimizing the expected stored energy, *i.e.*,

$$\begin{aligned}
\text{minimize} \quad & \mathbf{E}\,\mathcal{E}(x, f^{(i)}) \\
\text{subject to} \quad & l \le x_i \le u, \quad i = 1, \dots, m \\
& W_{\text{tot}}(x) \le W.
\end{aligned}$$

*Hint.* If $v$ is a random vector with zero mean and covariance $\Sigma$, then $\mathbf{E}\, v^T A v = \mathbf{E}\,\mathbf{tr}\, A v v^T = \mathbf{tr}\, A\,\mathbf{E}\, v v^T = \mathbf{tr}\, A\Sigma$.

(c) Formulate the four problems in (b) as semidefinite programming problems.

**18.4** *A structural optimization problem* [Bazaraa, Sherali, and Shetty]. The figure shows a two-bar truss with height $2h$ and width $w$. The two bars are cylindrical tubes with inner radius $r$ and outer radius $R$. We are interested in determining the values of $r$, $R$, $w$, and $h$ that minimize the weight of the truss subject to a number of constraints. The structure should be strong enough for two loading scenarios. In the first scenario a vertical force $F_1$ is applied to the node; in the second scenario the force is horizontal with magnitude $F_2$.



The weight of the truss is proportional to the total volume of the bars, which is given by

$$2\pi(R^2 - r^2)\sqrt{w^2 + h^2}$$

This is the cost function in the design problem.

The first constraint is that the truss should be strong enough to carry the load $F_1$, *i.e.*, the stress caused by the external force $F_1$ must not exceed a given maximum value. To formulate this constraint, we first determine the forces in each bar when the structure is subjected to the vertical load $F_1$. From the force equilibrium and the geometry of the problem we can determine that the magnitudes of the forces in two bars are equal and given by

$$\frac{\sqrt{w^2 + h^2}}{2h}F_1.$$

The maximum force in each bar is equal to the cross-sectional area times the maximum allowable stress $\sigma$ (which is a given constant). This gives us the first constraint:

$$\frac{\sqrt{w^2 + h^2}}{2h} F_1 \leq \sigma\pi(R^2 - r^2).$$

The second constraint is that the truss should be strong enough to carry the load $F_2$. When $F_2$ is applied, the magnitudes of the forces in two bars are again equal and given by

$$\frac{\sqrt{w^2 + h^2}}{2w} F_2,$$

which gives us the second constraint:

$$\frac{\sqrt{w^2 + h^2}}{2w} F_2 \leq \sigma\pi(R^2 - r^2).$$

We also impose limits $w_{\min} \leq w \leq w_{\max}$ and $h_{\min} \leq h \leq h_{\max}$ on the width and the height of the structure, and limits $1.1r \leq R \leq R_{\max}$ on the outer radius.

In summary, we obtain the following problem:

$$
\begin{aligned}
\text{minimize} \quad & 2\pi(R^2 - r^2)\sqrt{w^2 + h^2} \\
\text{subject to} \quad & \frac{\sqrt{w^2 + h^2}}{2h} F_1 \leq \sigma\pi(R^2 - r^2) \\
& \frac{\sqrt{w^2 + h^2}}{2w} F_2 \leq \sigma\pi(R^2 - r^2) \\
& w_{\min} \leq w \leq w_{\max} \\
& h_{\min} \leq h \leq h_{\max} \\
& 1.1r \leq R \leq R_{\max} \\
& R > 0, \quad r > 0, \quad w > 0, \quad h > 0.
\end{aligned}
$$

The variables are $R$, $r$, $w$, $h$.

Formulate this as a geometric programming problem.

**18.5** *Optimizing the inertia matrix of a 2D mass distribution.* An object has density $\rho(z)$ at the point $z = (x, y) \in \mathbf{R}^2$, over some region $\mathcal{R} \subset \mathbf{R}^2$. Its mass $m \in \mathbf{R}$ and center of gravity $c \in \mathbf{R}^2$ are given by

$$m = \int_{\mathcal{R}} \rho(z) \, dxdy, \qquad c = \frac{1}{m} \int_{\mathcal{R}} \rho(z)z \, dxdy,$$

and its inertia matrix $M \in \mathbf{R}^{2\times 2}$ is

$$M = \int_{\mathcal{R}} \rho(z)(z - c)(z - c)^T \, dxdy.$$

(You do not need to know the mechanics interpretation of $M$ to solve this problem, but here it is, for those interested. Suppose we rotate the mass distribution around a line passing through the

center of gravity in the direction $q \in \mathbf{R}^2$ that lies in the plane where the mass distribution is, at angular rate $\omega$. Then the total kinetic energy is $(\omega^2/2)q^T M q$.)

The goal is to choose the density $\rho$, subject to $0 \leq \rho(z) \leq \rho^{\mathrm{max}}$ for all $z \in \mathcal{R}$, and a fixed total mass $m = m^{\mathrm{given}}$, in order to maximize $\lambda_{\mathrm{min}}(M)$.

To solve this problem numerically, we will discretize $\mathcal{R}$ into $N$ pixels each of area $a$, with pixel $i$ having constant density $\rho_i$ and location (say, of its center) $z_i \in \mathbf{R}^2$. We will assume that the integrands above don't vary too much over the pixels, and from now on use instead the expressions

$$ m = a \sum_{i=1}^{N} \rho_i, \quad c = \frac{a}{m} \sum_{i=1}^{N} \rho_i z_i, \quad M = a \sum_{i=1}^{N} \rho_i (z_i - c)(z_i - c)^T. $$

The problem below refers to these discretized expressions.

(a) Explain how to solve the problem using convex (or quasiconvex) optimization.

(b) Carry out your method on the problem instance with data in `inertia_dens_data.m`. This file includes code that plots a density. Give the optimal inertia matrix and its eigenvalues, and plot the optimal density.

**18.6** *Truss loading analysis.* A truss (in 2D, for simplicity) consists of a set of $n$ nodes, with positions $p^{(1)}, \ldots, p^{(n)} \in \mathbf{R}^2$, connected by a set of $m$ bars with tensions $t_1, \ldots, t_m \in \mathbf{R}$ ($t_j < 0$ means bar $j$ operates in compression).

Each bar puts a force on the two nodes which it connects. Suppose bar $j$ connects nodes $k$ and $l$. The tension in this bar applies a force

$$ \frac{t_j}{\|p^{(l)} - p^{(k)}\|_2} (p^{(l)} - p^{(k)}) \in \mathbf{R}^2 $$

to node $k$, and the opposite force to node $l$. In addition to the forces imparted by the bars, each node has an external force acting on it. We let $f^{(i)} \in \mathbf{R}^2$ be the external force acting on node $i$. For the truss to be in equilibrium, the total force on each node, *i.e.*, the sum of the external force and the forces applied by all of the bars that connect to it, must be zero. We refer to this constraint as force balance.

The tensions have given limits, $T_j^{\mathrm{min}} \leq t_j \leq T_j^{\mathrm{max}}$, with $T_j^{\mathrm{min}} \leq 0$ and $T_j^{\mathrm{max}} \geq 0$, for $j = 1, \ldots, m$. (For example, if bar $j$ is a cable, then it can only apply a nonnegative tension, so $T_j^{\mathrm{min}} = 0$, and we interpret $T_j^{\mathrm{max}}$ as the maximum tension the cable can carry.)

The first $p$ nodes, $i = 1, \ldots, p$, are *free*, while the remaining $n - p$ nodes, $i = p + 1, \ldots, n$, are *anchored* (*i.e.*, attached to a foundation). We will refer to the external forces on the free nodes as *load forces*, and external forces at the anchor nodes as *anchor forces*. The anchor forces are unconstrained. (More accurately, the foundations at these points are engineered to withstand any total force that the bars attached to it can deliver.) We will assume that the load forces are just dead weight, *i.e.*, have the form

$$ f^{(i)} = \begin{bmatrix} 0 \\ -w_i \end{bmatrix}, \quad i = 1, \ldots, p, $$

where $w_i \geq 0$ is the weight supported at node $i$.

The set of weights $w \in \mathbf{R}_+^p$ is *supportable* if there exists a set of tensions $t \in \mathbf{R}^m$ and anchor forces $f^{(p+1)}, \ldots, f^{(n)}$ that, together with the given load forces, satisfy the force balance equations and respect the tension limits. (The tensions and anchor forces in a real truss will adjust themselves to have such values when the load forces are applied.) If there does not exist such a set of tensions and anchor forces, the set of load forces is said to be *unsupportable*. (In this case, a real truss will fail, or collapse, when the load forces are applied.)

Finally, we get to the questions.

(a) Explain how to find the maximum total weight, $\mathbf{1}^T w$, that is supportable by the truss.

(b) Explain how to find the minimum total weight that is not supportable by the truss. (Here we mean: Find the minimum value of $\mathbf{1}^T w$, for which $(1 + \epsilon)w$ is not supportable, for all $\epsilon > 0$.)

(c) Carry out the methods of parts (a) and (b) on the data given in `truss_load_data.m`. Give the critical total weights from parts (a) and (b), as well as the individual weight vectors.

*Notes.*

- In parts (a) and (b), we don't need a fully formal mathematical justification; a clear argument or explanation of anything not obvious is fine.

- The force balance equations can be expressed in the compact and convenient form

$$
At + \begin{bmatrix} f^{\text{load,x}} \\ f^{\text{load,y}} \\ f^{\text{anch}} \end{bmatrix} = 0,
$$

where

$$
\begin{aligned}
f^{\text{load,x}} &= (f_1^{(1)}, \ldots, f_1^{(p)}) \in \mathbf{R}^p, \\
f^{\text{load,y}} &= (f_2^{(1)}, \ldots, f_2^{(p)}) \in \mathbf{R}^p, \\
f^{\text{anch}} &= (f_1^{(p+1)}, \ldots, f_1^{(n)}, f_2^{(p+1)}, \ldots, f_2^{(n)}) \in \mathbf{R}^{2(n-p)},
\end{aligned}
$$

and $A \in \mathbf{R}^{2n \times m}$ is a matrix that can be found from the geometry data (truss topology and node positions). You may refer to $A$ in your solutions to parts (a) and (b). For part (c), *we have very kindly provided the matrix $A$ for you in the m-file*, to save you the time and trouble of working out the force balance equations from the geometry of the problem.

**18.7** *Least-cost road grading.* A road is to be built along a given path. We must choose the height of the roadbed (say, above sea level) along the path, minimizing the total cost of grading, subject to some constraints. The cost of grading (*i.e.*, moving earth to change the height of the roadbed from the existing elevation) depends on the difference in height between the roadbed and the existing elevation. When the roadbed is below the existing elevation it is called a *cut*; when it is above it is called a *fill*. Each of these incurs engineering costs; for example, fill is created in a series of *lifts*, each of which involves dumping just a few inches of soil and then compacting it. Deeper cuts and higher fills require more work to be done on the road shoulders, and possibly, the addition of reinforced concrete structures to stabilize the earthwork. This explains why the marginal cost of cuts and fills increases with their depth/height.

We will work with a discrete model, specifying the road height as $h_i$, $i = 1, \ldots, n$, at points equally spaced a distance $d$ from each other along the given path. These are the variables to be chosen. (The heights $h_1, \ldots, h_n$ are called a *grading plan*.) We are given $e_i$, $i = 1, \ldots, n$, the existing elevation, at the points. The grading cost is

$$C = \sum_{i=1}^{n} \left( \phi^{\text{fill}}((h_i - e_i)_+) + \phi^{\text{cut}}((e_i - h_i)_+) \right),$$

where $\phi^{\text{fill}}$ and $\phi^{\text{cut}}$ are the fill and cut cost functions, respectively, and $(a)_+ = \max\{a, 0\}$. The fill and cut functions are increasing and convex. The goal is to minimize the grading cost $C$.

The road height is constrained by given limits on the first, second, and third derivatives:

$$
\begin{aligned}
|h_{i+1} - h_i|/d &\leq D^{(1)}, & i = 1, \ldots, n-1 \\
|h_{i+1} - 2h_i + h_{i-1}|/d^2 &\leq D^{(2)}, & i = 2, \ldots, n-1 \\
|h_{i+1} - 3h_i + 3h_{i-1} - h_{i-2}|/d^3 &\leq D^{(3)}, & i = 3, \ldots, n-1,
\end{aligned}
$$

where $D^{(1)}$ is the maximum allowable road slope, $D^{(2)}$ is the maximum allowable curvature, and $D^{(3)}$ is the maximum allowable third derivative.

(a) Explain how to find the optimal grading plan.

(b) Find the optimal grading plan for the problem with data given in `road_grading_data.m`, and fill and cut cost functions

$$\phi^{\text{fill}}(u) = 2(u)_+^2 + 30(u)_+, \qquad \phi^{\text{cut}} = 12(u)_+^2 + (u)_+.$$

Plot $h_i - e_i$ for the optimal grading plan and report the associated cost.

(c) Suppose the optimal grading problem with $n = 1000$ can be solved on a particular machine (say, with one, or just a few, cores) in around one second. Assuming the author of the software took EE364a, about how long will it take to solve the optimal grading problem with $n = 10000$? Give a very brief justification of your answer, no more than a few sentences.

**18.8** *Lightest structure that resists a set of loads.* We consider a mechanical structure in 2D (for simplicity) which consists of a set of $m$ nodes, with known positions $p_1, \ldots, p_m \in \mathbf{R}^2$, connected by a set of $n$ bars (also called struts or elements), with cross-sectional areas $a_1, \ldots, a_n \in \mathbf{R}_+$, and internal tensions $t_1, \ldots, t_n \in \mathbf{R}$.

Bar $j$ is connected between nodes $r_j$ and $s_j$. (The indices $r_1, \ldots, r_n$ and $s_1, \ldots, s_n$ give the structure topology.) The length of bar $j$ is $L_j = \|p_{r_j} - p_{s_j}\|_2$, and the total volume of the bars is $V = \sum_{j=1}^{n} a_j L_j$. (The total weight is proportional to the total volume.)

Bar $j$ applies a force $(t_j/L_j)(p_{r_j} - p_{s_j}) \in \mathbf{R}^2$ to node $s_j$ and the negative of this force to node $r_j$. Thus, positive tension in a bar pulls its two adjacent nodes towards each other; negative tension (also called compression) pushes them apart. The ratio of the tension in a bar to its cross-sectional area is limited by its yield strength, which is symmetric in tension and compression: $|t_j| \leq \sigma a_j$, where $\sigma > 0$ is a known constant that depends on the material.

The nodes are divided into two groups: free and fixed. We will take nodes $1, \ldots, k$ to be free, and nodes $k+1, \ldots, m$ to be fixed. Roughly speaking, the fixed nodes are firmly attached to the ground, or a rigid structure connected to the ground; the free ones are not.

A *loading* consists of a set of external forces, $f_1, \ldots, f_k \in \mathbf{R}^2$ applied to the free nodes. Each free node must be in equilibrium, which means that the sum of the forces applied to it by the bars and the external force is zero. The structure can *resist* a loading (without collapsing) if there exists a set of bar tensions that satisfy the tension bounds and force equilibrium constraints. (For those with knowledge of statics, these conditions correspond to a structure made entirely with pin joints.)

Finally, we get to the problem. You are given a set of $M$ loadings, *i.e.*, $f_1^{(i)}, \ldots, f_k^{(i)} \in \mathbf{R}^2$, $i = 1, \ldots, M$. The goal is to find the bar cross-sectional areas that minimize the structure volume $V$ while resisting all of the given loadings. (Thus, you are to find *one* set of bar cross-sectional areas, and $M$ sets of tensions.) Using the problem data provided in `lightest_struct_data.m`, report $V^\star$ and $V^{\mathrm{unif}}$, the smallest feasible structure volume when all bars have the same cross-sectional area. The node positions are given as a $2 \times m$ matrix P, and the loadings as a $2 \times k \times M$ array F. Use the code included in the data file to visualize the structure with the bar cross-sectional areas that you find, and provide the plot in your solution.

*Hint.* You might find the graph incidence matrix $A \in \mathbf{R}^{m \times n}$ useful. It is defined as

$$
A_{ij} = \begin{cases} +1 & i = r_j \\ -1 & i = s_j \\ 0 & \text{otherwise.} \end{cases}
$$

*Remark.* You could reasonably ask, 'Does a mechanical structure really solve a convex optimization problem to determine whether it should collapse?'. It sounds odd, but the answer is, yes it does.

**18.9** *Maintaining static balance.* In this problem we study a human's ability to maintain balance against an applied external force. We will use a planar (two-dimensional) model to characterize the set of push forces a human can sustain before he or she is unable to maintain balance. We model the human as a linkage of 4 body segments, which we consider to be rigid bodies: the foot, lower leg, upper leg, and pelvis (into which we lump the upper body). The pose is given by the joint angles, but this won't matter in this problem, since we consider a fixed pose. A set of 40 muscles act on the body segments; each of these develops a (scalar) tension $t_i$ that satisfies $0 \le t_i \le T_i^{\mathrm{max}}$, where $T_i^{\mathrm{max}}$ is the maximum possible tension for muscle $i$. (The maximum muscle tensions depend on the pose, and the person, but here they are known constants.) An external pushing force $f^{\mathrm{push}} \in \mathbf{R}^2$ acts on the pelvis. Two (ground contact) forces act on the foot: $f^{\mathrm{heel}} \in \mathbf{R}^2$ and $f^{\mathrm{toe}} \in \mathbf{R}^2$. (These are shown at right.) These must satisfy

$$
|f_1^{\mathrm{heel}}| \le \mu f_2^{\mathrm{heel}}, \quad |f_1^{\mathrm{toe}}| \le \mu f_2^{\mathrm{toe}},
$$

where $\mu > 0$ is the coefficient of friction of the ground. There are also joint forces that act at the joints between the body segments, and gravity forces for each body segment, but we won't need them explicitly in this problem.

To maintain balance, the net force and torque on each each body segment must be satisfied. These equations can be written out from the geometry of the body (*e.g.*, attachment points for the

muscles) and the pose. They can be reduced to a set of 6 linear equations:

$$A^{\mathrm{musc}}t + A^{\mathrm{toe}}f^{\mathrm{toe}} + A^{\mathrm{heel}}f^{\mathrm{heel}} + A^{\mathrm{push}}f^{\mathrm{push}} = b,$$

where $t \in \mathbf{R}^{40}$ is the vector of muscle tensions, and $A^{\mathrm{musc}}$, $A^{\mathrm{toe}}$, $A^{\mathrm{heel}}$, and $A^{\mathrm{push}}$ are known matrices and $b \in \mathbf{R}^6$ is a known vector. These data depend on the pose, body weight and dimensions, and muscle lines of action. Fortunately for you, our biomechanics expert Apoorva has worked them out; you will find them in `static_balance_data.*` (along with $T^{\mathrm{max}}$ and $\mu$).

We say that the push force $f^{\mathrm{push}}$ can be *resisted* if there exist muscle tensions and ground contact forces that satisfy the constraints above. (This raises a philosophical question: Does a person solve an optimization to decide whether he or she should lose their balance? In any case, this approach makes good predictions.)

Find $\mathcal{F}^{\mathrm{res}} \subset \mathbf{R}^2$, the set of push forces that can be resisted. Plot it as a shaded region.

*Hints.* Show that $\mathcal{F}^{\mathrm{res}}$ is a convex set. For the given data, $0 \in \mathcal{F}^{\mathrm{res}}$. Then for $\theta = 1°, 2°, \ldots, 360°$, determine the maximum push force, applied in the direction $\theta$, that can be resisted. To make a filled region on a plot, you can use the command `fill()` in Matlab. For Python and Julia, `fill()` is also available through PyPlot. In Julia, make sure to use the ECOS solver with `solver = ECOSSolver(verbose=false)`.

*Remark.* A person can resist a much larger force applied to the hip than you might think.

**18.10** *Thermodynamic potentials.* We consider a mixture of $k$ chemical species. The *internal energy* of the mixture is

$$U(S, V, N_1, \ldots, N_k),$$

where $S$ is the entropy of the mixture, $V$ is the volume occupied by the mixture, and $N_i$ is the quantity (in moles) of chemical species $i$. We assume the function $U$ is convex. (Real internal energy functions satisfy this and other interesting properties, but we won't need any others for this problem.) The *enthalpy H*, the *Helmoltz free energy A*, and the *Gibbs free energy G* are defined as

$$
\begin{aligned}
H(S, P, N_1, \ldots, N_k) &= \inf_{V} \left( U(S, V, N_1, \ldots, N_k) - PV \right), \\
A(T, V, N_1, \ldots, N_k) &= \inf_{S} \left( U(S, V, N_1, \ldots, N_k) + TS \right), \\
G(T, P, N_1, \ldots, N_k) &= \inf_{S,V} \left( U(S, V, N_1, \ldots, N_k) + TS - PV \right).
\end{aligned}
$$

The variables $T$ and $P$ can be interpreted physically as the temperature and pressure of the mixture. These four functions are called *thermodynamic potentials*. We refer to the arguments $S$, $V$, and $N_1, \ldots N_k$ as the extensive variables, and the arguments $T$ and $P$ as the intensive variables.

(a) Show that $H$, $A$, and $G$ are convex in the extensive variables, when the intensive variables are fixed.

(b) Show that $H$, $A$, and $G$ are concave in the intensive variables, when the extensive variables are fixed.

(c) We consider a simple reaction involving three species,

$$2[\text{species } 1] \rightleftharpoons [\text{species } 2] + [\text{species } 3],$$

carried out at temperature $T_{\text{react}}$ and volume $V_{\text{react}}$. The Helmholtz free energy of the mixture is

$$A(T, V, N_1, N_2, N_3) = T \sum_{j=1}^{3} N_j(s_{0,j} - Rc_j) + TR \sum_{j=1}^{3} N_j \log\left(N_j \left(\frac{V_0}{V}\right)\left(\frac{T_0}{T}\right)^{c_j}\right),$$

where $R$, $V_0$, $T_0$, $s_{0,j}$, and $c_j$, for $j = 1, \ldots, k$, are known, positive constants. The equilibrium molar quantities $N_1^\star$, $N_2^\star$, and $N_3^\star$ of the three species are those that minimize $A(T_{\text{react}}, V_{\text{react}}, N_1, N_2, N_3)$ subject to the stoichiometry constraints

$$N_1 = N_{1,\text{init}} - 2z, \quad N_2 = N_{2,\text{init}} + z, \quad N_3 = N_{3,\text{init}} + z,$$

where $N_{j,\text{init}}$ is the initial quantity of species $j$, and the variable $z$ gives the amount of the reaction that has proceeded. For the values of $T_{\text{react}}$, $V_{\text{react}}$, $R$, $V_0$, $T_0$, $s_{0,j}$, and $c_j$ given in `thermo_potentials_data.*`, report the equilibrium molar quantities $N_1^\star$, $N_2^\star$, and $N_3^\star$.
**Note:** Julia users might want the ECOS solver. Include `using ECOS`, and solve by using `solve!(prob, ECOSSolver())`.

**18.11** *Elastic stored energy in a spring.* A spring is a mechanical device that exerts a force $F$ that depends on its extension $x$: $F = \phi(x)$, where $\phi : \mathbf{R} \to \mathbf{R}$. The domain $\mathbf{dom}\,\phi$ is an interval $[x^{\min}, x^{\max}]$ containing 0, where $x^{\min}$ ($x^{\max}$) is the minimum (maximum) possible extension of the spring. When $x > 0$, the spring is said to be extended, and when $x < 0$, it is said to be in compression. The force exerted by the spring must be *restoring*, which means that $F \geq 0$ when $x \geq 0$, and $F \leq 0$ when $x \leq 0$. (Our sign convention is that a positive force $F$ opposes a positive extension $x$.) This implies that $F = 0$ when $x = 0$, *i.e.*, zero force is developed when the spring is not extended or compressed.

The simplest spring is a Hooke (linear) spring, with $\phi(x) = Kx$, where $K > 0$ is the *spring constant*. (The constant $1/K$ is called the spring *compliance*.)

A spring is called *monotonic* if the function $\phi$ is nondecreasing, *i.e.*, larger extension leads to a stronger restoring force. Many, but not all, springs are monotonic. A classic example is a compound bow, which has a force that first increases with $x$, and then decreases to a small value at the extension $x$ where it is fully drawn. (This decrease in force from the maximum is called the *let off* of the bow.)

The elastic stored energy in the spring is

$$E(x) = \int_0^x \phi(x') \, dx',$$

with domain $[x^{\min}, x^{\max}]$.

Show that $E$ is quasi-convex. Show that $E$ is convex if and only if the spring is monotonic. You may assume $\phi$ is differentiable.

**18.12** *Quickest take-off.* This problem concerns the braking and thrust profiles for an airplane during take-off. For simplicity we will use a discrete-time model. The position (down the runway) and the velocity in time period $t$ are $p_t$ and $v_t$, respectively, for $t = 0, 1, \ldots$. These satisfy $p_0 = 0$, $v_0 = 0$, and $p_{t+1} = p_t + hv_t$, $t = 0, 1, \ldots$, where $h > 0$ is the sampling time period. The velocity updates as

$$v_{t+1} = (1 - \eta)v_t + h(f_t - b_t), \quad t = 0, 1, \ldots,$$

where $\eta \in (0, 1)$ is a friction or drag parameter, $f_t$ is the engine thrust, and $b_t$ is the braking force, at time period $t$. These must satisfy

$$0 \leq b_t \leq \min\{B^{\max}, f_t\}, \quad 0 \leq f_t \leq F^{\max}, \quad t = 0, 1, \ldots,$$

as well as a constraint on how fast the engine thrust can be changed,

$$|f_{t+1} - f_t| \leq S, \quad t = 0, 1, \ldots.$$

Here $B^{\max}$, $F^{\max}$, and $S$ are given parameters. The initial thrust is $f_0 = 0$. The take-off time is $T^{\mathrm{to}} = \min\{t \mid v_t \geq V^{\mathrm{to}}\}$, where $V^{\mathrm{to}}$ is a given take-off velocity. The take-off position is $P^{\mathrm{to}} = p_{T^{\mathrm{to}}}$, the position of the aircraft at the take-off time. The length of the runway is $L > 0$, so we must have $P^{\mathrm{to}} \leq L$.

(a) Explain how to find the thrust and braking profiles that minimize the take-off time $T^{\mathrm{to}}$, respecting all constraints. Your solution can involve solving more than one convex problem, if necessary.

(b) Solve the quickest take-off problem with data

$$h = 1, \quad \eta = 0.05, \quad B^{\max} = 0.5, \quad F^{\max} = 4, \quad S = 0.8, \quad V^{\mathrm{to}} = 40, \quad L = 300.$$

Plot $p_t$, $v_t$, $f_t$, and $b_t$ versus $t$. Comment on what you see. Report the take-off time and take-off position for the profile you find.

**18.13** *Minimum time maneuver for a crane.* A crane manipulates a load with mass $m > 0$ in two dimensions using two cables attached to the load. The cables maintain angles $\pm\theta$ with respect to vertical, as shown below.



The (scalar) tensions $T^{\mathrm{left}}$ and $T^{\mathrm{right}}$ in the two cables are independently controllable, from 0 up to a given maximum tension $T^{\max}$. The total force on the load is

$$F = T^{\mathrm{left}} \begin{bmatrix} -\sin\theta \\ \cos\theta \end{bmatrix} + T^{\mathrm{right}} \begin{bmatrix} \sin\theta \\ \cos\theta \end{bmatrix} + mg,$$

where $g = (0, -9.8)$ is the acceleration due to gravity. The acceleration of the load is then $F/m$.

We approximate the motion of the load using

$$p_{i+1} = p_i + hv_i, \quad v_{i+1} = v_i + (h/m)F_i, \quad i = 1, 2, \ldots,$$

where $p_i \in \mathbf{R}^2$ is the position of the load, $v_i \in \mathbf{R}^2$ is the velocity of the load, and $F_i \in \mathbf{R}^2$ is the force on the load, at time $t = ih$. Here $h > 0$ is a small (given) time step.

The goal is to move the load, which is initially at rest at position $p^{\text{init}}$ to the position $p^{\text{des}}$, also at rest, in minimum time. In other words, we seek the smallest $k$ for which

$$p_1 = p^{\text{init}}, \quad p_k = p^{\text{des}}, \quad v_1 = v_k = (0,0)$$

is possible, subject to the constraints described above.

(a) Explain how to solve this problem using convex (or quasiconvex) optimization.

(b) Carry out the method of part (a) for the problem instance with

$$m = 0.1, \quad \theta = 15°, \quad T^{\text{max}} = 2, \quad p^{\text{init}} = (0,0), \quad p^{\text{des}} = (10,2),$$

with time step $h = 0.1$. Report the minimum time $k^\star$. Plot the tensions versus time, and the load trajectory, $i.e.$, the points $p_1, \ldots, p_k$ in $\mathbf{R}^2$. Does the load move along the line segment between $p^{\text{init}}$ and $p^{\text{des}}$ ($i.e.$, the shortest path from $p^{\text{init}}$ and $p^{\text{des}}$)? Comment briefly.

# 19 Graphs and networks

**19.1** A *hypergraph* with nodes $1, \ldots, m$ is a set of nonempty subsets of $\{1, 2, \ldots, m\}$, called *edges*. An ordinary graph is a special case in which the edges contain no more than two nodes.

We consider a hypergraph with $m$ nodes and assume coordinate vectors $x_j \in \mathbf{R}^p$, $j = 1, \ldots, m$, are associated with the nodes. Some nodes are fixed and their coordinate vectors $x_j$ are given. The other nodes are free, and their coordinate vectors will be the optimization variables in the problem. The objective is to place the free nodes in such a way that some measure of the physical size of the nets is small.

As an example application, we can think of the nodes as modules in an integrated circuit, placed at positions $x_j \in \mathbf{R}^2$. Every edge is an interconnect network that carries a signal from one module to one or more other modules.

To define a measure of the size of a net, we store the vectors $x_j$ as columns of a matrix $X \in \mathbf{R}^{p \times m}$. For each edge $S$ in the hypergraph, we use $X_S$ to denote the $p \times |S|$ submatrix of $X$ with the columns associated with the nodes of $S$. We define

$$f_S(X) = \inf_y \| X_S - y\mathbf{1}^T \|. \tag{69}$$

as the *size* of the edge $S$, where $\| \cdot \|$ is a matrix norm, and $\mathbf{1}$ is a vector of ones of length $|S|$.

(a) Show that the optimization problem

$$\text{minimize} \quad \sum_{\text{edges } S} f_S(X)$$

is convex in the free node coordinates $x_j$.

(b) The size $f_S(X)$ of a net $S$ obviously depends on the norm used in the definition (69). We consider five norms.

- *Frobenius norm:*

$$\| X_s - y\mathbf{1}^T \|_F = \left( \sum_{j \in S} \sum_{i=1}^{p} (x_{ij} - y_i)^2 \right)^{1/2}.$$

- *Maximum Euclidean column norm:*

$$\| X_S - y\mathbf{1}^T \|_{2,1} = \max_{j \in S} \left( \sum_{i=1}^{p} (x_{ij} - y_i)^2 \right)^{1/2}.$$

- *Maximum column sum norm:*

$$\| X_S - y\mathbf{1}^T \|_{1,1} = \max_{j \in S} \sum_{i=1}^{p} |x_{ij} - y_i|.$$

- *Sum of absolute values norm:*

$$\| X_s - y\mathbf{1}^T \|_{\text{sav}} = \sum_{j \in S} \sum_{i=1}^{p} |x_{ij} - y_i|$$

- *Sum-row-max norm:*

$$\|X_s - y\mathbf{1}^T\|_{\mathrm{srm}} = \sum_{i=1}^{p} \max_{j \in S} |x_{ij} - y_i|$$

For which of these norms does $f_S$ have the following interpretations?

(i) $f_S(X)$ is the radius of the smallest Euclidean ball that contains the nodes of $S$.

(ii) $f_S(X)$ is (proportional to) the perimeter of the smallest rectangle that contains the nodes of $S$:

$$f_S(X) = \frac{1}{4} \sum_{i=1}^{p} (\max_{j \in S} x_{ij} - \min_{j \in S} x_{ij}).$$

(iii) $f_S(X)$ is the squareroot of the sum of the squares of the Euclidean distances to the mean of the coordinates of the nodes in $S$:

$$f_S(X) = \left( \sum_{j \in S} \|x_j - \bar{x}\|_2^2 \right)^{1/2} \quad \text{where} \quad \bar{x}_i = \frac{1}{|S|} \sum_{k \in S} x_{ik}, \quad i = 1, \dots, p.$$

(iv) $f_S(X)$ is the sum of the $\ell_1$-distances to the (coordinate-wise) median of the coordinates of the nodes in $S$:

$$f_S(X) = \sum_{j \in S} \|x_j - \hat{x}\|_1 \quad \text{where} \quad \hat{x}_i = \mathrm{median}(\{x_{ik} \mid k \in S\}), \quad i = 1, \dots, p.$$

**19.2** Let $W \in \mathbf{S}^n$ be a symmetric matrix with nonnegative elements $w_{ij}$ and zero diagonal. We can interpret $W$ as the representation of a weighted undirected graph with $n$ nodes. If $w_{ij} = w_{ji} > 0$, there is an edge between nodes $i$ and $j$, with weight $w_{ij}$. If $w_{ij} = w_{ji} = 0$ then nodes $i$ and $j$ are not connected. The *Laplacian* of the weighted graph is defined as

$$L(W) = -W + \mathbf{diag}(W\mathbf{1}).$$

This is a symmetric matrix with elements

$$L_{ij}(W) = \begin{cases} \sum_{k=1}^{n} w_{ik} & i = j \\ -w_{ij} & i \neq j. \end{cases}$$

The Laplacian has the useful property that

$$y^T L(W) y = \sum_{i \leq j} w_{ij} (y_i - y_j)^2$$

for all vectors $y \in \mathbf{R}^n$.

(a) Show that the function $f : \mathbf{S}^n \to \mathbf{R}$,

$$f(W) = \inf_{\mathbf{1}^T x = 0} n\lambda_{\max} \left( L(W) + \mathbf{diag}(x) \right),$$

is convex.

(b) Give a simple argument why $f(W)$ is an upper bound on the optimal value of the combinatorial optimization problem

$$
\begin{array}{ll}
\text{maximize} & y^T L(W) y \\
\text{subject to} & y_i \in \{-1, 1\}, \quad i = 1, \ldots, n.
\end{array}
$$

This problem is known as the *max-cut* problem, for the following reason. Every vector $y$ with components $\pm 1$ can be interpreted as a partition of the nodes of the graph in a set $S = \{i \mid y_i = 1\}$ and a set $T = \{i \mid y_i = -1\}$. Such a partition is called a *cut* of the graph. The objective function in the max-cut problem is

$$
y^T L(W) y = \sum_{i \leq j} w_{ij} (y_i - y_j)^2.
$$

If $y$ is $\pm 1$-vector corresponding to a partition in sets $S$ and $T$, then $y^T L(W) y$ equals four times the sum of the weights of the edges that join a point in $S$ to a point in $T$. This is called the weight of the cut defined by $y$. The solution of the max-cut problem is the cut with the maximum weight.

(c) The function $f$ defined in part 1 can be evaluated, for a given $W$, by solving the optimization problem

$$
\begin{array}{ll}
\text{minimize} & n \lambda_{\max}(L(W) + \mathbf{diag}(x)) \\
\text{subject to} & \mathbf{1}^T x = 0,
\end{array}
$$

with variable $x \in \mathbf{R}^n$. Express this problem as an SDP.

(d) Derive an alternative expression for $f(W)$, by taking the dual of the SDP in part 3. Show that the dual SDP is equivalent to the following problem:

$$
\begin{array}{ll}
\text{maximize} & \sum_{i \leq j} w_{ij} \|p_i - p_j\|_2^2 \\
\text{subject} & \|p_i\|_2 = 1, \quad i = 1, \ldots, n,
\end{array}
$$

with variables $p_i \in \mathbf{R}^n$, $i = 1, \ldots, n$. In this problem we place $n$ points $p_i$ on the unit sphere in $\mathbf{R}^n$ in such a way that the weighted sum of their squared pair-wise distances is maximized.

**19.3** *Utility versus latency trade-off in a network.* We consider a network with $m$ edges, labeled $1, \ldots, m$, and $n$ flows, labeled $1, \ldots, n$. Each flow has an associated nonnegative flow rate $f_j$; each edge or link has an associated positive capacity $c_i$. Each flow passes over a fixed set of links (its route); the total traffic $t_i$ on link $i$ is the sum of the flow rates over all flows that pass through link $i$. The flow routes are described by a routing matrix $R \in \mathbf{R}^{m \times n}$, defined as

$$
R_{ij} = \begin{cases} 1 & \text{flow } j \text{ passes through link } i \\ 0 & \text{otherwise.} \end{cases}
$$

Thus, the vector of link traffic, $t \in \mathbf{R}^m$, is given by $t = Rf$. The link capacity constraint can be expressed as $Rf \preceq c$. The (logarithmic) network utility is defined as $U(f) = \sum_{j=1}^n \log f_j$.

The (average queuing) delay on link $i$ is given by

$$
d_i = \frac{1}{c_i - t_i}
$$

(multiplied by a constant, that doesn't matter to us). We take $d_i = \infty$ for $t_i = c_i$. The delay or latency for flow $j$, denoted $l_j$, is the sum of the link delays over all links that flow $j$ passes through. We define the maximum flow latency as

$$L = \max\{l_1, \ldots, l_n\}.$$

We are given $R$ and $c$; we are to choose $f$.

(a) How would you find the flow rates that maximize the utility $U$, ignoring flow latency? (In particular, we allow $L = \infty$.) We'll refer to this maximum achievable utility as $U^{\max}$.

(b) How would you find the flow rates that minimize the maximum flow latency $L$, ignoring utility? (In particular, we allow $U = -\infty$.) We'll refer to this minimum achievable latency as $L^{\min}$.

(c) Explain how to find the optimal trade-off between utility $U$ (which we want to maximize) and latency $L$ (which we want to minimize).

(d) Find $U^{\max}$, $L^{\min}$, and plot the optimal trade-off of utility versus latency for the network with data given in `net_util_data.m`, showing $L^{\min}$ and $U^{\max}$ on the same plot. Your plot should cover the range from $L = 1.1L^{\min}$ to $L = 11L^{\min}$. Plot $U$ vertically, on a linear scale, and $L$ horizontally, using a log scale.

*Note.* For parts (a), (b), and (c), your answer can involve solving one or more convex optimization problems. But if there is a simpler solution, you should say so.

**19.4** *Allocation of interdiction effort.* A smuggler moves along a directed acyclic graph with $m$ edges and $n$ nodes, from a source node (which we take as node 1) to a destination node (which we take as node $n$), along some (directed) path. Each edge $k$ has a detection failure probability $p_k$, which is the probability that the smuggler passes over that edge undetected. The detection events on the edges are independent, so the probability that the smuggler makes it to the destination node undetected is $\prod_{j \in \mathcal{P}} p_j$, where $\mathcal{P} \subset \{1, \ldots, m\}$ is (the set of edges on) the smuggler's path. We assume that the smuggler knows the detection failure probabilities and will take a path that maximizes the probability of making it to the destination node undetected. We let $P^{\max}$ denote this maximum probability (over paths). (Note that this is a function of the edge detection failure probabilities.)

The edge detection failure probability on an edge depends on how much interdiction resources are allocated to the edge. Here we will use a very simple model, with $x_j \in \mathbf{R}_+$ denoting the effort (say, yearly budget) allocated to edge $j$, with associated detection failure probability $p_j = e^{-a_j x_j}$, where $a_j \in \mathbf{R}_{++}$ are given. The constraints on $x$ are a maximum for each edge, $x \preceq x^{\max}$, and a total budget constraint, $\mathbf{1}^T x \leq B$.

(a) Explain how to solve the problem of choosing the interdiction effort vector $x \in \mathbf{R}^m$, subject to the constraints, so as to minimize $P^{\max}$. Partial credit will be given for a method that involves an enumeration over all possible paths (in the objective or constraints). *Hint.* For each node $i$, let $P_i$ denote the maximum of $\prod_{k \in \mathcal{P}} p_k$ over all paths $\mathcal{P}$ from the source node 1 to node $i$ (so $P^{\max} = P_n$).

(b) Carry out your method on the problem instance given in `interdict_alloc_data.m`. The data file contains the data $a$, $x^{\max}$, $B$, and the graph incidence matrix $A \in \mathbf{R}^{n \times m}$, where

$$A_{ij} = \begin{cases} -1 & \text{if edge } j \text{ leaves node } i \\ +1 & \text{if edge } j \text{ enters node } i \\ 0 & \text{otherwise.} \end{cases}$$

Give $P^{\mathrm{max}\star}$, the optimal value of $P^{\mathrm{max}}$, and compare it to the value of $P^{\mathrm{max}}$ obtained with uniform allocation of resources, *i.e.*, with $x = (B/m)\mathbf{1}$.

*Hint.* Given a vector $z \in \mathbf{R}^n$, $A^T z$ is the vector of edge differences: $(A^T z)_j = z_k - z_l$ if edge $j$ goes from node $l$ to node $k$.

The following figure shows the topology of the graph in question. (The data file contains $A$; this figure, which is not needed to solve the problem, is shown here so you can visualize the graph.)



**19.5** *Network sizing.* We consider a network with $n$ directed arcs. The flow through arc $k$ is denoted $x_k$ and can be positive, negative, or zero. The flow vector $x$ must satisfy the network constraint $Ax = b$ where $A$ is the node-arc incidence matrix and $b$ is the external flow supplied to the nodes.

Each arc has a positive capacity or width $y_k$. The quantity $|x_k|/y_k$ is the flow density in arc $k$. The cost of the flow in arc $k$ depends on the flow density and the width of the arc, and is given by $y_k \phi_k(|x_k|/y_k)$, where $\phi_k$ is convex and nondecreasing on $\mathbf{R}_+$.

(a) Define $f(y, b)$ as the optimal value of the network flow optimization problem

$$\begin{array}{ll} \text{minimize} & \sum_{k=1}^{n} y_k \, \phi_k(|x_k|/y_k) \\ \text{subject to} & Ax = b \end{array}$$

with variable $x$, for given values of the arc widths $y \succ 0$ and external flows $b$. Is $f$ a convex function (jointly in $y$, $b$)? Carefully explain your answer.

(b) Suppose $b$ is a discrete random vector with possible values $b^{(1)}, \ldots, b^{(m)}$. The probability that $b = b^{(j)}$ is $\pi_j$. Consider the problem of sizing the network (selecting the arc widths $y_k$) so that the expected cost is minimized:

$$\text{minimize} \quad g(y) + \mathbf{E}\, f(y, b). \tag{70}$$

The variable is $y$. Here $g$ is a convex function, representing the installation cost, and $\mathbf{E}\, f(y, b)$ is the expected optimal network flow cost

$$\mathbf{E}\, f(y, b) = \sum_{j=1}^{m} \pi_j f(y, b^{(j)}),$$

where $f$ is the function defined in part 1. Is (70) a convex optimization problem?

**19.6** *Maximizing algebraic connectivity of a graph.* Let $G = (V, E)$ be a weighted undirected graph with $n = |V|$ nodes, $m = |E|$ edges, and weights $w_1, \ldots, w_m \in \mathbf{R}_+$ on the edges. If edge $k$ connects nodes $i$ and $j$, then define $a_k \in \mathbf{R}^n$ as $(a_k)_i = 1$, $(a_k)_j = -1$, with other entries zero. The *weighted Laplacian* (matrix) of the graph is defined as

$$L = \sum_{k=1}^{m} w_k a_k a_k^T = A\,\mathbf{diag}(w)A^T,$$

where $A = [a_1 \cdots a_m] \in \mathbf{R}^{n \times m}$ is the *incidence matrix* of the graph. Nonnegativity of the weights implies $L \succeq 0$.

Denote the eigenvalues of the Laplacian $L$ as

$$\lambda_1 \le \lambda_2 \le \cdots \le \lambda_n,$$

which are functions of $w$. The minimum eigenvalue $\lambda_1$ is always zero, while the second smallest eigenvalue $\lambda_2$ is called the *algebraic connectivity* of $G$ and is a measure of the connectedness of a graph: The larger $\lambda_2$ is, the better connected the graph is. It is often used, for example, in analyzing the robustness of computer networks.

Though not relevant for the rest of the problem, we mention a few other examples of how the algebraic connectivity can be used. These results, which relate graph-theoretic properties of $G$ to properties of the spectrum of $L$, belong to a field called *spectral graph theory*. For example, $\lambda_2 > 0$ if and only if the graph is connected. The eigenvector $v_2$ associated with $\lambda_2$ is often called the *Fiedler vector* and is widely used in a graph partitioning technique called *spectral partitioning*, which assigns nodes to one of two groups based on the sign of the relevant component in $v_2$. Finally, $\lambda_2$ is also closely related to a quantity called the *isoperimetric number* or *Cheeger constant* of $G$, which measures the degree to which a graph has a bottleneck.

The problem is to choose the edge weights $w \in \mathbf{R}_+^m$, subject to some linear inequalities (and the nonnegativity constraint) so as to maximize the algebraic connectivity:

$$\begin{aligned}
\text{maximize} \quad & \lambda_2 \\
\text{subject to} \quad & w \succeq 0, \quad Fw \preceq g,
\end{aligned}$$

with variable $w \in \mathbf{R}^m$. The problem data are $A$ (which gives the graph topology), and $F$ and $g$ (which describe the constraints on the weights).

(a) Describe how to solve this problem using convex optimization.

(b) *Numerical example.* Solve the problem instance given in `max_alg_conn_data.m`, which uses $F = \mathbf{1}^T$ and $g = 1$ (so the problem is to allocate a total weight of 1 to the edges of the graph). Compare the algebraic connectivity for the graph obtained with the optimal weights $w^\star$ to the one obtained with $w^{\text{unif}} = (1/m)\mathbf{1}$ (*i.e.*, a uniform allocation of weight to the edges).

Use the function `plotgraph(A,xy,w)` to visualize the weighted graphs, with weight vectors $w^\star$ and $w^{\text{unif}}$. You will find that the optimal weight vector $v^\star$ has some zero entries (which due to the finite precision of the solver, will appear as small weight values); you may want to round small values (say, those under $10^{-4}$) of $w^\star$ to exactly zero. Use the `gplot` function to visualize the original (given) graph, and the subgraph associated with nonzero weights in $w^\star$.

*Briefly* comment on the following (incorrect) intuition: "The more edges a graph has, the more connected it is, so the optimal weight assignment should make use of all available edges."

**19.7** *Graph isomorphism via linear programming.* An (undirected) graph with $n$ vertices can be described by its adjacency matrix $A \in \mathbf{S}^n$, given by

$$A_{ij} = \begin{cases} 1 & \text{there is an edge between vertices } i \text{ and } j \\ 0 & \text{otherwise.} \end{cases}$$

Two (undirected) graphs are *isomorphic* if we can permute the vertices of one so it is the same as the other (*i.e.*, the same pairs of vertices are connected by edges). If we describe them by their adjacency matrices $A$ and $B$, isomorphism is equivalent to the existence of a permutation matrix $P \in \mathbf{R}^{n \times n}$ such that $PAP^T = B$. (Recall that a matrix $P$ is a permutation matrix if each row and column has exactly one entry 1, and all other entries 0.) Determining if two graphs are isomorphic, and if so, finding a suitable permutation matrix $P$, is called the *graph isomorphism problem.*

*Remarks (not needed to solve the problem).* It is not currently known if the graph isomorphism problem is NP-complete or solvable in polynomial time. The graph isomorphism problem comes up in several applications, such as determining if two descriptions of a molecule are the same, or whether the physical layout of an electronic circuit correctly reflects the given circuit schematic diagram.

(a) Find a set of linear equalities and inequalities on $P \in \mathbf{R}^{n \times n}$, that together with the Boolean constraint $P_{ij} \in \{0, 1\}$, are necessary and sufficient for $P$ to be a permutation matrix satisfying $PAP^T = B$. Thus, the graph isomorphism problem is equivalent to a Boolean feasibility LP.

(b) Consider the relaxed version of the Boolean feasibility LP found in part (a), *i.e.*, the LP that results when the constraints $P_{ij} \in \{0, 1\}$ are replaced with $P_{ij} \in [0, 1]$. When this LP is infeasible, we can be sure that the two graphs are not isomorphic. If a solution of the LP is found that satisfies $P_{ij} \in \{0, 1\}$, then the graphs are isomporphic and we have solved the graph isomorphism problem. This of course does not always happen, even if the graphs are isomorphic.

A standard trick to encourage the entries of $P$ to take on the values 0 and 1 is to add a random linear objective to the relaxed feasibility LP. (This doesn't change whether the problem is feasible or not.) In other words, we minimize $\sum_{i,j} W_{ij} P_{ij}$, where $W_{ij}$ are chosen randomly (say, from $\mathcal{N}(0,1)$). (This can be repeated with different choices of $W$.)

Carry out this scheme for the two isomorphic graphs with adjacency matrices $A$ and $B$ given in `graph_isomorphism_data.*` to find a permutation matrix $P$ that satisfies $PAP^T = B$. Report the permutation vector, given by the matrix-vector product $Pv$, where $v = (1, 2, \ldots, n)$. Verify that all the required conditions on $P$ hold. To check that the entries of the solution of the LP are (close to) $\{0, 1\}$, report $\max_{i,j} P_{ij}(1 - P_{ij})$. And yes, you might have to try more than one instance of the randomized method described above before you find a permutation that establishes isomorphism of the two graphs.

**19.8** *Flow optimization on a lossy network.* We consider a network represented as a directed graph with $n$ nodes and $m$ edges, with a single commodity flowing across the edges. With each edge we associate *two* nonnegative flows, the input flow $u_j$ and the output flow $v_j$. We have $v_j \leq u_j$, with $u_j - v_j$ interpreted as the *loss* (of the commodity) on edge $j$. The relation between the input and output flows is given by an increasing convex function $\phi_j : \mathbf{R}_+ \to \mathbf{R}_+ \cup \{\infty\}$, with $u_j = \phi_j(v_j)$. These functions satisfy $\phi_j(0) = 0$ and $\phi_j(v_j) \geq v_j$. We think of $u_j = \phi_j(v_j)$ as giving the amount of flow that must go into edge $i$ to achieve a given output flow $v_j$. We interpret $\phi_j(v_j) = \infty$ as meaning that there is no amount of input flow that can achieve an output flow $v_j$. We write this in compact vector form as $u = \phi(v)$, where $\phi : \mathbf{R}_+^m \to (\mathbf{R} \cup \{\infty\})^m$ is defined as $\phi(v) = (\phi_1(v_1), \ldots, \phi_m(v_m))$.

An alternative, equivalent characterization is $v_j = \psi_j(u_j)$, where $\psi_j = \phi_j^{-1}$ gives the amount of output flow we achieve for a given input flow. These functions are increasing and concave, and satisfy $\psi_j(0) = 0$ and $\psi_j(u_j) \leq u_j$. We express this in compact vector form as $v = \psi(u)$.

Lossy edges occur in many practical problems, for example power networks, when we model losses in transmission lines, or financial networks, where there are costs associated with moving money or some other good across an edge.

Each node has an external source, with flow $s_i$ into the node. Thus $s_i > 0$ means external flow into the node, and $s_i < 0$ means that there is a flow of value $-s_i$ out of the node.

We have flow conservation at each node in the network. Flow comes into each node from the external source, and also from the output flows of each edge that is incoming to the node. Flow comes out of a node from each edge that is outgoing from the node, with the amount equal to the input flow of that edge. The total incoming and total outgoing flows must match. Let $A \in \mathbf{R}^{n \times m}$ denote the incidence matrix of the network, *i.e.*, $A_{ij} = 1$ if edge $j$ is incoming to node $i$, $A_{ij} = -1$ if edge $j$ is outgoing from node $i$, and $A_{ij} = 0$ otherwise. Define the matrices $A^{\mathrm{in}} = \max\{A, 0\}$ (elementwise) and $A^{\mathrm{out}} = \max\{-A, 0\}$, so $A = A^{\mathrm{in}} - A^{\mathrm{out}}$. The flow balance equations are then $A^{\mathrm{in}}v + s = A^{\mathrm{out}}u$. (We know that the description above is a lot to parse and follow; you can just use this equation as the flow balance constraint.)

Each node has a cost function associated with its external flow, given by $f_i(s_i)$. We will assume that these are convex, and their extended valued extensions are nondecreasing. You can think of $f_i(s_i)$ as the cost of injecting flow into the network, when $s_i > 0$, and $-f_i(s_i)$ as the revenue or utility from extracting $-s_i$ from the network, when $s_i < 0$. The objective we wish to minimize is the total of these external flow costs, $f(s) = \sum_{i=1}^{n} f_i(s_i)$.

Explain how to pose the problem of minimizing $f(s)$ subject to the constraints described above, with variables $u \in \mathbf{R}_+^m$, $v \in \mathbf{R}_+^m$, and the external flows $s \in \mathbf{R}^n$, as a convex optimization problem. If you use any relaxation, introduce new variables, or use a change of variables, be sure to justify it.

**19.9** *Some functions of graph weights.* Consider a connected weighted graph $\mathcal{G} = (\mathcal{V}, \mathcal{E})$, with weights $w_e \in \mathbf{R}_+$ for $e \in \mathcal{E}$.

(a) *Distance between two sets of vertices.* Let $S \subset \mathcal{V}$, $T \subset \mathcal{V}$ be disjoint sets of vertices. The distance between $S$ and $T$, denoted $\mathbf{dist}(S, T)$, is defined as the minimum of the sum of edge weights over all paths that start in $S$ and end in $T$.

Considered as a function of edge weights $w \in \mathbf{R}_+^{|\mathcal{E}|}$, is $\mathbf{dist}(S, T)$ convex, concave, or neither of these?

(b) *Optimal value of traveling salesman problem.* A tour is a path that includes each vertex in the graph exactly once. The traveling salesman problem is to find a tour that minimizes total edge weight along the tour. Its optimal value, denoted $\mathcal{T}^\star$, is the minimum of the total edge weight among all tours.

Considered as a function of edge weights $w \in \mathbf{R}_+^{|\mathcal{E}|}$, is $\mathcal{T}^\star$ convex, concave, or neither of these?

Please justify your answers. As always, we want the attribute you choose to hold with no further assumptions.

# 20 Energy and power

**20.1** *Power flow optimization with 'N − 1' reliability constraint.* We model a network of power lines as a graph with $n$ nodes and $m$ edges. The power flow along line $j$ is denoted $p_j$, which can be positive, which means power flows along the line in the direction of the edge, or negative, which means power flows along the line in the direction opposite the edge. (In other words, edge orientation is only used to determine the direction in which power flow is considered positive.) Each edge can support power flow in either direction, up to a given maximum capacity $P_j^{\max}$, *i.e.*, we have $|p_j| \le P_j^{\max}$.

Generators are attached to the first $k$ nodes. Generator $i$ provides power $g_i$ to the network. These must satisfy $0 \le g_i \le G_i^{\max}$, where $G_i^{\max}$ is a given maximum power available from generator $i$. The power generation costs are $c_i > 0$, which are given; the total cost of power generation is $c^T g$.

Electrical loads are connected to the nodes $k + 1, \dots, n$. We let $d_i \ge 0$ denote the demand at node $k + i$, for $i = 1, \dots, n - k$. We will consider these loads as given. In this simple model we will neglect all power losses on lines or at nodes. Therefore, power must balance at each node: the total power flowing into the node must equal the sum of the power flowing out of the node. This power balance constraint can be expressed as

$$Ap = \begin{bmatrix} -g \\ d \end{bmatrix},$$

where $A \in \mathbf{R}^{n \times m}$ is the node-incidence matrix of the graph, defined by

$$A_{ij} = \begin{cases} +1 & \text{edge } j \text{ enters node } i, \\ -1 & \text{edge } j \text{ leaves node } i, \\ 0 & \text{otherwise.} \end{cases}$$

In the basic power flow optimization problem, we choose the generator powers $g$ and the line flow powers $p$ to minimize the total power generation cost, subject to the constraints listed above. The (given) problem data are the incidence matrix $A$, line capacities $P^{\max}$, demands $d$, maximum generator powers $G^{\max}$, and generator costs $c$.

In this problem we will add a basic (and widely used) reliability constraint, commonly called an 'N − 1 constraint'. ($N$ is not a parameter in the problem; 'N − 1' just means 'all-but-one'.) This states that the system can still operate even if any one power line goes out, by re-routing the line powers. The case when line $j$ goes out is called 'failure contingency $j$'; this corresponds to replacing $P_j^{\max}$ with 0. The requirement is that there must exist a contingency power flow vector $p^{(j)}$ that satisfies all the constraints above, with $p_j^{(j)} = 0$, using the same given generator powers. (This corresponds to the idea that power flows can be re-routed quickly, but generator power can only be changed more slowly.) The 'N − 1 reliability constraint' requires that for each line, there is a contingency power flow vector. The 'N − 1 reliability constraint' is (implicitly) a constraint on the generator powers.

The questions below concern the specific instance of this problem with data given in `rel_pwr_flow_data.*`. (Executing this file will also generate a figure showing the network you are optimizating.) Especially for part (b) below, you must explain exactly how you set up the problem as a convex optimization problem.

(a) *Nominal optimization.* Find the optimal generator and line power flows for this problem instance (without the $N-1$ reliability constraint). Report the optimal cost and generator powers. (You do not have to give the power line flows.)

(b) *Nominal optimization with $N-1$ reliability constraint.* Minimize the nominal cost, but you must choose generator powers that meet the $N-1$ reliability requirement as well. Report the optimal cost and generator powers. (You do not have to give the nominal power line flows, or any of the contingency flows.)

**20.2** *Optimal generator dispatch.* In the *generator dispatch problem*, we schedule the electrical output power of a set of generators over some time interval, to minimize the total cost of generation while exactly meeting the (assumed known) electrical demand. One challenge in this problem is that the generators have dynamic constraints, which couple their output powers over time. For example, every generator has a maximum rate at which its power can be increased or decreased.

We label the generators $i = 1, \ldots, n$, and the time periods $t = 1, \ldots, T$. We let $p_{i,t}$ denote the (nonnegative) power output of generator $i$ at time interval $t$. The (positive) electrical demand in period $t$ is $d_t$. The total generated power in each period must equal the demand:

$$\sum_{i=1}^{n} p_{i,t} = d_t, \quad t = 1, \ldots, T.$$

Each generator has a minimum and maximum allowed output power:

$$P_i^{\min} \le p_{i,t} \le P_i^{\max}, \quad i = 1, \ldots, n, \quad t = 1, \ldots, T.$$

The cost of operating generator $i$ at power output $u$ is $\phi_i(u)$, where $\phi_i$ is an increasing strictly convex function. (Assuming the cost is mostly fuel cost, convexity of $\phi_i$ says that the thermal efficiency of the generator decreases as its output power increases.) We will assume these cost functions are quadratic: $\phi_i(u) = \alpha_i u + \beta_i u^2$, with $\alpha_i$ and $\beta_i$ positive.

Each generator has a maximum ramp-rate, which limits the amount its power output can change over one time period:

$$|p_{i,t+1} - p_{i,t}| \le R_i, \quad i = 1, \ldots, n, \quad t = 1, \ldots, T-1.$$

In addition, changing the power output of generator $i$ from $u_t$ to $u_{t+1}$ incurs an additional cost $\psi_i(u_{t+1} - u_t)$, where $\psi_i$ is a convex function. (This cost can be a real one, due to increased fuel use during a change of power, or a fictitious one that accounts for the increased maintenance cost or decreased lifetime caused by frequent or large changes in power output.) We will use the power change cost functions $\psi_i(v) = \gamma_i |v|$, where $\gamma_i$ are positive.

Power plants with large capacity (*i.e.*, $P_i^{\max}$) are typically more efficient (*i.e.*, have smaller $\alpha_i$, $\beta_i$), but have smaller ramp-rate limits, and higher costs associated with changing power levels. Small gas-turbine plants ('peakers') are less efficient, have less capacity, but their power levels can be rapidly changed.

The total cost of operating the generators is

$$C = \sum_{i=1}^{n} \sum_{t=1}^{T} \phi_i(p_{i,t}) + \sum_{i=1}^{n} \sum_{t=1}^{T-1} \psi_i(p_{i,t+1} - p_{i,t}).$$

Choosing the generator output schedules to minimize $C$, while respecting the constraints described above, is a convex optimization problem. The problem data are $d_t$ (the demands), the generator power limits $P_i^{\min}$ and $P_i^{\max}$, the ramp-rate limits $R_i$, and the cost function parameters $\alpha_i$, $\beta_i$, and $\gamma_i$. We will assume that problem is feasible, and that $p_{i,t}^{\star}$ are the (unique) optimal output powers.

(a) *Price decomposition.* Show that there are power prices $Q_1, \ldots, Q_T$ for which the following holds: For each $i$, $p_{i,t}^{\star}$ solves the optimization problem

$$
\begin{array}{ll}
\text{minimize} & \sum_{t=1}^{T} \left( \phi_i(p_{i,t}) - Q_t p_{i,t} \right) + \sum_{t=1}^{T-1} \psi_i(p_{i,t+1} - p_{i,t}) \\
\text{subject to} & P_i^{\min} \leq p_{i,t} \leq P_i^{\max}, \quad t = 1, \ldots, T \\
& |p_{i,t+1} - p_{i,t}| \leq R_i, \quad t = 1, \ldots, T-1.
\end{array}
$$

The objective here is the portion of the objective for generator $i$, minus the revenue generated by the sale of power at the prices $Q_t$. Note that this problem involves *only* generator $i$; it can be solved independently of the other generators (once the prices are known). How would you find the prices $Q_t$?

You do not have to give a full formal proof; but you must explain your argument fully. You are welcome to use results from the text book.

(b) Solve the generator dispatch problem with the data given in `gen_dispatch_data.m`, which gives (fake, but not unreasonable) demand data for 2 days, at 15 minute intervals. This file includes code to plot the demand, optimal generator powers, and prices. (You must replace these variables with their correct values.) Comment on anything you see in your solution that might at first seem odd. Using the prices found, solve the problems in part (a) for the generators separately, to be sure they give the optimal powers (up to some small numerical errors).

*Remark.* While beyond the scope of this course, we mention that there are very simple price update mechanisms that adjust the prices in such a way that when the generators independently schedule themselves using the prices (as described above), we end up with the total power generated in each period matching the demand, *i.e.*, the optimal solution of the whole (coupled) problem. This gives a decentralized method for generator dispatch.

**20.3** *Optimizing a portfolio of energy sources.* We have $n$ different energy sources, such as coal-fired plants, several wind farms, and solar farms. Our job is to size each of these, *i.e.*, to choose its capacity. We will denote by $c_i$ the capacity of plant $i$; these must satisfy $c_i^{\min} \leq c_i \leq c_i^{\max}$, where $c_i^{\min}$ and $c_i^{\max}$ are given minimum and maximum values.

Each generation source has a cost to build and operate (including fuel, maintenance, government subsidies and taxes) over some time period. We lump these costs together, and assume that the cost is proportional to $c_i$, with (given) coefficient $b_i$. Thus, the total cost to build and operate the energy sources is $b^T c$ (in, say, \$/hour).

Each generation source is characterized by an availability $a_i$, which is a random variable with values in $[0, 1]$. If source $i$ has capacity $c_i$, then the power available from the plant is $c_i a_i$; the total power available from the portfolio of energy sources is $c^T a$, which is a random variable. A coal fired plant has $a_i = 1$ almost always, with $a_i < 1$ when one of its units is down for maintenance. A wind farm, in contrast, is characterized by strong fluctations in availability with $a_i = 1$ meaning a strong wind

is blowing, and $a_i = 0$ meaning no wind is blowing. A solar farm has $a_i = 1$ only during peak sun hours, with no cloud cover; at other times (such as night) we have $a_i = 0$.

Energy demand $d \in \mathbf{R}_+$ is also modeled as a random variable. The components of $a$ (the availabilities) and $d$ (the demand) are *not* independent. Whenever the total power available falls short of the demand, the additional needed power is generated by (expensive) peaking power plants at a fixed positive price $p$. The average cost of energy produced by the peakers is

$$\mathbf{E}\, p(d - c^T a)_+,$$

where $x_+ = \max\{0, x\}$. This average cost has the same units as the cost $b^T c$ to build and operate the plants.

The objective is to choose $c$ to minimize the overall cost

$$C = b^T c + \mathbf{E}\, p(d - c^T a)_+.$$

**Sample average approximation.** To solve this problem, we will minimize a cost function based on a sample average of peaker cost,

$$C^{\mathrm{sa}} = b^T c + \frac{1}{N} \sum_{j=1}^{N} p(d^{(j)} - c^T a^{(j)})_+$$

where $(a^{(j)}, d^{(j)})$, $j = 1, \ldots, N$, are (given) samples from the joint distribution of $a$ and $d$. (These might be obtained from historical data, weather and demand forecasting, and so on.)

**Validation.** After finding an optimal value of $c$, based on the set of samples, you should double check or validate your choice of $c$ by evaluating the overall cost on another set of (validation) samples, $(\tilde{a}^{(j)}, \tilde{d}^{(j)})$, $j = 1, \ldots, N^{\mathrm{val}}$,

$$C^{\mathrm{val}} = b^T c + \frac{1}{N^{\mathrm{val}}} \sum_{j=1}^{N^{\mathrm{val}}} p(\tilde{d}^{(j)} - c^T \tilde{a}^{(j)})_+.$$

(These could be another set of historical data, held back for validation purposes.) If $C^{\mathrm{sa}} \approx C^{\mathrm{val}}$, our confidence that each of them is approximately the optimal value of $C$ is increased.

Finally we get to the problem. Get the data in `energy_portfolio_data.m`, which includes the required problem data, and the samples, which are given as a $1 \times N$ row vector `d` for the scalars $d^{(j)}$, and an $n \times N$ matrix `A` for $a^{(j)}$. A second set of samples is given for validation, with the names `d_val` and `A_val`.

Carry out the optimization described above. Give the optimal cost obtained, $C^{\mathrm{sa}}$, and compare to the cost evaluated using the validation data set, $C^{\mathrm{val}}$.

Compare your solution with the following naive ('certainty-equivalent') approach: Replace $a$ and $d$ with their (sample) means, and then solve the resulting optimization problem. Give the optimal cost obtained, $C^{\mathrm{ce}}$ (using the average values of $a$ and $d$). Is this a lower bound on the optimal value of the original problem? Now evaluate the cost for these capacities on the validation set, $C^{\mathrm{ce,val}}$. Make a brief statement.

**20.4** *Optimizing processor speed.* A set of $n$ tasks is to be completed by $n$ processors. The variables to be chosen are the processor speeds $s_1, \ldots, s_n$, which must lie between a given minimum value $s_{\min}$ and a maximum value $s_{\max}$. The computational load of task $i$ is $\alpha_i$, so the time required to complete task $i$ is $\tau_i = \alpha_i / s_i$.

The power consumed by processor $i$ is given by $p_i = f(s_i)$, where $f : \mathbf{R} \to \mathbf{R}$ is positive, increasing, and convex. Therefore, the total energy consumed is

$$E = \sum_{i=1}^{n} \frac{\alpha_i}{s_i} f(s_i).$$

(Here we ignore the energy used to transfer data between processors, and assume the processors are powered down when they are not active.)

There is a set of *precedence constraints* for the tasks, which is a set of $m$ ordered pairs $\mathcal{P} \subseteq \{1, \ldots, n\} \times \{1, \ldots, n\}$. If $(i, j) \in \mathcal{P}$, then task $j$ cannot start until task $i$ finishes. (This would be the case, for example, if task $j$ requires data that is computed in task $i$.) When $(i, j) \in \mathcal{P}$, we refer to task $i$ as a *precedent* of task $j$, since it must precede task $j$. We assume that the precedence constraints define a directed acyclic graph (DAG), with an edge from $i$ to $j$ if $(i, j) \in \mathcal{P}$.

If a task has no precedents, then it starts at time $t = 0$. Otherwise, each task starts as soon as all of its precedents have finished. We let $T$ denote the time for all tasks to be completed.

To be sure the precedence constraints are clear, we consider the very small example shown below, with $n = 6$ tasks and $m = 6$ precedence constraints.

$$\mathcal{P} = \{(1, 4), \ (1, 3), \ (2, 3), \ (3, 6), \ (4, 6), \ (5, 6)\}.$$



In this example, tasks 1, 2, and 5 start at time $t = 0$ (since they have no precedents). Task 1 finishes at $t = \tau_1$, task 2 finishes at $t = \tau_2$, and task 5 finishes at $t = \tau_5$. Task 3 has tasks 1 and 2 as precedents, so it starts at time $t = \max\{\tau_1, \tau_2\}$, and ends $\tau_3$ seconds later, at $t = \max\{\tau_1, \tau_2\} + \tau_3$. Task 4 completes at time $t = \tau_1 + \tau_4$. Task 6 starts when tasks 3, 4, and 5 have finished, at time $t = \max\{\max\{\tau_1, \tau_2\} + \tau_3, \tau_1 + \tau_4, \tau_5\}$. It finishes $\tau_6$ seconds later. In this example, task 6 is the last task to be completed, so we have

$$T = \max\{\max\{\tau_1, \tau_2\} + \tau_3, \tau_1 + \tau_4, \tau_5\} + \tau_6.$$

(a) Formulate the problem of choosing processor speeds (between the given limits) to minimize completion time $T$, subject to an energy limit $E \leq E_{\max}$, as a convex optimization problem.

The data in this problem are $\mathcal{P}$, $s_{\min}$, $s_{\max}$, $\alpha_1, \ldots, \alpha_n$, $E_{\max}$, and the function $f$. The variables are $s_1, \ldots, s_n$.

Feel free to change variables or to introduce new variables. Be sure to explain clearly why your formulation of the problem is convex, and why it is equivalent to the problem statement above.

*Important:*

- Your formulation must be convex for any function $f$ that is positive, increasing, and convex. You cannot make any further assumptions about $f$.
- This problem refers to the general case, not the small example described above.

(b) Consider the specific instance with data given in `proc_speed_data.m`, and processor power

$$f(s) = 1 + s + s^2 + s^3.$$

The precedence constraints are given by an $m \times 2$ matrix `prec`, where $m$ is the number of precedence constraints, with each row giving one precedence constraint (the first column gives the precedents).

Plot the optimal trade-off curve of energy $E$ versus time $T$, over a range of $T$ that extends from its minimum to its maximum possible value. (These occur when all processors operate at $s_{\max}$ and $s_{\min}$, respectively, since $T$ is monotone nonincreasing in $s$.) On the same plot, show the energy-time trade-off obtained when all processors operate at the same speed $\bar{s}$, which is varied from $s_{\min}$ to $s_{\max}$.

*Note:* In this part of the problem there is no limit $E^{\max}$ on $E$ as in part (a); you are to find the optimal trade-off of $E$ versus $T$.

**20.5** *Minimum energy processor speed scheduling.* A single processor can adjust its speed in each of $T$ time periods, labeled $1, \ldots, T$. Its speed in period $t$ will be denoted $s_t$, $t = 1, \ldots, T$. The speeds must lie between given (positive) minimum and maximum values, $S^{\min}$ and $S^{\max}$, respectively, and must satisfy a slew-rate limit, $|s_{t+1} - s_t| \leq R$, $t = 1, \ldots, T-1$. (That is, $R$ is the maximum allowed period-to-period change in speed.) The energy consumed by the processor in period $t$ is given by $\phi(s_t)$, where $\phi : \mathbf{R} \to \mathbf{R}$ is increasing and convex. The total energy consumed over all the periods is $E = \sum_{t=1}^{T} \phi(s_t)$.

The processor must handle $n$ jobs, labeled $1, \ldots, n$. Each job has an availability time $A_i \in \{1, \ldots, T\}$, and a deadline $D_i \in \{1, \ldots, T\}$, with $D_i \geq A_i$. The processor cannot start work on job $i$ until period $t = A_i$, and must complete the job by the end of period $D_i$. Job $i$ involves a (nonnegative) total work $W_i$. You can assume that in each time period, there is at least one job available, *i.e.*, for each $t$, there is at least one $i$ with $A_i \leq t$ and $D_i \geq t$.

In period $t$, the processor allocates its effort across the $n$ jobs as $\theta_t$, where $\mathbf{1}^T \theta_t = 1$, $\theta_t \succeq 0$. Here $\theta_{ti}$ (the $i$th component of $\theta_t$) gives the fraction of the processor effort devoted to job $i$ in period $t$. Respecting the availability and deadline constraints requires that $\theta_{ti} = 0$ for $t < A_i$ or $t > D_i$. To complete the jobs we must have

$$\sum_{t=A_i}^{D_i} \theta_{ti} s_t \geq W_i, \quad i = 1, \ldots, n.$$

(a) Formulate the problem of choosing the speeds $s_1, \ldots, s_T$, and the allocations $\theta_1, \ldots, \theta_T$, in order to minimize the total energy $E$, as a convex optimization problem. The problem data are $S^{\min}$, $S^{\max}$, $R$, $\phi$, and the job data, $A_i$, $D_i$, $W_i$, $i = 1, \ldots, n$. Be sure to justify any change of variables, or introduction of new variables, that you use in your formulation.

(b) Carry out your method on the problem instance described in `proc_sched_data.m`, with quadratic energy function $\phi(s_t) = \alpha + \beta s_t + \gamma s_t^2$. (The parameters $\alpha$, $\beta$, and $\gamma$ are given in the data file.) Executing this file will also give a plot showing the availability times and deadlines for the jobs.

Give the energy obtained by your speed profile and allocations. Plot these using the command `bar((s*ones(1,n)).*theta,1,'stacked')`, where $s$ is the $T \times 1$ vector of speeds, and $\theta$ is the $T \times n$ matrix of allocations with components $\theta_{ti}$. This will show, at each time period, how much effective speed is allocated to each job. The top of the plot will show the speed $s_t$. (You don't need to turn in a color version of this plot; B&W is fine.)

**20.6** *AC power flow analysis via convex optimization.* This problem concerns an AC (alternating current) power system consisting of $m$ transmission lines that connect $n$ nodes. We describe the topology by the node-edge incidence matrix $A \in \mathbf{R}^{n \times m}$, where

$$
A_{ij} = \begin{cases} +1 & \text{line } j \text{ leaves node } i \\ -1 & \text{line } j \text{ enters node } i \\ 0 & \text{otherwise.} \end{cases}
$$

The power flow on line $j$ is $p_j$ (with positive meaning in the direction of the line as defined in $A$, negative meaning power flow in the opposite direction).

Node $i$ has voltage phase angle $\phi_i$, and external power input $s_i$. (If a generator is attached to node $i$ we have $s_i > 0$; if a load is attached we have $s_i < 0$; if the node has neither, $s_i = 0$.) Neglecting power losses in the lines, and assuming power is conserved at each node, we have $Ap = s$. (We must have $\mathbf{1}^T s = 0$, which means that the total power pumped into the network by generators balances the total power pulled out by the loads.)

The line power flows are a nonlinear function of the difference of the phase angles at the nodes they connect to:
$$
p_j = \kappa_j \sin(\phi_k - \phi_l),
$$
where line $j$ goes from node $k$ to node $l$. Here $\kappa_j$ is a known positive constant (related to the inductance of the line). We can write this in matrix form as $p = \mathbf{diag}(\kappa) \sin(A^T \phi)$, where sin is applied elementwise.

The *DC power flow equations* are

$$
Ap = s, \qquad p = \mathbf{diag}(\kappa) \sin(A^T \phi).
$$

In the power analysis problem, we are given $s$, and want to find $p$ and $\phi$ that satisfy these equations. We are interested in solutions with voltage phase angle differences that are smaller than $\pm 90°$. (Under normal conditions, real power lines are never operated with voltage phase angle differences more than $\pm 20°$ or so.)

You will show that the DC power flow equations can be solved by solving the convex optimization problem

$$\begin{array}{ll} \text{minimize} & \sum_{i=j}^{m} \psi_j(p_j) \\ \text{subject to} & Ap = s, \end{array}$$

with variable $p$, where

$$\psi_j(u) = \int_0^u \sin^{-1}(v/\kappa_j) \, dv = u \sin^{-1}(u/\kappa_j) + \kappa_j(\sqrt{1 - (u/\kappa_j)^2} - 1),$$

with domain $\mathbf{dom}\,\psi_j = (-\kappa_j, \kappa_j)$. (The second expression will be useless in this problem.)

(a) Show that the problem above is convex.

(b) Suppose the problem above has solution $p^\star$, with optimal dual variable $\nu^\star$ associated with the equality constraint $Ap = s$. Show that $p^\star$, $\phi = \nu^\star$ solves the DC power flow equation. *Hint.* Write out the optimality conditions for the problem above.

**20.7** *Power transmission with losses.* A power transmission grid is modeled as a set of $n$ nodes and $m$ directed edges (which represent transmission lines), with topology described by the node-edge incidence matrix $A \in \mathbf{R}^{n \times m}$, defined by

$$A_{ij} = \begin{cases} +1 & \text{edge } j \text{ enters node } i, \\ -1 & \text{edge } j \text{ leaves node } i, \\ 0 & \text{otherwise.} \end{cases}$$

We let $p_j^{\text{in}} \geq 0$ denote the power that flows into the tail of edge $j$, and $p_j^{\text{out}} \geq 0$ the power that emerges from the head of edge $j$, for $j = 1, \ldots, m$. Due to transmission losses, the power that flows into each edge is more than the power that emerges:

$$p_j^{\text{in}} = p_j^{\text{out}} + \alpha (L_j/R_j^2)(p_j^{\text{out}})^2, \quad j = 1, \ldots, m,$$

where $L_j > 0$ is the length of transmission line $j$, $R_j > 0$ is the radius of the conductors on line $j$, and $\alpha > 0$ is a constant. (The second term on the righthand side above is the transmission line power loss.) In addition, each edge has a maximum allowed input power, that also depends on the conductor radius: $p_j^{\text{in}} \leq \sigma R_j^2$, $j = 1, \ldots, m$, where $\sigma > 0$ is a constant.

Generators are attached to nodes $i = 1, \ldots, k$, and loads are attached to nodes $i = k+1, \ldots, n$. We let $g_i$ denote the (nonnegative) power injected into node $i$ by its generator, for $i = 1, \ldots, k$. We let $l_i$ denote the (nonnegative) power pulled from node $i$ by the load, for $i = k+1, \ldots, n$. These load powers are known and fixed.

We must have power balance at each node. For $i = 1, \ldots, k$, the sum of all power entering the node from incoming transmission lines, plus the power supplied by the generator, must equal the sum of all power leaving the node on outgoing transmission lines:

$$\sum_{j \in \mathcal{E}(i)} p_j^{\text{out}} + g_i = \sum_{j \in \mathcal{L}(i)} p_j^{\text{in}}, \quad i = 1, \ldots, k,$$

254

where $\mathcal{E}(i)$ ($\mathcal{L}(i)$) is the set of edge indices for edges entering (leaving) node $i$. For the load nodes $i = k+1, \ldots, n$ we have a similar power balance condition:

$$\sum_{j \in \mathcal{E}(i)} p_j^{\text{out}} = \sum_{j \in \mathcal{L}(i)} p_j^{\text{in}} + l_i, \quad i = k+1, \ldots, n.$$

Each generator can vary its power $g_i$ over a given range $[0, G_i^{\text{max}}]$, and has an associated cost of generation $\phi_i(g_i)$, where $\phi_i$ is convex and strictly increasing, for $i = 1, \ldots, k$.

(a) *Minimum total cost of generation.* Formulate the problem of choosing generator and edge input and output powers, so as to minimize the total cost of generation, as a convex optimization problem. (All other quantities described above are known.) Be sure to explain any additional variables or terms you introduce, and to justify any transformations you make.

*Hint*: You may find the matrices $A_+ = (A)_+$ and $A_- = (-A)_+$ helpful in expressing the power balance constraints.

(b) *Marginal cost of power at load nodes.* The (marginal) cost of power at node $i$, for $i = k+1, \ldots, n$, is the partial derivative of the minimum total power generation cost, with respect to varying the load power $l_i$. (We will simply assume these partial derivatives exist.) Explain how to find the marginal cost of power at node $i$, from your formulation in part (a).

(c) *Optimal sizing of lines.* Now suppose that you can optimize over generator powers, edge input and output powers (as above), *and* the power line radii $R_j$, $j = 1, \ldots, m$. These must lie between given limits, $R_j \in [R_j^{\text{min}}, R_j^{\text{max}}]$ ($R_j^{\text{min}} > 0$), and we must respect a total volume constraint on the lines,

$$\sum_{j=1}^{m} L_j R_j^2 \leq V^{\text{max}}.$$

Formulate the problem of choosing generator and edge input and output powers, as well as power line radii, so as to minimize the total cost of generation, as a convex optimization problem. (Again, explain anything that is not obvious.)

(d) *Numerical example.* Using the data given in `ptrans_loss_data.m`, find the minimum total generation cost and the marginal cost of power at nodes $k+1, \ldots, n$, for the case described in parts (a) and (b) (*i.e.*, using the fixed given radii $R_j$), and also for the case described in part (c), where you are allowed to change the transmission line radii, keeping the same total volume as the original lines. For the generator costs, use the quadratic functions

$$\phi_i(g_i) = a_i g_i + b_i g_i^2, \quad i = 1, \ldots, k,$$

where $a$, $b \in \mathbf{R}_+^k$. (These are given in the data file.)

*Remark*: In the m-file, we give you a load vector $l \in \mathbf{R}^{n-k}$. For consistency, the $i$th entry of this vector corresponds to the load at node $k+i$.

**20.8** *Utility/power trade-off in a wireless network.* In this problem we explore the trade-off between total utility and total power usage in a wireless network in which the link transmit powers can be adjusted. The network consists of a set of nodes and a set of links over which data can be transmitted. There are $n$ routes, each corresponding to a sequence of links from a source to a

destination node. Route $j$ has a data flow rate $f_j \in \mathbf{R}_+$ (in units of bits/sec, say). The total utility (which we want to maximize) is

$$U(f) = \sum_{j=1}^{n} U_j(f_j),$$

where $U_j : \mathbf{R} \to \mathbf{R}$ are concave increasing functions.

The network topology is specified by the routing matrix $R \in \mathbf{R}^{m \times n}$, defined as

$$R_{ij} = \begin{cases} 1 & \text{route } j \text{ passes over link } i \\ 0 & \text{otherwise.} \end{cases}$$

The total traffic on a link is the sum of the flows that pass over the link. The traffic (vector) is thus $t = Rf \in \mathbf{R}^m$. The traffic on each link cannot exceed the capacity of the link, i.e., $t \preceq c$, where $c \in \mathbf{R}_+^m$ is the vector of link capacities.

The link capacities, in turn, are functions of the link transmit powers, given by $p \in \mathbf{R}_+^m$, which cannot exceed given limits, i.e., $p \preceq p^{\max}$. These are related by

$$c_i = \alpha_i \log(1 + \beta_i p_i),$$

where $\alpha_i$ and $\beta_i$ are positive parameters that characterize link $i$. The second objective (which we want to minimize) is $P = \mathbf{1}^T p$, the total (transmit) power.

(a) Explain how to find the optimal trade-off curve of total utility and total power, using convex or quasiconvex optimization.

(b) Plot the optimal trade-off curve for the problem instance with $m = 20$, $n = 10$, $U_j(x) = \sqrt{x}$ for $j = 1, \ldots, n$, $p_i^{\max} = 10$, $\alpha_i = \beta_i = 1$ for $i = 1, \ldots, m$, and network topology generated using

```
rand('seed',3);
R = round(rand(m,n));
```

Your plot should have the total power on the horizontal axis.

**20.9** *Energy storage trade-offs.* We consider the use of a storage device (say, a battery) to reduce the total cost of electricity consumed over one day. We divide the day into $T$ time periods, and let $p_t$ denote the (positive, time-varying) electricity price, and $u_t$ denote the (nonnegative) usage or consumption, in period $t$, for $t = 1, \ldots, T$. Without the use of a battery, the total cost is $p^T u$.

Let $q_t$ denote the (nonnegative) energy stored in the battery in period $t$. For simplicity, we neglect energy loss (although this is easily handled as well), so we have $q_{t+1} = q_t + c_t$, $t = 1, \ldots, T-1$, where $c_t$ is the charging of the battery in period $t$; $c_t < 0$ means the battery is discharged. We will require that $q_1 = q_T + c_T$, i.e., we finish with the same battery charge that we start with. With the battery operating, the net consumption in period $t$ is $u_t + c_t$; we require this to be nonnegative (i.e., we do not pump power back into the grid). The total cost is then $p^T(u + c)$.

The battery is characterized by three parameters: The capacity $Q$, where $q_t \leq Q$; the maximum charge rate $C$, where $c_t \leq C$; and the maximum discharge rate $D$, where $c_t \geq -D$. (The parameters $Q$, $C$, and $D$ are nonnegative.)

(a) Explain how to find the charging profile $c \in \mathbf{R}^T$ (and associated stored energy profile $q \in \mathbf{R}^T$) that minimizes the total cost, subject to the constraints.

(b) Solve the problem instance with data $p$ and $u$ given in `storage_tradeoff_data.*`, $Q = 35$, and $C = D = 3$. Plot $u_t$, $p_t$, $c_t$, and $q_t$ versus $t$.

(c) *Storage trade-offs.* Plot the minimum total cost versus the storage capacity $Q$, using $p$ and $u$ from `storage_tradeoff_data.*`, and charge/discharge limits $C = D = 3$. Repeat for charge/discharge limits $C = D = 1$. (Put these two trade-off curves on the same plot.) Give an interpretation of the endpoints of the trade-off curves.

20.10 *Cost-comfort trade-off in air conditioning.* A heat pump (air conditioner) is used to cool a residence to temperature $T_t$ in hour $t$, on a day with outside temperature $T_t^{\mathrm{out}}$, for $t = 1, \ldots, 24$. These temperatures are given in Kelvin, and we will assume that $T_t^{\mathrm{out}} \geq T_t$.

A total amount of heat $Q_t = \alpha(T_t^{\mathrm{out}} - T_t)$ must be removed from the residence in hour $t$, where $\alpha$ is a positive constant (related to the quality of thermal insulation).

The electrical energy required to pump out this heat is given by $E_t = Q_t / \gamma_t$, where

$$\gamma_t = \eta \frac{T_t}{T_t^{\mathrm{out}} - T_t}$$

is the *coefficient of performance* of the heat pump and $\eta \in (0, 1]$ is the efficiency constant. The efficiency is typically around 0.6 for a modern unit; the theoretical limit is $\eta = 1$. (When $T_t = T_t^{\mathrm{out}}$, we take $\gamma_t = \infty$ and $E_t = 0$.)

Electrical energy prices vary with the hour, and are given by $P_t > 0$ for $t = 1, \ldots, 24$. The total energy cost is $C = \sum_t P_t E_t$. We will assume that the prices are known.

Discomfort is measured using a piecewise-linear function of temperature,

$$D_t = (T_t - T^{\mathrm{ideal}})_+,$$

where $T^{\mathrm{ideal}}$ is an ideal temperature, below which there is no discomfort. The total daily discomfort is $D = \sum_{t=1}^{24} D_t$. You can assume that $T^{\mathrm{ideal}} < T_t^{\mathrm{out}}$.

To get a point on the optimal cost-comfort trade-off curve, we will minimize $C + \lambda D$, where $\lambda > 0$. The variables to be chosen are $T_1, \ldots, T_{24}$; all other quantities described above are given.

Show that this problem has an analytical solution of the form $T_t = \psi(P_t, T_t^{\mathrm{out}})$, where $\psi : \mathbf{R}^2 \to \mathbf{R}$. The function $\psi$ can depend on the constants $\alpha$, $\eta$, $T^{\mathrm{ideal}}$, $\lambda$. Give $\psi$ explicitly. You are free (indeed, encouraged) to check your formula using CVX, with made up values for the constants.

*Disclaimer.* The focus of this course is *not* on deriving 19th century pencil and paper solutions to problems. But every now and then, a practical problem will actually have an analytical solution. This is one of them.

20.11 *Optimal electric motor drive currents.* In this problem you will design the drive current waveforms for an AC (alternating current) electric motor. The motor has a magnetic rotor which spins with constant angular velocity $\omega \geq 0$ inside the stationary stator. The stator contains three circuits (called *phase windings*) with (vector) current waveform $i : \mathbf{R} \to \mathbf{R}^3$ and (vector) voltage waveform

$v : \mathbf{R} \to \mathbf{R}^3$, which are $2\pi$-periodic functions of the angular position $\theta$ of the rotor. The circuit dynamics are

$$v(\theta) = Ri(\theta) + \omega L \frac{d}{d\theta} i(\theta) + \omega k(\theta),$$

where $R \in \mathbf{S}_{++}^3$ is the resistance matrix, $L \in \mathbf{S}_{++}^3$ is the inductance matrix, and $k : \mathbf{R} \to \mathbf{R}^3$, a $2\pi$-periodic function of $\theta$, is the back-EMF waveform (which encodes the electromagnetic coupling between the rotor permanent magnets and the phase windings). The angular velocity $\omega$, the matrices $R$ and $L$, and the back-EMF waveform $k$, are known.

We must have $|v_i(\theta)| \leq v^{\mathrm{supply}}$, $i = 1, 2, 3$, where $v^{\mathrm{supply}}$ is the (given) supply voltage. The output torque of the motor at rotor position $\theta$ is $\tau(\theta) = k(\theta)^T i(\theta)$. We will require the torque to have a given constant nonnegative value: $\tau(\theta) = \tau^{\mathrm{des}}$ for all $\theta$.

The average power loss in the motor is

$$P^{\mathrm{loss}} = \frac{1}{2\pi} \int_0^{2\pi} i(\theta)^T R i(\theta)\, d\theta.$$

The mechanical output power is $P^{\mathrm{out}} = \omega \tau^{\mathrm{des}}$, and the motor efficiency is

$$\eta = P^{\mathrm{out}} / (P^{\mathrm{out}} + P^{\mathrm{loss}}).$$

The objective is to choose the current and voltage waveforms to maximize $\eta$.

*Discretization.* To solve this problem we consider a discretized version in which $\theta$ takes on the $N$ values $\theta = h, 2h, \ldots, Nh$, where $h = 2\pi/N$. We impose the voltage and torque constraints for these values of $\theta$. We approximate the power loss as

$$P^{\mathrm{loss}} = (1/N)\sum_{j=1}^{N} i(jh)^T R i(jh).$$

The circuit dynamics are approximated as

$$v(jh) = Ri(jh) + \omega L \frac{i((j+1)h) - i(jh)}{h} + \omega k(jh), \quad j = 1, \ldots, N,$$

where here we take $i((N+1)h) = i(h)$ (by periodicity).

Find optimal (discretized) current and voltage waveforms for the problem instance with data given in `ac_motor_data.m`. The back-EMF waveform is given as a $3 \times N$ matrix K. Plot the three current waveform components on one plot, and the three voltage waveforms on another. Give the efficiency obtained.

**20.12** *Decomposing a PV array output time series.* We are given a time series $p \in \mathbf{R}_+^T$ that gives the output power of a photo-voltaic (PV) array in 5-minute intervals, over $T = 2016$ periods (one week), given in `pv_output_data.*`. In this problem you will use convex optimization to decompose the time series into three components:

- The *clear sky output* $c \in \mathbf{R}_+^T$, a smooth daily-periodic component, which gives what the PV output would have been without clouds. This signal is 24-hour-periodic, *i.e.*, $c_{t+288} = c_t$ for $t = 1, \ldots, T - 288$. (The clear sky output is zero at night, but we will not use this prior information in our decomposition method.)

- A *weather shading loss* component $s \in \mathbf{R}_+^T$, which gives the loss of power due to clouds. This component satisfies $0 \preceq s \preceq c$, can change rapidly, and is not periodic.

- A *residual* $r \in \mathbf{R}^T$, which accounts for measurement error, anomalies, and other errors.

These components satisfy $p = c - s + r$.

We will assume that the average absolute value of the residual is no more than 4 (which is less than 1% of the average of $p$).

Smoothness of $c$ is measured by its Laplacian,

$$\mathcal{L}(c) = (c_1 - c_2)^2 + \cdots + (c_{287} - c_{288})^2 + (c_{288} - c_1)^2.$$

(Note that the term involves $c_1$ and $c_{288}$.)

We will choose $c$, $s$, and $r$ by minimizing $\mathcal{L}(c) + \lambda \mathbf{1}^T s$ subject to the constraints described above, where $\lambda$ is a positive parameter, that we take to be one.

Solve this problem, and plot the resulting $c$, $s$, $r$, and $p$ (which is given), on separate plots. Give the average values of $c$, $s$, and $p$, and the average absolute value of $r$ (which should be 4).

**20.13** *Optimal operation of a microgrid.* We consider a small electrical microgrid that consists of a photo-voltaic (PV) array, a storage device (battery), a load, and a connection to an external grid. We will optimize the operation of the microgrid over one day, in 15 minute increments, so all powers, and the battery charge, are represented as vectors in $\mathbf{R}^{96}$. The load power is $p^{\mathrm{ld}}$, which is nonnegative and known. The power that we take from the external grid is $p^{\mathrm{grid}}$; $p_i^{\mathrm{grid}} \geq 0$ means we are consuming power from the grid, and $p_i^{\mathrm{grid}} < 0$ means we are sending power back into the grid, in time period $i$. The PV array output, which is nonnegative and known, is denoted as $p^{\mathrm{pv}}$. The battery power is $p^{\mathrm{batt}}$, with $p_i^{\mathrm{batt}} \geq 0$ meaning the battery is discharging, and $p_i^{\mathrm{batt}} < 0$ meaning the battery is charging. These powers must balance in all periods, *i.e.*, we have

$$p^{\mathrm{ld}} = p^{\mathrm{grid}} + p^{\mathrm{batt}} + p^{\mathrm{pv}}.$$

(This is called the power balance constraint. The lefthand side is the load power, and the righthand side is the sum of the power coming from the grid, the battery, and the PV array.) All powers are given in kW.

The battery state of charge is given by $q \in \mathbf{R}^{96}$. It must satisfy $0 \leq q_i \leq Q$ for all $i$, where $Q$ is the battery capacity (in kWh). The battery dynamics are

$$q_{i+1} = q_i - (1/4)p_i^{\mathrm{batt}}, \quad i = 1, \ldots, 95, \quad q_1 = q_{96} - (1/4)p_{96}^{\mathrm{batt}}.$$

(The last equation means that we seek a periodic operation of the microgrid.) The battery power must satisfy $-C \leq p_i^{\mathrm{batt}} \leq D$ for all $i$, where $C$ and $D$ are (positive) known maximum charge and maximum discharge rates.

When we buy power (*i.e.*, $p_i^{\mathrm{grid}} \geq 0$) we pay for it at the rate of $R_i^{\mathrm{buy}}$ (in \$/kWh). When we sell power to the grid (*i.e.*, $p_i^{\mathrm{grid}} < 0$) we are paid for it at the rate of $R_i^{\mathrm{sell}}$. These (positive) prices vary with time period, and are known. The total cost of the grid power (in \$) is

$$(1/4)\left(R^{\mathrm{buy}}\right)^T \left(p^{\mathrm{grid}}\right)_+ - (1/4)\left(R^{\mathrm{sell}}\right)^T \left(p^{\mathrm{grid}}\right)_-,$$

where $(p^{\text{grid}})_+ = \max\{p^{\text{grid}}, 0\}$ and $(p^{\text{grid}})_- = \max\{-p^{\text{grid}}, 0\}$ (elementwise). You can assume that $R_i^{\text{buy}} > R_i^{\text{sell}} > 0$, *i.e.*, in every period, you pay at a higher rate to consume power from the grid than you are paid when you send power back into the grid.

The data for the problem are

$$p^{\text{ld}}, \quad p^{\text{pv}}, \quad Q, \quad C, \quad D, \quad R^{\text{buy}}, \quad R^{\text{sell}}.$$

(a) Explain how to find the powers and battery state of charge that minimize the total cost of the grid power. Carry out your method using the data given in `microgrid_data.*`. Report the optimal cost of the grid power. Plot $p^{\text{grid}}$, $p^{\text{load}}$, $p^{\text{pv}}$, $p^{\text{batt}}$, and $q$ versus $i$. *Note.* For CVXPY, you might need to specify `solver=cvx.ECOS` when you call the `solve()` method.

(b) *Price and payments.* Let $\nu \in \mathbf{R}^{96}$ denote the optimal dual variable associated with the power balance constraint. The vector $4\nu$ can be interpreted as the (time-varying) price of electricity at the microgrid, and is called the *locational marginal price* (LMP). The LMP is in \$/kWh, and is generally positive; the factor 4 converts between 15 minute power intervals and per kWh prices. Find and plot the LMP, along with the grid buy and sell prices, versus $i$. Make a very brief comment comparing the LMP prices with the buy and sell grid prices. *Hint.* Depending on how you express the power balance constraint, your software might return $-\nu$ instead of $\nu$. Feel free to use $-4\nu$ instead of $\nu$, or to switch the left-hand and righ-hand sides of your power balance constraint.

(c) The LMPs can be used as a system for payments among the load, the PV array, the battery, and the grid. The load pays $\nu^T p^{\text{ld}}$; the PV array is paid $\nu^T p^{\text{pv}}$; the battery is paid $\nu^T p^{\text{batt}}$; and the grid is paid $\nu^T p^{\text{grid}}$. Note carefully the directions of these payments. Also note that the battery and grid, whose powers can have either sign, can be paid in some time intervals and pay in others.

Use this pricing scheme to calculate the LMP payments made by the load, and to the PV array, the battery, and the grid. If all goes well, these payments will balance, *i.e.*, the load will pay an amount equal to the sum of the others.

When you execute the script that contains the data, it will create plots showing the various powers and prices versus time. Your are welcome to use these as templates for plotting your results. You are very welcome to look inside the script to see how the data is generated.

*Remark.* (Not needed to solve the problem.) The given data is approximately consistent with a group of ten houses, a common or pooled PV array of around 100 panels, and two Tesla Powerwall batteries.

**20.14** *Electric vehicle charging.* A group of $N$ electric vehicles need to charge their batteries over the next $T$ time periods. The charging energy for vehicle $i$ in period $t$ is given by $c_{t,i} \geq 0$, for $t = 1, \ldots, T$ and $i = 1, \ldots, N$. In each time period, the total charging energy over all vehicles cannot exceed $C^{\max}$, *i.e.*, $\sum_{i=1}^{N} c_{t,i} \leq C^{\max}$ for $t = 1, \ldots, T$.

The state of charge for vehicle $i$ in period $t$ is denoted $q_{t,i} \geq 0$. The charging dynamics is

$$q_{t+1,i} = q_{t,i} + c_{t,i}, \quad t = 1, \ldots, T, \quad i = 1, \ldots, N.$$

Note that $q_{t,i}$ is defined for $t = T + 1$. The initial vehicle charges $q_{1,i}$ are given. The charging energy and state of charge are given in kWh (kilowatt-hours).

The vehicles have different preferences for how much charge they acquire over time. This is expressed by a target minimum charge level over time, given by $q_{t,i}^{\text{tar}} \in \mathbf{R}_+$, $t = 1, \ldots, T+1$. These are nondecreasing, *i.e.*, $q_{t+1,i}^{\text{tar}} \geq q_{t,i}^{\text{tar}}$ for $t = 1, \ldots, T$, $i = 1, \ldots, N$. The charging shortfall in period $t$ for vehicle $i$ is given by

$$s_{t,i} = (q_{t,i}^{\text{tar}} - q_{t,i})_+, \quad t = 1, \ldots, T+1, \quad i = 1, \ldots, N,$$

where $(a)_+ = \max\{a, 0\}$. Our objective is to minimize the mean square shortfall, given by

$$S = \frac{1}{(T+1)N} \sum_{t=1}^{T+1} \sum_{i=1}^{N} s_{t,i}^2.$$

This is the same as minimizing the root-mean-square (RMS) shortfall, given by $\sqrt{S}$ (which has units of kWh).

Explain how to solve the problem using convex optimization, and solve the following problem instance. We have $N = 4$ vehicles, $T = 90$ time periods, and $C^{\max} = 3$. The initial charges $q_{1,i}$ are 20, 0, 30, and 25, respectively. The target minimum charge profiles have the form

$$q_{t,i}^{\text{tar}} = \left(\frac{t}{T+1}\right)^{\gamma_i} q_i^{\text{des}}, \quad t = 1, \ldots, T+1, \quad i = 1, \ldots, N,$$

with $\gamma$ values $0.5, 0.3, 2.0, 0.6$ and $q_i^{\text{des}}$ values $60, 100, 75, 125$. Note that $q_i^{\text{des}}$ gives the final value of the target minimum charge level for vehicle $i$, and the parameter $\gamma_i$ sets the 'urgency' of charging, with smaller values indicating more urgency, *i.e.*, a target minimum charge value that rises more quickly.

(With the charges all given in kWh, and the time period 5 minutes, these values are all realistic. The total charging period is 7.5 hours, and the maximum charging of 3kWh/period corresponds to a real power of 36kW. And no, you do not need to know or understand this to solve the problem.)

Give the optimal RMS shortfall, *i.e.*, the squareroot of the optimal objective value. Plot the target minimum charge values and optimal state of charge for each vehicle, with dashed lines showing the target and solid lines showing the optimal charge. Plot the optimal charging energies $c_{t,i}$ over time in a stack plot.

*Constant charging.* Compare the optimal charging above to a very simple charging policy: Charge each vehicle at a constant energy per period, proportional to $q_i^{\text{des}} - q_{1,i}$, *i.e.*,

$$c_{t,i} = \theta_i C^{\max}, \quad i = 1, \ldots, N, \quad t = 1, \ldots, T,$$

with

$$\theta_i = \frac{q_i^{\text{des}} - q_{1,i}}{\sum_{j=1}^{N}(q_j^{\text{des}} - q_{1,j})}, \quad i = 1, \ldots, N.$$

Give the associated RMS shortfall, and the same plots as above.

*Plotting hints.* In Python, a basic stack plot is obtained with

```
import matplotlib.pyplot as plt
plt.stackplot(rr, y.T)
```

where `rr` is a range object (like `range(a, b)`) with `len(list(rr)) == n` and `y` is an $n \times N$ NumPy array.

In Julia, a basic stack plot is obtained with

```
using Plots
areaplot(rr, y)
```

where `rr` is a range object (like `a:b`) and `y` is an $n \times N$ Matrix{Float64} object, with $n = b - a + 1$.

For those using Julia, you'll be better off using the solver ECOS, and not SCS or OSQP.

# 21 Miscellaneous applications

**21.1** *Earth mover's distance.* In this exercise we explore a general method for constructing a distance between two probability distributions on a finite set, called the *earth mover's distance*, *Wasserstein metric*, *Dubroshkin metric*, or *optimal transport metric*. Let $x$ and $y$ be two probability distributions on $\{1, \ldots, n\}$, i.e., $\mathbf{1}^T x = \mathbf{1}^T y = 1$, $x \succeq 0$, $y \succeq 0$. We imagine that $x_i$ is the amount of earth stored at location $i$; our goal is to move the earth between locations to obtain the distribution given by $y$. Let $C_{ij}$ be the cost of moving one unit of earth from location $j$ to location $i$. We assume that $C_{ii} = 0$, and $C_{ij} = C_{ji} > 0$ for $i \neq j$. (We allow $C_{ij} = \infty$, which means that earth cannot be moved directly from node $j$ to node $i$.) Let $S_{ij} \geq 0$ denote the amount of earth moved from location $j$ to location $i$. The total cost is $\sum_{i,j=1}^n S_{ij} C_{ij} = \mathbf{tr}\, C^T S$. The shipment matrix $S$ must satisfy the balance equations,

$$\sum_{j=1}^n S_{ij} = y_i, \quad i = 1, \ldots, n, \qquad \sum_{i=1}^n S_{ij} = x_j, \quad j = 1, \ldots, n,$$

which we can write compactly as $S\mathbf{1} = y$, $S^T \mathbf{1} = x$. (The first equation states that the total amount shipped into location $i$ equals $y_i$; the second equation states that the total shipped out from location $j$ is $x_j$.) The earth mover's distance between $x$ and $y$, denoted $d(x, y)$, is given by the minimal cost of earth moving required to transform $x$ to $y$, *i.e.*, the optimal value of the problem

$$
\begin{array}{ll}
\text{minimize} & \mathbf{tr}\, C^T S \\
\text{subject to} & S_{ij} \geq 0, \quad i, j = 1, \ldots, n \\
& S\mathbf{1} = y, \quad S^T \mathbf{1} = x,
\end{array}
$$

with variables $S \in \mathbf{R}^{n \times n}$.

We can also give a probability interpretation of $d(x, y)$. Consider a random variable $Z$ on $\{1, \ldots, n\}^2$ with values $C_{ij}$. We seek the joint distribution $S$ that minimizes the expected value of the random variable $Z$, with given marginals $x$ and $y$.

The earth mover's distance is used to compare, for example, 2D images, with $C_{ij}$ equal to the distance between pixels $i$ and $j$. If $x$ and $y$ represent two photographs of the same scene, from slightly different viewpoints and with an offset in camera position (say), $d(x, y)$ will be small, but the distance between $x$ and $y$ measured by most common norms (*e.g.*, $\|x - y\|_1$) will be large.

(a) Show that $d$ satisfies the following.
- *Symmetry*: $d(x, y) = d(y, x)$.
- *Nonnegativity*: $d(x, y) \geq 0$.
- *Definiteness*: $d(x, x) = 0$, and $d(x, y) > 0$ for $x \neq y$.

(Without further assumptions on $C$, the triangle inequality need not hold.)

(b) Show that $d(x, y)$ is the optimal value of the problem

$$
\begin{array}{ll}
\text{maximize} & \nu^T x + \mu^T y \\
\text{subject to} & \nu_i + \mu_j \leq C_{ij}, \quad i, j = 1, \ldots, n,
\end{array}
$$

with variables $\nu$, $\mu \in \mathbf{R}^n$.

**21.2** *Radiation treatment planning.* In radiation treatment, radiation is delivered to a patient, with the goal of killing or damaging the cells in a tumor, while carrying out minimal damage to other tissue. The radiation is delivered in beams, each of which has a known pattern; the level of each beam can be adjusted. (In most cases multiple beams are delivered at the same time, in one 'shot', with the treatment organized as a sequence of 'shots'.) We let $b_j$ denote the level of beam $j$, for $j = 1, \ldots, n$. These must satisfy $0 \leq b_j \leq B^{\max}$, where $B^{\max}$ is the maximum possible beam level. The exposure area is divided into $m$ voxels, labeled $i = 1, \ldots, m$. The dose $d_i$ delivered to voxel $i$ is linear in the beam levels, *i.e.*, $d_i = \sum_{j=1}^{n} A_{ij} b_j$. Here $A \in \mathbf{R}_+^{m \times n}$ is a (known) matrix that characterizes the beam patterns. We now describe a simple radiation treatment planning problem.

A (known) subset of the voxels, $\mathcal{T} \subset \{1, \ldots, m\}$, corresponds to the tumor or target region. We require that a minimum radiation dose $D^{\text{target}}$ be administered to each tumor voxel, *i.e.*, $d_i \geq D^{\text{target}}$ for $i \in \mathcal{T}$. For all other voxels, we would like to have $d_i \leq D^{\text{other}}$, where $D^{\text{other}}$ is a desired maximum dose for non-target voxels. This is generally not feasible, so instead we settle for minimizing the penalty

$$E = \sum_{i \notin \mathcal{T}} ((d_i - D^{\text{other}})_+)^2,$$

where $(\cdot)_+$ denotes the nonnegative part. We can interpret $E$ as the sum of the squares of the nontarget excess doses.

(a) Show that the treatment planning problem is convex. The optimization variable is $b \in \mathbf{R}^n$; the problem data are $B^{\max}$, $A$, $\mathcal{T}$, $D^{\text{target}}$, and $D^{\text{other}}$.

(b) Solve the problem instance with data given in the file `treatment_planning_data.m`. Here we have split the matrix $A$ into `Atarget`, which contains the rows corresponding to the target voxels, and `Aother`, which contains the rows corresponding to other voxels. Give the optimal value. Plot the dose histogram for the target voxels, and also for the other voxels. Make a brief comment on what you see. *Remark.* The beam pattern matrix in this problem instance is randomly generated, but similar results would be obtained with realistic data.

**21.3** *Flux balance analysis in systems biology.* Flux balance analysis is based on a very simple model of the reactions going on in a cell, keeping track only of the gross rate of consumption and production of various chemical species within the cell. Based on the known stoichiometry of the reactions, and known upper bounds on some of the reaction rates, we can compute bounds on the other reaction rates, or cell growth, for example.

We focus on $m$ metabolites in a cell, labeled $M_1, \ldots, M_m$. There are $n$ reactions going on, labeled $R_1, \ldots, R_n$, with nonnegative reaction rates $v_1, \ldots, v_n$. Each reaction has a (known) stoichiometry, which tells us the rate of consumption and production of the metabolites per unit of reaction rate. The stoichiometry data is given by the *stoichiometry matrix* $S \in \mathbf{R}^{m \times n}$, defined as follows: $S_{ij}$ is the rate of production of $M_i$ due to unit reaction rate $v_j = 1$. Here we consider consumption of a metabolite as negative production; so $S_{ij} = -2$, for example, means that reaction $R_j$ causes metabolite $M_i$ to be consumed at a rate $2v_j$.

As an example, suppose reaction $R_1$ has the form $M_1 \rightarrow M_2 + 2M_3$. The consumption rate of $M_1$, due to this reaction, is $v_1$; the production rate of $M_2$ is $v_1$; and the production rate of $M_3$ is $2v_1$. (The reaction $R_1$ has no effect on metabolites $M_4, \ldots, M_m$.) This corresponds to a first column of $S$ of the form $(-1, 1, 2, 0, \ldots, 0)$.

Reactions are also used to model flow of metabolites into and out of the cell. For example, suppose that reaction $R_2$ corresponds to the flow of metabolite $M_1$ into the cell, with $v_2$ giving the flow rate. This corresponds to a second column of $S$ of the form $(1, 0, \ldots, 0)$.

The last reaction, $R_n$, corresponds to biomass creation, or cell growth, so the reaction rate $v_n$ is the cell growth rate. The last column of $S$ gives the amounts of metabolites used or created per unit of cell growth rate.

Since our reactions include metabolites entering or leaving the cell, as well as those converted to biomass within the cell, we have conservation of the metabolites, which can be expressed as $Sv = 0$. In addition, we are given upper limits on *some* of the reaction rates, which we express as $v \preceq v^{\max}$, where we set $v_j^{\max} = \infty$ if no upper limit on reaction rate $j$ is known. The goal is to find the maximum possible cell growth rate (*i.e.*, largest possible value of $v_n$) consistent with the constraints

$$Sv = 0, \qquad v \succeq 0, \qquad v \preceq v^{\max}.$$

The questions below pertain to the data found in `fba_data.m`.

(a) Find the maximum possible cell growth rate $G^\star$, as well as optimal Lagrange multipliers for the reaction rate limits. How sensitive is the maximum growth rate to the various reaction rate limits?

(b) *Essential genes and synthetic lethals.* For simplicity, we'll assume that each reaction is controlled by an associated gene, *i.e.*, gene $G_i$ controls reaction $R_i$. Knocking out a set of genes associated with some reactions has the effect of setting the reaction rates (or equivalently, the associated $v^{\max}$ entries) to zero, which of course reduces the maximum possible growth rate. If the maximum growth rate becomes small enough or zero, it is reasonable to guess that knocking out the set of genes will kill the cell. An *essential gene* is one that when knocked out reduces the maximum growth rate below a given threshold $G^{\min}$. (Note that $G_n$ is always an essential gene.) A *synthetic lethal* is a pair of non-essential genes that when knocked out reduces the maximum growth rate below the threshold. Find all essential genes and synthetic lethals for the given problem instance, using the threshold $G^{\min} = 0.2 G^\star$.

**21.4** *Online advertising displays.* When a user goes to a website, one of a set of $n$ ads, labeled $1, \ldots, n$, is displayed. This is called an *impression*. We divide some time interval (say, one day) into $T$ periods, labeled $t = 1, \ldots, T$. Let $N_{it} \geq 0$ denote the number of impressions in period $t$ for which we display ad $i$. In period $t$ there will be a total of $I_t > 0$ impressions, so we must have $\sum_{i=1}^{n} N_{it} = I_t$, for $t = 1, \ldots, T$. (The numbers $I_t$ might be known from past history.) You can treat all these numbers as real. (This is justified since they are typically very large.)

The revenue for displaying ad $i$ in period $t$ is $R_{it} \geq 0$ per impression. (This might come from click-through payments, for example.) The total revenue is $\sum_{t=1}^{T} \sum_{i=1}^{n} R_{it} N_{it}$. To maximize revenue, we would simply display the ad with the highest revenue per impression, and no other, in each display period.

We also have in place a set of $m$ contracts that require us to display certain numbers of ads, or mixes of ads (say, associated with the products of one company), over certain periods, with a penalty for any shortfalls. Contract $j$ is characterized by a set of ads $\mathcal{A}_j \subseteq \{1, \ldots, n\}$ (while it does not affect the math, these are often disjoint), a set of periods $\mathcal{T}_j \subseteq \{1, \ldots, T\}$, a target number of impressions

$q_j \geq 0$, and a shortfall penalty rate $p_j > 0$. The *shortfall* $s_j$ for contract $j$ is

$$s_j = \left( q_j - \sum_{t \in \mathcal{T}_j} \sum_{i \in \mathcal{A}_j} N_{it} \right)_+ ,$$

where $(u)_+$ means $\max\{u, 0\}$. (This is the number of impressions by which we fall short of the target value $q_j$.) Our contracts require a total penalty payment equal to $\sum_{j=1}^m p_j s_j$. Our net profit is the total revenue minus the total penalty payment.

(a) Explain how to find the display numbers $N_{it}$ that maximize net profit. The data in this problem are $R \in \mathbf{R}^{n \times T}$, $I \in \mathbf{R}^T$ (here $I$ is the vector of impressions, not the identity matrix), and the contract data $\mathcal{A}_j$, $\mathcal{T}_j$, $q_j$, and $p_j$, $j = 1, \ldots, m$.

(b) Carry out your method on the problem with data given in `ad_disp_data.m`. `ad_disp_data.py`. The data $\mathcal{A}_j$ and $\mathcal{T}_j$, for $j = 1, \ldots, m$ are given by matrices $A^{\mathrm{contr}} \in \mathbf{R}^{n \times m}$ and $T^{\mathrm{contr}} \in \mathbf{R}^{T \times m}$, with

$$A_{ij}^{\mathrm{contr}} = \begin{cases} 1 & i \in \mathcal{A}_j \\ 0 & \text{otherwise,} \end{cases} \qquad T_{tj}^{\mathrm{contr}} = \begin{cases} 1 & t \in \mathcal{T}_j \\ 0 & \text{otherwise.} \end{cases}$$

Report the optimal net profit, and the associated revenue and total penalty payment. Give the same three numbers for the strategy of simply displaying in each period only the ad with the largest revenue per impression.

**21.5** *Ranking by aggregating preferences.* We have $n$ objects, labeled $1, \ldots, n$. Our goal is to assign a real valued rank $r_i$ to the objects. A *preference* is an ordered pair $(i, j)$, meaning that object $i$ is preferred over object $j$. The ranking $r \in \mathbf{R}^n$ and preference $(i, j)$ are *consistent* if $r_i \geq r_j + 1$. (This sets the scale of the ranking: a gap of one in ranking is the threshold for preferring one item over another.) We define the *preference violation* of preference $(i, j)$ with ranking $r \in \mathbf{R}^n$ as

$$v = (r_j + 1 - r_i)_+ = \max\{r_j + 1 - r_i, 0\}.$$

We have a set of $m$ preferences among the objects, $(i^{(1)}, j^{(1)}), \ldots, (i^{(m)}, j^{(m)})$. (These may come from several different evaluators of the objects, but this won't matter here.)

We will select our ranking $r$ as a minimizer of the total preference violation penalty, defined as

$$J = \sum_{k=1}^m \phi(v^{(k)}),$$

where $v^{(k)}$ is the preference violation of $(i^{(k)}, j^{(k)})$ with $r$, and $\phi$ is a nondecreasing convex penalty function that satisfies $\phi(u) = 0$ for $u \leq 0$.

(a) Make a (simple, please) suggestion for $\phi$ for each of the following two situations:

(i) We don't mind some small violations, but we really want to avoid large violations.

(ii) We want as many preferences as possible to be consistent with the ranking, but will accept some (hopefully, few) larger preference violations.

(b) Find the rankings obtained using the penalty functions proposed in part (a), on the data set found in `rank_aggr_data.m`. Plot a histogram of preference violations for each case and *briefly* comment on the differences between them. Give the number of positive preference violations for each case. (Use `sum(v>0.001)` to determine this number.)

*Remark.* The objects could be candidates for a position, papers at a conference, movies, websites, courses at a university, and so on. The preferences could arise in several ways. Each of a set of evaluators provides some preferences, for example by rank ordering a subset of the objects. The problem can be thought of as aggregating the preferences given by the evaluators, to come up with a composite ranking.

**21.6** *Time release formulation.* A patient is treated with a drug (say, in pill form) at different times. Each treatment (or pill) contains (possibly) different amounts of various formulations of the drug. Each of the formulations, in turn, has a characteristic pattern as to how quickly it releases the drug into the bloodstream. The goal is to optimize the blend of formulations that go into each treatment, in order to achieve a desired drug concentration in the bloodstream over time.

We will use discrete time, $t = 1, 2, \ldots, T$, representing hours (say). There will be $K$ treatments, administered at known times $1 = \tau_1 < \tau_2 < \cdots < \tau_K < T$. We have $m$ drug formulations; each treatment consists of a mixture of these $m$ formulations. We let $a^{(k)} \in \mathbf{R}_+^m$ denote the amounts of the $m$ formulations in treatment $k$, for $k = 1, \ldots, K$.

Each formulation $i$ has a time profile $p_i(t) \in \mathbf{R}_+$, for $t = 1, 2, \ldots$. If an amount $a_i^{(k)}$ of formulation $i$ from treatment $k$ is administered at time $t_0$, the drug concentration in the bloodstream (due to this formulation) is given by $a_i^{(k)} p_i(t - t_0)$ for $t > t_0$, and 0 for $t \leq t_0$. To simplify notation, we will define $p_i(t)$ to be zero for $t = 0, -1, -2, \ldots$. We assume the effects of the different formulations and different treatments are additive, so the total bloodstream drug concentration is given by

$$c(t) = \sum_{k=1}^{K} \sum_{i=1}^{m} p_i(t - \tau_k) a_i^{(k)}, \quad t = 1, \ldots, T.$$

(This is just a vector convolution.) Recall that $p_i(t - \tau_k) = 0$ for $t \leq \tau_k$, which means that the effect of treatment $k$ does not show up until time $\tau_k + 1$.

We require that $c(t) \leq c^{\max}$ for $t = 1, \ldots, T$, where $c^{\max}$ is a given maximum permissible concentration. We define the therapeutic time $T^{\mathrm{ther}}$ as

$$T^{\mathrm{ther}} = \min\{t \mid c(\tau) \geq c^{\min} \text{ for } \tau = t, \ldots, T\},$$

with $T^{\mathrm{ther}} = \infty$ if $c(t) < c^{\min}$ for $t = 1, \ldots, T$. Here, $c^{\min}$ is the minimum concentration for the drug to have therapeutic value. Thus, $T^{\mathrm{ther}}$ is the first time at which the drug concentration reaches, and stays above, the minimum therapeutic level.

Finally, we get to the problem. The optimization variables are the treatment formulation vectors $a^{(1)}, \ldots, a^{(K)}$. There are two objectives: $T^{\mathrm{ther}}$ (which we want to be small), and

$$J^{\mathrm{ch}} = \sum_{k=1}^{K-1} \|a^{(k+1)} - a^{(k)}\|_\infty$$

(which we also want to be small). This second objective is a penalty for changing the formulation amounts in the treatments.

The rest of the problem concerns the specific instance with data given in the file `time_release_form_data.m`. This gives data for $T = 168$ (one week, starting from 8AM Monday morning), with treatments occuring 3 times each day, at 8AM, 2PM, and 11PM, so we have a total of $K = 21$ treatments. We have $m = 6$ formulations, with profiles with length 96 (*i.e.*, $p_i(t) = 0$ for $t > 96$).

- Explain how to find the optimal trade-off curve of $T^{\text{ther}}$ versus $J^{\text{ch}}$. Your method may involve solving several convex optimization problems.

- Plot the trade-off curve over a reasonable range, and be sure to explain or at least comment on the endpoints of the trade-off curve.

- Plot the treatment formulation amounts versus $k$, and the bloodstream concentration versus $t$, for the two trade-off curve endpoints, and one corresponding to $T^{\text{ther}} = 8$.

*Warning.* We've found that CVX can experience numerical problems when solving this problem (depending on how it is formulated). In one case, `cvx_status` is "Solved/Inaccurate" when in fact the problem has been solved (just not to the tolerances SeDuMi likes to see). You can ignore this status, taking it to mean Optimal. You can also try switching to the SDPT3 solver. In any case, please do not spend much time worrying about, or dealing with, these numerical problems.

**21.7** *Sizing a gravity feed water supply network.* A water supply network connects water supplies (such as reservoirs) to consumers via a network of pipes. Water flow in the network is due to gravity (as opposed to pumps, which could also be added to the formulation). The network is composed of a set of $n$ nodes and $m$ directed edges between pairs of nodes. The first $k$ nodes are supply or reservoir nodes, and the remaining $n - k$ are consumer nodes. The edges correspond to the pipes in the water supply network.

We let $f_j \geq 0$ denote the water flow in pipe (edge) $j$, and $h_i$ denote the (known) altitude or height of node $i$ (say, above sea level). At nodes $i = 1, \ldots, k$, we let $s_i \geq 0$ denote the flow into the network from the supply. For $i = 1, \ldots, n - k$, we let $c_i \geq 0$ denote the water flow taken out of the network (by consumers) at node $k + i$. Conservation of flow can be expressed as

$$Af = \begin{bmatrix} -s \\ c \end{bmatrix},$$

where $A \in \mathbf{R}^{n \times m}$ is the incidence matrix for the supply network, given by

$$A_{ij} = \begin{cases} -1 & \text{if edge } j \text{ leaves node } i \\ +1 & \text{if edge } j \text{ enters node } i \\ 0 & \text{otherwise.} \end{cases}$$

We assume that each edge is oriented from a node of higher altitude to a node of lower altitude; if edge $j$ goes from node $i$ to node $l$, we have $h_i > h_l$. The pipe flows are determined by

$$f_j = \frac{\alpha \theta_j R_j^2 (h_i - h_l)}{L_j},$$

where edge $j$ goes from node $i$ to node $l$, $\alpha > 0$ is a known constant, $L_j > 0$ is the (known) length of pipe $j$, $R_j > 0$ is the radius of pipe $j$, and $\theta_j \in [0, 1]$ corresponds to the valve opening in pipe $j$.

Finally, we have a few more constraints. The supply feed rates are limited: we have $s_i \leq S_i^{\max}$. The pipe radii are limited: we have $R_j^{\min} \leq R_j \leq R_j^{\max}$. (These limits are all known.)

(a) *Supportable consumption vectors.* Suppose that the pipe radii are fixed and known. We say that $c \in \mathbf{R}_+^{n-k}$ is supportable if there is a choice of $f$, $s$, and $\theta$ for which all constraints and conditions above are satisfied. Show that the set of supportable consumption vectors is a polyhedron, and explain how to determine whether or not a given consumption vector is supportable.

(b) *Optimal pipe sizing.* You must select the pipe radii $R_j$ to minimize the cost, which we take to be (proportional to) the total volume of the pipes, $L_1 R_1^2 + \cdots + L_m R_m^2$, subject to being able to support a set of consumption vectors, denoted $c^{(1)}, \ldots, c^{(N)}$, which we refer to as consumption scenarios. (This means that any consumption vector in the convex hull of $\{c^{(1)}, \ldots, c^{(N)}\}$ will be supportable.) Show how to formulate this as a convex optimization problem. *Note.* You are asked to choose *one* set of pipe radii, and $N$ sets of valve parameters, flow vectors, and source vectors; one for each consumption scenario.

(c) Solve the instance of the optimal pipe sizing problem with data defined in the file `grav_feed_network_data.m`, and report the optimal value and the optimal pipe radii. The columns of the matrix $C$ in the data file are the consumption vectors $c^{(1)}, \ldots, c^{(N)}$.

*Hint.* $-A^T h$ gives a vector containing the height differences across the edges.

**21.8** *Optimal political positioning.* A political constituency is a group of voters with similar views on a set of political issues. The electorate (*i.e.*, the set of voters in some election) is partitioned (by a political analyst) into $K$ constituencies, with (nonnegative) populations $P_1, \ldots, P_K$. A candidate in the election has an initial or prior position on each of $n$ issues, but is willing to consider (presumably small) deviations from her prior positions in order to maximize the total number of votes she will receive. We let $x_i \in \mathbf{R}$ denote the change in her position on issue $i$, measured on some appropriate scale. (You can think of $x_i < 0$ as a move to the 'left' and $x_i > 0$ as a move to the 'right' on the issue, if you like.) The vector $x \in \mathbf{R}^n$ characterizes the changes in her position on all issues; $x = 0$ represents the prior positions. On each issue she has a limit on how far in each direction she is willing to move, which we express as $l \preceq x \preceq u$, where $l \prec 0$ and $u \succ 0$ are given.

The candidate's position change $x$ affects the fraction of voters in each constituency that will vote for her. This fraction is modeled as a logistic function,

$$f_k = g(w_k^T x + v_k), \quad k = 1, \ldots, K.$$

Here $g(z) = 1/(1 + \exp(-z))$ is the standard logistic function, and $w_k \in \mathbf{R}^n$ and $v_k \in \mathbf{R}$ are given data that characterize the views of constituency $k$ on the issues. Thus the total number of votes the candidate will receive is

$$V = P_1 f_1 + \cdots + P_K f_K.$$

The problem is to choose $x$ (subject to the given limits) so as to maximize $V$. The problem data are $l$, $u$, and $P_k$, $w_k$, and $v_k$ for $k = 1, \ldots, K$.

(a) *The general political positioning problem.* Show that the objective function $V$ need not be quasiconcave. (This means that the general optimal political positioning problem is not a quasiconvex problem, and therefore also not a convex problem.) In other words, choose problem data for which $V$ is not a quasiconcave function of $x$.

(b) *The partisan political positioning problem.* Now suppose the candidate focuses only on her core constituencies, *i.e.*, those for which a significant fraction will vote for her. In this case we interpret the $K$ constituencies as her core constituencies; we assume that $v_k \geq 0$, which means that with her prior position $x = 0$, at least half of each of her core constituencies will vote for her. We add the constraint that $w_k^T x + v_k \geq 0$ for each $k$, which means that she will not take positions that alienate a majority of voters from any of her core constituencies.

Show that the partisan political positioning problem (*i.e.*, maximizing $V$ with the additional assumptions and constraints) is convex.

(c) *Numerical example.* Find the optimal positions for the partisan political positioning problem with data given in `opt_pol_pos_data.m`. Report the number of votes from each constituency under the politician's prior positions ($x = 0$) and optimal positions, as well as the total number of votes $V$ in each case.

You may use the function

$$g_{\text{approx}}(z) = \min\{1, \ g(i) + g'(i)(z - i) \text{ for } i = 0, 1, 2, 3, 4\}$$

as an approximation of $g$ for $z \geq 0$. (The function $g_{\text{approx}}$ is also an upper bound on $g$ for $z \geq 0$.) For your convenience, we have included function definitions for $g$ and $g_{\text{approx}}$ (`g` and `gapx`, respectively) in the data file. You should report the results (votes from each constituency and total) using $g$, but be sure to check that these numbers are close to the results using $g_{\text{approx}}$ (say, within one percent or so).

**21.9** *Resource allocation in stream processing.* A large data center is used to handle a stream of $J$ types of jobs. The traffic (number of instances per second) of each job type is denoted $t \in \mathbf{R}_+^J$. Each instance of each job type (serially) invokes or calls a set of processes. There are $P$ types of processes, and we describe the job-process relation by the $P \times J$ matrix

$$R_{pj} = \begin{cases} 1 & \text{job } j \text{ invokes process } p \\ 0 & \text{otherwise.} \end{cases}$$

The process loads (number of instances per second) are given by $\lambda = Rt \in \mathbf{R}^P$, *i.e.*, $\lambda_p$ is the sum of the traffic from the jobs that invoke process $p$.

The latency of a process or job type is the average time that it takes one instance to complete. These are denoted $l^{\text{proc}} \in \mathbf{R}^P$ and $l^{\text{job}} \in \mathbf{R}^J$, respectively, and are related by $l^{\text{job}} = R^T l^{\text{proc}}$, *i.e.*, $l_j^{\text{job}}$ is the sum of the latencies of the processes called by $j$. Job latency is important to users, since $l_j^{\text{job}}$ is the average time the data center takes to handle an instance of job type $j$. We are given a maximum allowed job latency: $l^{\text{job}} \preceq l^{\max}$.

The process latencies depend on the process load and also how much of $n$ different resources are made available to them. These resources might include, for example, number of cores, disk storage, and network bandwidth. Here, we represent amounts of these resources as (nonnegative) real numbers, so $x_p \in \mathbf{R}_+^n$ represents the resources allocated to process $p$. The process latencies are given by

$$l_p^{\text{proc}} = \psi_p(x_p, \lambda_p), \quad p = 1, \dots, P,$$

where $\psi_p : \mathbf{R}^n \times \mathbf{R} \to \mathbf{R} \cup \{\infty\}$ is a known (extended-valued) convex function. These functions are nonincreasing in their first (vector) arguments, and nondecreasing in their second arguments (*i.e.*,

more resources or less load cannot increase latency). We interpret $\psi_p(x_p, \lambda_p) = \infty$ to mean that the resources given by $x_p$ are not sufficient to handle the load $\lambda_p$.

We wish to allocate a total resource amount $x^{\text{tot}} \in \mathbf{R}_{++}^n$ among the $P$ processes, so we have $\sum_{p=1}^{P} x_p \preceq x^{\text{tot}}$. The goal is to minimize the objective function

$$\sum_{j=1}^{J} w_j (t_j^{\text{tar}} - t_j)_+,$$

where $t_j^{\text{tar}}$ is the target traffic level for job type $j$, $w_j > 0$ give the priorities, and $(u)_+$ is the nonnegative part of a vector, *i.e.*, $u_i = \max\{u_i, 0\}$. (Thus the objective is a weighted penalty for missing the target job traffic.) The variables are $t \in \mathbf{R}_+^J$ and $x_p \in \mathbf{R}_+^n$, $p = 1, \ldots, P$. The problem data are the matrix $R$, the vectors $l^{\max}$, $x^{\text{tot}}$, $t^{\text{tar}}$, and $w$, and the functions $\psi_p$, $p = 1, \ldots, P$.

(a) Explain why this is a convex optimization problem.

(b) Solve the problem instance with data given in `res_alloc_stream_data.m`, with latency functions

$$\psi_p(x_p, \lambda_p) = \begin{cases} 1/(a_p^T x_p - \lambda_p) & a_p^T x_p > \lambda_p, \quad x_p \succeq x_p^{\min} \\ \infty & \text{otherwise} \end{cases}$$

where $a_p \in \mathbf{R}_{++}^n$ and $x_p^{\min} \in \mathbf{R}_{++}^n$ are given data. The vectors $a_p$ and $x_p^{\min}$ are stored as the columns of the matrices `A` and `x_min`, respectively.

Give the optimal objective value and job traffic. Compare the optimal job traffic with the target job traffic.

**21.10** *Optimal parimutuel betting.* In *parimutuel betting*, participants bet nonnegative amounts on each of $n$ outcomes, exactly one of which will actually occur. (For example, the outcome can be which of $n$ horses wins a race.) The total amount bet by all participants on all outcomes is called the *pool* or *tote*. The house takes a commission from the pool (typically around 20%), and the remaining pool is divided among those who bet on the outcome that occurs, in proportion to their bets on the outcome. This problem concerns the choice of the amount to bet on each outcome.

Let $x_i \geq 0$ denote the amount we bet on outcome $i$, so the total amount we bet on all outcomes is $\mathbf{1}^T x$. Let $a_i > 0$ denote the amount bet by all other participants on outcome $i$, so after the house commission, the remaining pool is $P = (1-c)(\mathbf{1}^T a + \mathbf{1}^T x)$, where $c \in (0, 1)$ is the house commission rate. Our *payoff* if outcome $i$ occurs is then

$$p_i = \left( \frac{x_i}{x_i + a_i} \right) P.$$

The goal is to choose $x$, subject to $\mathbf{1}^T x = B$ (where $B$ is the total amount to be bet, which is given), so as to maximize the expected utility

$$\sum_{i=1}^{n} \pi_i U(p_i),$$

where $\pi_i$ is the probability that outcome $i$ occurs, and $U$ is a concave increasing utility function, with $U(0) = 0$. You can assume that $a_i$, $\pi_i$, $c$, $B$, and the function $U$ are known.

(a) Explain how to find an optimal $x$ using convex or quasiconvex optimization. If you use a change of variables, be sure to explain how your variables are related to $x$.

(b) Suggest a fast method for computing an optimal $x$. You can assume that $U$ is strictly concave, and that scalar optimization problems involving $U$ (such as evaluating the conjugate of $-U$) are easily and quickly solved.

*Remarks.*

- To carry out this betting strategy, you'd need to know $a_i$, and then be the last participant to place your bets (so that $a_i$ don't subsequently change). You'd also need to know the probabilities $\pi_i$. These could be estimated using sophisticated machine learning techniques or insider information.

- The formulation above assumes that the total amount to bet (*i.e.*, $B$) is known. If it is not known, you could solve the problem above for a range of values of $B$ and use the value of $B$ that yields the largest optimal expected utility.

**21.11** *Perturbing a Hamiltonian to maximize an energy gap.* A finite dimensional approximation of a quantum mechanical system is described by its Hamiltonian matrix $H \in \mathbf{S}^n$. We label the eigenvalues of $H$ as $\lambda_1 \leq \cdots \leq \lambda_n$, with corresponding orthonormal eigenvectors $v_1, \ldots, v_n$. In this context the eigenvalues are called the energy levels of the system, and the eigenvectors are called the eigenstates. The eigenstate $v_1$ is called the ground state, and $\lambda_1$ is the ground energy. The energy gap (between the ground and next state) is $\eta = \lambda_2 - \lambda_1$.

By changing the environment (say, applying external fields), we can perturb a nominal Hamiltonian matrix to obtain the perturbed Hamiltonian, which has the form

$$H = H^{\mathrm{nom}} + \sum_{i=1}^{k} x_i H_i.$$

Here $H^{\mathrm{nom}} \in \mathbf{S}^n$ is the nominal (unperturbed) Hamiltonian, $x \in \mathbf{R}^k$ gives the strength or value of the perturbations, and $H_1, \ldots, H_k \in \mathbf{S}^n$ characterize the perturbations. We have limits for each perturbation, which we express as $|x_i| \leq 1$, $i = 1, \ldots, k$. The problem is to choose $x$ to maximize the gap $\eta$ of the perturbed Hamiltonian, subject to the constraint that the perturbed Hamiltonian $H$ has the same ground state (up to scaling, of course) as the unperturbed Hamiltonian $H^{\mathrm{nom}}$. The problem data are the nominal Hamiltonian matrix $H^{\mathrm{nom}}$ and the perturbation matrices $H_1, \ldots, H_k$.

(a) Explain how to formulate this as a convex or quasiconvex optimization problem. If you change variables, explain the change of variables clearly.

(b) Carry out the method of part (a) for the problem instance with data given in `hamiltonian_gap_data.*`. Give the optimal perturbations, and the energy gap for the nominal and perturbed systems. The data $H_i$ are given as a cell array; `H{i}` gives $H_i$.

**21.12** *Theory-applications split in a course.* A professor teaches an advanced course with 20 lectures, labeled $i = 1, \ldots, 20$. The course involves some interesting theoretical topics, and many practical applications of the theory. The professor must decide how to split each lecture between theory and applications. Let $T_i$ and $A_i$ denote the fraction of the $i$th lecture devoted to theory and applications, for $i = 1, \ldots, 20$. (We have $T_i \geq 0$, $A_i \geq 0$, and $T_i + A_i = 1$.)

A certain amount of theory has to be covered before the applications can be taught. We model this in a crude way as

$$A_1 + \cdots + A_i \leq \phi(T_1 + \cdots + T_i), \quad i = 1, \ldots, 20,$$

where $\phi : \mathbf{R} \to \mathbf{R}$ is a given nondecreasing function. We interpret $\phi(u)$ as the cumulative amount of applications that can be covered, when the cumulative amount of theory covered is $u$. We will use the simple form $\phi(u) = a(u - b)_+$, with $a, b > 0$, which means that no applications can be covered until $b$ lectures of the theory is covered; after that, each lecture of theory covered opens the possibility of covering $a$ lectures on applications.

The theory-applications split affects the emotional state of students differently. We let $s_i$ denote the emotional state of a student after lecture $i$, with $s_i = 0$ meaning neutral, $s_i > 0$ meaning happy, and $s_i < 0$ meaning unhappy. Careful studies have shown that $s_i$ evolves via a linear recursion (dynamics)

$$s_i = (1 - \theta)s_{i-1} + \theta(\alpha T_i + \beta A_i), \quad i = 1, \ldots, 20,$$

with $s_0 = 0$. Here $\alpha$ and $\beta$ are parameters (naturally interpreted as how much the student likes or dislikes theory and applications, respectively), and $\theta \in [0, 1]$ gives the emotional volatility of the student (*i.e.*, how quickly he or she reacts to the content of recent lectures). The student's terminal emotional state is $s_{20}$.

Now consider a specific instance of the problem, with course material parameters $a = 2$, $b = 3$, and three groups of students, with emotional dynamics parameters given as follows.

|          | Group 1 | Group 2 | Group 3 |
|----------|---------|---------|---------|
| $\theta$ | 0.05    | 0.1     | 0.3     |
| $\alpha$ | -0.1    | 0.8     | -0.3    |
| $\beta$  | 1.4     | -0.3    | 0.7     |

Find (four different) theory-applications splits that maximize the terminal emotional state of the first group, the terminal emotional state of the second group, the terminal emotional state of the third group, and, finally, the minimum of the terminal emotional states of all three groups.

For each case, plot $T_i$ and the emotional state $s_i$ for the three groups, versus $i$. Report the numerical values of the terminal emotional states for each group, for each of the four theory-applications splits.

**21.13** *Optimal material blending.* A standard industrial operation is to blend or mix raw materials (typically fluids such as different grades of crude oil) to create blended materials or products. This problem addresses optimizing the blending operation. We produce $n$ blended materials from $m$ raw materials. Each raw and blended material is characterized by a vector that gives the concentration of each of $q$ constituents (such as different octane hydrocarbons). Let $c_1, \ldots, c_m \in \mathbf{R}_+^q$ and $\tilde{c}_1, \ldots, \tilde{c}_n \in \mathbf{R}_+^q$ be the concentration vectors of the raw materials and the blended materials, respectively. We have $\mathbf{1}^T c_j = \mathbf{1}^T \tilde{c}_i = 1$ for $i = 1, \ldots, n$ and $j = 1, \ldots, m$. The raw material concentrations are given; the blended product concentrations must lie between some given bounds, $\tilde{c}_i^{\min} \preceq \tilde{c}_i \preceq \tilde{c}_i^{\max}$.

Each blended material is created by pumping raw materials (continuously) into a vat or container where they are mixed to produce the blended material (which continuously flows out of the mixing vat). Let $f_{ij} \geq 0$ denote the flow of raw material $j$ (say, in kg/s) into the vat for product $i$, for

$i = 1, \ldots, n$, $j = 1, \ldots, m$. These flows are limited by the total availability of each raw material: $\sum_{i=1}^{n} f_{ij} \leq F_j$, $j = 1, \ldots, m$, where $F_j > 0$ is the maximum total flow of raw material $j$ available. Let $\tilde{f}_i \geq 0$ denote the flow rates of the blended materials. These also have limits: $\tilde{f}_i \leq \tilde{F}_i$, $i = 1, \ldots, n$.

The raw and blended material flows are related by the (mass conservation) equations

$$\sum_{j=1}^{m} f_{ij} c_j = \tilde{f}_i \tilde{c}_i, \quad i = 1, \ldots, n.$$

(The lefthand side is the vector of incoming constituent mass flows and the righthand side is the vector of outgoing constituent mass flows.)

Each raw and blended material has a (positive) price, $p_j$, $j = 1, \ldots, m$ (for the raw materials), and $\tilde{p}_i$, $i = 1, \ldots, n$ (for the blended materials). We pay for the raw materials, and get paid for the blended materials. The total profit for the blending process is

$$-\sum_{i=1}^{n} \sum_{j=1}^{m} f_{ij} p_j + \sum_{i=1}^{n} \tilde{f}_i \tilde{p}_i.$$

The goal is to choose the variables $f_{ij}$, $\tilde{f}_i$, and $\tilde{c}_i$ so as to maximize the profit, subject to the constraints. The problem data are $c_j$, $\tilde{c}_i^{\min}$, $\tilde{c}_i^{\max}$, $F_j$, $\tilde{F}_i$, $p_j$, and $\tilde{p}_j$.

(a) Explain how to solve this problem using convex or quasi-convex optimization. You must justify any change of variables or problem transformation, and explain how you recover the solution of the blending problem from the solution of your proposed problem.

(b) Carry out the method of part (a) on the problem instance given in `material_blending_data.*`. Report the optimal profit, and the associated values of $f_{ij}$, $\tilde{f}_i$, and $\tilde{c}_i$.

**21.14** *Ideal preference point.* A set of $K$ choices for a decision maker is parametrized by a set of vectors $c^{(1)}, \ldots, c^{(K)} \in \mathbf{R}^n$. We will assume that the entries $c_i$ of each choice are normalized to lie in the range $[0, 1]$. The *ideal preference point model* posits that there is an ideal choice vector $c^{\text{ideal}}$ with entries in the range $[0, 1]$; when the decision maker is asked to choose between two candidate choices $c$ and $\tilde{c}$, she will choose the one that is closest (in Euclidean norm) to her ideal point. Now suppose that the decision maker has chosen between all $K(K - 1)/2$ pairs of given choices $c^{(1)}, \ldots, c^{(K)}$. The decisions are represented by a list of pairs of integers, where the pair $(i, j)$ means that $c^{(i)}$ is chosen when given the choices $c^{(i)}, c^{(j)}$. You are given these vectors and the associated choices.

(a) How would you determine if the decision maker's choices are consistent with the ideal preference point model?

(b) Assuming they are consistent, how would you determine the bounding box of ideal choice vectors consistent with her decisions? (That is, how would you find the minimum and maximum values of $c_i^{\text{ideal}}$, for $c^{\text{ideal}}$ consistent with being the ideal preference point.)

(c) Carry out the method of part (b) using the data given in `ideal_pref_point_data.*`. These files give the points $c^{(1)}, \ldots, c^{(K)}$ and the choices, and include the code for plotting the results. Report the width and the height of the bounding box and include your plot.

**21.15** *Matrix equilibration.* We say that a matrix is $\ell_p$ *equilibrated* if each of its rows has the same $\ell_p$ norm, and each of its columns has the same $\ell_p$ norm. (The row and column $\ell_p$ norms are related by $m$, $n$, and $p$.) Suppose we are given a matrix $A \in \mathbf{R}^{m \times n}$. We seek diagonal invertible matrices $D \in \mathbf{R}^{m \times m}$ and $E \in \mathbf{R}^{n \times n}$ for which $DAE$ is $\ell_p$ equilibrated.

(a) Explain how to find $D$ and $E$ using convex optimization. (Some matrices cannot be equilibrated. But you can assume that all entries of $A$ are nonzero, which is enough to guarantee that it can be equilibrated.)

(b) Equilibrate the matrix $A$ given in the file `matrix_equilibration_data.*`, with

$$m = 20, \quad n = 10, \quad p = 2.$$

Print the row $\ell_p$ norms and the column $\ell_p$ norms of the equilibrated matrix as vectors to check that each matches.

*Hints.*

- Work with the matrix $B$, with $B_{ij} = |A_{ij}|^p$.
- Consider the problem of minimizing $\sum_{i=1}^{m} \sum_{j=1}^{n} B_{ij} e^{u_i + v_j}$ subject to $\mathbf{1}^T u = 0$, $\mathbf{1}^T v = 0$. (Several variations on this idea will work.)
- We have found that expressing the terms in the objective as $e^{\log B_{ij} + u_i + v_j}$ leads to fewer numerical problems.

**21.16** *Approximations of the PSD cone.* A symmetric matrix is positive semidefinite if and only if all its principal minors are nonnegative. Here we consider approximations of the positive-semidefinite cone produced by partially relaxing this condition.

Denote by $K_{1,n}$ the cone of matrices whose $1 \times 1$ principal minors (*i.e.*, diagonal elements) are nonnegative, so that

$$K_{1,n} = \{X \in \mathbf{S}^n \mid X_{ii} \geq 0 \text{ for all } i\}.$$

Similarly, denote by $K_{2,n}$ the cone of matrices whose $1 \times 1$ and $2 \times 2$ principal minors are nonnegative:

$$K_{2,n} = \left\{ X \in \mathbf{S}^n \;\middle|\; \begin{bmatrix} X_{ii} & X_{ij} \\ X_{ij} & X_{jj} \end{bmatrix} \succeq 0, \text{ for all } i \neq j \right\},$$

*i.e.*, the cone of symmetric matrices with positive semidefinite $2 \times 2$ principal submatrices. These two cones are convex (and in fact, proper), and satisfy the relation:

$$K_{1,n}^* \subseteq K_{2,n}^* \subseteq \mathbf{S}_+^n \subseteq K_{2,n} \subseteq K_{1,n},$$

where $K_{1,n}^*$ and $K_{2,n}^*$ are the dual cones of $K_{1,n}$ and $K_{2,n}$, respectively. (The last two inclusions are immediate, and the first two inclusions follow from the second bullet on page 53 of the text.)

(a) Give an explicit characterization of $K_{1,n}^*$.

(b) Give an explicit characterization of $K_{2,n}^*$.
**Hint:** You can use the fact that if $K = K_1 \cap \cdots \cap K_m$, then $K^* = K_1^* + \cdots + K_m^*$.

(c) Consider the problem

$$
\begin{array}{ll}
\text{minimize} & \mathbf{tr}\,CX \\
\text{subject to} & \mathbf{tr}\,AX = b \\
& X \in K
\end{array}
$$

with variable $X \in \mathbf{S}^n$. The problem parameters are $C \in \mathbf{S}^n$, $A \in \mathbf{S}^n$, $b \in \mathbf{R}$, and the cone $K \subseteq \mathbf{S}^n$. Using the data in `psd_cone_approx_data.*`, solve this problem five times, each time replacing $K$ with one of the five cones $K_{1,n}$, $K_{2,n}$, $\mathbf{S}^n_+$, $K^*_{2,n}$, and $K^*_{1,n}$. Report the five different optimal values you obtain.

**Note:** For parts (a) and (b), the shorter and clearer your description is, the more points you will receive. At the very least, it should be possible to implement your description in CVX*.

**21.17** *Equilibrating chemical reactions.* A chemical system involving $n$ species eventually reaches thermodynamic equilibrium. The composition of such a system is described by $x \in \mathbf{R}^n_{++}$, where $x_i$ denotes the amount of species $i$, measured in moles. We will assume for simplicity that all species stay in the same phase for the entire process (this is usually violated, but is easy enough to deal with). As time passes, the species in the system react. For example, consider the following chemical reaction,

$$ \mathrm{N_2 + 3\,H_2} \quad \rightleftharpoons \quad \mathrm{2\,NH_3}. $$

This means that one mole of $\mathrm{N_2}$ and 3 moles of $\mathrm{H_2}$ can form 2 moles of $\mathrm{NH_3}$, and vice versa. Such reactions are termed *reversible*, because they can proceed in either direction. Hence, we may think of such a reaction as an equation, $\mathrm{N_2 + 3\,H_2 - 2\,NH_3} = 0$. In general, many reactions among the $n$ species may be possible. We assume for our system, there are $m$ possible reversible reactions, described by equations

$$ a_{i1}X_1 + a_{i2}X_2 + \cdots + a_{in}X_n = 0, \qquad i = 1, \ldots, m. $$

For reaction $i$, the vector $a_i = (a_{i1}, \ldots, a_{in})$ describes the effect of a single reaction on the composition of the system. In terms of the forward reactions, $a_{ij} > 0$ if species $X_j$ is consumed during reaction $i$, $a_{ij} < 0$ if species $X_i$ is produced in reaction $i$, and $a_{ij} = 0$ if the quantity of $X_j$ is left unchanged during the $i$th reaction.

As the system proceeds towards thermodynamic equilibrium, each reaction occurs $z_i \in \mathbf{R}$ times, $i = 1, \ldots, m$. Thus, $z_i a_i$ describes the change in composition due to $z_i$ instances of reaction $i$. The equilibrium composition of the system, $x_e$, minimizes the total free energy of the system. For simplicity, an assumption that chemists sometimes make is that their system is comprised of ideal gasses and liquids, in which case the total free energy of the system at composition $x$ is

$$ G(x) = c^T x + \sum_{i=1}^{n} x_i \log(x_i / \mathbf{1}^T x), $$

where $c \in \mathbf{R}^n$ is a given vector determined by system conditions, such as temperature and pressure. This free energy is often measured in joules (J) or kilo-joules (kJ).

Importantly, matter is conserved, which means that change in composition due to the reactions must be equal to the the difference between the initial and equilibrium compositions, so that the difference in composition between the equilibrium and initial composition, $x_e - x_0$ is precisely the change in composition due to the $m$ reactions.

Assuming the reactants in the system act as ideal gasses and liquids, explain how to use convex or quasiconvex optimization to compute the equilibrium composition of the system, given $a_i$, initial composition $x_0$, and free energy parameter $c \in \mathbf{R}^n$. You must justify any statement about curvature or monotonicity that you use. If you make a change of variables, you must justify it as well.

**21.18** *To randomize or not to randomize.* At a start-up, two colleagues Alice and Bob are debating what ad to run in a new marketing campaign. There are $n$ options to choose from. The start-up has data on the distribution of revenue $x_j$ generated per view for each ad $j$. The distribution for each ad is discretetized over $m$ possible outcomes for revenue, $c_1, \ldots, c_m \in \mathbf{R}$, with $c_1 < c_2 < \cdots < c_m$. Alice and Bob use a single matrix $P \in \mathbf{R}^{m \times n}$ to describe all $n$ distributions, with

$$P(x_j = c_i) = P_{ij}.$$

Alice argues for building a new system to randomly display different ads to visitors, with each ad $j$ appearing for a fraction $\theta_j$ of the time. Bob disagrees and believes that the old system, which shows the same ad every time, is sufficient.

Under a randomized policy, the revenue per view $x_{\mathrm{mix}}$ follows the discrete distribution $p = P\theta$, where $\theta \in \mathbf{R}^n_+$, $\mathbf{1}^T\theta = 1$, and $P(x_{\mathrm{mix}} = c_i) = p_i$. The start-up will lose money on the campaign if $x_{\mathrm{mix}} < 0$, and will consider the campaign successful if $x_{\mathrm{mix}} > L$. Alice and Bob's goal is to maximize the probability of a successful campaign while ensuring the probability of a loss is no more than $\beta$.

Using the data `n`, `m`, `P`, `c`, `beta`, and `L` in `rand_policy_data.*`, determine whether it is better to show a single ad or a randomized assortment, and explain why.

**21.19** *Typesetting TEX.* TEX uses a mechanical spring model to determine the spacing before and after each character, on each line of a document. A line consists of $n$ characters, each with width $w_i$, $i = 1, \ldots, n$, and $n + 1$ spaces before and after each character. The spaces have width $s_i$, $i = 1, \ldots, n + 1$. We will assume that $\sum_{i=1}^n w_i + \sum_{i=1}^{n+1} s_i = W$, *i.e.*, the characters and spaces fill the line. We are to determine the widths $s_i$, subject to the line-filling constraint.

In TEX, spaces are modeled as springs that can be compressed or extended from their natural length (or in this context, width). This is expressed by an energy associated with the width $s_i$, given by

$$E_i(s_i) = \begin{cases} \frac{k_i^{\mathrm{ext}}}{2}(s_i - N_i)^2 & s_i > N_i \\ \frac{k_i^{\mathrm{comp}}}{2}(s_i - N_i)^2 & N_i \geq s_i \end{cases}$$

where $k_i^{\mathrm{ext}}$, $N_i$, and $k_i^{\mathrm{comp}}$ are given positive parameters. (We have left out a few details.)

We can interpret the parameters as follows. The parameter $N_i$ is the *natural space*, *i.e.*, the space's minimum energy width. The parameters $k_i^{\mathrm{ext}}$ and $k_i^{\mathrm{comp}}$ are the stiffness of the space in extension and compression, respectively.

The space widths are chosen to minimize the total energy

$$E(s_1, \ldots, s_{n+1}) = E_1(s_1) + \cdots + E_{n+1}(s_{n+1}),$$

subject to the line-filling constraint.

(a) Explain how to find the space widths $s_1, \ldots, s_{n+1}$ by solving a convex optimization problem. You do not need to constrain $s_1, \ldots, s_{n+1}$ to be nonnegative.

(b) Write out the KKT conditions for the optimization problem you derived. Use the KKT conditions to find an analytical solution to the problem.

**21.20** *Train time-table optimization.* We consider a transit system with $K$ trains, denoted $k = 1, \ldots, K$. Each train $k$ travels over a route, which is a sequence of $S_k$ stops. For simplicity, we will assume that each train has the same number of stops, $S$. The train schedule or time-table is given by the arrival and departure times for each train, at each of the stops on its route. We let $A_{ks} \in \mathbf{R}$ be the arrival time of train $k$ at stop $s$ for $s = 1, \ldots S$ and $D_{ks} \in \mathbf{R}$ be the departure time of train $k$ at stop $s$, for $s = 1, \ldots S$. These times are given in minutes from some starting or reference time. The first station arrival times $A_{k1}$ and the last station arrival times $A_{kS}$ are given, for $k = 1, \ldots, K$. Our goal is to choose the remaining arrival and departure times.

We let $d_{ks} \in \mathbf{R}$ be the distance between stop $s + 1$ and stop $s$ for train $k$, for $k = 1, \ldots, K$ and $s = 1, \ldots, S - 1$. There are minimum and maximum speed limits on each travel segment between stops, $v^{\min}$ and $v^{\max}$, respectively. In this simple model, you can assume the trains travel at constant speed between stops.

At each stop, each train must stop for at least $\tau^{\min}$ minutes, *i.e.*, $D_{ks} - A_{ks} \geq \tau^{\min}$ for $k = 1, \ldots, K$, $s = 1, \ldots, S - 1$.

Trains are meant to overlap at various stops called connections. We have $C$ connections, indexed by $c = 1, \ldots, C$. Each connection consists of a pair of trains and stops; $(k, s, k', s')$ means that the $s$ stop of train $k$ should connect with the $s'$ stop of train $k'$. (Presumably this means the trains stop at the same station, but we're not keeping track of the stations where the trains stop here.) The connection time associated with connection $c$ is

$$T_c = \min\{D_{ks}, D_{k's'}\} - \max\{A_{ks}, A_{k's'}\},$$

which is the time interval during which both trains are at the station. There is a required minimum connection time, *i.e.*, $T_c \geq T^{\min}$.

The objective is to maximize the sum of the logs of the connection times (or equivalently, their geometric mean), subject to the constraints described above.

(a) Show how to pose this as a convex optimization problem. If you introduce new variables, or change variables, you must explain how to recover the optimal arrival and departure times from the solution of your problem.

*Hint.* The geometric mean may be a more numerically stable objective when optimizing with CVX*.

(b) Carry out your method on the problem instance described in `train_schedule_data.*`. Report the optimal objective value, *i.e.*, the sum of the logs of the connection times. Plot the optimal schedule using the given function `scheduleDraw(A, D, C)` where A and D are matrices containing the optimal arrival and departure times and C is connections. Also, plot the histogram of connection times using the given function `get_hist(A, D, C)`.

**21.21** *Radiation therapy dose scheduling.* An oncology patient is given a dose of radiation $d_t \in \mathbf{R}_+$ in time periods $t = 1, \ldots, T - 1$, with the goal of shrinking a tumor to some specified target size while

minimizing the damage to the patient's health. We can choose the doses $d_t$, subject to the limit $d_t \le d^{\max}$, where $d^{\max}$ is a given maximum dose. This problem has several names, including *dose scheduling*, *dose planning*, and *dose fractionation*. (The last name refers to how we break up the total dose $\sum_{t=1}^{T-1} d_t$ into the doses delivered in each period.)

We let $S_t \in \mathbf{R}_+$ denote the tumor size in period $t$. The tumor size evolves as

$$S_{t+1} = \alpha e^{-\beta d_t} S_t, \quad t = 1, \ldots, T-1,$$

where $\alpha > 1$ is the per-period tumor growth rate with no radiation, and $\beta > 0$ is a known constant. (Since $d_t \ge 0$ and $\beta > 0$, we see that the radiation applied in one period shrinks the tumor in the next period.) The initial tumor size $S_1$ is given. The goal is to achieve $S_T \le S^{\text{tar}}$, where $S^{\text{tar}}$ is a target final tumor size.

We let $H_t \in \mathbf{R}_+$ denote some measure of the damage to the patient's health from the radiation treatments. It evolves as

$$H_{t+1} = \gamma e^{\delta d_t} H_t, \quad t = 1, \ldots, T-1,$$

where $\gamma \in (0,1]$ is the per-period damage recovery rate with no radiation, and $\delta > 0$ is a known constant. (Since $d_t \ge 0$ and $\delta > 0$, we see that the radiation applied in one period increases the damage in the next period.) The initial damage $H_1$ is given.

The goal is to find a series of doses $d_1, \ldots, d_{T-1}$ that satisfies the constraints described above, and minimizes the maximum damage $H^{\max} = \max_{t=1,\ldots,T} H_t$.

(a) Explain how to solve this problem using convex optimization. If you change variables or form a relaxation, you must explain and justify it.

(b) Solve the problem with $T = 20$ and

$$d^{\max} = 1.2, \quad \alpha = 1.05, \quad \beta = 0.6, \quad \gamma = 0.9, \quad \delta = 0.3, \quad S_1 = 1, \quad S^{\text{tar}} = 0.01, \quad H_1 = 1.$$

Report the optimal objective value, *i.e.*, the maximum damage. Plot the dose $d_t$, damage $H_t$, and tumor size $S_t$ versus $t$, for an optimal dose plan. Plot the same for the case when no treatment is given, *i.e.*, $d_t = 0$ for $t = 1, \ldots, T-1$.

**21.22** *Optimal policies for and shipments between two blood banks.* We consider two blood banks, each with their own supply of and demand for the four types of blood, O, A, B, and AB, which we label 1, 2, 3, and 4. We let $d \in \mathbf{R}_+^4$ denote the demand for the 4 blood types at the first bank, and $\tilde{d} \in \mathbf{R}_+^4$ denote the demand at the second bank. We let $s \in \mathbf{R}_+^4$ denote the supply of the 4 blood types at the first bank, and $\tilde{s} \in \mathbf{R}_+^4$ denote the supply at the second bank. (These values are given in units of blood.)

Some blood types can be substituted for others, according to the following list of possible substitutions.

- Type O demand can be satisfied only with type O blood.
- Type A demand can be satisfied with type O and A blood.
- Type B demand can be satisfied by type O and B blood.
- Type AB demand can be satisfied by all blood types.

For example, the demand for type B blood can be satisfied using any combination of type O and type B blood.

Each bank has a policy which specifies how much of each blood type is used to satisfy the demands for the different blood types. These are expressed as the matrices $B \in \mathbf{R}_+^{4 \times 4}$ and $\tilde{B} \in \mathbf{R}_+^{4 \times 4}$ for the first and second banks, respectively. Here $B_{ij}$ denotes the amount of blood type $j$ we use to satisfy demand for blood type $i$, at the first bank (and similarly for the second bank). The substitution list above imposes sparsity constraints on $B$ and $\tilde{B}$. Note that $B^T \mathbf{1}$ is the vector of total amounts of blood used, and $B\mathbf{1}$ is the vector of total amount of demand that is satisfied, at the first bank, and similarly for the second bank.

We can transport blood between the two banks. We let $t \in \mathbf{R}^4$ denote the amounts of the 4 types that are sent or transported from the first to the second bank, with $t_i < 0$ meaning that blood of type $i$ is sent from the second bank to the first. These shipments incur a cost $\kappa \|t\|_1$, where $\kappa \in \mathbf{R}_+$ is the transport cost per unit. The effect of the shipments is to change the blood supply at the two banks from $s$ and $\tilde{s}$ to $s^+ = s - t$ and $\tilde{s}^+ = \tilde{s} + t$, respectively. (The superscript means $s^+$ and $\tilde{s}^+$ are the post-shipment supplies at the two banks.) We require that $s^+$ and $\tilde{s}^+$ are nonnegative.

Your task is to choose the shipments between banks $t$, and the policy for each bank $B$ and $\tilde{B}$, in order to satisfy the demand at each bank (with the post-shipment supplies). You must minimize the cost, which is the shipment cost plus the total cost of all blood consumed at the two banks, using the prices $p \in \mathbf{R}_{++}^4$. (So for example, $p_3$ is the cost for one unit of type B blood.)

*Remark.* We consider here a static problem with only two blood banks just to keep things simple. A more realistic problem formulation would plan over a sequence of time periods, and include aspects such as shipping time, blood storage life, and donations to the banks over time, as well as more than two banks.

(a) Explain how to solve this problem using convex optimization. If you change variables or relax the problem, you must justify and explain it.

(b) Solve the problem instance with $\kappa = 0.5$ and the given data

$$
p = \begin{bmatrix} 4 \\ 2 \\ 2 \\ 1 \end{bmatrix}, \quad
d = \begin{bmatrix} 20 \\ 5 \\ 10 \\ 15 \end{bmatrix}, \quad
s = \begin{bmatrix} 30 \\ 10 \\ 5 \\ 0 \end{bmatrix}, \quad
\tilde{d} = \begin{bmatrix} 10 \\ 25 \\ 5 \\ 15 \end{bmatrix}, \quad
\tilde{s} = \begin{bmatrix} 5 \\ 20 \\ 15 \\ 20 \end{bmatrix}.
$$

Report the optimal shipment vector $t$ and the optimal policies $B$ and $\tilde{B}$ for the two banks. Give the optimal cost.

Verify that the problem is infeasible when shipments are not allowed, *i.e.*, $t = 0$, and explain why.

**21.23** *Combining partial rankings.* In the rank aggregation problem, we are given several ordered lists of items, and want to construct a single list that reflects the orderings in the given lists. Suppose we have $m$ ordered lists of $k$ indices $i \in \{1, \dots, n\}$, each of the form

$$
\sigma^j = (i_1^j, i_2^j, \dots, i_k^j), \quad j = 1, \dots, m.
$$

The meaning of the lists is that, according to list $j$, $i_1^j$ is preferred to $i_2^j$, is preferred to $i_3^j$, and so on. (The lists have the same number of items, $k$, for notational simplicity. Everything works in the more realistic case when the lists have different lengths.)

We will search for a set of *scores* for the items, denoted by $s \in \mathbf{R}^n$. This set of scores induces a ranking of the items, with the item of highest score the first, second highest second, and so on. (If there are repeated entries in $s$, the ranking is ambiguous.)

We say that a score $s$ is *consistent* with a ranking $\sigma^j$ if

$$s_{i_1^j} > s_{i_2^j} > \cdots > s_{i_k^j}.$$

(a) *Finding a consistent score.* Explain how to use convex optimization to find a set of scores (and therefore also a ranking) that is consistent with the given lists, assuming there is one. *Note.* No, you cannot solve convex problems with strict inequalities.

(b) Use your method on the data in `ranked_lists_data.*`. Give the ordering you get. (Be sure to include your code.)

(c) *Finding a score consistent with many of the lists.* Suppose there is no consistent score for the set of lists. Suggest a convex optimization problem that is a heuristic for finding a score that is consistent with as many of the given lists as possible. Note that this is not the same as finding a score for which many of the inequalities hold; all $k - 1$ inequalities in a given list must hold for the scores to be consistent with the list. *Note.* We will accept any reasonable solution; there are several we can think of.

(d) Use your method on the data in `ranked_lists_inconsistent_data.*`. Give the ordering you get as well as the number of lists for which your solution is inconsistent (*i.e.*, where at least one of the $k - 1$ pairs in the list is mis-ordered).

**21.24** *Allocating memory.* A multicore processor has $n$ cores and $m$ memory blocks. Each core $i$ is allocated a (nonnegative) amount $M_{ij}$ from memory block $j$. Core $i$ requires a total of $b_i$ memory, so $M\mathbf{1} = b$. Memory block $j$ has a total capacity $c_j$, so we have $M^T\mathbf{1} \preceq c$. Our goal is to find a memory allocation $M \in \mathbf{R}_+^{n \times m}$ that satisfies these requirements and minimizes the cost

$$\sum_{i=1}^n \sum_{j=1}^m \left(C_{ij} M_{ij} + D_{ij} M_{ij}^2\right),$$

where $C_{ij}$, $D_{ij}$ are given nonnegative cost rates. (Typically $C_{ij}$ and $D_{ij}$ are increasing functions of the $\ell_1$ distance between memory block $j$ and core $i$, but you don't need to know this to solve the problem.)

The data in the problem are the core memory requirements $b_i$, the memory block capacities $c_j$, and the cost rates $C_{ij}$, $D_{ij}$. You are to determine an optimal memory allocation $M \in \mathbf{R}_+^{n \times m}$.

Solve the problem instance with the data given in `allocate_memory_data.*`. This file also contains plotting code to show a memory allocation. Use this to plot your optimal allocation.